


Table of Content

| | |
|--|-----------|
| CHAPTER 1: INTRODUCTION | 1 |
| 1.1 Project Background | 1 |
| 1.2 Objective of the Project | 6 |
| 1.3 Scope of the Project | 7 |
| 1.4 Meetings with Clients and Stakeholders | 8 |
| 1.5 Structure of the Report | 8 |
| CHAPTER 2: SURVEYS AND INVESTIGATIONS | 10 |
| 2.1 Introduction | 10 |
| 2.2 Road Inventory and Condition Surveys | 10 |
| 2.3 Road Junctions | 36 |
| 2.4 Bus Shelters / Bus Bays / Bus Stop | 39 |
| 2.5 Pavement Condition Survey | 40 |
| 2.6 Traffic Survey | 44 |
| 2.7 Existing Pavement Structure | 47 |
| 2.8 Pavement structural Evaluation using Falling Weight Deflectometer Studies | 47 |
| 2.9 Inventory and Condition Survey of Culverts, Bridges, Grade Separators / VUPs / PUPs | 60 |
| 2.10 Topographic Survey | 60 |
| CHAPTER 3: IMPROVEMENT PROPOSALS | 62 |
| 3.1 General | 62 |
| 3.2 Discussions made with various Stake Holders | 62 |
| 3.3 Initial Improvement Works | 64 |
| 3.3.1 Preliminary Works: | 66 |

| | |
|--|-----------|
| 3.3.2 Carriageway Improvements: - | 66 |
| 3.3.3 Junction Improvements: | 67 |
| 3.3.4 Footpath and Kerb | 69 |
| 3.3.5 Green Hedging: - | 69 |
| 3.3.6 Median and Guard rail: - | 70 |
| 3.3.7 Bus Bays: - | 72 |
| 3.3.8 Drainage and Structural Improvements: - | 73 |
| 3.3.9 Road Markings, Traffic Signboards and other Appurtenances: - | 73 |
| 3.4 Annual Maintenance Proposals | 74 |
| 3.4.1 Traffic Incident Management | 78 |
| CHAPTER 4: COST ESTIMATE | 80 |
| 4.1 General | 80 |
| 4.2 Construction Items | 80 |
| 4.3 Project Costing | 81 |
| 4.4 Total Project Cost | 82 |
| 4.5 Implementation Plan | 83 |
| 4.6 Packaging | 83 |
| 4.7 Time Schedule. | 83 |

List of Tables

| | |
|---|----|
| Table 1.1: Length of Project Corridors in Package 1 | 2 |
| Table 2.1: Table showing details of RoW along for HDC-01 Bellary Road | 11 |
| Table 2.2: Table showing details of RoW along for HDC-02 Old Madras Road | 11 |
| Table 2.3: Table showing details of RoW along for HDC-12b Gorguntepalya to KR Puram | 12 |
| Table 2.4: Table showing details of Carriageway and shoulder along main carriage way for HDC-01 Bellary Road. | 14 |



| | | |
|-------------|--|----|
| Table 2.5: | Table showing details of Carriageway and shoulder along main carriage way for HDC-02 Old Madras Road..... | 15 |
| Table 2.6: | Table showing details of Carriageway and shoulder along main carriage way for HDC-12b Gorguntepalya to KR Puram..... | 20 |
| Table 2.7: | Table showing details of Carriageway and shoulder along service road for HDC-01 Bellary Road..... | 24 |
| Table 2.8: | Table showing details of Carriageway and shoulder along service road for HDC-02 Old Madras Road | 25 |
| Table 2.9: | Table showing details of drain for HDC-01 Bellary Road | 25 |
| Table 2.10: | Table showing details of drain for HDC-02 Old Madras Road..... | 26 |
| Table 2.11: | Table showing details of drain for HDC-12b Gorguntepalya to KR Puram | 29 |
| Table 2.12: | Table showing details of footpath for HDC-01 Bellary Road | 32 |
| Table 2.13: | Table showing details of footpath for HDC-02 Old Madras Road | 33 |
| Table 2.14: | Table showing details of footpath for HDC-12b Gorguntepalya to KR Puram..... | 34 |
| Table 2.15: | Table showing details of Major Junctions | 37 |
| Table 2.16: | Table showing Bus Bays / Bus Stops | 39 |
| Table 2.17: | Table showing Camber with Intervals | 44 |
| Table 2.18: | CVPD for Bellary Road | 46 |
| Table 2.19: | CVPD for Old Madras Road (Link-1) | 46 |
| Table 2.20: | CVPD for Old Madras Road (Link-2) | 46 |
| Table 2.21: | CVPD for Outer Ring Road (Gorguntepalya to K R Puram) | 46 |
| Table 2.22: | Bituminous Crust Thickness by Core Cutter | 47 |
| Table 2.23: | Summary of Normalized Deflection for Bellary Road | 50 |
| Table 2.24: | Summary of Normalized Deflection for Old Madras Road (Link-1) | 53 |
| Table 2.25: | Summary of Normalized Deflection for Old Madras Road (Link-2) | 56 |
| Table 2.26: | Summary of Normalized Deflection for Outer Ring Road (Gorguntepalya to K R Puram) | 58 |
| Table 2.27: | Summary of FWD Analysis and Overlay Design | 59 |
| Table 2.28: | Showing Summary of Structures along the Corridor | 60 |
| Table 3.1 | Lane Configuration..... | 62 |
| Table 3.2 | Table of Assets | 63 |
| Table 3.3 | Tendered length of BBMP and BMRCL | 64 |

| | | |
|-----------|---------------------------------|----|
| Table 3.4 | Police Requirements | 67 |
| Table 3.1 | Bus Priority Lane..... | 68 |
| Table 3.1 | Initial Improvement Length..... | 68 |
| Table 3.1 | Overlay Proposal..... | 70 |

List of Figures

| | | |
|--------------|---|----|
| Figure 2.1:- | Summary of existing Pavement condition of HDC 01 Bellary Road | 43 |
| Figure 2.2:- | Summary of existing Pavement condition of HDC 02 Old Madras Road (Link-1) | 43 |
| Figure 2.3:- | Summary of existing Pavement condition of HDC 02 Old Madras Road (Link-2) | 43 |
| Figure 2.4:- | Summary of existing Pavement condition of HDC 12b Outer Ring Road from Gorguntepalya Palya to KR Puram | 44 |
| Figure 2.5:- | Process Flow to determine pavement modulus values..... | 56 |
| Figure 2.6:- | : Input data for KGPBack Application | 59 |
| Figure 2.7:- | Output data from KGPBack Application | 60 |
| Figure 2.8:- | Providing the input values, obtained via KGP back | 61 |
| Figure 2.9:- | Providing the input values, obtained via KGP back | 61 |


1.1 Project Background

Bangalore is one of the fastest growing cities in Asia and also one of the most sought after cities in India by people, companies and multinationals. The massive growth that the city has witnessed in the last decade is a clear indication of this city being developed to be at par with the most modern cities in the world. The population of Bangalore has grown enormously on account of migration of people from all corners of India, neighboring countries and from countries in the West. Bengaluru 's road network exceeds 3,000 km (1,800 mi) and consists of ring roads, arterial roads, sub-arterial roads and residential streets.

The main arterial roads of Bengaluru coming into the city include Bellary Road in the north, Tumkur Road and Mysore Road in the west, Kanakapura Road, Bannerghatta Road and Hosur Road in the south and Airport Road and Old Madras Road in the east, these high-volume traffic arterial roads are inter connected with Outer Ring Road. Bangalore Commissioner of Police notified these 12 Major Roads connecting inter-districts and inter-states as High Traffic Density Corridors vide Notification dated:03-09-2016, and are named as High-Density Corridors.

Roads, and means of transport, make a crucial contribution to economic development and growth and bring important social benefits. Poorly maintained roads constrain mobility, significantly raise vehicle operating costs, increase accident rates and their associated human and property costs. Deterioration of constructed pavement is natural. It's natural because over time the materials that make up Bitumen begin to break down and become affected by elements such as rain, sunlight and chemicals that come into contact with the pavement surface. The liquid Bitumen binder that is the "glue" of the pavement begins to lose its natural resistance to water, allowing it to penetrate into and underneath the pavement. Once this happens, the surface can quickly fall prey to a number of different types of deterioration.

The construction and maintenance of roads to address the growing traffic in the city has been a challenge to the BDA and the BBMP. To reduce the pressure of hectic maintenance activities for BBMP and to ensure the effective maintenance of high-volume traffic arterial roads it has been proposed to handover the maintenance of High-density corridors to KRDCL.



The decision has been taken in the meeting held on 06-11-2019 under the Chairmanship of Hon'ble Chief Minister, Govt. Of Karnataka for Upgradation and maintenance of 12 High Traffic Density Corridors as per IRC guidelines to be taken by Karnataka Road Development Corporation Ltd.


Karnataka Road Development Corporation Limited (KRDCL) was incorporated on 21st of July 1999 as a wholly owned Government of Karnataka Company as per the Provisions of the Company's Act, 1956. The company is managed by a Board of Directors chaired by Principal Secretary to Government, PWP and IWID with Members from other organizations.

KRDCL is a company under the Public Works, Ports & Inland Water Transport Department. This Company was established to promote surface infrastructure by taking up Road Works, Bridges etc., and to improve road network by taking up construction, widening and strengthening of roads, construction of bridges, maintenance of roads etc., and to take up projects on BOT, BOOT, BOLT. With the emerging industrial and economic development of the past few decades, there has been a tremendous growth in terms of the traffic on all the roads

Karnataka Road Development Corporation Limited (KRDCL) has appointed M/s Infra Support Engineering Consultants Pvt Ltd (ISECPL) as consultants for Preparation of DPR and Project Management Consultancy (Including Detailed Designs) for High Density Corridors (HDC) Package - 1 in Bengaluru, Karnataka comprising of the following roads: [HDC 1: Bellary Road, HDC 2: Old Madras Road, HDC 12b: Outer Ring Road from Gorguntepalya to Old Madras Road in Bangalore city, Karnataka. Total Length 44.55 Km.

Table 1.1: Length of Project Corridors in Package 1

| Sl. No | Name of the Road / Junction | Project length considered in km |
|--------------|---|---------------------------------|
| 1 | HDC 1: Bellary Road - from Chalukya Circle to Hebbal up to start of NH limits via Mekhri Circle | 7.45 |
| 2 | HDC 2: Old Madras Road - Link 1: from Trinity Circle to NH limits via Indiranagar, KR Puram Cable stay Bridge, and Link 2: from KR Puram Railway Station to Hope farm on Whitefield Road via Hoodi. | 18.50 |
| 3 | HDC 12b: Outer Ring Road - from Gorguntepalya to Old Madras Road via BEL Circle, Hebbal Junction. Nagavara. | 18.60 |
| Total length | | 44.55 |



Index Map of Project Road – Package 1

HDC No.1 starts at Chalukya circle in Bellary Road (NH-75) and ends at Hebbal flyover with a total length of approximately 7.45 Kms out of which 5.47 Km is considered for improvements and remaining 1.98 Km road is in ongoing tendered works under BBMP/Smart City/BMRCL.





Figure 1.1 Key Plan of Alignment (Bellary road)

HDC No. 2 Old Madras road consisting of two sections, link road-1 and link road-2. Link road-1 starts at Trinity circle and ends at start of NH-75 limits and link-2 road starts KR Puram Railway station and ends at Hope farm junction with a total length of 18.5 Km out of which 10.0 Km is considered for improvements and remaining 8.5 Km road is in ongoing tendered works under BBMP/Smart City/BMRCL.






| Index | | |
|--------------|---|----------|
| | Work considered by KRDCL for Initial Improvements | 10.0 Km |
| | Ongoing / Tendered works under BBMP | 2.65 Km |
| | Ongoing / Tendered works under BMRCL | 5.85 Km |
| Total Length | | 18.50 Km |

Figure 1.2 Key Plan of Alignment (Old Madras Road)

HDC No. 12B Outer ring road from Gorguntepalya to Old Airport road starts at Gorguntepalya junction and ends at old madras road near Benniganahalli with a total length of 18.6 Km out of which 1.55 Km is considered for improvements and remaining 17.05 Km road is in ongoing tendered works under BBMP/Smart City/BMRCL,



| Index | | |
|-------|---|----------|
| | Work considered by KRDCL for Initial Improvements | 1.55 Km |
| | Ongoing / Tendered works under BBMP | 17.05 Km |
| | Total Length | 18.60 Km |

Figure 1.3 Key Plan of Alignment (Outer Ring Road)

1.2 Objective of the Project

The objective of the consultancy Services is to provide the required technical services to KRDCL in preparation of Detailed designs, Drawings, Estimations, Assisting in Tender Processes, and Project Management including construction supervision, maintenance supervision of the High-Density Corridors.

The following works are intended to be carried out on the Project Road:

1. Identification of possible improvements in the existing alignment.
2. Improvement of drainage at poor drainage locations and clear identification of the same on the drawings.
3. Rehabilitation /Reconstruction of bridges and culverts where necessary,
4. Improvement to junctions/intersections
5. Improvement of sidewalks with all required appurtenances like bollards, chamber covers, landscaping, access to properties, lighting etc.



6. Improvements to Signage, road markings
7. Street lighting of the corridor
8. Requirement for Provision of pedestrian facilities
9. Requirement for Improvement of junctions/intersections.
10. Assessing the Provision of road furniture and adequate road markings.
11. Assessing the Provision of traffic control devices where appropriate.
12. Preparation of roadway plans, sidewalk, median and all required drawings to be issued for good for construction.
13. Preparation of BOQ, specifications, estimates.
14. Preparation of routine maintenance intervals and specifications.
15. Presentations, meetings and discussions with various stakeholders in city.
16. Assisting in Preparation of bidding documents (schedules, specifications and drawings).
17. Bid processing assistance.

1.3 Scope of the Project

The broad scope of work encompasses

Stage 1: Carrying out surveys, investigations, detailed designs on the project roads, estimation, costing and submission of good for construction drawings and

Stage 2: Project management including construction supervision, maintenance supervision, progress reports and PMS uploading.

Following is the brief scope of work as extracted from the RFP Document for Stage 1.

- Analysis of Available Reports and data's from KRDCL, BBMP and other departments.
- Survey and investigations of the Project Road
- Traffic Studies and Analysis
- Road safety assessment
- Pavement Structural Strength
- Topographic Survey
- Bridge / Structures Inventory and Condition Survey
- Hydrology and Drainage Investigations
- Pavement crust thickness

- Detailed Design
- Report and Drawings
- Bid process management

1.4 Meetings with Clients and Stakeholders

During the course of preparation of DPR meetings are held with client and Stakeholders for finalization of improvement proposals and other technical aspects. Following Meetings were held with various stakeholders for administration and Technical approval.

Table 1.1 : Meeting Dates

| Sl No | Meeting held on | Meeting Chaired by | Meeting Location |
|-------|-----------------|---|--------------------------|
| 1 | 30/11/2020 | Additional Chief Secretary, PWD & Home | Vikasa Soudha |
| 2 | 1/12/2020 | Additional Commissioner, Bangalore Traffic Police | Bangalore Traffic Centre |
| 3 | 2/12/2020 | DULT Commissioner | DULT office |
| 4 | 11/12/2020 | Additional Commissioner, Bangalore Traffic Police | Bangalore Traffic Centre |
| 5 | 11/12/2020 | Additional Chief Secretary, PWD & Home | Vikasa Soudha |
| 6 | 16/12/2020 | Managing Director, KRDCL | KRDCL Office |
| 7 | 24/12/2020 | Chief Secretary | Vidhana Soudha |
| 8 | 29/12/2020 | DULT Commissioner | Online |
| 9 | 4/1/2021 | Chairman, Technical committee | KRDCL Office |
| 10 | 8/1/2021 | Additional Chief Secretary, UDD | Vikasa Soudha |
| 11 | 12/1/2021 | Additional Chief Secretary, UDD | Vikasa Soudha |
| 12 | 13/1/2021 | Additional Chief Secretary, UDD | Vikasa Soudha |

1.5 Structure of the Report

The Draft Project Report has been structured as follows.

Volume – 1: Main report

Chapter 1 : Project back ground

Chapter 2 : Surveys and investigations carried out and Interpretation of data

Chapter 3 : Improvement Proposals

Chapter 4 : Cost Estimation

Annexures

Volume – 2: Drawings

Strip Plan



Plan with Sections

Standard Drawings

Volume – 3: Cost Estimation

Bill of Quantities - Package 1

Bill of Quantities – Individual Roads in Package 1

Cost Estimation - Individual Roads in Package 1

Rate Analysis

Volume – 4: Schedules

Schedule A: Existing Features

Schedule B: Initial Improvement Proposals.

Schedule C: Specifications and Standards

Schedule D: Interim Milestones for Initial Improvement Works

Schedule E: Applicable Permits

Schedule F: Maintenance Requirements

Schedule G : Control And Command Centre

Schedule H: Payments Schdule

Schedule I: Safety Requirements

Schedule J: Inter-Departmental Coordination Standard Operating Procedure
(Sop) & Support Agreement

Schedule K: Format of Bank Guarantee For Performance Security.

Schedule L: Appoitment of Proejct Management Consultant

Schedule M : Format of Bank Guarantee For Advance Payment

Schedule N : Change of Scope Formats

Schedule O : Work Order Format for Additional Works

CHAPTER 2: SURVEYS AND INVESTIGATIONS

2.1 Introduction

This chapter deals with various surveys and Investigations carried out as per the Terms of Reference and required for quality compliance of the Project design and report preparation.

Major surveys and Investigations carried out are as follows:

- Road Inventory
- Pavement condition survey
- Structural Inventory
- Traffic surveys
- Topographic surveys
- FWD Survey

2.2 Road Inventory and Condition Surveys

2.2.1 Road Inventory

Road Inventory surveys have been conducted. Surveys are carried out as per the standard methodology / IRC guidelines. However brief methodology is given below:

As per the ToR consultants have to propose improvement proposals for the existing roads along the project corridors. Hence, the road and bridge inventory and condition surveys were conducted accordingly.

The road inventory survey involves making visual estimates and actual measurements of geometric and cross-sectional elements of the road and its deficiencies. This survey involves the collection of the data pertaining to the existing road such as the pavement type, width of the carriageway, type of the shoulder and its width, condition of road, type and condition of drain, footpath, median islands, number of CD structures, available land widths etc. Road inventory has been recorded in a standard format.

The team has travelled and walked along the alignments and adjacent roads collected first-hand information on the width and type of carriage way, type and condition of road, junctions, traffic intensity, width of footpath cum drains, Median islands, cross drainage structures, Bus stops/Bus bays/Bus shelters and relevant details of Grade separators, Metro Rail crossings and skywalks comprising in the project corridor are noted.



2.2.2 Right of Way

The Right of way details for the project road is taken by measuring drain to drain or footpath outer edge at regular intervals, RoW vary from 12m to 60 m. Details of RoW is shown in below table.

Table 2.1: Table showing details of RoW along for HDC-01 Bellary Road

| From in Kms | To in Kms | Length in m | ROW in m |
|-------------|-----------|-------------|----------|
| 0+000 | 0+210 | 210.00 | 48.70 |
| 0+210 | 0+840 | 630.00 | 25.50 |
| 0+840 | 1+690 | 850.00 | 23.20 |
| 1+690 | 1+860 | 170.00 | 19.70 |
| 1+860 | 1+980 | 120.00 | 40.90 |
| 1+980 | 2+360 | 380.00 | 24.50 |
| 2+360 | 2+920 | 560.00 | 28.90 |
| 2+920 | 3+100 | 180.00 | 36.80 |
| 3+100 | 3+650 | 550.00 | 26.50 |
| 3+650 | 4+160 | 510.00 | 39.80 |
| 4+160 | 4+430 | 270.00 | 27.00 |
| 4+430 | 5+780 | 1350.00 | 23.40 |
| 5+780 | 6+450 | 670.00 | 34.10 |

Table 2.2: Table showing details of RoW along for HDC-02 Old Madras Road

| From in Kms | To in Kms | Length in m | ROW in m |
|------------------------------------|-----------|-------------|----------|
| Link 1 - Trinity to Budigere Cross | | | |
| 0+000 | 0+680 | 680 | 15 |
| 0+680 | 0+800 | 120 | 22 |
| 0+800 | 0+975 | 175 | 27 |
| 0+975 | 1+780 | 805 | 23 |
| 1+780 | 2+500 | 720 | 19 |
| 2+500 | 3+860 | 1360 | 26 |
| 3+860 | 4+440 | 580 | 32 |
| 4+440 | 4+600 | 160 | 29 |
| 4+600 | 4+970 | 370 | 24 |
| 4+970 | 5+400 | 430 | 29 |
| 5+400 | 6+050 | 650 | 37 |
| 6+050 | 6+150 | 100 | 30 |
| 6+150 | 8+650 | 2500 | 29 |


| From in Kms | To in Kms | Length in m | ROW in m |
|-------------|-----------|-------------|----------|
| 8+400 | 9+500 | 1100 | 35 |
| 9+500 | 10+370 | 870 | 27 |
| 7+400 | 7+500 | 100 | 29.1 |
| 7+500 | 7+650 | 150 | 19.1 |
| 7+650 | 7+800 | 150 | 27 |
| 7+800 | 7+900 | 100 | 19.6 |
| 7+900 | 8+500 | 600 | 24.9 |
| 8+500 | 8+600 | 100 | 15.4 |
| 8+600 | 9+220 | 620 | 22.7 |
| 9+220 | 9260 | 40 | 19.3 |
| 9+260 | 9620 | 360 | 27 |
| 9+620 | 9750 | 130 | 29.2 |
| 9+750 | 10520 | 770 | 23.7 |
| 7+400 | 7+500 | 100 | 29.1 |
| 10+520 | 10660 | 140 | 17.8 |
| 10+660 | 11720 | 1060 | 24 |
| 11+720 | 12160 | 440 | 18.5 |
| 12160 | 13140 | 980 | 20.7 |
| 13140 | 13850 | 710 | 18.6 |
| 13800 | 14330 | 530 | 22.3 |
| 14330 | 14530 | 200 | 15.4 |
| 14530 | 15290 | 760 | 23.7 |
| 15290 | 16070 | 780 | 18.4 |

Table 2.3: Table showing details of RoW along for HDC-12b Gorguntepalya to KR Puram

| From in Kms | To in Kms | Length in m | ROW in m |
|-------------|-----------|-------------|----------|
| 0+000 | 0+100 | 100 | 21.5 |
| 0+100 | 0+800 | 700 | 17.4 |
| 0+800 | 1+400 | 600 | 11.9 |
| 1+400 | 1+700 | 300 | 13.4 |
| 1+700 | 3+200 | 1500 | 16.8 |
| 3+200 | 6+650 | 3450 | 24.3 |
| 6+650 | 9+700 | 3050 | 22.5 |
| 9+700 | 10+800 | 1100 | 26.3 |
| 10+800 | 18+000 | 7200 | 27.3 |

2.2.3 Land use

The largest proportion of land abutting the project corridors are Commercial followed by Residential.



2.2.4 Carriageway and Median

Measurements were taken at locations where the cross-section changes w.r.t Types and widths of Main Carriageway, Service Roads, Footpath, Median, and Drains from beginning to end of the project roads. Along with carriageway measurements and median as a part of inventory survey. The carriageway varies from Three lane divided carriageway to six lane divided carriageway. The pattern of existing carriageway for four lane and six lanes, shoulder and median is given in Table 2.4 to Table 2.6.

2.2.6 Footpath

At some locations drain cum footpath is provided where land availability is limited where sufficient land is available footpaths are provided separately. Details are shown in below table.

Table 2.12: Table showing details of footpath for HDC-01 Bellary Road

| From in Kms | To in Kms | Length in m | Footpath | | | |
|----------------|--------------|----------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | RHS | |
| | | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 0+000 | 0+210 | 210.00 | Paved | 1.0 | Paved | 2.3 |
| 0+210 | 0+790 | 580.00 | - | - | Paved | 2.2 |
| 0+790 | 0+840 | 50.00 | - | - | Paved | 0.6 |
| 0+840 | 0+890 | 50.00 | - | - | Paved | 1.8 |
| 0+890 | 1+160 | 270.00 | - | - | Paved | 1.8 |
| 1+160 | 1+410 | 250.00 | - | - | - | - |
| 1+410 | 1+510 | 100.00 | Paved | 2.4 | - | - |
| 1+510 | 1+690 | 180.00 | - | - | Paved | 4.1 |
| 1+690 | 1+860 | 170.00 | - | - | Paved | 3.1 |
| 1+860 | 1+980 | 120.00 | Paved | 1.6 | Paved | 0.6 |
| 1+980 | 2+250 | 270.00 | Paved | 1.7 | Paved | 2.8 |
| 2+250 | 2+360 | 110.00 | Paved | 1.6 | - | 0.8 |
| 2+360 | 2+860 | 500.00 | Paved | 6.7 | Paved | 0.8 |
| 2+860 | 2+920 | 60.00 | Paved | 5.0 | - | - |
| 2+920 | 3+100 | 180.00 | Paved | 5.3 | Paved | 1.0 |
| 3+100 | 3+650 | 550.00 | - | - | Paved | 0.8 |
| 3+650 | 3+730 | 80.00 | Paved | 1.4 | Paved | 2.8 |
| 3+730 | 4+160 | 430.00 | Paved | 3.9 | Paved | 0.5 |
| 4+160 | 4+290 | 130.00 | Paved | 2.9 | - | - |
| 4+290 | 4+430 | 140.00 | Paved | 1.9 | - | - |
| 4+430 | 4+670 | 240.00 | - | - | - | - |
| 4+670 | 5+060 | 390.00 | - | - | - | - |
| 5+060 | 5+780 | 720.00 | - | - | - | - |
| 5+780 | 6+230 | 450.00 | - | - | Paved | 1.3 |
| 6+230 | 6+330 | 100.00 | Paved | 1.5 | - | - |
| 6+330 | 6+450 | 120.00 | - | - | - | - |

Table 2.13: Table showing details of footpath for HDC-02 Old Madras Road

| From in Kms | To in Kms | Length in m | Footpath | | | |
|------------------------------------|--------------|----------------|-------------------------|-------|-------------------------|---------|
| | | | LHS | | RHS | |
| | | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| Link 1 - Trinity to Budigere Cross | | | | | | |
| 0+000 | 0+270 | 270 | - | - | Paved | 1.8 |
| 0+270 | 0+380 | 110 | - | - | Paved | 0.8 |
| 0+380 | 0+610 | 230 | Paved | 1.2 | Paved | 1.2 |
| 0+610 | 0+680 | 70 | - | - | - | - |
| 0+680 | 0+800 | 120 | - | - | - | - |
| 0+800 | 0+870 | 70 | - | - | - | - |
| 0+870 | 0+975 | 105 | Paved | 2.5 | - | - |
| 0+975 | 1+100 | 125 | - | - | - | - |
| 1+100 | 1+280 | 180 | - | - | - | - |
| 1+280 | 1+780 | 500 | Paved | 2.4 | - | - |
| 1+780 | 2+000 | 220 | Paved | 1.2 | - | - |
| 2+000 | 2+280 | 280 | - | - | - | - |
| 2+280 | 2+500 | 220 | - | - | - | - |
| 2+500 | 2+750 | 250 | - | - | - | - |
| 2+750 | 3+050 | 300 | - | - | - | - |
| 3+050 | 3+100 | 50 | - | - | Paved | 1.4+2.8 |
| 3+100 | 3+150 | 50 | - | - | Paved | 1.4+2.8 |
| 3+150 | 3+260 | 110 | - | - | Paved | 2.7 |
| 3+260 | 3+490 | 230 | - | - | Paved | 2.7 |
| 3+490 | 3+690 | 200 | Paved | 2.5 | Paved | 2.7 |
| 3+690 | 3+750 | 60 | - | - | - | - |
| 3+750 | 3+860 | 110 | Paved | 2.5 | Paved | 2.7 |
| 3+860 | 4+000 | 140 | Paved | 2.5 | Paved | 5.4 |
| 4+000 | 4+440 | 440 | Paved | 4.6 | Paved | 5.4 |
| 4+440 | 4+560 | 120 | Paved | 3.0 | Paved | 5.4 |
| 4+560 | 4+600 | 40 | Paved | 3 | Paved | 6 |
| 4600 | 4830 | 230 | Paved | 6.7 | Paved | 6 |
| 4830 | 4970 | 140 | Paved | 6.7 | Paved | 8.4 |
| 4970 | 5100 | 130 | Paved | 6.7 | Paved | 8.4 |
| 5100 | 5300 | 200 | Paved | 6.7 | Paved | 1.5 |
| 5300 | 5400 | 100 | Paved | 6 | Paved | 1.5 |
| 5400 | 5600 | 200 | Paved | 6 | Paved | 2.9 |
| 5600 | 5800 | 200 | Paved | 1.5 | Paved | 1.3 |
| 5800 | 6050 | 250 | - | - | Paved | 1.3 |
| 6050 | 6150 | 100 | - | - | - | - |
| 6150 | 6300 | 150 | - | - | - | - |
| 6300 | 8120 | 1820 | Paved | 1.5 | Paved | 1.3 |
| 8120 | 8300 | 180 | - | - | Paved | 0.6 |

| From in Kms | To in Kms | Length in m | Footpath | | | |
|---------------------------------|--------------|----------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | RHS | |
| | | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 8300 | 8400 | 100 | - | - | Paved | 1.6 |
| 8400 | 8650 | 250 | - | - | Paved | 2.6 |
| 8400 | 8970 | 570 | - | - | Paved | 2.6 |
| 8970 | 9000 | 30 | Paved | 3 | Paved | 0.6 |
| 9000 | 9240 | 240 | Paved | 3 | Paved | - |
| 9240 | 9500 | 260 | Paved | 2.5 | Paved | - |
| 9500 | 9750 | 250 | - | - | - | - |
| 9750 | 10125 | 375 | - | - | - | - |
| 10125 | 10370 | 245 | - | - | - | - |
| 10370 | 10500 | 130 | - | - | - | - |
| Link 2 - K R Puram to Hope Farm | | | | | | |
| 11+660 | 11+720 | 60 | Paved | 3.8 | Paved | 1.6 |
| 11+720 | 11+880 | 160 | Paved | 2.6 | Paved | 2.3 |
| 11+880 | 11+940 | 60 | Paved | 2.6 | Paved | 2.3 |
| 11+940 | 12+150 | 210 | Paved | 3.6 | Paved | 3.3 |
| 12+150 | 12+160 | 10 | Paved | 0.8 | Paved | 5.4 |
| 12+160 | 12+440 | 280 | Paved | 0.8 | Paved | 5.4 |
| 12+440 | 12+570 | 130 | Paved | 0.7 | Paved | 5.4 |
| 12+570 | 12+920 | 350 | - | - | Paved | 5.4 |
| 12+920 | 13+000 | 80 | Paved | 4.1 | Paved | 1.9 |
| 13+000 | 13+050 | 50 | Paved | 4.1 | Paved | 1.9 |
| 13+050 | 13+140 | 90 | Paved | 4.1 | Paved | 2.6 |
| 13+140 | 13+690 | 550 | Paved | 3 | Paved | 2.6 |
| 13+690 | 13+750 | 60 | Paved | 3 | Paved | 2.6 |
| 13+750 | 13+850 | 100 | Paved | 3 | Paved | 2.4 |

Table 2.14: Table showing details of footpath for HDC-12b Gorguntepalya to KR Puram

| Chainage, km | | Length, m | Footpath | | | |
|--------------|-------|--------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | LHS | |
| From | To | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 0+000 | 0+100 | 100 | - | - | Paved | 0.8 |
| 0+100 | 0+200 | 100 | Paved | 1.9 | Paved | 0.9 |
| 0+200 | 0+300 | 100 | - | - | Paved | 1.3 |
| 0+300 | 0+400 | 100 | - | - | Paved | 0.8 |
| 0+400 | 0+500 | 100 | - | - | Paved | 4.8 |
| 0+500 | 0+600 | 100 | - | - | Paved | 6.8 |
| 0+600 | 0+700 | 100 | - | - | - | - |
| 0+700 | 0+800 | 100 | Paved | 6.1 | - | - |
| 0+800 | 0+900 | 100 | - | - | Paved | 1.1 |

| Chainage, km | | Length, m | Footpath | | | |
|--------------|-------|--------------|-------------------------|-------|-------------------------|-------|
| From | To | | LHS | | LHS | |
| | | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 0+900 | 1+000 | 100 | - | - | - | - |
| 1+000 | 1+100 | 100 | - | - | Paved | 0.8 |
| 1+100 | 1+200 | 100 | - | - | - | - |
| 1+200 | 1+300 | 100 | - | - | - | - |
| 1+300 | 1+400 | 100 | - | - | - | - |
| 1+400 | 1+500 | 100 | - | - | - | - |
| 1+500 | 1+600 | 100 | - | - | - | - |
| 1+580 | 1+630 | 50 | - | - | - | - |
| 1+600 | 1+700 | 100 | - | - | - | - |
| 1+700 | 1+750 | 50 | - | - | - | - |
| 1+750 | 1+800 | 50 | Paved | 3.1 | Paved | 2.9 |
| 1+800 | 1+900 | 100 | Paved | 2.1 | Paved | 2.0 |
| 1+900 | 2+000 | 100 | Paved | 2.7 | Paved | 0.7 |
| 2+000 | 2+100 | 100 | Paved | 2.7 | Paved | 0.9 |
| 2+100 | 2+200 | 100 | Paved | 2.0 | Paved | 1.8 |
| 2+200 | 2+300 | 100 | Paved | 2.7 | Paved | 1.6 |
| 2+300 | 2+400 | 100 | Paved | 1.7 | Paved | 1.3 |
| 2+400 | 2+500 | 100 | Paved | 2.3 | Paved | 1.7 |
| 2+500 | 2+510 | 10 | Paved | 1.7 | Paved | 0.9 |
| 2+510 | 3+200 | 690 | Paved | 0.8 | - | - |
| 3+200 | 3+520 | 320 | - | - | - | - |
| 3+500 | 3+600 | 100 | - | - | - | - |
| 3+600 | 3+700 | 100 | - | - | - | - |
| 3+700 | 3+800 | 100 | - | - | - | - |
| 3+800 | 3+900 | 100 | - | - | - | - |
| 3+900 | 4+000 | 100 | - | - | - | - |
| 4+000 | 4+100 | 100 | - | - | - | - |
| 4+100 | 4+200 | 100 | Paved | 0.7 | - | - |
| 4+200 | 4+300 | 100 | Paved | 0.8 | - | - |
| 4+300 | 4+400 | 100 | - | - | - | - |
| 4+400 | 4+500 | 100 | Paved | 1.2 | Paved | 1.2 |
| 4+500 | 4+600 | 100 | Paved | 1.2 | Paved | 1.2 |
| 4+600 | 4+700 | 100 | - | - | - | - |
| 4+700 | 4+800 | 100 | - | - | - | - |
| 4+800 | 4+900 | 100 | - | - | - | - |
| 4+900 | 5+000 | 100 | - | - | - | - |
| 5+000 | 5+100 | 100 | - | - | - | - |
| 5+100 | 5+200 | 100 | - | - | - | - |
| 5+200 | 5+300 | 100 | - | - | - | - |
| 5+300 | 5+400 | 100 | - | - | - | - |
| 5+400 | 6+100 | 700 | Paved | 1.3 | Paved | 1.4 |
| 6+100 | 6+650 | 550 | Paved | 2.6 | Paved | 1.1 |
| 6+650 | 6+800 | 150 | - | - | - | - |
| 6+800 | 7+000 | 200 | Paved | 1.7 | Paved | 1.5 |
| 7+000 | 7+100 | 100 | Paved | - | Paved | 1.4 |

| Chainage, km | | Length, m | Footpath | | | |
|--------------|--------|--------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | LHS | |
| From | To | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 7+120 | 7+200 | 80 | Paved | 1.6 | Paved | 1.8 |
| 7+200 | 7+700 | 500 | Paved | 1.6 | Paved | 1.7 |
| 7+700 | 7+900 | 200 | Paved | 1.6 | Paved | 2.2 |
| 7+900 | 8+500 | 600 | Paved | 1.6 | Paved | 2.2 |
| 8+500 | 8+950 | 450 | Paved | 1.5 | Paved | 3.1 |
| 9+010 | 9+300 | 290 | - | - | - | - |
| 9+330 | 9+360 | 30 | - | - | - | - |
| 9+400 | 9+700 | 300 | - | - | - | - |
| 9+750 | 10+100 | 350 | Paved | 0.7 | Paved | 3.5 |
| 10+100 | 10+200 | 100 | - | - | Paved | 2.7 |
| 10+200 | 10+300 | 100 | - | - | Paved | 2.4 |
| 10+350 | 10+800 | 450 | - | - | - | - |
| 10+800 | 11+000 | 200 | - | - | - | - |
| 11+000 | 11+400 | 400 | Paved | 0.6 | Paved | 1.8 |
| 11+400 | 11+900 | 500 | Paved | 0.6 | Paved | 1.8 |
| 11+900 | 12+000 | 100 | Paved | - | Paved | 1.4 |
| 12+000 | 12+600 | 600 | - | - | - | - |
| 12+600 | 12+750 | 150 | Paved | 10.7 | Paved | 9.7 |
| 12+750 | 13+100 | 350 | Paved | 16.2 | Paved | 12.6 |
| 13+100 | 13+200 | 100 | Paved | 8.7 | Paved | 6.7 |
| 13+200 | 13+800 | 600 | - | - | - | - |
| 13+800 | 14+800 | 1000 | Paved | 12.9 | Paved | 13.2 |
| 14+800 | 15+300 | 500 | - | - | - | - |
| 15+300 | 15+550 | 250 | Paved | 6.7 | Paved | 1.5 |
| 15+550 | 15+800 | 250 | Paved | 1.6 | Paved | 1.5 |
| 15+800 | 16+250 | 450 | - | - | - | - |
| 16+250 | 16+600 | 350 | Paved | 0.9 | Paved | 1.8 |
| 16+400 | 16+600 | 200 | Paved | 0.9 | Paved | 1.8 |
| 16+600 | 17+000 | 400 | Paved | 6.0 | Paved | 2.8 |
| 17+000 | 17+300 | 300 | Paved | 1.5 | Paved | 2.9 |
| 17+300 | 17+800 | 500 | Paved | 3.0 | Paved | 1.6 |
| 17+800 | 17+900 | 100 | Paved | 0.8 | Paved | 0.8 |
| 17+900 | 18+000 | 100 | Paved | 0.8 | Paved | 0.8 |

2.3 Road Junctions

Significant transport benefits, across all modes, can be achieved through junction improvement and management. These improvements will aid free flow of Traffic to and from cross roads, thereby reducing travel time of through traffic. Total number of Major and minor junctions identified during inventory study are presented in the Table 2.4 and the detailed drawings for the junction improvements have been presented in Drawing Volume.







Table 2.15: Table showing details of Major Junctions

| Sl. No | Existing chainage | Type of Junction | Location |
|--|-------------------|------------------|--|
| HDC-01 Bellary Road | | | |
| 1 | 0+230 | Staggered | High Grounds Old Police station circle |
| 2 | 1+150 | Y | Windsor Manor Circle |
| 3 | 1+442 | T | Railway parallel Road |
| 4 | 1+590 | T | Palace Road Junction |
| 5 | 2+254 | Y | Mahalakshmi Mandir Circle |
| 6 | 3+435 | + | Mekhri Circle |
| 7 | 4+400 | Y | Sanjay Nagar Rad junction |
| 8 | 4+870 | T | CBI Junction |
| HDC-02 Old Madras Road - Link 1 - Trinity to Budigere Cross | | | |
| 9 | 0+214 | + | - |
| 10 | 0+360 | Y | Gurudwara Junction |
| 11 | 1+100 | Y | Baskaran Road |
| 12 | 2+670 | T | Paramahansa Yogananda Road |
| 13 | 3+042 | Y | 100 Feet Road Indiranagar |
| 14 | 3+564 | T | Swami Vivekananda Metro Junction |
| 15 | 3+888 | Y | Srujandas Junction |
| 16 | 3+918 | Y | Srujandas Junction |
| 17 | 4+987 | Y | Byappanahalli |
| 18 | 9+300 | T | KR Puram Govt Hospital Jn. |
| 19 | 10+120 | Y | KR Puram Extension |
| 20 | 10+900 | T | T C Palya Gate |
| 21 | 11+550 | Staggered | Bhattarahalli |
| 22 | 17+000 | T | Budigere Cross |
| Link 2 - K R Puram to Hope Farm | | | |
| 23 | 8+970 | T | Narayanapura / Singayyanapalya |
| 24 | 11+400 | Y | Hoodi Circle |
| 25 | 13+850 | Y | ITPL |
| 26 | 15+400 | Y | - |
| HDC 12 b Gorgunte Palya to KR Puram | | | |
| 27 | 0+000 | T | Gorgunte Palya junction |
| 28 | 0+400 | + | Pipeline Road Jn |
| 29 | 2+500 | + | Pipeline and MES Road Jn |
| 30 | 2+850 | + | Bell Circle flyover Jn |

| Sl. No | Existing chainage | Type of Junction | Location |
|---------------------|-------------------|------------------|--|
| HDC-01 Bellary Road | | | |
| 31 | 3+300 | + | Kuvempu Circle Bell Jn |
| 32 | 5+000 | Staggered | Kodigehalli main Road and Gundappa Road Jn |
| 33 | 6+750 | + | Hebbal Junction |
| 34 | 9+370 | + | Kempapura Main Road Jn |
| 35 | 10+600 | + | Thanisandra Nagawara Road Jn |
| 36 | 12+270 | Staggered | Hennur Junction |
| 37 | 12+780 | T | 80 feet Road Jn |
| 38 | 13+500 | + | 7 th Main Road Jn Kalyan nagar |
| 39 | 14+950 | + | Horamavu Jn |
| 40 | 16+030 | + | Rammurthy Nagar Jn |

From the inventory, it is found that there are 57 minor junctions in Bellary road, 48 minor junctions in old madras road link 1, 25 minor junctions in old madras road link 2 and 109 minor junctions in Gorguntepalya to K R Puram road.



2.4 Bus Shelters / Bus Bays / Bus Stop

There are 64 number of Bus stops are in provided in project corridors, all bus stops are provided with Bus shelters. At some locations Bus bays are provided, details are shown in below table.:

Table 2.16: Table showing Bus Bays / Bus Stops

| Sl. No | Chainage | Side | | Remarks |
|--|----------|------|-----|--------------------------------|
| | | LHS | RHS | |
| HDC 01 – Bellary road | | | | |
| 1 | 0+180 | Yes | - | Sophia school |
| 2 | 1+820 | - | Yes | Palace guttahalli |
| 3 | 3+000 | - | Yes | Palace grounds |
| 4 | 3+750 | Both | | mekhri circle |
| 5 | 4+100 | Yes | - | mekhri circle |
| 6 | 4+700 | Both | | CBI |
| 7 | 5+230 | Both | | Veternary hospital |
| 8 | 5+500 | Both | | Canara bank |
| 9 | 5+900 | Both | | Hebbal |
| HDC 02 – Old Madras Road | | | | |
| Link 01 Trinity circle to Budigere cross | | | | |
| 10 | 0+230 | Both | | - |
| 11 | 0+350 | Yes | - | Gurudwara Junciton |
| 12 | 1+200 | Yes | - | Near Kensington Junction |
| 13 | 2+400 | Both | | Kadirayanapalya Junction |
| 14 | 2+950 | - | Yes | - |
| 15 | 3+550 | Yes | - | Near Vivekananda Metro station |
| 16 | 4+000 | Both | | - |
| 17 | 4+150 | Both | | - |
| 18 | 4+600 | Yes | - | - |
| 19 | 5+500 | Both | | - |
| 20 | 5+750 | Both | | Near Benniganahalli RUB |
| 21 | 6+500 | Yes | - | - |
| 22 | 7+350 | Both | | K R Puram Railway Station |
| 23 | 7+550 | Both | | - |
| 24 | 8+450 | Both | | ITI Junciton |
| 25 | 9+600 | - | Yes | K R Puram |
| 26 | 10+100 | Both | | - |
| 27 | 10+850 | - | Yes | - |
| Link 02 K R Puram to Hope farm | | | | |
| 28 | 8+000 | Both | | - |
| 29 | 8+200 | Both | | Mahadevapura |
| 30 | 9+500 | Both | | Pheonix Market city |

| Sl. No | Chainage | Side | | Remarks |
|---|----------|------|-----|---------------------------------|
| | | LHS | RHS | |
| 31 | 10+300 | Both | | Garudacharpalya |
| 32 | 10+700 | Yes | - | - |
| 33 | 11+900 | Both | | - |
| 34 | 12+420 | Both | | - |
| 35 | 12+910 | Yes | - | - |
| 36 | 13+330 | | Yes | - |
| 37 | 13+750 | Both | | Big Bazar Junction |
| 38 | 13+900 | Both | | ITPL |
| 39 | 14+300 | Both | | - |
| 40 | 15+000 | Both | | - |
| 41 | 15+500 | - | Yes | - |
| HDC 12 b Gorguntepalya to KR Puram | | | | |
| 42 | 1+550 | Yes | Yes | BBMP Bus Stop |
| 43 | 2+440 | - | Yes | MES Road Bus Stop |
| 44 | 2+790 | - | Yes | BEL Circle Bus stop |
| 45 | 3+250 | - | Yes | Kuvempu Circle Bus Stop |
| 46 | 4+330 | - | Yes | BBMP Bus Stop |
| 47 | 4+850 | - | Yes | BBMP Bus Stop |
| 48 | 6+670 | - | Yes | Hebbal Outer Ring Road Bus Stop |
| 49 | 6+810 | - | Yes | Hebbal Bus Stop |
| 50 | 7+340 | - | Yes | Bethel Church Bus Stop |
| 51 | 7+860 | - | Yes | Kempapura Bus Stop |
| 52 | 9+100 | - | Yes | Veerannapalya Bus Stop |
| 53 | 9+900 | - | Yes | Manyata Tech Park Bus Stop |
| 54 | 10+450 | - | Yes | Nagavara Junction Bus Stop |
| 55 | 11+080 | - | Yes | HRBR Layout 5th Block Bus Stop |
| 56 | 11+530 | - | Yes | HBR Layout 4th Block Bus Stop |
| 57 | 11+910 | Yes | - | HRBR Layout 3rd Block Bus Stop |
| 58 | 12+250 | Yes | - | Hennur Junction Bus Stop |
| 59 | 12+690 | - | Yes | Kalyan Nagar Bus stop |
| 60 | 13+960 | Yes | Yes | Babusapalya Bus Stop |
| 61 | 14+800 | Yes | - | Hormavu Signal Bus Stop |
| 62 | 15+480 | - | Yes | Vijaya Bank Colony Bus Stop |
| 63 | 16+190 | - | Yes | B.Channasandra Bus stop |
| 64 | 17+050 | Yes | Yes | Kasturi Nagar Bus Stop |

2.5 Pavement Condition Survey

The survey regarding road inventory and pavement condition was carried out along the project corridor. The width of the carriageway along the project road varies from 4 lane divided carriage way to six lane divided carriageway. Visual inspection of the road showed

a generally Fair surface condition.

The condition of the pavement has been evaluated based on the field measurements of primary pavement surface distress of cracking (narrow and wide), patching, raveling and potholes, noted for each kilometer length. The extent of each distress has been visually estimated for every kilometer length of the road in terms of percentage area affected and then averaged for one-kilometer road length.

The distress conditions are measured under the following sub-heads:

- Cracking (%)
- Potholes (%)
- Raveling (%)
- Patching (%)
- Settlement & Upheaval (%)

2.5.1 Cracks

Pavement cracking is a typical failure commonly observed in flexible / bituminous pavements occurring predominantly due to the higher number of repetitions of heavier axle loads. Pavement Cracks (%) details along the existing project corridor are in **Annexure 2.1**. The average values of minimum, maximum and average percentage of cracks in the project roads are 0.50%, 5.50%, 2.81% respectively for Bellary road, 2.20%, 5.50%, 3.83% for Old Madaras Road (Link-1), 2.20%, 5.50%, 3.45% for Old Madaras Road (Link-2) and 2.4%, 7.5%, 4.65% for Outer ring Road.

2.5.2 Patching

The variation of Pavement Patching (%) with length is shown in Figure 2.2. Pavement patching (%) details along project corridor is in **Annexure 2.1**. No significant patching is noticed except at few localized spots. The average values of minimum, maximum and average percentage of patching area in the project roads are 0.8%, 7.0 %, 3.98 % respectively for Bellary Road, 2.20%, 7.25%, 4.18% for Old Madaras Road (Link-1), 2.70%, 6.00%, 4.26% for Old Madaras Road (Link-2) and 6.5%, 8.5%, 7.37% for Outer Ring Road.

2.5.3 Ravelling

Disintegration of the pavement surface caused due to failure of binder to hold the material together causing blowing off of fine aggregates leaving behind pock marks and when larger particles are broken free with stripping of aggregates is termed as

Raveling. Pavement raveling (%) details along the project corridor is in **Annexure 2.1**. The average values of minimum, maximum and average percentage of raveling in the project roads are 1.50%, 8.50%, 5.59% for Bellary Road, 3.20%, 7.00%, 4.81% for Old Madaras Road (Link-1), 2.65%, 7.50%, 4.25% for Old Madaras Road (Link-2) and 2.5%, 8.5% and 6.00% for Outer Ring Road.

2.5.4 Potholes

Potholes are bowl-shaped holes of varying sizes in the surface layer extending into the base course. Potholes are mainly formed due of loose base course or base course not covered properly with wearing course or due to inadequate bonding between base course and subsequent top layers. Pavement Potholes (%) details along the project corridor are in **Annexure 2.1**. The average values of minimum, maximum and average percentage of potholes in the project roads are 0.5%, 3.5%, 1.63% for Bellary Road, 1.50%, 5.50%, 2.70% for Old Madaras Road (Link-1), 1.90%, 4.50%, 3.19% for Old Madaras Road (Link-2) and 6.5%, 8.5%, 7.67% for Outer Ring Road.

2.5.5 Rutting

Rutting is a surface depression in the wheel path. Pavement uplift (shearing) may occur along the sides of the rut. Ruts are particularly evident after a rain when they are filled with water. There are two basic types of rutting: mix rutting and subgrade rutting. Mix rutting occurs when the subgrade does not rut yet the pavement surface exhibits wheel path depressions as a result of compaction/mix design problems. Subgrade rutting occurs when the subgrade exhibits wheel path depressions due to loading. In this case, the pavement settles into the subgrade ruts causing surface depressions in the wheel path. Pavement Rutting (%) details along the project corridor are in **Annexure 2. 1**. The average values of minimum, maximum and average percentage of potholes in the project roads are 0%, 0.09%, 0.02% for Bellary Road, 0%, 0.80%, 0.15% for Old Madaras Road (Link-1), 0.0%, 0.80%, 0.08% for Old Madaras Road (Link-2) and 0%, 0.5%, 0.17% for Outer Ring Road.

2.5.6 Summary of Observations on Pavement Condition

The overall condition of the pavement is in fair to Good condition with around 85.97 % of the pavement area in fair condition for Bellary Road, 84.39% of the pavement area in fair condition for Old Madaras Road and 74.15% of pavement area in fair condition for Outer Ring Road the percentage various of distresses for each road is shown below.




Figure 2.1:- Summary of existing Pavement condition of HDC 01 Bellary Road




Figure 2.2:- Summary of existing Pavement condition of HDC 02 Old Madras Road (Link-1)




Figure 2.3:- Summary of existing Pavement condition of HDC 02 Old Madras Road (Link-2)




Figure 2.4:- Summary of existing Pavement condition of HDC 12b Outer Ring Road from Gorguntepalya Palya to KR Puram

2.6 Camber

Carriageway camber is checked at intervals to assess the camber at site, the camber is very important for effective drainage of rain water. The standard camber is 2.5% on our roads, but quite often the camber reduces or becomes non uniform during the course of life of road in urban roads due to distress, frequent overlays. Following table represents the camber on the existing roads

Table 2.17: Table showing Camber with Intervals

| Sl. No | Chainage, m | Camber, % | |
|--------------------------|-------------|-----------|--------|
| | | LHS | RHS |
| HDC 01 – Bellary Road | | | |
| 1 | 0+230 | -3.05% | 1.54% |
| 2 | 0+730 | -3.05% | 1.06% |
| 3 | 1+230 | -0.17% | 1.79% |
| 4 | 1+730 | -0.32% | 1.36% |
| 5 | 2+230 | 3.81% | -0.76% |
| 6 | 3+700 | -0.79% | 1.74% |
| 7 | 4+200 | -0.32% | 1.19% |
| 8 | 4+700 | -0.24% | 0.39% |
| 9 | 5+200 | -2.02% | 2.41% |
| 10 | 5+700 | -1.15% | 0.53% |
| 11 | 6+400 | -1.12% | 0.76% |
| 12 | 6+900 | -1.19% | 0.82% |
| HDC 02 – Old Madras Road | | | |
| 13 | 0+980 | 3.68% | 4.82% |
| 14 | 1+480 | -1.78% | 0.66% |
| 15 | 1+980 | -1.23% | 2.22% |

| Sl. No | Chainage, m | Camber, % | |
|---|-------------|-----------|-------|
| | | LHS | RHS |
| 16 | 2+480 | -2.81% | 3.58% |
| 17 | 2+980 | 0.19% | 3.15% |
| 18 | 3+480 | -4.83% | 2.56% |
| 19 | 3+980 | 0.27% | 2.44% |
| 20 | 4+480 | -1.87% | 3.23% |
| 21 | 4+980 | -3.16% | 2.84% |
| 22 | 5+480 | 0.17% | 1.94% |
| 23 | 5+980 | -3.02% | 2.83% |
| 24 | 6+480 | -0.78% | 2.01% |
| 25 | 6+980 | -2.06% | 2.59% |
| 26 | 7+480 | -1.57% | 1.32% |
| 27 | 7+980 | -1.73% | 2.44% |
| 28 | 8+480 | -2.25% | 4.32% |
| HDC 12b – ORR from Gorgunte Palya to K R Puram | | | |
| 29 | 0+000 | -1.47% | 2.04% |
| 30 | 0+500 | 0.56% | 0.85% |
| 31 | 1+000 | 0.19% | 2.77% |
| 32 | 1+500 | -0.80% | 1.51% |
| 33 | 2+000 | 3.39% | 4.43% |
| 34 | 2+500 | 3.01% | 3.96% |

2.7 Traffic Survey

Traffic surveys are an integral component of any transport study where appreciation of existing traffic and travel characteristics of the study area are extremely important. However, Traffic surveys are not required in this assignment as no additional widening is proposed beyond available ROW. However, the traffic survey details available with KRDCL are collected for Analysis of pavement Evaluation and overlay design.

At the outset, ISECPL has collated available traffic survey details to establish the base line data for the study.

The classified traffic volume count data available was processed and compiled using Spread Sheet software packages to get Commercial Vehicles per day, which is further utilized to compute the design traffic. Traffic Survey details referred are conducted during the year 2016, and this traffic is projected to Design Base year. The CVPD adopted for each road is shown below:

- CVPD

Table 2.18: CVPD for Bellary Road

| Mode | CVPD (2016) | Projected CVPD |
|------------|-------------|----------------|
| Std Bus | 3211 | 4099 |
| LCV | 2771 | 3537 |
| 2 Axle | 327 | 418 |
| 3 Axle | 182 | 233 |
| Multi Axle | 74 | 95 |

Table 2.19: CVPD for Old Madras Road (Link-1)

| Mode | CVPD (2016) | Projected CVPD |
|------------|-------------|----------------|
| Std Bus | 5002 | 6384 |
| LCV | 895 | 1143 |
| 2 Axle | 3751 | 4788 |
| 3 Axle | 1452 | 1854 |
| Multi Axle | 921 | 1176 |

Table 2.20: CVPD for Old Madras Road (Link-2)

| Mode | CVPD (2016) | Projected CVPD |
|------------|-------------|----------------|
| Std Bus | 1348 | 1721 |
| LCV | 1706 | 2178 |
| 2 Axle | 858 | 1096 |
| 3 Axle | 350 | 447 |
| Multi Axle | 196 | 251 |

Table 2.21: CVPD for Outer Ring Road (Gorguntepalya to K R Puram)

| Mode | CVPD (2016) | Projected CVPD |
|------------|-------------|----------------|
| Std Bus | 2828 | 3610 |
| LCV | 7207 | 9199 |
| 2 Axle | 1860 | 2374 |
| 3 Axle | 1711 | 2184 |
| Multi Axle | 1331 | 1699 |

- Design life: - Design Life of 5 Years is considered for the overlay design as per IRC: SP: 115 - 2014.
- Growth rate: - Annual Growth rate of 5% is considered for designs.
- VDF: - The adopted vehicle damage factor considered for the overlay design is shown in the table below.

CHAPTER 3: IMPROVEMENT PROPOSALS

3.1 General

The project corridors are studied thoroughly with respect to the existing features on the project roads viz No of lanes, carriageway details, Drains and CDs, Footpaths, Medians, Junctions, Bus bays, sign Boards and other traffic Appurtenances as discussed in Chapter 2. the project corridors under package 1 i.e., HDC 01: Bellary Road, HDC 02: Old Madras Road, and HDC 12b: Outer Ring Road from Goraguntepalya Palya to KR Puram comprise carriageway varying from 4 lane to 6 lanes.

Table 3.1 Lane Configuration

| SI No | Road Name | Lane Km | | | |
|-------|----------------------------|----------|-----------|-------------|---------------|
| | | 4 Lane | 6 Lane | For SR Lane | Total Lane Km |
| 1 | Bellary Road | 10.60 Km | 28.80 Km | 7.40 Km | 47.00 Km |
| 2 | Old Madras Road | 45.92 Km | 42.12 Km | 2.60 Km | 91.00 Km |
| 3 | Goraguntepalya to KR Puram | 13.60 Km | 91.20 Km | 54.30 Km | 160.00 Km |
| | Total | 70.12 Km | 162.12 Km | 64.30 Km | 298.00 Km |

Since the project corridors are under control of BBMP, there are already various improvement works have been carrying out or already tendered by BBMP in the project corridors. Improvement proposals are made for the remaining length which has not been considered for improvement works under BBMP / BMRCL.

The Project Proposals are Prepared in 2 Parts

1. Initial Improvement Proposals
2. Annual Maintenance Proposal

3.2 Discussions made with various Stake Holders

3.2.1 Assets to be included as part of the maintenance project

KRDCL has informed that several meetings were held on this project at various levels of ACS, CS and it was concluded to include and exclude the following assets as part of maintenance by KRDCL.




Table 3.2 Table of Assets

| SL No | Assets Proposed for Maintenance |
|---|--|
| Assets Included for Maintenance by KRDCL | |
| 1 | Carriageway |
| 2 | Median |
| 3 | Junctions |
| 4 | Grade Separators (Flyovers/Underpasses/RoB/RUB) |
| 5 | Bus Bays |
| 6 | Service Roads / Slip Roads / Parking Lanes |
| 7 | Road Markings |
| 8 | Sign Boards |
| 9 | Footpath |
| 10 | Pedestrian Guard Rails |
| 11 | Bollards |
| 12 | High Raised Pedestrian Crossings |
| 13 | Traffic Signals at Junctions |
| 14 | Installation of Traffic KIOSK / Umbrella for Policemen |
| 15 | Side Drains |
| 16 | Cross Drainage Structures |
| 17 | Road Sweeping |
| 18 | Manhole chamber Improvements |
| 19 | Tree Guards |
| 20 | Tree pruning |
| 21 | Road Cutting and Restoration |
| 23 | Removal of Construction and Demolition Debris |
| Assets Excluded for Maintenance by KRDCL | |
| 1 | Bus Shelters |
| 2 | Sky Walks |
| 3 | Solid Waste Management |
| 4 | Encroachment Clearance |
| 5 | Street Lighting |
| 6 | Land Acquisition for improvements |
| 7 | Water Supply and Sanitary lines leakages by BWSSB |
| 8 | Faulty Power Lines by BESCOM/KPTCL |
| 9 | Gas Leakages in Gas Lines by GAIL |

3.2.2 Proposals from Bruhat Bengaluru Mahanagara Palike (BBMP)

Meetings and Discussions are held with BBMP officials regarding the ongoing improvement works or tendered works along the project length of the High-Density corridors. The details of the works which are already considered by BBMP and BMRCL are collected and summary of the same is tabulated below. The stretch wise details of the works considered by BBMP / BMRCL are annexed with the report.

Table 3.3 Tendered length of BBMP and BMRCL

| HDC No | Corridor Name | Total Length of the corridor, Km | BBMP ongoing work length, Km | BMRCL ongoing work length, Km |
|----------------------|-----------------------------------|----------------------------------|------------------------------|-------------------------------|
| 1 | Bellary Road - | 7.45 | 1.98 | 0.00 |
| 2 | Old Madras Road - | 18.50 | 2.65 | 5.85 |
| 12b | Goraguntepalya to K R Puram (ORR) | 18.60 | 17.05 | 0.00 |
| Package I Length, Km | | 44.55 | 21.68 | 5.85 |

3.2.3 Proposals from Traffic Police Department

Police department has prepared a corridor wise proposal for the works to be considered in Short Term, Mid Term and Long-Term measures to improve the Traffic discipline, reduce the congestion, and minimize the accidents and fatalities. the detailed report submitted by the department is annexed with this report and the prominent, short term measures, Midterm Measures, and long-Term measures, which are included in the project proposal are Summarized in the table below.

Table 3.4 Police Requirements

| SI No | Items Considered in Estimate as per Traffic Police Requirement | Quantity | | |
|-------|--|----------|----------|----------|
| | | HDC 01 | HDC 02 | HDC 12b |
| 1 | Junction Improvement | 12 Nos | 7 Nos | 12 Nos |
| 2 | High Raised Pedestrian Crossing | 19 Nos | 31 Nos | 12 Nos |
| 3 | Median Guard Railing | 6.0 Km | 16.65 Km | 16.65 Km |
| 4 | Bus Bay | 4 Nos | 9 Nos | 4 Nos |
| 5 | Widening of road | 300 m | - | 600 m |
| 6 | Traffic Sign Boards | 246 Nos | 463 nos | 371 Nos |
| 7 | Traffic Umbrella/Kiosk | 4 | 4 Nos | 6 Nos |
| 8 | Traffic Signals | 1 No | 2 Nos | 4 Nos |
| 9 | Skywalks | 3 Nos | 8 Nos | 3 Nos |
| 10 | Surveillance and Enforcement Cameras installation | 16 Nos | 56 Nos | 24 Nos |

Various discussion held with ACS, CS on these issues concluded that the skywalks shall be

taken up on PPP basis separately and cameras will be taken up under separate head, hence these two items are excluded from the current scope of project.

3.2.4 Proposals from DULT

DULT suggested to provide bus lanes and cycle lanes in all roads as per the budgetary announcement made by Hon'ble CM. various discussions held on this at ACS, CS level and following suggested to include bus lanes at roads (preferably Outer Ring Road) where 6 lanes are more exists at present and any other stretches needed will be added alter with proper permission/approval from Govt.

The bus priority lanes are provided at following sections

Table 3.1 Bus Priority Lane

| SI No | High Density Corridor | Length of Bus Priority Lane Considered, Km |
|-------|--|--|
| 1 | HDC 01 – Bellary road | Nil |
| 2 | HDC 02 – Old Madras road | Nil |
| 3 | HDC 12 B – ORR from Goraguntepalya to KR Puram | 13.55 Km |
| | Total Length of Bus Lane in Package 1 | 13.55 Km |

3.3 Initial Improvement Works

Initial improvement works are proposed in the Balance length of the corridors which are not considered for improvement by BBMP / BMRCL. The summary of the initial improvement lengths of the 3 corridors under Package 1 is represented below.

Table 3.1 Initial Improvement Length

| HDC No | Corridor Name | Length Considered for Initial Improvement, Km | Total Length of the corridor, Km | BBMP ongoing work length, Km | BMRCL ongoing work length, Km |
|-----------------------------|------------------------------------|---|----------------------------------|------------------------------|-------------------------------|
| 1 | Bellary Road - | 5.47 | 7.45 | 1.98 | 0.00 |
| 2 | Old Madras Road - | 10.00 | 18.50 | 2.65 | 5.85 |
| 12b | Goragunte Palya to K R Puram (ORR) | 1.55 | 18.60 | 17.05 | 0.00 |
| Package I Length, Km | | 17.02 | 44.55 | 21.68 | 5.85 |

The Proposals have been split into following Major Heads.

- (i) Where No works are taken up by BBMP or BMRCL, these stretches the project improvement proposals includes
- Carriageway Improvements
 - Junction Improvements
 - Footpath Improvement and Construction of Green Hedging
 - Median Improvements and Guardrail
 - Construction of Bus Bays & Road Widening
 - Drain Improvements
 - Traffic Signs, Road Markings and Other Appurtenances
- (ii) Whereas for the section where, works taken by BBMP / are under progress or already tendered, only the following works are provisioned.
- Median Guardrail Provisioned
 - Construction of Green Hedging
 - Missing Sign Boards installation
 - Selected Junction Improvements

3.3.1 Preliminary Works:

Following works are considered under preliminary works along the project roads under Package 01, viz Bellary Road, Old Madras Road and Outer ring road. Clearing and grubbing is considered for removal and disposal of unwanted plants and waste materials from the project site. The damaged portion of Medians, Kerbs and Footpaths are proposed for Dismantling and refixing.

3.3.2 Carriageway Improvements: -

Uniform lanes: the carriageways are widened over a period of time and there's no standard lane widths at present, the outer lane widths varies and at few places, its less than the standard lane width. Based on tender sure experience, the lane widths are standardized as below, the outer lane shall be of 3.5 m as buses move on this lane, center lane shall be 3.0 m as this is predominately LMV's for and inner lane shall be 3.25 m giving a shyness of 0.25 m for median. This is been done in discussion with DULT and BBMP as per the tender sure experience.


Resurfacing: lanes or Carriageway is proposed with functional overlay or strengthening and Overlay as per the pavement evaluation and overlay design. Prior to laying overlay, milling of existing bituminous surface is considered in order to achieve required camber and to reduce profile correction course. The carriage way is proposed

with uniform lane markings, and installation of raised pavement markers. Carriageway improvements are represented in volume 3 – Drawings.

Table below shows the resurfacing proposed through FWD studies:

Table 3.1 Overlay Proposal

| Sl No | Corridor Name | Chainage | | Overlay Thickness, mm | |
|-------|--|----------|-------|-----------------------|----|
| | | From | To | DBM | BC |
| 1 | HDC 01: Bellary Road | 0+230 | 1+700 | 0 | 40 |
| 2 | | 3+450 | 7+450 | | |
| 3 | HDC 02: Old Madras Road Link 1 | 0+000 | 3+100 | 50 | 40 |
| 4 | | 3+100 | 8+400 | 0 | 40 |
| 5 | HDC 02: Old Madras Road Link 1 | 0+000 | 0+500 | 0 | 40 |
| 6 | | 6+250 | 8+450 | | |
| 7 | HDC 02: ORR (from Goragunte Palya to KR Puram) | 1+050 | 2+600 | 50 | 40 |



3.3.3 Junction Improvements:

The selected junctions along the corridor are proposed with carriageway improvements, road markings, sign board installations, construction or modification of traffic channelizing islands, provision for precast new jersey barrier to guide the traffic. the junctions are redesigned in order to ensure safe maneuvering of vehicles and pedestrians. In coordination with police department few selected junctions which are not in initial improvement section are also considered for improvement. Junctions considered for

improvement are tabulated below.

Bellary Road: -

| SI No | Junction Chainage | Junction Name |
|-------|-------------------|----------------------|
| 1 | 0+200 | Balbrooi junction |
| 2 | 1+100 | Windsor Yield circle |
| 3 | 1+800 | Ramanujan junction |
| 4 | 2+200 | Kaveri junction |
| 5 | 3+450 | Mekhri junction |
| 6 | 4+400 | Sanjaynagar |
| 7 | 1+500 | 5th main road |
| 8 | 1+600 | Palace cross road |
| 9 | 3+750 | Taralabalu road |
| 10 | 3+980 | Binny mill road |
| 11 | 4+850 | CBI road |
| 12 | 6+100 | 4th main road |

Old Madras Road: -

| SI No | Junction Chainage | Junction Name |
|---------------|-------------------|--------------------------|
| Link-1 | | |
| 1 | 1+100 | Kensington Junction |
| 2 | 1+700 | Thamarai Kannan Jn |
| 3 | 2+000 | Anjaneya Junction |
| 4 | 2+390 | Kadirayanpalya Jn |
| 5 | 2+670 | Double Road Junction |
| 6 | 3+050 | 100ft Road Junction |
| 7 | 3+270 | Kalahalli Junction |
| 8 | 3+950 | Suranjandas Junction |
| 9 | 5+020 | Cross Road |
| 10 | 8+420 | ITI Junction |
| Link-2 | | |
| 1 | 7+400 | KR Puram Railway station |
| 2 | 10+230 | Cross Road |
| 3 | 11+800 | Hoodi Junction |
| 4 | 13+620 | Big Bazar Junction |

Outer Ring Road: -

| SI No | Junction Chainage | Junction Name |
|-------|-------------------|-------------------------|
| 1 | 1+750 | Mutyala Nagara Junction |
| 2 | 2+850 | BEL circle |
| 3 | 1+900 | Cross road |
| 4 | 1+950 | Cross road |
| 5 | 2+100 | Cross road |
| 6 | 2+120 | Cross road |

| SI No | Junction Chainage | Junction Name |
|-------|-------------------|---------------|
| 7 | 2+200 | Cross road |
| 8 | 2+250 | Cross road |
| 9 | 2+310 | Cross road |
| 10 | 2+450 | Cross road |
| 11 | 2+500 | Cross road |
| 12 | 6+750 | Hebbal |

3.3.4 Footpath and Kerb

Footpath proposal includes construction of new walkways with interlocking paver blocks, where space is available or where existing footpath is in poor condition. In addition, replacement of damaged Kerbs and paver blocks are also considered.

Bellary Road: -

| SL No | From | To | Length in m (including both sides) |
|-------|-------|-------|---------------------------------------|
| 1 | 0+250 | 1+150 | 1800 |
| 2 | 1+170 | 1+590 | 840 |
| 3 | 4+430 | 4+640 | 420 |
| 4 | 4+780 | 5+030 | 500 |
| 5 | 4+870 | 4+970 | 200 |
| 6 | 5+450 | 5+550 | 200 |
| 7 | 4+310 | 4+380 | 140 |

Old madras Road: -


| SL No | From | To | Length in m (including both sides) |
|---------------|--------|--------|---------------------------------------|
| Link-1 | | | |
| 1 | 1+150 | 2+000 | 1700 |
| 2 | 2+200 | 2+650 | 900 |
| 3 | 2+700 | 3+000 | 600 |
| 4 | 6+000 | 6+300 | 600 |
| 5 | 9+350 | 9+650 | 600 |
| 6 | 9+700 | 10+350 | 1300 |
| Link-2 | | | |
| 1 | 11+900 | 12+800 | 1800 |
| 2 | 13+700 | 13+800 | 200 |

Outer Ring Road: -


Footpath construction is considered from chainage 1+750 to 2+650 on both sides.

3.3.5 Green Hedging: -

With the intention to improve the aesthetics of the high-density corridors, Green Hedging



is proposed on the footpath sides of the carriageway. the proposal includes installation of additional kerb line and supplying and spreading of farm yard Manure to support planting of permanent hedges. Green hedging is proposed at all feasible locations which are being improved by both BBMP or KRDCL. in addition, provision for chute drains is made along the Kerb line to guide the carriageway runoff to the drain. Cross sections indicating green hedging is represented below.



3.3.6 Median and Guard rail: -

Two types of median are considered for improvement one is the conventional median with both side Kerb with grassing and the other is 900mm standard new Jersey barrier. This is proposed in consultation with Traffic police department. The first type is considered where there is already existing conventional median but in poor condition and the second type is considered as per the police requirement in places where there is existing low height concrete median or at specified places by the police department. Similarly, Guard rail is also proposed in two designs, one is to install over conventional median and the second type is proposed to install over new jersey barrier in such a way to maintain uniform height. Typical section of median with guard rail is represented below.

Bellary Road: -

| Sl No | From | To | Length in m |
|-------|-------|-------|-------------|
| 1 | 0+230 | 1+300 | 1070 |
| 2 | 1+490 | 3+450 | 1960 |
| 3 | 3+680 | 4+420 | 740 |
| 4 | 4+450 | 4+680 | 230 |





| Sl No | From | To | Length in m |
|-------|-------|-------|-------------|
| 5 | 4+950 | 6+340 | 1390 |
| 6 | 6+340 | 6+600 | 260 |
| 7 | 7+100 | 7+450 | 350 |

Old madras Road: -

| Sl No | From | To | Length in m |
|---------------|--------|--------|-------------|
| Link-1 | | | |
| 1 | 0+350 | 1+050 | 700 |
| 2 | 1+150 | 2+000 | 850 |
| 3 | 2+050 | 2+650 | 600 |
| 4 | 2+700 | 3+000 | 300 |
| 5 | 3+100 | 3+880 | 780 |
| 6 | 3+950 | 4+950 | 1000 |
| 7 | 5+030 | 6+050 | 1020 |
| 8 | 6+500 | 9+350 | 2850 |
| 9 | 9+390 | 10+500 | 1110 |
| Link-2 | | | |
| 1 | 7+400 | 7+650 | 250 |
| 2 | 8+000 | 11+200 | 3200 |
| 3 | 11+550 | 11+750 | 200 |
| 4 | 11+850 | 13+600 | 1750 |
| 5 | 13+650 | 13+800 | 150 |
| 6 | 14+000 | 15+600 | 1600 |
| 7 | 15+800 | 15+940 | 140 |

Outer Ring Road: -

| SI No | From | To | Length, m |
|-------|--------|--------|-----------|
| 1 | 0+000 | 1+200 | 1200 |
| 2 | 1+650 | 2+870 | 1220 |
| 3 | 3+450 | 4+800 | 1350 |
| 4 | 5+270 | 6+730 | 1460 |
| 5 | 6+850 | 9+000 | 2150 |
| 6 | 9+700 | 10+530 | 830 |
| 7 | 10+850 | 12+000 | 1150 |
| 8 | 12+670 | 13+230 | 560 |
| 9 | 13+870 | 14+700 | 830 |
| 10 | 15+200 | 15+950 | 750 |
| 11 | 16+250 | 17+750 | 1500 |
| 12 | 18+300 | 18+600 | 300 |



3.3.7 Bus Bays:-

Improvement proposal of Existing bus bays includes pavement overlay in case of Flexible Pavement, Pavement Markings, and Sign Board installations. in Bellary road Existing bus bays are proposed for improvements as discussed. But, with respect to Old Madras road and Outer ring road project reaches new bus bays are proposed as required by traffic police department.

Bellary Road

| SI No | Bus bay Chainage | Location |
|-------|------------------|--------------------|
| 1 | 4+046 | Mekhri circle |
| 2 | 4+776 | Ganganagar |
| 3 | 5+238 | Veterinary college |
| 4 | 6+166 | Hebbal |

Old Madras Road

| SI No | Bus Bay Chainage | Location |
|--------|------------------|--------------------------------|
| Link-1 | | |
| 1 | 1+200 | Near Kensington Junction |
| 2 | 2+400 | Kadirayanapalya Junction |
| 3 | 3+700 | Near Vivekananda Metro station |
| 4 | 5+750 | Near Benniganahalli RUB |

| SI No | Bus Bay Chainage | Location |
|-----------------------------|------------------|---------------------------|
| 5 | 7+200 | K R Puram Railway Station |
| Link-2 | | |
| 1 | 10+200 | Garudacharpalya |
| 2 | 13+550 | Big Bazar Junction |
| Additional Provision | | 2 Nos |

Outer Ring Road

| SI No | Bus bay Chainage | Location |
|-------|------------------|---|
| 1 | 1+750 | Mutyala Nagara |
| 2 | 1+760 | Mutyala Nagara |
| 3 | 2+250 | Opposite to Mother Teresa Public school |
| 4 | 2+260 | Opposite to Mother Teresa Public school |

3.3.8 Drainage and Structural Improvements: -

Existing Drainage facility is studied along the project corridors, for availability and functioning, based on which it is proposed for construction of New Drain with coverslab and replacement of damaged cover slab. in addition, it is also provisioned for any emergency repairs of RE Wall portions of the Grade Separators.

Bellary Road: -

| SI No | From | To | Length in m |
|-------|-------|-------|------------------|
| 1 | 0+230 | 1+040 | 810 |
| 2 | 3+700 | 4+220 | 1040 (Both Side) |
| 3 | 7+100 | 7+450 | 350 |
| 4 | 7+100 | 7+450 | 350 |

Old Madaras Road: -

| SI No | From | To | Length in m |
|---------------|-------|-------|-------------|
| 1 | 1+150 | 1+950 | 800 |
| 2 | 2+050 | 2+650 | 600 |
| 3 | 2+700 | 3+000 | 300 |
| 4 | 6+100 | 6+250 | 150 |
| 5 | 9+350 | 9+650 | 300 |
| 6 | 9+700 | 9+800 | 100 |
| Link-2 | | | |
| 1 | 7+400 | 7+900 | 500 |

Outer Ring Road: -

Drainage improvement is considered from chainage 1+750 to 2+650 on both sides.

3.3.9 Utility and Ducts: -

There are no proposals for shifting of utilities in these stretches, further the initial



improvements are taken only for a part length of 191 kms, the provision of utility ducts are not considered as there will be no continuity of ducts if provided. Further it was decided in various meetings that the current project is of maintenance nature and utilities are in the scope of respective utility departments and KRDCL will focus on maintenance of road assets.

3.3.10 Road Markings, Traffic Signboards and other Appurtenances: -

Road Markings viz Edge lines, Centre lines, Pedestrian Crossings, Directional Arrows are proposed as per the standard requirements and as indicated in the drawings. Similarly raised pavement markers or Road studs are proposed along road markings, at Junctions, at HRPCs as per standards and as indicated in the Drawings. Different Type of Sign boards are provisioned for the project corridors and Appropriate Type & number of sign boards shall be Installed as per the Good for Construction Drawings. The provisions under this head also includes Road Delineators, Hazard markers, Bollards, Single arrow directional sign Boards, overhead gantry sign boards, Traffic Umbrella / KIOSK for Traffic Policemen, Traffic Signals, and Gratings at VUPs. Road Delineators are provided to demarcation of the Bus priority lane, turning demarcation and at edges of the islands. Hazard markers are provisioned for installation at approaches of all structures, at Median openings, etc. Single Arrow directional signboards are provisioned to aid in identification of cross roads, where the board is not available. Over Head Gantry Sign Boards, Traffic KIOSKs and Traffic Signals are all included for costing as per the requirements of the traffic police department.

3.4 Annual Maintenance Proposals

As part of maintenance proposals, government has decided to go for a 5 years long term maintenance and during which the road has to be kept in the good condition for easy and safe movement of traffic and pedestrians at all time. **Road Maintenance** includes routine Maintenance, preventive Maintenance, periodic Maintenance, disaster Maintenance, exigencies and inspections.

- **Periodic Maintenance:** works such as re-surfacing of pavements may be required to restore the functional deficiencies that have developed over a time period. Which shall be decided based on functional and structural valuation studies.
- **Routine Maintenance:** Contractor shall carry out day-to-day site inspection of the designated road stretches and note down the damages that have occurred due to natural or artificial causes, they should take immediate steps to correct or rectify

the damages. Routine Maintenance are undertaken by the maintenance staff almost round the year.

- **Preventive Maintenance:** The preventive maintenance is performed to improve or extend the functional life of pavement surface while in good condition. This may defer the need of periodic maintenance and rehabilitation
- **Disaster Maintenance:** Occasionally several damages are caused to roads cross drainage and other road assets. structures by floods or very heavy down pour or rains, though these may not occur every year. Under such circumstances works are to be completed as early as possible and the road infrastructure shall be restored so as to minimised the inconvenience to road users.
- **Safety & Traffic Management** – this includes enforcement of regulations together with the relevant authorities. Keep project roads safer, this also includes hazard response and Road patrols
- **Asset management** – this includes daily, routine and periodic inspections, Maintenance, repairs, housekeeping and emergency Maintenance

following are the maintenance activities suggested with Time limits for rectification.

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|---------|--|-------------------------------------|
| A | Carriageway/Road surface, Hard shoulders, Drains and Cross Drainage works, Bridges / Interchanges / Grade Separators (Fly Overs/ RUB/ ROB/ Under Pass / any other Road structure). | |
| 1 | Maintaining a public relations unit to interface with and attend to suggestions from the Users, government agencies, media and other agencies and deploying the required staff. Equipment Installation and Office setup (Large TV, Computers, Printers and other equipment), deploying Three non-technical and two technical staff | On or before 30 days from LOA |
| 2 | all surplus construction machinery and materials, waste materials (including hazardous materials and waste water), rubbish and other debris (including, without limitation, accident debris) and keep the Project in a clean, tidy and orderly condition, and in conformity with Applicable Laws, Applicable Permits and Good Industry Practice. | Daily |
| 3 | Carriageway Sweeping using mechanical sweepers and footpath manual cleaning Minimum 4 vehicle mounted sweeping machines to be deployed all the debris/dust/litter shall be safely carried and disposed away at designated | Daily |

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|---------|--|---|
| | places. | |
| 4 | Breach or blockade (the item of works shall be removal of fallen concrete wall, trees, electric pole etc. | Temporary restoration of traffic within 3 hours' permanent restoration within 7 days |
| 5 | Roughness not more than 2600mm/km for each lane in a km length (as measured by a standardized rough meter/bump integrator). | As indicated in the Work order, for this work. |
| 6 | Skid Resistance (Skid Number, SN, minimum Desirable shall be 55 SN | As indicated in the Work order, for this work |
| 7 | Potholes | 24 hours |
| 8 | Cracking all types in less than 5% of road surface for each lane in a km length | 3 (Three) days |
| 9 | Ravelling/Stripping of bitumen and all types in less than 5% of road surface for each lane in a km length | 3 (Three) days |
| 10 | Settlement all types in less than 5% of road surface for each lane in a km length | 3 (Three) days |
| 11 | Rutting exceeding 5 mm in more than 2% of road surface for each lane in a km length (measured ROMDAS or equivalent technology) | 7 (Seven) days |
| 12 | Bleeding | 3 (Three) days |
| 13 | Damage to pavement edges exceeding 100 mm | 24 hours |
| 14 | Painting of Kerb, railing, parapets, crash barriers, | Twice every year |
| 15 | All types of Road Marking | Retro reflectivity mcd/m ² /lux of 150 during the contract period / Twice every year |
| 16 | Joint Sealing in concrete pavement | 7 (Seven) days |
| 17 | Replacement of Pavement Quality Concrete slabs | 15 (fifteen) days |
| 18 | Rain cuts/gullies in slope | 3 (Three) days |
| 19 | Damage to or silting of culverts and side drains during and immediately preceding the rainy season | 3 (Three) days |
| 20 | Desilting of drains in Road side Drains | 3 (Three) days |
| 21 | Cracks - Temporary measures | Within 48 hours |
| 22 | Spalling/scaling | 3 (Three) days |
| 23 | Foundations-cavitation | 3 (Three) days |
| 24 | Piers, abutments, return walls, RE-walls Cracks and damages including settlement and tilting Temporary measures | 30 (Thirty) days |

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|----------|---|---|
| 25 | Bearings All type- Replacements | As indicated in the Work order, for this work |
| 26 | Joints in bridges: Loosening and malfunctioning of joints | As indicated in the Work order, for this work |
| 27 | Deforming of pads in elastomeric bearings | As indicated in the Work order, for this work |
| 28 | Gathering of dirt in bearings and joints or clogging of spouts, weep holes and vent-holes | 3 (Three) days |
| 29 | Damage or deterioration in parapets and handrails | 3 (Three) days |
| 30 | Rain-cuts or erosion of banks of the side slopes of approaches | 3 (Three) days |
| 31 | Resurfacing of wearing coat | As indicated in the Work order, for this work |
| 32 | Damage or deterioration in approach slabs | 3 (Three) days |
| 33 | Growth of vegetation affecting the structure or obstructing the waterway | 3 (Three) days |
| B | Foot Path/Medians/Drains | |
| 34 | Manual cleaning of footpaths, all the debris/dust/litter shall be safely carried and disposed away at designated places | Daily |
| 35 | Damage to paver blocks or concrete surface or tiles of footpath | 3 (Three) days |
| 36 | Damage to Kerbs, bollards, tree guards, pedestrian railings | 3 (Three) days |
| 37 | Road side Drains and inlets | Should be Clean at all times |
| 38 | Damage to drain cover, walls | 3 (Three) days |
| C | Road safety and furniture including all road sign boards and pavement raised marking (road studs) | |
| 39 | Damage to shape or position, poor visibility or loss of retro-reflectivity | 48 hours |
| 40 | Damaged/missing road signs requiring replacement | 7 (seven) days |
| 41 | Painting of railing, parapets, crash barriers | Once every year |
| 42 | Reflective Pavement Markers (Road Studs) Numbers and Functionality as per specification in IRC :SP:84-2014 and IRC :35-2015, unless specified | At all times |
| 43 | Pedestrian Guard rail : Functionality: Functioning of guardrail as intended | At all times |
| 44 | Traffic Safety Barriers: Functionality: Functioning of Safety Barriers as intended | At all times |
| 45 | Overhead Sign Structures shall be structurally and functionally adequate | At all times |
| D | Miscellaneous Works (Trees and Plantation, Road Patrol, Road Cutting Restoration, Road lighting) | |
| 46 | Obstruction in a minimum head-room of 5 m above | 24 hours |

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|---------|---|---|
| | carriageway or obstruction in visibility of road signs | |
| 47 | Deterioration in health of trees and bushes | Timely watering and treatment |
| 48 | Replacement/replanting of plants and bushes on medians, islands, footpaths and green edges | 3 (Three) days |
| 49 | Removal of vegetation affecting sight line and road structures | 3 (Three) days |
| 50 | Patrolling of roads by a vehicle of Bolero or equivalent with a driver, assistant and a supervisor at all times - 2 vehicles and two teams | All through the day |
| 51 | Restoration of road cutting as per IRC specifications Temporary Permanent | As indicated in the Work order, for this work |
| 52 | Road lighting | Not Included. |
| E | Emergency Works | |
| 53 | Removal of Fallen Trees | 3 hours |
| 54 | Towing of Accident vehicle / Breakdown vehicle / Abandoned vehicle, mandatory deployment of: • LMV Towing vehicle –for towing of light commercial vehicles and below – 1 nos • HCV Towing vehicle –for towing of buses/ heavy commercial vehicles - 1 nos | 1 hour |
| 55 | Water logging / Ponding on road surface / grade separators, mandatory deployment of Tippers, pumps, sucking machines, etc., as needed | 1 hour |
| 56 | Fallen Street pole / Sign Boards / any other structure | 1 hour |

3.4.1 Traffic Incident Management

As a part of maintenance proposals, The Project corridors are required to Patrol continually through dedicated staff and Vehicle, to monitor any possible hindrance for the free flow of traffic and to ensure good condition of all Road Assets. Two patrol vehicles with staff are provided for each package of work

During the discussions with the police department, provision of cranes for toeing was asked to toe away the vehicles stranded, met in accident or illegally parked on HDC's. provision of two toeing vehicles one for heavy vehicles like buses and trucks and another for LMV's is proposed.

Water logging at selected locations is a perennial issue during rainy season, especially at

underpasses. In the even of water logging, the provision of sucking machines, pumps and Labour is also provisioned in the maintenance work.

CHAPTER 4: COST ESTIMATE

4.1 General

The Project cost is worked out based on estimated quantities from the detailed engineering design including road works, drainage works, pavement, culverts, road furniture, road safety appurtenances etc.

4.2 Construction Items

The following factors have been considered to arrive at the unit rates for various construction items.

The project cost estimates have been prepared separately for initial improvement works and Annual Maintenance works based on various items of works considered for the upgradation and annual maintenance of the project roads. The Major items rates are considered from **PWP IWTD SoR 2018-19, Bangalore Circle**, Govt. of Karnataka along with latest issue rates, and for few items derived rates are adopted.

Table 4.1 Adopted Unit Rates for Some of the Major Items (Excluding Area Weight Factor)

| Sl. No. | Items | Unit | Rate |
|---------|--|---------|----------|
| 1 | Milling of Existing Bituminous Layer | Sqm | 70.00 |
| 2 | Granular Sub base | Cum | 1882.00 |
| 3 | Wet Mix Macadam | Cum | 1888.00 |
| 4 | Dense Bituminous Macadam (DBM) | Cum | 6045.00 |
| 5 | Bituminous Concrete (BC) | Cum | 6939.00 |
| 6 | Interlocking Paver Blocks | Sqm | 1110.00 |
| 7 | M15 for Kerb Laying | Cum | 5422.00 |
| 8 | Kerb | Nos | 450.00 |
| 9 | Painting two Coats for Kerb | Sqm | 82.00 |
| 10 | Yard Manure | Cum | 204.00 |
| 11 | Planting permanent hedge | Mt | 296.00 |
| 12 | Tree Guard / Grating and Median guard Rail | Quintal | 7187.00 |
| 13 | Providing and Laying M20 for Drain | Cum | 6670.00 |
| 14 | Steel Reinforcement | Tonnes | 61365.00 |
| 15 | Road Marking- Thermoplastic | Sqm | 429.00 |
| 16 | Moulded Shank Raised Pavement Markers | Nos | 337.00 |

4.3 Project Costing

Quantification

The quantification of various items of work is based upon the proposals recommended in the previous chapters. The quantities have been worked out separately for different items of work. The construction cost has been sub-divided into Preliminary Works, Carriageway improvement, Junction Improvement, Footpath and Kerbs, Medians and guard rails, Bus bays and Road Widening Works, Drainage Improvement and other structural Works, Traffic signs, Marking and other Appurtenances.

The following are the Bill wise of works, which have been estimated:

Preliminary Works including Dismantling, Clearance and Earthworks: The area considered for Site Clearance is the area within the proposed Right of Way width. and the damaged portions of Median Kerbs, and Footpath are proposed for dismantling.

Carriageway Improvements: Carriageway improvements costs includes Milling of existing bituminous surface, Strengthening and overlay as per the structural evaluation and Pavement design.

Junction Improvements: Junction improvement cost includes overlay for carriageway, Road markings, installation of sign Boards, High raised pedestrian crossings, construction of channelization islands as per the requirement.

Footpath and Kerbs: Footpath works cost includes removal of damaged paver blocks, kerb stones, etc and replacement with the new ones. In addition, the costing also includes the Green Hedging provision along the footpath

Median and Guardrail: The estimation of quantities for Median construction were based on site inventory, and Median Guard rails for pedestrian safety as per police department instruction is considered.

Bus Bays and Road Widening Works: The estimation of quantities for Bus bays and road widening works were based on the police department requirements, detailed design and drawings.

Drainage Improvement and Structural Works: Provision under this sub-head has been made for cost for construction of side drains, and repairs of RE wall.

Traffic Sign, Markings and Other Appurtenances: Proper traffic signs were selected at required locations along the project corridor. It is reviewed considering the traffic, pedestrian safety, and modified if required. Centre line and edge markings required

from safety point of view were considered in the quantity estimate.

4.4 Total Project Cost

The total project cost of **package 1** is **142.17 Crores**, which includes Initial Improvement cost of **86.48 Crores**, Annual maintenance cost of **23.30 Crores**, 12% for GST, 5% Administration Charges, 3% for DPR and PMC charges, 10% Contingencies. The summary of the project is given in **Table 4.2** below for Total Project Cost along with Road Wise Cost Summary.

The detailed rate analysis and quantity estimation is given in Volume-3: Cost Estimate.

Table 4.2: Summary of Cost for the Project

| Sl. No | Description | HDC 01 | HDC 02 | HDC 12B | Package I |
|--------|---|-----------------|-----------------|-----------------|-----------------|
| | | Amount (Crores) | Amount (Crores) | Amount (Crores) | Amount (Crores) |
| 1 | Preliminary Works including Dismantling, Clearance and Earthworks | 0.26 | 0.44 | 0.08 | 0.78 |
| 2 | Carriageway Improvements | 8.87 | 14.39 | 3.12 | 26.38 |
| 3 | Junction Improvements | 0.53 | 0.67 | 1.00 | 2.21 |
| 4 | Footpath and Kerbs | 4.62 | 7.25 | 6.60 | 18.48 |
| 5 | Median and Guardrail | 1.91 | 5.37 | 5.26 | 12.55 |
| 6 | Bus Bays and Road Widening Works | 0.87 | 0.34 | 1.10 | 2.31 |
| 7 | Drainage Improvement and Structural Works | 2.95 | 6.47 | 2.45 | 11.86 |
| 8 | Traffic Sign, Markings and Other Appurtenances | 1.69 | 2.92 | 7.30 | 11.91 |
| A. | Initial Improvement Cost | 21.70 | 37.85 | 26.92 | 86.48 |
| B. | Annual Maintenance Cost | 3.67 | 8.37 | 11.26 | 23.30 |
| C. | GST @ 12% of (A+B) | 3.05 | 5.55 | 4.58 | 13.17 |
| D. | Administrative Charges @ 5% on (A+B) | 1.27 | 2.31 | 1.91 | 5.49 |
| E. | DPR & PMC Charges @ 3% on (A+B) | 0.65 | 1.62 | 1.63 | 3.90 |
| F. | Contingencies @ 10% | 1.90 | 3.82 | 4.07 | 9.79 |
| G. | Miscellaneous and Rounding off | 0.01 | 0.01 | 0.01 | 0.03 |
| H. | Total Project Cost (A+B+C+D+E+F+G) | 32.26 | 59.53 | 50.38 | 142.17 |

4.5 Implementation Plan

An implementation plan refers to a detailed description of actions that demonstrate how to implement an activity within the project in the context of achieving the objectives, addressing the requirements, and meeting the expectations. The above project is to be implemented in two forms.

1. Initial Improvement and
2. Maintenance

Initial Improvement: Initial improvement is to be done within first nine months of the project tenure year for carriage way, Junctions improvements, Footpath and Drain improvements, Traffic lane markings and sign boards, median island improvements and providing green edge in ongoing BBMP Tender works.

Maintenance: The proposed project roads are to be maintained periodically by clearing of pavement, Repair of traffic signs and road markings, Repair of damage caused by traffic accidents. The project corridors is to be maintained for 5 years as per decision of Govt.

4.6 Packaging

The Total Length of the all the high-density corridor is 191 Km which is spreaded over the entire Bengaluru city. this will make the task of maintaining the road very cumbersome, as it will be very difficult to accesses, Monitor and control the activities over entire length. Hence the Total 15 roads of high-density corridors are grouped in to four packages, such that it will be convenient to Access, Monitor and control the different activities running along the corridor within each package.

4.7 Time Schedule.

The duration for the initial improvement works is 270 days covering various stages of work. The time schedule of the Project along with work programme of activities is given below.




Table 4.3 Time Schedule of Project

| SL NO | DESCRIPTION | DURATION | START DATE | END DATE |
|-------|---|----------|------------|------------|
| A | INITIAL IMPROVEMENT WORKS | 270 DAYS | 01-04-2021 | 31-12-2021 |
| 1 | Strengthening/Resurfacing, Road Marking, Traffic Signs for priority stretches | 90 Days | 01-04-2021 | 30-06-2021 |
| 2 | Drainage and Utility works | 90 Days | 01-04-2021 | 30-06-2021 |
| 3 | Footpath and Kerbs | 90 Days | 01-05-2021 | 31-07-2021 |
| 4 | Median and Guardrails | 60 Days | 01-07-2021 | 31-08-2021 |
| 5 | Junction Improvements | 60 Days | 01-09-2021 | 31-10-2021 |
| 6 | Strengthening/Resurfacing, Road Marking, Traffic signs Road Appurtenances for other stretches | 90 Days | 01-10-2021 | 31-12-2021 |

The Annual Maintenance works needs to be executed continually throughout the year for the project duration of 5 Years.




Annexures 3.1


Details from BBMP


MAINTENANCE OF HIGH DENSITY CORRIDORS IN BENGALURU CITY.


Summary of Works Under HDC No. 1 - Bellary Road Corridor

| Sl. No. | Chainage in km | | Location | | BBMP Department | Ongoing Works / Completed Works Implemented By | Works Considered by KRDCL for Initial Improvement | Maintenance Proposal |
|---------|----------------|----------|--------------------------------|--------------------------------|-----------------|--|---|---|
| | From | To | From | To | | | | |
| 1 | Ch.0.000 | Ch.0.230 | Chalukya Circle | Balabrooie Jn. | RI-East | Proposed Improvement by Smart City | - | 1. Routine Maintenance incl. Mechanical Sweeping of carriageways and Manual Cleaning of Footpath. 2. Removal debries, roadside silt, C&D Wastes & allied works using Tractor Labours. 3. Patrolling. 4. Maintenance of Carriageway. 5. Maintenance of Drain & Footpath. 6. Street Light Maintenance. 7. Other Allied Works on emergent days |
| 2 | Ch.0.230 | Ch.1.700 | Balabrooie Jn. | BDA Fly Over (Palace Rd Cross) | | - | Proposed Improvement by KRDCL | |
| 3 | Ch.1.700 | Ch.3.450 | BDA Fly Over (Palace Rd Cross) | Mekhri Circle Underpass | | Proposed Improvement by RI-Road Widening | - | |
| 4 | Ch.3.450 | Ch.5.500 | Mekhri Circle Underpass | UAS Quarters | | - | Proposed Improvement by KRDCL | |
| | Ch.5.500 | Ch.6.300 | UAS Quarters | Start of Hebbal Flyover | | Proposed partial Resurfacing of LHS reach by RI-East | Proposed Improvement by KRDCL | |
| 5 | Ch.6.300 | Ch.7.450 | Start of Hebbal Flyover | End of Hebbal Flyover | | - | Proposed Improvement by KRDCL | |


EE (RI-East)


EE (RI-Road Widening)


EE (RI-TEC)


EE (KRDCL-NORTH)

MAINTENANCE OF HIGH DENSITY CORRIDORS IN BENGALURU CITY.

Summary of Works Under HDC No. 2 - Old Madras Road Corridor

| Sl. No. | Chainage in km | | Location | | BBMP Department | Ongoing Works / Completed Works Implemented By | Works Considered by KRDCCL for Initial Improvement | Maintenance Proposal |
|--|----------------|-----------|----------------------------------|----------------------------------|-----------------|---|--|---|
| | From | To | From | To | | | | |
| Link o1 - Trinity Circle to Medahalli Junction | | | | | | | | |
| 1 | Ch.0.000 | Ch.1.100 | Trinity Circle | Kensington Road Junction | RI-East | Proposed White Topping Work by Central Project (BBMP) | - | 1. Routine Maintenance incl. Mechanical Sweeping of carriageways and Manual Cleaning of Footpath. 2. Removal debries, roadside silt, C&D Wastes & allied works using Tractor Labours. 3. Patrolling. 4. Maintenance of Carriageway. 5. Maintenance of Drain & Footpath. 6. Street Light Maintenance. 7. Other Allied Works on emergent days |
| 2 | Ch.1.100 | Ch.3.100 | Kensington Road Junction | Indira Nagar 100ft Road Junction | RI-East | Footpath partially developed near Swami Vivekananda Road Junction | Proposed Improvement by KRDCCL | |
| 3 | Ch.3.100 | Ch.5.900 | Indira Nagar 100ft Road Junction | Benniganahalli RUB | RI-East | Partial Improvement Considered under Single Free Corridor by Central Project (BBMP) | Proposed Improvement by KRDCCL for Untackled reaches | |
| 4 | Ch.5.900 | Ch.8.400 | Benniganahalli RUB | End of Cable Stayed Bridge | RI-KR Puram | Except Memo reaches | Proposed Improvement by KRDCCL | |
| 5 | Ch.8.400 | Ch.10.500 | End of Cable Stayed Bridge | Start of NH 75 Limits | RI-KR Puram | Proposed Improvement by RI KR Puram ✓ | - | |
| 6 | Ch.10.500 | Ch.17.000 | Start of NH 75 Limits | Budigere Cross | NHAI Limits | - | - | |

EE (RI-East)

EE (RI-KR Puram)

EE (Project-Central)

EE (KRDCCL-South)

Executive Engineer

Traffic Engineering Cell (RI)

Bangalore Manager Pallik

Bangalore-560 002

M. Ramalaya Reddy
Assistant Executive Engineer-3
Project Office Bengaluru South
K.R.D.C.L., Bengaluru.

- Executive Engineer
Project Office Bengaluru South
K.R.D.C.L., Bengaluru.

MAINTENANCE OF HIGH DENSITY CORRIDORS IN BENGALURU CITY.

Summary of Works Under HDC No. 2 - Old Madras Road Corridor


| Sl. No. | Chainage in km | | Location | | BBMP Department | Ongoing Works / Completed Works Implemented By | Works Considered by KRDCL for Initial Improvement | Maintenance Proposal |
|---|----------------|----------|--------------------------|--------------------|------------------|---|---|--|
| | From | To | From | To | | | | |
| Link o2 - K R Puram Railway Station to Hope Farm Junction | | | | | | | | |
| 4 | Ch.0.000 | Ch.0.500 | KR Puram Railway Station | Lowry Junction | RI - KR Puram | - | Proposed Improvement by KRDCL | 1. Routine Maintenance incl. Mechanical Sweeping of carriageways and Manual Cleaning of Footpath. 2. Removal debris, roadside silt, C&D Wastes & allied works using Tractor Labours. 3. Patrolling. 4. Maintenance of Carriageway. 5. Maintenance of Drain & Footpath. 6. Street Light Maintenance. 7. Other Allied Works on emergent days |
| 2 | Ch.0.500 | Ch.4.250 | Lowry Junction | Hoodi Junction | RI - Mahadevpura | Work under progress by BMRL | - | |
| 3 | Ch.4.250 | Ch.6.450 | Hoodi Junction | Big Bazar Junction | RI - Mahadevpura | Grade Separators are Proposed at Hoodi Junction and Big Bazar Junction by Project Central. Work is yet to Start | Proposed Improvement by KRDCL | |
| 4 | Ch.6.450 | Ch.8.550 | Big Bazar Junction | Hope Farm Junction | RI - Mahadevpura | Work under progress by BMRL | - | |



EE (RI-KR Puram)


EE (RI-Mahadevpura)

EE (Project-Central)

EE (KRDCL-South)


M. Ramalinga Reddy
Assistant Executive Engineer-3
Project Office Bengaluru South
K.R.D.C.L., Bengaluru.


Executive Engineer
Project Office Bengaluru South
K.R.D.C.L., Bengaluru


Executive Engineer
Traffic Engineering Cell (RI)
Bengaluru Mahanagar Palika
Bengaluru-560 002

MAINTENANCE OF HIGH DENSITY CORRIDORS IN BENGALURU CITY.

Summary of Works Under HDC No. 12(b) - Outer Ring Road Corridor (Tumkur Road to Old Madras Road)

| Outer Ring Road Corridor (Tumkur Road to Old Madras Road) | | | | | | | | |
|---|----------------|-----------|-------------------------------|----------------------------------|-----------------|--|---|---|
| Sl. No. | Chainage in km | | Location | | BBMP Department | Ongoing Works / Completed Works Implemented By | Works Considered by KRDCL for Initial Improvement | Maintenance Proposal |
| | From | To | From | To | | | | |
| 1 | Ch.0.000 | Ch.1.050 | Gorguntepalya (Tumkur Road) | Start of ROB | RI-RR Nagar | Proposed Improvement by RI-TEC ✓ | - | 1. Routine Maintenance incl. Mechanical Sweeping of carriageways and Manual Cleaning of Footpath. 2. Removal debries, roadside silt, C&D Wastes & allied works using Tractor Labours. 3. Patrolling. 4. Maintenance of Carriageway. 5. Maintenance of Drain & Footpath. 6. Street Light Maintenance. 7. Other Allied Works on emergent days |
| 2 | Ch.1.050 | Ch.1.700 | Start of ROB | End of ROB | | - | Proposed Improvement by KRDCL | |
| 3 | Ch.1.700 | Ch.2.600 | End of ROB | Start of BEL Circle Underpass | | - | | |
| 4 | Ch.2.600 | Ch.3.450 | Start of BEL Circle Underpass | End of BEL Circle Underpass | RI-East | - | - | |
| 5 | Ch.3.450 | Ch.6.750 | End of BEL Circle Underpass | Hebbal Flyover | | White Topping Work in progress by Central Project (BBMP) | | |
| 6 | Ch.6.750 | Ch.10.600 | Hebbal Flyover | Nagavara Jn. | | | | |
| 7 | Ch.10.600 | Ch.18.600 | Nagavara Jn. | Old Madras Road (Benniganahalli) | | | | |
| Length of Corridor: 18.600km | | | | | Total Cost | | Rs.14.67 Crores | Rs.11.99 Crores / year |

EE (RI-RR Nagar)

EE (RI-East)

EE (RI-TEC)

EE (Project-Central)

EE (KRDCL NORTH)

| | | |
|---------------------------------------|--|-----------|
| 3.3.2 | Carriageway Improvements: - | 65 |
| 3.3.3 | Junction Improvements: | 66 |
| 3.3.4 | Footpath and Kerb | 67 |
| 3.3.5 | Green Hedging: - | 68 |
| 3.3.6 | Median and Guard rail: - | 69 |
| 3.3.7 | Bus Bays: - | 71 |
| 3.3.8 | Drainage and Structural Improvements: - | 71 |
| 3.3.9 | Road Markings, Traffic Signboards and other Appurtenances: - | 72 |
| 3.4 | Annual Maintenance Proposals | 72 |
| 3.4.1 | Traffic Incident Management | 77 |
| CHAPTER 4: COST ESTIMATE | | 78 |
| 4.1 | General | 78 |
| 4.2 | Construction Items | 78 |
| 4.3 | Project Costing | 79 |
| 4.4 | Total Project Cost | 80 |
| 4.5 | Implementation Plan | 80 |
| 4.6 | Packaging | 81 |
| 4.7 | Time Schedule. | 81 |

List of Table

| | | |
|------------|--|----|
| Table 1.1: | Length of Project Corridors in Package 2 | 2 |
| Table 2.1: | Table showing details of RoW along for HDC-03 Old Airport Road | 11 |
| Table 2.2: | Table showing details of RoW along for HDC-04 Sarjapur Road | 12 |
| Table 2.3: | Table showing details of RoW along for HDC-Outer Ring Road KR Puram to Silk Board | 12 |
| Table 2.4: | Table showing details of RoW along for HDC-03 Old Airport Road | 13 |
| Table 2.5: | Table showing details of Carriageway and shoulder along main carriage way | |

| | | |
|-------------|--|----|
| | for HDC-04 Sarjapur Road..... | 20 |
| Table 2.6: | Table showing details of Carriageway and shoulder along main carriage way for HDC-12c Outer Ring Road KR Puram to Silk Board..... | 20 |
| Table 2.7: | Table showing details of Carriageway and shoulder along service road for HDC-12c-part-2 Outer Ring Road..... | 24 |
| Table 2.8: | Table showing details of drain for HDC-03 Old Airport Road | 24 |
| Table 2.9: | Table showing details of drain for HDC-04 Sarjapur Road..... | 28 |
| Table 2.10: | Table showing details of drain for HDC-12c Outer Ring Road | 28 |
| Table 2.11: | Table showing details of footpath for HDC-03 Old Airport Road | 30 |
| Table 2.12: | Table showing details of footpath for HDC-04 Sarjapur Road | 35 |
| Table 2.13: | Table showing details of footpath for HDC-12c Outer Ring Road | 36 |
| Table 2.14: | Table showing details of Major Junctions | 37 |
| Table 2.15: | Table showing Bus Bays / Bus Stops | 39 |
| Table 2.16: | Table showing Camber with Intervals | 45 |
| Table 2.17: | CVPD for Old Airport Road | 47 |
| Table 2.18: | CVPD for Sarjapur Road | 47 |
| Table 2.19: | CVPD for Outer Ring Road (K R Puram to Silk Board)..... | 47 |
| Table 2.20: | Bituminous Crust Thickness by Core Cutter | 48 |
| Table 2.21: | Summary of Normalized Deflection for Old Airport Road | 51 |
| Table 2.22: | Summary of Normalized Deflection for Sarjapur Road | 53 |
| Table 2.23: | Summary of Normalized Deflection for Outer Ring Road (K R Puram to Silk Board) | 53 |
| Table 2.24: | Summary of FWD Analysis and Overlay Design | 58 |
| | Old Airport Road..... | 58 |
| Table 2.25: | Showing Summary of Structures along the Corridor..... | 59 |
| Table 3.1 | Lane Configuration..... | 61 |
| Table 3.2 | Table of Assets | 62 |
| Table 3.3 | Tendered length of BBMP and BMRCL | 63 |
| Table 3.4 | Proposals considered as per Traffic Police Department | 63 |
| Table 3.5 | Proposals of DULT..... | 64 |
| Table 3.6 | Table below shows the Length of Initial Improvement Works..... | 64 |
| Table 3.7 | Table below shows resurfacing proposed..... | 66 |

List of Figures

| | |
|--|----|
| Figure 1.1: Key Plan of Alignment (Old Airport Road) | 4 |
| Figure 1.2 Key Plan of Alignment (Sarjapur Road) | 5 |
| Figure 1.3 Key Plan of Alignment (Outer Ring Road) | 6 |
| Figure 2.1: Summary of existing Pavement condition of HDC 03 Old Airport Road..... | 43 |
| Figure 2.2: Summary of existing Pavement condition of HDC 04 Sarjapura Road..... | 43 |
| Figure 2.3: Summary of existing Pavement condition of HDC 12c Outer Ring Road.... | 44 |

1.1 Project Background

Bangalore is one of the fastest growing cities in Asia and also one of the most sought after cities in India by people, companies and multinationals. The massive growth that the city has witnessed in the last decade is a clear indication of this city being developed to be at par with the most modern cities in the world. The population of Bangalore has grown enormously on account of migration of people from all corners of India, neighboring countries and from countries in the West. Bengaluru's road network exceeds 3,000 km (1,800 mi) and consists of ring roads, arterial roads, sub-arterial roads and residential streets.

The main arterial roads of Bengaluru coming into the city include Bellary Road in the north, Tumkur Road and Mysore Road in the west, Kanakapura Road, Bannerghatta Road and Hosur Road in the south and Airport Road and Old Madras Road in the east, these high-volume traffic arterial roads are inter connected with Outer Ring Road. Bangalore Commissioner of Police notified these 12 Major Roads connecting inter-districts and inter-states as High Traffic Density Corridors vide Notification dated:03-09-2016, and are named as High-Density Corridors.

Roads, and means of transport, make a crucial contribution to economic development and growth and bring important social benefits. Poorly maintained roads constrain mobility, significantly raise vehicle operating costs, increase accident rates and their associated human and property costs. Deterioration of constructed pavement is natural. It's natural because over time the materials that make up Bitumen begin to break down and become affected by elements such as rain, sunlight and chemicals that come into contact with the pavement surface. The liquid Bitumen binder that is the "glue" of the pavement begins to lose its natural resistance to water, allowing it to penetrate into and underneath the pavement. Once this happens, the surface can quickly fall prey to a number of different types of deterioration.

The construction and maintenance of roads to address the growing traffic in the city has been a challenge to the BDA and the BBMP. To reduce the pressure of hectic maintenance activities for BBMP and to ensure the effective maintenance of high-volume traffic arterial roads it has been proposed to handover the maintenance of High-density corridors to KRDCCL.

The decision has been taken in the meeting held on 06-11-2019 under the Chairmanship of Hon'ble Chief Minister, Govt. of Karnataka for Upgradation and maintenance of 12 High Traffic Density Corridors as per IRC guidelines to be taken by Karnataka Road Development Corporation Ltd.


Karnataka Road Development Corporation Limited (KRDCL) was incorporated on 21st of July 1999 as a wholly owned Government of Karnataka Company as per the Provisions of the Company's Act, 1956. The company is managed by a Board of Directors chaired by Principal Secretary to Government, PWP and IWID with Members from other organizations.

KRDCL is a company under the Public Works, Ports & Inland Water Transport Department. This Company was established to promote surface infrastructure by taking up Road Works, Bridges etc., and to improve road network by taking up construction, widening and strengthening of roads, construction of bridges, maintenance of roads etc., and to take up projects on BOT, BOOT, BOLT. With the emerging industrial and economic development of the past few decades, there has been a tremendous growth in terms of the traffic on all the roads

Karnataka Road Development Corporation Limited (KRDCL) has appointed *M/s Infra Support Engineering Consultants Pvt Ltd* (ISECPL) as consultants for Preparation of DPR and Project Management Consultancy (Including Detailed Designs) for High Density Corridors (HDC) Package - 2 in Bengaluru, Karnataka comprising of the following roads: [HDC 3: Old Airport Road, HDC 4: Sarjapura Road, HDC HDC 12c: Outer Ring Road K R Puram to Silk Board. Total Length 42.40 Km (Approximate)].

Table 1.1: Length of Project Corridors in Package 2


| Sl. No | Name of the Road / Junction | Project length considered in km |
|--------------------|--|---------------------------------|
| Package - 2 | | |
| 1 | HDC 3: Old Airport Road - from ASC Center to Kadugodi via HAL, Hope farm on Whitefield Road. | 17.15 |
| 2 | HDC 4: Sarjapur Road - from Hosur Road to Caremelram Bridge via Jakkasandra, Iblur. | 8.75 |
| 6 | HDC 12c Part 2: Outer Ring Road - K R Puram to Silk Board | 16.5 |
| Total length in Km | | 42.40 |



Index Map of Project Road – Package 2

HDC 3: Old Airport Road - from ASC Center to Kadugodi via HAL, Hopefarm on Whitefield Road.

The scope of work for the stretch starts at ASC Centre on HAL Old Airport Road and ends at Hopefarm on Whitefield Road with a total length of approximately 17.15 Kms. This road has 4 lane divided Carriageway. This stretch is the mix of commercial and residential layouts on both sides. A sketch indicating the alignment plan is shown below.




| Index | | |
|-------|---|-----------------|
| | Work considered by KRDCL for Initial Improvements | 14.00 Km |
| | Ongoing / Tendered works under BBMP | 3.15 Km |
| | Total Length | 17.15 Km |

Figure 1.1 Key Plan of Alignment (Old Airport Road)

HDC 4: Sarjapur Road - from Hosur Road to Caremelram Bridge via Jakkasandra, Iblur.

The scope of work for the stretch HDC No. 4 starts from Hosur Road and ends at Caremelram Bridge Via Jakkasandra, Iblur with a total length of 8.75 Km. This road has 4 lane divided Carriageway. This stretch is the mix of commercial and residential layouts on both sides. A sketch indicating the alignment plan is shown below.



| Index | | |
|-------|---|----------------|
| | Work considered by KRDCL for Initial Improvements | 1.10 Km |
| | Ongoing / Tendered works under BBMP | 7.65 Km |
| | Total Length | 8.75 Km |

Figure 1.2 Key Plan of Alignment (Sarjapur Road)

HDC 12c: Outer Ring Road – from K R Puram to Silk Board

The scope of work for the stretch HDC No.12c Outer Ring Road starts at K R Puram and ends at Silkboard with a total length of 16.500 Km. This road has 6 lane divided Carriageway. This stretch is the mix of commercial and residential layouts on both sides. A sketch indicating the alignment plan is shown below.

| Index | | |
|-------|---|----------------|
| | Work considered by KRDCL for Initial Improvements | 11.9 Km |
| | Ongoing / Tendered works under BBMP | 4.6 Km |
| | Total Length | 16.5 Km |




Figure 1.3 Key Plan of Alignment (Outer Ring Road)

1.2 Objective of the Project

The objective of the consultancy Services is to provide the required technical services to KRDCL in preparation of Detailed designs, Drawings, Estimations, Assisting in Tender Processes, and Project Management including construction supervision, maintenance supervision of the High-Density Corridors.

The following works are intended to be carried out on the Project Road:

1. Identification of possible improvements in the existing alignment.
2. Improvement of drainage at poor drainage locations and clear identification of the same on the drawings.
3. Rehabilitation /Reconstruction of bridges and culverts where necessary,
4. Improvement to junctions/intersections
5. Improvement of sidewalks with all required appurtenances like bollards, chamber covers, landscaping, access to properties, lighting etc.
6. Improvements to Signage, road markings
7. Street lighting of the corridor

8. Requirement for Provision of pedestrian facilities
9. Requirement for Improvement of junctions/intersections.
10. Assessing the Provision of road furniture and adequate road markings.
11. Assessing the Provision of traffic control devices where appropriate.
12. Preparation of roadway plans, sidewalk, median and all required drawings to be issued for good for construction.
13. Preparation of BOQ, specifications, estimates.
14. Preparation of routine maintenance intervals and specifications.
15. Presentations, meetings and discussions with various stakeholders in city.
16. Assisting in Preparation of bidding documents (schedules, specifications and drawings).
17. Bid processing assistance.

1.3 Scope of the Project

The broad scope of work encompasses

Stage 1: Carrying out surveys, investigations, detailed designs on the project roads, estimation, costing and submission of good for construction drawings and

Stage 2: Project management including construction supervision, maintenance supervision, progress reports and PMS uploading.

Following is the brief scope of work as extracted from the RFP Document for Stage 1.

- Analysis of Available Reports and data's from KRDCL, BBMP and other departments.
- Survey and investigations of the Project Road
- Traffic Studies and Analysis
- Road safety assessment
- Pavement Structural Strength
- Topographic Survey
- Bridge / Structures Inventory and Condition Survey
- Hydrology and Drainage Investigations
- Pavement crust thickness
- Detailed Design
- Report and Drawings

➤ Bid process management

1.4 Meetings with Clients and Stakeholders

During the course of preparation of DPR meetings are held with client and Stakeholders for finalization of improvement proposals and other technical aspects. Following Meetings were held with various stakeholders for administration and Technical approval.

| Sl No | Meeting held on | Meeting Chaired by | Meeting Location |
|-------|-----------------|---|--------------------------|
| 1 | 30/11/2020 | Additional Chief Secretary, PWD | Vikasa Soudha |
| 2 | 1/12/2020 | Additional Commissioner, Bangalore Traffic Police | Bangalore Traffic Centre |
| 3 | 2/12/2020 | DULT Commissioner | DULT office |
| 4 | 11/12/2020 | Additional Commissioner, Bangalore Traffic Police | Bangalore Traffic Centre |
| 5 | 11/12/2020 | Additional Chief Secretary, PWD | Vikasa Soudha |
| 6 | 16/12/2020 | Managing Director, KRDCL | KRDCL Office |
| 7 | 24/12/2020 | Chief Secretary | Vidhana Soudha |
| 8 | 29/12/2020 | DULT Commissioner | Online |
| 9 | 4/1/2021 | Chairman, Technical committee | KRDCL Office |
| 10 | 8/1/2021 | ACS, UDD | Vikasa Soudha |
| 11 | 12/1/2021 | ACS, UDD | Vikasa Soudha |
| 12 | 13/1/2021 | ACS, UDD | Vikasa Soudha |

1.5 Structure of the Report

The Draft Project Report has been structured as follows.

Volume – I: Main report

Chapter 1 : Project back ground

Chapter 2 : Surveys and investigations carried out and Interpretation of data

Chapter 3 : Improvement Proposals

Chapter 4 : Cost Estimation

Annexures

Volume – II: Drawings

Strip Plan

Plan with Sections

Standard Drawings

Volume – III: Cost Estimation

Bill of Quantities - Package 2

Bill of Quantities – Individual Roads in Package 2

Cost Estimation - Individual Roads in Package 2

Rate Analysis

Volume – IV: Schedules

Schedule A: Existing Features

Schedule B: Initial Improvement Proposals.

Schedule C: Specifications and Standards

Schedule D: Interim Milestones for Initial Improvement Works

Schedule E: Applicable Permits

Schedule F: Maintenance Requirements

Schedule G: Control and Command Centre

Schedule H: Payments Schedule

Schedule I: Safety Requirements

Schedule J: Inter-Departmental Coordination Standard Operating Procedure
(Sop) & Support Agreement

Schedule K: Format of Bank Guarantee for Performance Security.

Schedule L: Appointment of Project Management Consultant

Schedule M: Format of Bank Guarantee for Advance Payment

Schedule N: Change of Scope Formats

Schedule O: Work Order Format for Additional Works

CHAPTER 2: SURVEYS AND INVESTIGATIONS

2.1 Introduction

This chapter deals with various surveys and Investigations carried out as per the Terms of Reference and required for quality compliance of the Project design and report preparation.

Major surveys and Investigations carried out are as follows:

- Road Inventory
- Pavement condition survey
- Structural Inventory
- Traffic surveys
- Topographic surveys
- FWD Survey

2.2 Road Inventory and Condition Surveys

2.2.1 Road Inventory

Road Inventory surveys have been conducted. Surveys are carried out as per the standard methodology / IRC guidelines. However brief methodology is given below:

As per the ToR consultants have to propose improvement proposals for the existing roads along the project corridors. Hence, the road and bridge inventory and condition surveys were conducted accordingly.

The road inventory survey involves making visual estimates and actual measurements of geometric and cross-sectional elements of the road and its deficiencies. This survey involves the collection of the data pertaining to the existing road such as the pavement type, width of the carriageway, type of the shoulder and its width, condition of road, type and condition of drain, footpath, median islands, number of CD structures, available land widths etc. Road inventory has been recorded in a standard format.

The team has travelled and walked along the alignments and adjacent roads collected first-hand information on the width and type of carriage way, type and condition of road, junctions, traffic intensity, width of footpath cum drains, Median islands, cross drainage structures, Bus stops/Bus bays/Bus shelters and relevant details of Grade separators, Metro Rail crossings and skywalks comprising in the project corridor are noted.

2.2.2 Right of Way

The Right of way details for the project road is taken by measuring drain to drain or footpath outer edge at regular intervals, RoW vary from 12m to 60 m. Details of RoW is shown in below table

Table 2.1: Table showing details of RoW along for HDC-03 Old Airport Road

| From in Kms | To in Kms | Length in m | ROW in m |
|-------------|-----------|-------------|----------|
| 0+000 | 0+310 | 310 | 22 |
| 0+310 | 0+390 | 80 | 18 |
| 0+390 | 0+810 | 420 | 22 |
| 0+810 | 0+880 | 70 | 18 |
| 0+880 | 1+450 | 570 | 21 |
| 1+450 | 1+880 | 430 | 27 |
| 1+880 | 3+420 | 1540 | 23 |
| 3+420 | 3+850 | 430 | 26 |
| 3+850 | 4+220 | 370 | 21 |
| 4+220 | 4+400 | 180 | 24 |
| 4+400 | 4+670 | 270 | 27 |
| 4+670 | 4+930 | 260 | 33 |
| 4+930 | 5+220 | 290 | 26 |
| 5+220 | 5+980 | 760 | 23 |
| 5+980 | 6+500 | 520 | 20 |
| 6+500 | 6+920 | 420 | 24 |
| 6+920 | 7+860 | 940 | 28 |
| 7+860 | 8+290 | 430 | 31 |
| 8+290 | 9+230 | 940 | 22 |
| 9+230 | 9+420 | 190 | 29 |
| 9+420 | 10+130 | 710 | 24 |
| 10+130 | 10+230 | 100 | 28 |
| 10+230 | 10+960 | 730 | 25 |
| 10+960 | 12+500 | 1540 | 22 |
| 12+500 | 13+000 | 500 | 19 |
| 13+000 | 13+980 | 980 | 25 |
| 13+980 | 14+180 | 200 | 21 |
| 14+180 | 14+360 | 180 | 26 |
| 14+360 | 15+100 | 740 | 22 |
| 15+100 | 15+740 | 640 | 27 |
| 15+740 | 16+280 | 540 | 23 |
| 16+280 | 16+630 | 350 | 21 |
| 16+630 | 17+000 | 370 | 24 |
| 17+000 | 17+150 | 150 | 20 |

Table 2.2: Table showing details of RoW along for HDC-04 Sarjapur Road

| From in Kms | To in Kms | Length in m | ROW in m |
|-------------|-----------|-------------|----------|
| 3+000 | 3+120 | 120.00 | 31 |
| 3+120 | 3+220 | 100.00 | 27 |
| 3+220 | 3+270 | 50.00 | 31 |
| 3+270 | 3+520 | 250.00 | 27 |
| 3+520 | 3+620 | 100.00 | 27 |
| 3+620 | 3+870 | 250.00 | 26 |
| 3+870 | 3+950 | 80.00 | 26 |
| 3+950 | 4+100 | 150.00 | 26 |

Table 2.3: Table showing details of RoW along for HDC-Outer Ring Road KR Puram to Silk Board



| From in Kms | To in Kms | Length in m | ROW in m |
|-------------|-----------|-------------|----------|
| 0+000 | 1+730 | 1730.00 | 26 |
| 1+730 | 3+440 | 1710.00 | 24 |
| 3+440 | 4+410 | 970.00 | 28 |
| 4+410 | 4+630 | 220.00 | 35 |
| 4+630 | 7+530 | 2900.00 | 26 |
| 7+530 | 8+850 | 1320.00 | 26 |
| 8+850 | 8+930 | 80.00 | 34 |
| 8+930 | 12+770 | 3840.00 | 28 |
| 12+770 | 16+500 | 3730.00 | 24 |

2.2.3 Land use

The largest proportion of land abutting the project corridors are Commercial followed by Residential.

2.2.4 Carriageway and Median

Measurements were taken at locations where the cross-section changes w.r.t Types and widths of Main Carriageway, Service Roads, Footpath, Median, and Drains from beginning to end of the project roads. Along with carriageway measurements and median as a part of inventory survey. The carriageway varies from Three lane divided carriageway to six lane divided carriageway. The pattern of existing carriageway for four lane and six lanes, shoulder and median is given in Table 2.4 to Table 2.6.



2.2.6 Footpath

At some locations drain cum footpath is provided where land availability is limited where sufficient land is available footpaths are provided separately. Details are shown in below table.

Table 2.11: Table showing details of footpath for HDC-03 Old Airport Road

| From in Kms | To in Kms | Length in m | Footpath | | | |
|----------------|--------------|----------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | RHS | |
| | | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 0+000 | 0+250 | 250 | Paved | 2.2 | Paved | 1.5 |
| 0+250 | 0+310 | 60 | Paved | 2.2 | Paved | 0.6 |
| 0+310 | 0+350 | 40 | Paved | 1.1 | Paved | 0.6 |
| 0+350 | 0+390 | 40 | Paved | 1.1 | Paved | 0.5 |
| 0+390 | 0+460 | 70 | Paved | 2.8 | Paved | 0.5 |
| 0+460 | 0+650 | 190 | Paved | 1.4 | Paved | 0.5 |

| From in Kms | To in Kms | Length in m | Footpath | | | |
|----------------|--------------|----------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | RHS | |
| | | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 0+000 | 0+250 | 250 | Paved | 2.2 | Paved | 1.5 |
| 0+250 | 0+310 | 60 | Paved | 2.2 | Paved | 0.6 |
| 0+310 | 0+350 | 40 | Paved | 1.1 | Paved | 0.6 |
| 0+350 | 0+390 | 40 | Paved | 1.1 | Paved | 0.5 |
| 0+390 | 0+460 | 70 | Paved | 2.8 | Paved | 0.5 |
| 0+460 | 0+650 | 190 | Paved | 1.4 | Paved | 0.5 |
| 0+650 | 0+660 | 10 | Paved | 1.4 | Paved | 3.0 |
| 0+660 | 0+730 | 70 | Paved | 1.9 | Paved | 3.0 |
| 0+730 | 0+810 | 80 | Paved | 3 | Paved | 3.0 |
| 0+810 | 0+820 | 10 | Paved | 0.4 | Paved | 3.0 |
| 0+820 | 0+880 | 60 | Paved | 0.4 | Paved | 1.5 |
| 0+880 | 0+950 | 70 | Paved | 3.2 | Paved | 1.5 |
| 0+950 | 1+190 | 240 | Paved | 3.2 | Paved | 1.6 |
| 1+190 | 1+240 | 50 | Paved | 2.2 | Paved | 1.6 |
| 1+240 | 1+290 | 50 | Paved | 0.7 | Paved | 1.6 |
| 1+290 | 1+300 | 10 | Paved | 2.8 | Paved | 1.6 |
| 1+300 | 1+450 | 150 | Paved | 2.8 | Paved | 0.9 |
| 1+450 | 1+520 | 70 | Paved | 2.8 | Paved | 2.0 |
| 1+520 | 1+690 | 170 | Paved | 4.3 | Paved | 2.0 |
| 1+690 | 1+750 | 60 | Paved | 2.1 | Paved | 2.0 |
| 1+750 | 1+880 | 130 | Paved | 2.1 | Paved | 0.6 |
| 1+880 | 1+900 | 20 | Paved | 2.7 | Paved | 0.6 |
| 1+900 | 2+050 | 150 | Paved | 2.7 | Paved | 2.3 |
| 2+050 | 2+090 | 40 | Paved | 2.7 | Paved | 2.4 |
| 2+090 | 2+350 | 260 | Paved | 3.2 | Paved | 2.4 |
| 2+350 | 2+390 | 40 | Paved | 3.2 | Paved | 1.9 |
| 2+390 | 2+500 | 110 | Paved | 3.0 | Paved | 1.9 |
| 2+500 | 2+630 | 130 | Paved | 3.0 | Paved | 1.4 |
| 2+630 | 2+680 | 50 | Paved | 1.4 | Paved | 1.4 |
| 2+680 | 2+800 | 120 | Paved | 1.4 | Paved | |
| 2+800 | 2+900 | 100 | Paved | 1.6 | Paved | |
| 2+900 | 2+970 | 70 | Paved | 1.6 | Paved | 2.0 |
| 2+970 | 3+150 | 180 | Paved | 1.8 | Paved | 2.0 |

| From in Kms | To in Kms | Length in m | Footpath | | | |
|----------------|--------------|----------------|-------------------------|-------|-------------------------|-----------|
| | | | LHS | | RHS | |
| | | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 3+150 | 3+230 | 80 | Paved | 1.8 | Paved | 2.7 |
| 3+230 | 3+420 | 190 | Paved | 2.9 | Paved | 2.7 |
| 3+420 | 3+450 | 30 | Paved | 2.9 | Paved | 3.5 |
| 3+450 | 3+550 | 100 | Paved | 1.4 | Paved | 3.5 |
| 3+550 | 3+600 | 50 | Paved | 2.7 | Paved | 3.5 |
| 3+600 | 3+740 | 140 | Paved | 1.3 | Paved | 3.5 |
| 3+740 | 3+850 | 110 | Paved | 1.3 | Paved | 3.5 |
| 3+850 | 3+970 | 120 | | | Paved | 3.5 |
| 3+970 | 4+190 | 220 | | | | |
| 4+190 | 4+220 | 30 | | | Paved | 0.7 |
| 4+220 | 4+280 | 60 | Paved | 0.6 | Paved | 0.7 |
| 4+280 | 4+320 | 40 | Paved | 0.6 | Paved | 2.5 |
| 4+320 | 4+400 | 80 | Paved | 0.6 | Paved | 2.5 |
| 4+400 | 4+500 | 100 | Paved | 0.6 | Paved | 6.1 - 1.5 |
| 4+500 | 4+550 | 50 | Paved | 1.5 | Paved | 6.1 - 1.5 |
| 4+550 | 4+650 | 100 | Paved | 1.5 | Paved | 1.4 |
| 4+650 | 4+670 | 20 | Paved | 1.5 | Paved | 1.9 |
| 4+670 | 4+800 | 130 | Paved | 4.1 | Paved | 1.9 |
| 4+800 | 4+880 | 80 | Paved | 4.1 | Paved | 2.2 |
| 4+880 | 4+930 | 50 | Paved | 3.3 | Paved | 2.2 |
| 4+930 | 5+050 | 120 | Paved | 3.3 | Paved | 2.3 |
| 5+050 | 5+100 | 50 | Paved | 2.2 | Paved | 2.3 |
| 5+100 | 5+200 | 100 | Paved | 2.2 | Paved | 2.2 |
| 5+200 | 5+220 | 20 | Paved | 2.2 | Paved | 2.3 |
| 5+220 | 5+600 | 380 | Paved | 1.9 | Paved | 2.3 |
| 5+600 | 5+650 | 50 | Paved | 3.1 | Paved | 2.8 |
| 5+650 | 5+690 | 40 | Paved | 3.1 | Paved | 3.0 |
| 5+690 | 5+810 | 120 | Paved | 3.2 | Paved | 3.0 |
| 5+810 | 5+850 | 40 | Paved | 3.2 | Paved | 3.1 |
| 5+850 | 5+980 | 130 | Paved | 3.1 | Paved | 3.1 |
| 5+980 | 6+060 | 80 | Paved | 3.1 | Paved | 1.5 |
| 6+060 | 6+230 | 170 | Paved | 1.8 | Paved | 1.5 |
| 6+230 | 6+440 | 210 | Paved | 1.8 | Paved | 1.5 |

| From in Kms | To in Kms | Length in m | Footpath | | | |
|----------------|--------------|----------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | RHS | |
| | | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 6+440 | 6+500 | 60 | Paved | 2.2 | Paved | 1.5 |
| 6+500 | 6+530 | 30 | Paved | 2.2 | Paved | 2.2 |
| 6+530 | 6+550 | 20 | Paved | 2.0 | Paved | 2.2 |
| 6+550 | 6+920 | 370 | Paved | 2.0 | Paved | 2.2 |
| 6+920 | 7+000 | 80 | Paved | 2.0 | Paved | 3.0 |
| 7+000 | 7+100 | 100 | | | Paved | 3.0 |
| 7+100 | 7+200 | 100 | Paved | 3.2 | Paved | 3.0 |
| 7+200 | 7+300 | 100 | Paved | 3.2 | Paved | 2.2 |
| 7+300 | 7+360 | 60 | Paved | 2.9 | Paved | 2.2 |
| 7+360 | 7+480 | 120 | Paved | 2.9 | Paved | 2.5 |
| 7+480 | 7+780 | 300 | Paved | 3.0 | Paved | 2.5 |
| 7+780 | 7+860 | 80 | Paved | 3.0 | Paved | 1.8 |
| 7+860 | 7+980 | 120 | Paved | 2.8 | Paved | 1.8 |
| 7+980 | 8+050 | 70 | Paved | 2.8 | Paved | 1.7 |
| 8+050 | 8+130 | 80 | Paved | 3.6 | Paved | 1.7 |
| 8+130 | 8+250 | 120 | Paved | 3.6 | Paved | 1 |
| 8+250 | 8+290 | 40 | | | Paved | 1.5 |
| 8+290 | 8+490 | 200 | | | Paved | 1.5 |
| 8+490 | 8+520 | 30 | | | Paved | 1.1 |
| 8+520 | 8+650 | 130 | | | Paved | 1.1 |
| 8+650 | 8+700 | 50 | | | Paved | 0.5 |
| 8+700 | 8+860 | 160 | | | Paved | 0.5 |
| 8+860 | 8+970 | 110 | | | Paved | 1.0 |
| 8+970 | 9+000 | 30 | | | Paved | 1.0 |
| 9+000 | 9+040 | 40 | | | Paved | 1.0 |
| 9+040 | 9+210 | 170 | | | | |
| 9+210 | 9+230 | 20 | Paved | 2.5 | | |
| 9+230 | 9+400 | 170 | Paved | 2.5 | | |
| 9+400 | 9+420 | 20 | Paved | 3.5 | | |
| 9+420 | 9+510 | 90 | UP Paved | 1.0 | | |
| 9+510 | 9+520 | 10 | UP Paved | 1.0 | | |
| 9+520 | 10+110 | 590 | UP Paved | 1.0 | | |
| 10+110 | 10+130 | 20 | | | | |

| From in Kms | To in Kms | Length in m | Footpath | | | |
|----------------|--------------|----------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | RHS | |
| | | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 10+130 | 10+200 | 70 | Paved | 3.0 | | |
| 10+200 | 10+230 | 30 | Paved | 3.0 | Paved | 2.3 |
| 10+230 | 10+370 | 140 | | | Paved | 2.3 |
| 10+370 | 10+480 | 110 | Paved | 1.8 | Paved | 2.3 |
| 10+480 | 10+550 | 70 | Paved | 1.8 | | |
| 10+550 | 10+620 | 70 | Paved | 1.2 | | |
| 10+620 | 10+960 | 340 | Paved | 1.2 | Paved | 1.8 |
| 10+960 | 11+030 | 70 | | | Paved | 1.8 |
| 11+030 | 11+130 | 100 | Paved | 1.7 | Paved | 1.8 |
| 11+130 | 11+250 | 120 | Paved | 1.7 | | |
| 11+250 | 11+400 | 150 | Paved | 3.2 | | |
| 11+400 | 11+560 | 160 | Paved | 2.9 | | |
| 11+560 | 11+800 | 240 | Paved | 1.6 | | |
| 11+800 | 11+880 | 80 | Paved | 1.9 | Paved | 1.8 |
| 11+880 | 12+390 | 510 | Paved | 1.9 | Paved | 1.8 |
| 12+390 | 12+500 | 110 | Paved | 1.9 | Paved | 1.8 |
| 12+500 | 12+600 | 100 | | | Paved | 1.8 |
| 12+600 | 12+780 | 180 | | | Paved | 2 |
| 12+780 | 13+000 | 220 | Paved | 0.9 | Paved | 2 |
| 13+000 | 13+100 | 100 | Paved | 2.3 | Paved | 3.4 |
| 13+100 | 13+380 | 280 | Paved | 2.3 | Paved | 2.4 |
| 13+380 | 13+810 | 430 | Paved | 2.3 | Paved | 1.6 |
| 13+810 | 13+820 | 10 | Paved | 4.1 | Paved | 1.6 |
| 13+820 | 13+980 | 160 | Paved | 4.1 | Paved | 1.8 |
| 13+980 | 13+990 | 10 | Paved | 2 | Paved | 1.8 |
| 13+990 | 14+140 | 150 | Paved | 2 | Paved | 0.5 |
| 14+140 | 14+180 | 40 | Paved | 2 | | |
| 14+180 | 14+200 | 20 | Paved | 1.2 | | |
| 14+200 | 14+250 | 50 | Paved | 1.2 | Paved | 2.6 |
| 14+250 | 14+350 | 100 | Paved | 2.4 | Paved | 2.6 |
| 14+350 | 14+360 | 10 | Paved | 2.4 | Paved | 1.6 |
| 14+360 | 14+450 | 90 | Paved | 3.1 | Paved | 1.6 |
| 14+450 | 14+680 | 230 | Paved | 3.1 | Paved | 1.6 |

| From in Kms | To in Kms | Length in m | Footpath | | | |
|----------------|--------------|----------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | RHS | |
| | | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 14+680 | 14+730 | 50 | Paved | 3.1 | Paved | 2.0 |
| 14+730 | 14+750 | 20 | Paved | 2.0 | Paved | 2.0 |
| 14+750 | 14+850 | 100 | Paved | 2.0 | Paved | 3.4 |
| 14+850 | 15+030 | 180 | Paved | 2.0 | | |
| 15+030 | 15+050 | 20 | | | | |
| 15+050 | 15+100 | 50 | Paved | 1.8 | | |
| 15+100 | 15+280 | 180 | Paved | 1.8 | Paved | 5.4 |
| 15+280 | 15+350 | 70 | Paved | 2.9 | Paved | 3.2 |
| 15+350 | 15+550 | 200 | Paved | 2.9 | Paved | 3.2 |
| 15+550 | 15+670 | 120 | Paved | 2.9 | Paved | 3.2 |
| 15+670 | 15+740 | 70 | Paved | 2.1 | Paved | 3.2 |
| 15+740 | 15+800 | 60 | | | Paved | 3.2 |
| 15+800 | 15+840 | 40 | | | Paved | 4.1 |
| 15+840 | 15+870 | 30 | | | Paved | 4.4 |
| 15+870 | 15+990 | 120 | Paved | 2.3 | Paved | 4.4 |
| 15+990 | 16+100 | 110 | Paved | 2.4 | Paved | 4.4 |
| 16+100 | 16+280 | 180 | | | Paved | 3.3 |
| 16+280 | 16+370 | 90 | | | Paved | 2.5 |
| 16+370 | 16+450 | 80 | Paved | 4.0 | Paved | 2.5 |
| 16+450 | 16+480 | 30 | | | Paved | 2.5 |
| 16+480 | 16+630 | 150 | | | Paved | 2.5 |
| 16+630 | 16+750 | 120 | Paved | 2.7 | Paved | 2.5 |
| 16+750 | 16+860 | 110 | Paved | 2.7 | Paved | 2.3 |
| 16+860 | 17+000 | 140 | Paved | 0.8 | Paved | 2.3 |
| 17+000 | 17+080 | 80 | Paved | 0.8 | Paved | 1.8 |
| 17+080 | 17+110 | 30 | Paved | 1.0 | Paved | 1.8 |
| 17+110 | 17+150 | 40 | Paved | 1.0 | Paved | 3.5 |

Table 2.12: Table showing details of footpath for HDC-04 Sarjapur Road

| From in Kms | To in Kms | Length in m | Footpath | | | |
|----------------|--------------|----------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | RHS | |
| | | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 3+000 | 3+120 | 120 | Un Paved | 2 | Paved | 1.8 |

| From in Kms | To in Kms | Length in m | Footpath | | | |
|----------------|--------------|----------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | RHS | |
| | | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 3+120 | 3+220 | 100 | | | Paved | 1.3 |
| 3+220 | 3+270 | 50 | | | Paved | 1.5 |
| 3+270 | 3+520 | 250 | | | Paved | 1.2 |
| 3+520 | 3+620 | 100 | | | Paved | 1.5 |
| 3+620 | 3+870 | 250 | | | | |
| 3+870 | 3+950 | 80 | | | | |
| 3+950 | 4+100 | 150 | | | | |

Table 2.13: Table showing details of footpath for HDC-12c Outer Ring Road

| Chainage, km | | Length, m | Footpath | | | |
|--------------|-------|--------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | LHS | |
| From | To | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 0+000 | 0+240 | 240 | Paved | 1.00 | Paved | 2.00 |
| 0+240 | 0+530 | 290 | Paved | 1.00 | Paved | 1.00 |
| 0+530 | 1+330 | 800 | Paved | 0.80 | Paved | 1.00 |
| 1+130 | 1+230 | 100 | Paved | 0.80 | | |
| 1+230 | 1+730 | 500 | | | | |
| 1+730 | 1+830 | 100 | Paved | 1.00 | | |
| 1+830 | 2+530 | 700 | | | Paved | 1.20 |
| 2+530 | 2+630 | 100 | | | | |
| 2+630 | 3+340 | 710 | Paved | 1.00 | | |
| 3+340 | 3+440 | 100 | Paved | 1.20 | | |
| 3+440 | 3+530 | 90 | Paved | 3.40 | Unpaved | 1.20 |
| 3+530 | 3+800 | 270 | Paved | 1.20 | Unpaved | 1.20 |
| 3+800 | 4+320 | 520 | Paved | 1.20 | Paved | 1.00 |
| 4+320 | 4+410 | 90 | | | Paved | 1.00 |
| 4+410 | 4+450 | 40 | | | Paved | 1.20 |
| 4+450 | 4+630 | 180 | Paved | 1.20 | Paved | 1.20 |
| 4+630 | 5+350 | 720 | | | Paved | 1.20 |
| 5+350 | 5+980 | 630 | | | | |
| 5+980 | 6+120 | 140 | | | Paved | 1.00 |
| 6+120 | 6+400 | 280 | | | Paved | 1.00 |
| 6+400 | 6+910 | 510 | | | Paved | 1.00 |
| 6+910 | 6+960 | 50 | | | Paved | 1.00 |
| 6+960 | 7+530 | 570 | | | | |
| 7+530 | 7+620 | 90 | | | | |
| 7+620 | 7+860 | 240 | | | | |
| 7+860 | 8+000 | 140 | | | Paved | 1.00 |
| 8+000 | 8+170 | 170 | Paved | 0.50 | Paved | 1.00 |
| 8+170 | 8+230 | 60 | Paved | 1.00 | Paved | 1.00 |
| 8+230 | 8+850 | 620 | Paved | 1.20 | Paved | 1.00 |
| 8+850 | 8+880 | 30 | Paved | 1.20 | Paved | 1.00 |

| Chainage, km | | Length, m | Footpath | | | |
|--------------|--------|--------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | LHS | |
| From | To | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 8+880 | 8+910 | 30 | Paved | 1.20 | | |
| 8+910 | 8+930 | 20 | | | | |
| 8+930 | 9+010 | 80 | | | | |
| 9+010 | 9+640 | 630 | | | | |
| 9+640 | 9+920 | 280 | Paved | 3.00 | | |
| 9+920 | 10+600 | 680 | | | | |
| 10+600 | 10+660 | 60 | | | Paved | 1.50 |
| 10+660 | 11+350 | 690 | Paved | 1.00 | Paved | 1.20 |
| 11+350 | 11+450 | 100 | Paved | 1.00 | Paved | 1.00 |
| 11+450 | 11+800 | 350 | | | Paved | 1.20 |
| 11+800 | 11+960 | 160 | | | | |
| 11+960 | 12+770 | 810 | Paved | 2.00 | Paved | 2.00 |
| 12+770 | 12+850 | 80 | Paved | 2.00 | | |
| 12+850 | 12+900 | 50 | | | | |
| 12+900 | 13+630 | 730 | | | | |
| 13+630 | 13+680 | 50 | | | | |
| 13+680 | 14+620 | 940 | Paved | 2.00 | | |
| 14+620 | 14+740 | 120 | | | | |
| 14+740 | 15+310 | 570 | | | | |
| 15+310 | 15+360 | 50 | | | | |
| 15+360 | 16+000 | 640 | Paved | 1.50 | Paved | 1.20 |
| 16+000 | 16+500 | 500 | Paved | 2.00 | | |

2.3 Road Junctions


Significant transport benefits, across all modes, can be achieved through junction improvement and management. These improvements will aid free flow of Traffic to and from cross roads, thereby reducing travel time of through traffic. Total number of Major and minor junctions identified during inventory study are presented in the Table 2.4 and the detailed drawings for the junction improvements have been presented in Drawing Volume.

Table 2.14: Table showing details of Major Junctions

| Sl. No | Existing chainage | Type of Junction | Location |
|-------------------------|-------------------|------------------|--|
| HDC-03 Old Airport Road | | | |
| 1 | 0+150 | T | ASC Junction |
| 2 | 0+520 | Y | Cambridge Road Jn |
| 3 | 2+370 | + | Junction with 7 th cross road and Prof U R Road |
| 4 | 2+560 | + | Junction with 100 feet Road |
| 5 | 5+260 | T | HAL Circle |
| 6 | 6+810 | T | HAL Junction |

| Sl. No | Existing chainage | Type of Junction | Location |
|--|-------------------|------------------|-------------------------------------|
| 7 | 8+110 | T | Doddanekundi Road Jn |
| 8 | 9+150 | + | Ring Road Junction |
| 9 | 10+640 | + | Kundalahalli Gate Jn |
| 10 | 12+390 | + | Pattandur Agrahara Main Road Jn |
| 11 | 15+260 | T | Borewell Road Jn |
| 12 | 15+540 | T | Immadihalli Main Road Jn |
| 13 | 15+750 | T | - |
| HDC-04 Sarjapur Road | | | |
| 14 | 0+660 | + | 100 Feet Road Junction |
| 15 | 1+370 | T | 11 th Main Road Junction |
| 16 | 1+580 | T | Madiwala Road Jn |
| 17 | 2+120 | T | 80 feet Road Jn |
| 18 | 2+850 | T | 100 Feet Road Indiranagar |
| 19 | 4+180 | T | 14 th Main Road Junction |
| 20 | 5+680 | T | Iblur Junction |
| 21 | 6+110 | T | Haralur main Road Jn |
| 22 | 7+250 | + | - |
| 23 | 9+350 | + | Doddakanelli Road Jn |
| HDC 12 c Outer Ring Road KR Puram to Silk Board | | | |
| 24 | 1+700 | T | MahadevpuraJn |
| 25 | 2+750 | T | - |
| 26 | 3+400 | Staggered | Doddanekundi Maiin Road Jn |
| 27 | 3+550 | Y | - |
| 28 | 5+000 | Y | -Chinnapanahalli Main Road Jn |
| 29 | 6+350 | Staggered | |
| 30 | 7+500 | + | |
| 31 | 7+700 | + | |
| 32 | 8+050 | T | |
| 33 | 8+250 | Staggered | |
| 34 | 9+000 | + | |
| 35 | 11+050 | + | |
| 36 | 13+750 | Staggered | |
| 37 | 16+500 | Y | |

From the inventory, it is found that there are 145 minor junctions in Old airport road, 156 minor junctions in Sarajapura road and 39 minor junctions in K R Puram to Silk Board road.



2.4 Bus Shelters / Bus Bays / Bus Stop

There are 64 number of Bus stops are in provided in project corridors, all bus stops are provided with Bus shelters. At some locations Bus bays are provided, details are shown in below table.:

Table 2.15: Table showing Bus Bays / Bus Stops

| Sl. No | Chainage | Side | | Remarks |
|---------------------------|----------|------|-----|------------------------|
| | | LHS | RHS | |
| HDC 03 – Old Airport road | | | | |
| 1 | 0+880 | Yes | - | - |
| 2 | 9+400 | Yes | - | - |
| 3 | 11+000 | Yes | - | Kundanahalli Busstop |
| 4 | 11+396 | - | | Yes |
| 5 | 11+530 | Yes | - | Thubaranahalli Busstop |
| 6 | 12+510 | - | | Yes |
| 7 | 13+350 | - | | Yes |
| 8 | 13+550 | Yes | | - |
| 9 | 14+050 | - | | Yes |
| 10 | 14+360 | Yes | | - |
| 11 | 15+030 | Yes | | - |
| 12 | 15+050 | Yes | | - |
| 13 | 15+100 | - | | Yes |
| 14 | 15+740 | Yes | | - |
| 15 | 15+780 | - | | Yes |
| 16 | 15+870 | Yes | | - |
| 17 | 16+110 | Yes | | - |
| 18 | 16+280 | - | | Yes |
| 19 | 16+450 | Yes | | - |
| HDC 04 – Sarjapur Road | | | | |
| 20 | 0+050 | Both | | St Johns hospital |

| Sl. No | Chainage | Side | | Remarks |
|--|----------|------|-------------------|---------------------------|
| | | LHS | RHS | |
| 21 | 0+640 | | Both | Koramangal water tank |
| 22 | 1+100 | | Both | CPWD quarters |
| 23 | 1+650 | Yes | Kripanidi college | Kadirayanapalya Junction |
| 24 | 1+800 | | Both | John Fowler |
| 25 | 2+150 | | Both | Koramangala |
| 26 | 2+630 | | Both | Jakkasandra |
| 27 | 2+880 | Yes | Bhagini | - |
| 28 | 3+950 | Yes | Agara | - |
| 29 | 5+730 | Yes | Jn of sarjapura | - |
| 30 | 6+180 | | Both | Bellandur gate |
| 31 | 7+250 | | Both | Kaikondrahalli stop |
| 32 | 8+070 | Yes | Junnasandra gate | K R Puram Railway Station |
| 33 | 9+340 | | Both | Doddakannahalli |
| 34 | 10+350 | | Both | Carmelram Gate |
| HDC 12 c Part-2 Outer Ring Road | | | | |
| 35 | 2+650 | - | Yes | Silk board |
| 36 | 3+240 | - | Yes | HSR apartment |
| 37 | 4+160 | Yes | - | HSR 14th main |
| 38 | 4+180 | - | Yes | HSR 14th main |
| 39 | 4+900 | - | Yes | Hsr mantri |
| 40 | 5+920 | Yes | - | Agara |
| 41 | 7+210 | - | Yes | Iblur |
| 42 | 7+270 | - | Yes | Iblur |
| 43 | 7+330 | Yes | - | Iblur |
| 44 | 8+230 | Yes | - | Bellandur petrol bunk |
| 45 | 8+875 | - | Yes | Bellandur |
| 46 | 9+310 | Yes | - | Eco space |
| 47 | 9+475 | - | Yes | Eco space |
| 48 | 9+888 | - | Yes | Devarabeesanahalli |
| 49 | 10+150 | Yes | - | Devarabeesanahalli |
| 50 | 10+780 | Yes | - | New horizon college |
| 51 | 10+860 | - | Yes | New horizon college |
| 52 | 11+450 | Yes | - | Kadubeesanahalli |
| 53 | 11+795 | - | Yes | Kadubeesanahalli |
| 54 | 11+830 | Yes | - | JP morgon |
| 55 | 12+930 | Yes | - | Innovative multiplex |
| 56 | 13+030 | - | Yes | Innovative multiplex |
| 57 | 13+910 | Yes | - | Kalamandir |
| 58 | 14+850 | - | Yes | Karthik nagar |

| Sl. No | Chainage | Side | | Remarks |
|--------|----------|------|-----|----------------|
| | | LHS | RHS | |
| 59 | 16+195 | - | Yes | Doddnekudi |
| 60 | 17+780 | Yes | - | Mahadevpura |
| 61 | 18+485 | Yes | - | B Narayanapura |



2.5 Pavement Condition Survey

The survey regarding road inventory and pavement condition was carried out along the project corridor. The width of the carriageway along the project road varies from 4 lane divided carriage way to six lane divided carriageway. Visual inspection of the road showed a generally Fair surface condition.

The condition of the pavement has been evaluated based on the field measurements of primary pavement surface distress of cracking (narrow and wide), patching, raveling and potholes, noted for each kilometer length. The extent of each distress has been visually estimated for every kilometer length of the road in terms of percentage area affected and then averaged for one-kilometer road length.

The distress conditions are measured under the following sub-heads:

- Cracking (%)
- Potholes (%)

- Raveling (%)
- Patching (%)
- Settlement & Upheaval (%)

2.4.1 Cracks

Pavement cracking is a typical failure commonly observed in flexible / bituminous pavements occurring predominantly due to the higher number of repetitions of heavier axle loads. Pavement Cracks (%) details along the existing project corridor are in **Annexure 2.2**. The average values of minimum, maximum and average percentage of cracks in the project roads are 2.5%, 5.50%, 3.58% respectively for Old Airport road, 3.25%, 5.50%, 3.94% for Old Sarjapur Road and 1.5%, 4.5%, 2.73% for Outer ring Road.

2.4.2 Patching

The variation of Pavement Patching (%) with length is shown in Figure 2.2. Pavement patching (%) details along project corridor is in **Annexure 2.1**. No significant patching is noticed except at few localized spots. The average values of minimum, maximum and average percentage of patching area in the project roads are 1.5%, 8.5 %, 3.76 % respectively for Old Airport Road, 2.20%, 7.25%, 4.18% for Sarjapur Road, and 1.05%, 4.5%, 2.27% for Outer Ring Road.

2.4.3 Ravelling

Disintegration of the pavement surface caused due to failure of binder to hold the material together causing blowing off of fine aggregates leaving behind pock marks and when larger particles are broken free with stripping of aggregates is termed as Raveling. Pavement raveling (%) details along the project corridor is in **Annexure 2.1**. The average values of minimum, maximum and average percentage of raveling in the project roads are 3.15%, 7.60%, 4.46% for Old Airport Road, 3.50%, 8.50%, 6.00% for Sarjapur Road and 6.65% and 4.16% for Outer Ring Road.

2.4.4 Potholes

Potholes are bowl-shaped holes of varying sizes in the surface layer extending into the base course. Potholes are mainly formed due of loose base course or base course not covered properly with wearing course or due to inadequate bonding between base course and subsequent top layers. Pavement Potholes (%) details along the project corridor are in **Annexure 2.1**. The average values of minimum, maximum and average percentage of potholes in the project roads are 1.5%, 7.0%, 4.06% for Old Airport Road, 0.65%, 2.60%,

1.90% for Sarjapur Road (Link-1 and 1.75%, 3.5%, 2.52% for Outer Ring Road.

2.4.5 Rutting

Rutting is a surface depression in the wheel path. Pavement uplift (shearing) may occur along the sides of the rut. Ruts are particularly evident after a rain when they are filled with water. There are two basic types of rutting: mix rutting and subgrade rutting. Mix rutting occurs when the subgrade does not rut yet the pavement surface exhibits wheel path depressions as a result of compaction/mix design problems. Subgrade rutting occurs when the subgrade exhibits wheel path depressions due to loading. In this case, the pavement settles into the subgrade ruts causing surface depressions in the wheel path. Pavement Rutting (%) details along the project corridor are in Annexure2. 1. The average values of minimum, maximum and average percentage of potholes in the project roads are 0%, 0.10%, 0.02% for Old Airport Road, 0%, 0.09%, 0.2% for Sarjapur Road and 0%, 0.2%, 0.3% for Outer Ring Road.

2.4.6 Summary of Observations on Pavement Condition

The overall condition of the pavement is in fair to Good condition with around 85.97 % of the pavement area in fair condition for Bellary Road, 84.39% of the pavement area in fair condition for Old Madaras Road and 74.15% of pavement area in fair condition for Outer Ring Road the percentage various of distresses for each road is shown below.




Figure 2.1:- Summary of existing Pavement condition of HDC 03 Old Airport Road




Figure 2.2:- Summary of existing Pavement condition of HDC 04 Sarjapur Road




Figure 2.3:- Summary of existing Pavement condition of HDC 12c Outer Ring Road

2.6 Camber

Carriageway camber is checked at intervals to assess the camber at site, the camber is very important for effective drainage of rain water. The standard camber is 2.5% on our roads, but quite often the camber reduces or becomes non uniform during the course of life of road in urban roads due to distress, frequent overlays. Following table represents

1.90% for Sarjapur Road (Link-1 and 1.75%, 3.5%, 2.52% for Outer Ring Road.

2.4.5 Rutting

Rutting is a surface depression in the wheel path. Pavement uplift (shearing) may occur along the sides of the rut. Ruts are particularly evident after a rain when they are filled with water. There are two basic types of rutting: mix rutting and subgrade rutting. Mix rutting occurs when the subgrade does not rut yet the pavement surface exhibits wheel path depressions as a result of compaction/mix design problems. Subgrade rutting occurs when the subgrade exhibits wheel path depressions due to loading. In this case, the pavement settles into the subgrade ruts causing surface depressions in the wheel path. Pavement Rutting (%) details along the project corridor are in Annexure 2. 1. The average values of minimum, maximum and average percentage of potholes in the project roads are 0%, 0.10%, 0.02% for Old Airport Road, 0%, 0.09%, 0.2% for Sarjapur Road and 0%, 0.2%, 0.3% for Outer Ring Road.

2.4.6 Summary of Observations on Pavement Condition

The overall condition of the pavement is in fair to Good condition with around 85.97 % of the pavement area in fair condition for Bellary Road, 84.39% of the pavement area in fair condition for Old Madaras Road and 74.15% of pavement area in fair condition for Outer Ring Road the percentage various of distresses for each road is shown below.




Figure 2.1:- Summary of existing Pavement condition of HDC 03 Old Airport Road

the camber on the existing roads

Table 2.16: Table showing Camber with Intervals

| Sl. No | Chainage, m | Camber, % | |
|---------------------------|----------------|-----------|-------|
| | | LHS | RHS |
| HDC 01 – Old Airport Road | | | |
| 1 | 500 | -3.04% | 1.29% |
| 2 | 1000 | -3.04% | 1.46% |
| 3 | 1500 | -2.78% | 0.59% |
| 4 | 2000 | -2.45% | 1.42% |
| 5 | 2500 | -3.29% | 2.84% |
| 6 | 3000 | 3.14% | 3.45% |
| 7 | 3500 | -3.17% | 3.27% |
| 8 | 4000 | 2.08% | 2.86% |
| 9 | 4500 | -2.78% | 2.97% |
| 10 | 5000 | -1.99% | 2.09% |
| 11 | 5500 | 1.79% | 0.86% |
| 12 | 6000 | -1.42% | 4.78% |
| 13 | 6500 | -1.86% | 2.44% |
| 14 | 7000 | -1.88% | 0.86% |
| 15 | 7500 | 0.79% | 2.24% |
| 16 | 8000 | -3.25% | 2.03% |
| 17 | 8500 | -1.41% | 3.22% |
| 18 | 9000 | -1.58% | 2.64% |
| 19 | 9500 | -2.97% | 3.68% |
| 20 | 10000 | -2.99% | 2.02% |
| 21 | 10500 | -3.45% | 3.27% |
| 22 | 11000 | -2.47% | 2.52% |
| 23 | 11500 | -2.84% | 1.95% |
| 24 | 12000 | -0.62% | 3.13% |
| 25 | 12500 | -1.26% | 3.22% |
| 26 | 13000 | -2.58% | 2.79% |
| 27 | 13500 | -1.80% | 2.41% |
| 28 | 14000 | -2.19% | 4.52% |
| 29 | 14500 | -3.17% | 2.99% |
| 30 | 15000 | -3.65% | 3.31% |
| 31 | 15500 | -3.27% | 2.85% |
| 32 | 16000 | -5.38% | 3.76% |
| 33 | 16500 | -3.71% | 1.56% |
| 34 | 17000 | -2.97% | 4.46% |
| HDC 04 – Sarjapura Road | | | |
| 35 | 0+000 | 2.84% | 2.24% |

*Sl. No
20000*

| Sl. No | Chainage, m | Camber, % | |
|--|----------------|-----------|--------|
| | | LHS | RHS |
| 36 | 0+500 | 3.61% | 2.74% |
| 37 | 1+000 | -2.73% | 3.23% |
| 38 | 1+500 | 3.15% | 2.15% |
| HDC 12c – ORR from K R Puram to Silkboard | | | |
| 39 | 0+000 | 1.01% | -0.72% |
| 40 | 0+500 | -2.12% | -0.68% |
| 41 | 1+000 | 2.35% | 2.41% |
| 42 | 1+500 | -1.65% | 2.21% |
| 43 | 2+000 | 1.38% | 0.44% |
| 44 | 2+500 | 2.84% | 2.24% |
| 45 | 3+000 | 3.61% | 2.74% |
| 46 | 3+500 | -2.73% | 3.23% |
| 47 | 4+000 | 3.15% | 3.53% |
| 48 | 4+500 | 2.38% | 2.15% |
| 49 | 5+000 | -0.88% | 2.48% |
| 50 | 5+500 | 2.28% | 2.01% |
| 51 | 6+000 | 3.14% | 2.26% |
| 52 | 6+500 | 1.74% | 2.46% |
| 53 | 7+000 | 2.03% | 2.39% |
| 54 | 7+500 | -4.75% | 5.48% |
| 55 | 8+500 | 3.18% | 9.37% |
| 56 | 9+000 | 2.21% | 2.91% |
| 57 | 9+500 | -4.18% | 5.16% |
| 58 | 10+000 | 2.87% | 2.36% |
| 59 | 10+500 | 2.51% | 2.13% |
| 60 | 11+000 | 2.34% | 3.23% |
| 61 | 11+500 | 3.78% | 2.99% |
| 62 | 11+900 | -2.96% | 2.55% |

2.7 Traffic Survey

Traffic surveys are an integral component of any transport study where appreciation of existing traffic and travel characteristics of the study area are extremely important. However, Traffic surveys are not required in this assignment as no additional widening is proposed beyond available ROW. However, the traffic survey details available with KRDCCL are collected for Analysis of pavement Evaluation and overlay design.

At the outset, ISECPL has collated available traffic survey details to establish the base line data for the study.

The classified traffic volume count data available was processed and compiled using Spread Sheet software packages to get Commercial Vehicles per day, which is further utilized to compute the design traffic. Traffic Survey details referred are conducted during the year 2016, and this traffic is projected to Design Base year. The CVPD adopted for each road is shown below:

Table 2.17: CVPD for Old Airport Road

| Mode | CVPD (2016) | Projected CVPD |
|------------|-------------|----------------|
| Std Bus | 1297 | 1656 |
| LCV | 1233 | 1574 |
| 2 Axle | 428 | 547 |
| 3 Axle | 359 | 459 |
| Multi Axle | 63 | 81 |

Table 2.18: CVPD for Sarjapur Road

| Mode | CVPD (2016) | Projected CVPD |
|------------|-------------|----------------|
| Std Bus | 889 | 1135 |
| LCV | 1723 | 2200 |
| 2 Axle | 234 | 299 |
| 3 Axle | 224 | 286 |
| Multi Axle | 4 | 6 |

Table 2.19: CVPD for Outer Ring Road (K R Puram to Silk Board)

| Mode | CVPD (2016) | Projected CVPD |
|------------|-------------|----------------|
| Std Bus | 2831 | 3614 |
| LCV | 2911 | 3716 |
| 2 Axle | 1140 | 1455 |
| 3 Axle | 584 | 746 |
| Multi Axle | 162 | 207 |

- Design life: - Design Life of 5 Years is considered for the overlay design of Flexible Pavement Design as per IRC: SP: 115 - 2014.
- Growth rate: - Annual Growth rate of 5% is considered for designs.
- VDF: - The adopted vehicle damage factor considered for the overlay design is 1.0 for Buses & LCV, and 5.0 for other HCVs.
- Lane Distribution factor: - Lane distribution factor is adopted as indicated in IRC 37 - 2018.
- The Design Traffic obtained for a design period of 5 Years as per IRC 37 2018 is

Tabulated below.

| Road | HDC 03- Old Airport Road | HDC 04 – Sarjapura Road | HDC 12c – ORR from KR Puram to Silk Board |
|---------------------|-----------------------------|----------------------------|---|
| Design Traffic, msa | 13 | 10 | 23 |

2.8 Existing Pavement Structure

The bituminous layers contribute the major part of the strength of the flexible pavement structure. Hence pavement investigation is carried out to know the Existing Bituminous Thickness without disturbing the surrounding area of test pit, the existing bituminous layer thickness is measured by cutting a bituminous core cutting equipment. The core samples are taken on all the project roads at an effective interval of 2 Km. The photographs taken during core cutting in project stretch are given in following paragraphs.

Table 2.20: Bituminous Crust Thickness by Core Cutter

| Sl. No | Chainage | Pavement Crust Thickness in (mm) | | Total Thickness in (mm) |
|--|----------|----------------------------------|----------------|-------------------------|
| | | Bituminous Layer | Granular Layer | |
| HDC-3 Old Airport Road | | | | |
| 1 | 1+750 | 210 | 280 | 490 |
| 2 | 8+500 | 220 | 280 | 500 |
| HDC-4 Sarjapur Road | | | | |
| 1 | 3+250 | 220 | 290 | 510 |
| HDC-12c Outer Ring Road KR Puram to Silk Board | | | | |
| 1 | 3+900 | 220 | 300 | 520 |
| 2 | 7+300 | 220 | 290 | 510 |

2.9 Pavement structural Evaluation using Falling Weight Deflectometer Studies

Falling Weight Deflectometer (FWD) applies dynamic load on the pavement, which closely simulates the duration and amplitude of the load pulses produced by moving wheel loads. The FWD test was carried out in accordance with IRC: 115-2014 "Guidelines for structural evaluation and strengthening of flexible road pavements using Falling Weight Deflectometer (FWD) Technique. FWD readings were taken along the wheel path. Readings were taken at 250m interval, with test points staggered on both sides. Adjustments to reading locations were made to avoid culverts, bridge decks and locally damaged areas. Pavement and air temperatures were recorded for the purpose of

temperature correction. Subgrade moisture data was also obtained from field moisture measurements for applying seasonal corrections to deflection measurements.

Principle of Pavement evaluation using FWD

Performance of flexible pavements can be evaluated by applying loads on the pavements that simulate the traffic loading, recording the response to such loading by measuring the elastic deflection under such loads, and analyzing these data duly considering the factors influencing the performance such as subgrade strength, pavement thickness and quality of each of the pavement layers, drainage conditions, pavement surface temperature etc.

Among the equipment available for structural evaluation of pavements, the Falling Weight Deflectometer (FWD) is extensively used world-wide because it simulates, to a large extent, the actual loading conditions of the pavement. When a moving wheel load passes over the pavement it produces load pulses. The resulting load-deflection data can be interpreted through appropriate analytical techniques, such as back calculation technique, to estimate the elastic moduli of the pavement layers. The computed moduli are, in turn, used for (i) the strength evaluation of different layers of in-service pavements (ii) the estimation of the remaining life of in-service pavement (iii) determination of strengthening requirement, if any and (iv) evaluation of different rehabilitation alternatives (overlay, recycling, partial reconstruction, etc.

Falling Weight Deflectometer (FWD) is an impulse-loading device in which a transient load is applied to the pavement and the deflected shape of the pavement surface is measured. Impulse load is applied by means of a falling mass, which is allowed to drop vertically on a system of springs placed over a circular loading plate. The deflected shape of the pavement surface is measured using displacement sensors which are placed at different radial distances starting with the center of the load plate. Trailer mounted as well as vehicle mounted FWD models are available commercially. The working principle of all these FWD models is essentially the same. A mass of weights is dropped from a predetermined height onto a series of springs/ buffers placed on top of a loading plate. The corresponding peak load and peak vertical surface deflections at different radial locations are measured and recorded.

FWD is non-destructive test equipment for pavements. It applies a dynamic load to a pavement structure which simulates a moving load, unlike in case of BBD where static load is applied, which does not simulate moving load. FWD provides fast, non-destructive

evaluation of pavements and is safe in operating with traffic. It evaluates the condition of underlying pavement layers and can trace the complete shape of bowl formed under dynamic loading.

The survey has been carried out by conducting deflection studies over the existing carriageway along the wheel paths at an effective interval of 250 m alternatively on both lanes of carriageway on each side. The deflections are measured by lowering the loading plate in proper contact with the pavement surface along with the required number of geophones placed at known distance from the loading plate. A target load of 40KN is achieved by dropping the mass from predetermined height. At each study point the load is applied once as seating load and the corresponding deflection is need not be recorded. After seating load, Raise the mass and drop minimum 3 times and record load and deflection data into the computer through data acquisition system on all 3 drops. While peak load and peak deflections at different selected radial positions must be recorded. After that the loading plate and Geophone frames are raised to original position and vehicle is moved to next test point. Temperatures are recorded at an interval of half hour and it has ensured FWD studies are not carried with pavement temperature greater than 45°C.

Temperature Correction

Back calculated moduli values of the bituminous layers evaluated by FWD survey are influenced by the pavement temperature. Hence the back calculated moduli obtained at temperatures other than the identified standard temperature will have to be corrected. For areas in India having a tropical climate, the standard pavement temperature is recommended as 35°C.

Correction for Seasonal Variation

Moisture content affects the strength of subgrade and granular subbase/base layers. The extent to which the strength is affected will depend on the nature of subgrade soil, gradation and nature of fines in the granular layers, etc. For applying these guidelines, it is intended that the pavement layer moduli values should pertain to the period when the subgrade is at its weakest condition. In India, this period occurs during the recession of monsoon. It is, therefore, desirable to conduct deflection measurements during this period. Where the same is not feasible, a correction procedure should be adopted.

The deflection measurement results with due temperature, seasonal corrections and

characteristic deflections are presented in **Annexure 2.2**.

The Summar of Normalized deflection are presented in Table 2.17 to Table 2.20 and the summary for FWD analysis and pavement overlay design is presented in Table 2.21 to the completed details of FWD analysis and overlay design is Annexed with this report.

Table 2.21: Summary of Normalized Deflection for Old Airport Road

| Station ID | Load, KN | Contact Pressure | Normalized Deflections, mm | | | | | | |
|------------|----------|------------------|----------------------------|-------|-------|-------|-------|-------|-------|
| | | | D1 | D2 | D3 | D4 | D5 | D6 | D7 |
| 0 | 40 | 0.56 | 0.151 | 0.13 | 0.115 | 0.096 | 0.069 | 0.059 | 0.041 |
| 250 | 40 | 0.56 | 0.23 | 0.198 | 0.178 | 0.149 | 0.114 | 0.094 | 0.069 |
| 500 | 40 | 0.56 | 0.12 | 0.107 | 0.097 | 0.083 | 0.064 | 0.055 | 0.042 |
| 750 | 40 | 0.56 | 0.111 | 0.095 | 0.084 | 0.072 | 0.056 | 0.049 | 0.036 |
| 1000 | 40 | 0.56 | 0.135 | 0.113 | 0.098 | 0.082 | 0.062 | 0.053 | 0.04 |
| 1250 | 40 | 0.56 | 0.134 | 0.114 | 0.103 | 0.087 | 0.066 | 0.057 | 0.041 |
| 1500 | 40 | 0.56 | 0.097 | 0.081 | 0.074 | 0.063 | 0.049 | 0.042 | 0.031 |
| 1750 | 40 | 0.56 | 0.125 | 0.107 | 0.095 | 0.082 | 0.063 | 0.054 | 0.041 |
| 2000 | 40 | 0.56 | 0.099 | 0.082 | 0.073 | 0.061 | 0.046 | 0.039 | 0.028 |
| 2250 | 40 | 0.56 | 0.178 | 0.157 | 0.141 | 0.118 | 0.087 | 0.072 | 0.05 |
| 2500 | 40 | 0.56 | 0.119 | 0.1 | 0.09 | 0.078 | 0.061 | 0.053 | 0.04 |
| 2750 | 40 | 0.56 | 0.155 | 0.126 | 0.11 | 0.09 | 0.065 | 0.054 | 0.037 |
| 3000 | 40 | 0.56 | 0.149 | 0.128 | 0.113 | 0.093 | 0.067 | 0.056 | 0.042 |
| 3250 | 40 | 0.56 | 0.16 | 0.132 | 0.114 | 0.094 | 0.07 | 0.059 | 0.043 |
| 3500 | 40 | 0.56 | 0.16 | 0.132 | 0.114 | 0.095 | 0.069 | 0.062 | 0.047 |
| 3750 | 40 | 0.56 | 0.127 | 0.108 | 0.097 | 0.082 | 0.059 | 0.052 | 0.039 |
| 3800 | 40 | 0.56 | 0.187 | 0.146 | 0.123 | 0.1 | 0.073 | 0.063 | 0.046 |
| 4100 | 40 | 0.56 | 0.063 | 0.06 | 0.059 | 0.059 | 0.054 | 0.051 | 0.04 |
| 4350 | 40 | 0.56 | 0.262 | 0.213 | 0.178 | 0.131 | 0.082 | 0.063 | 0.041 |
| 4600 | 40 | 0.56 | 0.085 | 0.063 | 0.052 | 0.04 | 0.02 | 0.015 | 0.008 |
| 4850 | 40 | 0.56 | 0.129 | 0.1 | 0.081 | 0.065 | 0.049 | 0.043 | 0.034 |
| 5100 | 40 | 0.56 | 0.28 | 0.239 | 0.203 | 0.157 | 0.103 | 0.082 | 0.055 |
| 5200 | 40 | 0.56 | 0.216 | 0.186 | 0.165 | 0.134 | 0.1 | 0.082 | 0.06 |
| 5500 | 40 | 0.56 | 0.331 | 0.27 | 0.226 | 0.174 | 0.104 | 0.083 | 0.048 |
| 5750 | 40 | 0.56 | 0.233 | 0.197 | 0.169 | 0.136 | 0.094 | 0.079 | 0.055 |
| 6000 | 40 | 0.56 | 0.238 | 0.203 | 0.177 | 0.139 | 0.097 | 0.079 | 0.056 |
| 6250 | 40 | 0.56 | 0.266 | 0.222 | 0.191 | 0.151 | 0.105 | 0.086 | 0.059 |
| 6500 | 40 | 0.56 | 0.36 | 0.298 | 0.26 | 0.208 | 0.146 | 0.122 | 0.072 |
| 6750 | 40 | 0.56 | 0.319 | 0.275 | 0.246 | 0.209 | 0.162 | 0.134 | 0.098 |
| 7000 | 40 | 0.56 | 0.431 | 0.361 | 0.306 | 0.238 | 0.16 | 0.133 | 0.086 |
| 7250 | 40 | 0.56 | 0.352 | 0.311 | 0.278 | 0.232 | 0.177 | 0.147 | 0.099 |
| 7500 | 40 | 0.56 | 0.384 | 0.328 | 0.29 | 0.236 | 0.168 | 0.14 | 0.096 |

CHAPTER 3: IMPROVEMENT PROPOSALS

3.1 General

The project corridors are studied thoroughly with respect to the existing features on the project roads viz No of lanes, carriageway details, Drains and CDs, Footpaths, Medians, Junctions, Bus bays, sign Boards and other traffic Appurtenances as discussed in Chapter 2. the project corridors under package 1 i.e., HDC 03: Old Airport Road, HDC 02: Sarjapur Road, and HDC 12c: Outer Ring Road from Old Airport Road to Silk Board comprise carriageway varying from 4 lane to 6 lanes.

Table 3.1 Lane Configuration

| SI No | Road Name | Lane Km | | | |
|-------|-------------------------|----------|----------|-------------|---------------|
| | | 4 Lane | 6 Lane | For SR Lane | Total Lane Km |
| 1 | Old Airport Road | 68.60 Km | - | - | 68.60 Km |
| 2 | Sarjapur Road | 35.00 Km | - | - | 35.00 Km |
| 3 | K R Puram to Silk Board | - | 99.00 Km | 66.00 Km | 165.00 Km |
| | Total | 103.6 Km | 99.00 Km | 66.00 Km | 268.60 Km |

Since the project corridors are under control of BBMP, there are already various improvement works have been carrying out or already tendered by BBMP in the project corridors. Improvement proposals are made for the remaining length which has not been considered for improvement works under BBMP / BMRCL.

The Project Proposals are Prepared in 2 Parts

1. Initial Improvement Proposals
2. Annual maintenance Proposal

3.2 Discussions made with various Stake Holders

3.2.1 Assets to be included as part of the maintenance project

KRDCL has informed that several meetings were held on this project at various levels of ACS, CS and it was concluded to include and exclude the following assets as part of maintenance by KRDCL

Table 3.2 Table of Assets

| SL No | Assets Proposed for Maintenance |
|---|--|
| Assets Included for Maintenance by KRDCL | |
| 1 | Carriageway |
| 2 | Median |
| 3 | Junctions |
| 4 | Grade Separators (Flyovers/Underpasses/RoB/RUB) |
| 5 | Bus Bays |
| 6 | Service Roads / Slip Roads / Parking Lanes |
| 7 | Road Markings |
| 8 | Sign Boards |
| 9 | Footpath |
| 10 | Pedestrian Guard Rails |
| 11 | Bollards |
| 12 | High Raised Pedestrian Crossings |
| 13 | Traffic Signals at Junctions |
| 14 | Installation of Traffic KIOSK / Umbrella for Policemen |
| 15 | Side Drains |
| 16 | Cross Drainage Structures |
| 17 | Road Sweeping |
| 18 | Manhole chamber Improvements |
| 19 | Tree Guards |
| 20 | Tree pruning |
| 21 | Road Cutting and Restoration |
| 23 | Removal of Construction and Demolition Debris |
| Assets Excluded for Maintenance by KRDCL | |
| 1 | Bus Shelters |
| 2 | Sky Walks |
| 3 | Solid Waste Management |
| 4 | Encroachment Clearance |
| 5 | Street Lighting |
| 6 | Land Acquisition for improvements |
| 7 | Water Supply and Sanitary lines leakages by BWSSB |
| 8 | Faulty Power Lines by BESCO/KPTCL |
| 9 | Gas Leakages in Gas Lines by GAIL |

3.2.2 Proposals from Bruhat Bengaluru Mahanagara Palike (BBMP)

Meetings and Discussions are held with BBMP officials regarding the ongoing improvement works or tendered works along the project length of the High-Density corridors. The details of the works which are already considered by BBMP and BMRCL are collected and summary of the same is tabulated below. The stretch wise details of the works considered by BBMP / BMRCL are annexed with the report.

Table 3.3 Tendered length of BBMP and BMRCL

| HDC No | Corridor Name | Total Length of the corridor, Km | BBMP ongoing work length, Km | BMRCL ongoing work length, Km |
|------------------------------|------------------------|----------------------------------|------------------------------|-------------------------------|
| 3 | Old Airport Road | 17.15 | 3.15 | 0.00 |
| 4 | Sarjapur Road | 8.75 | 7.65 | 0.00 |
| 12c | KR Puram to Silk Board | 16.5 | 4.60 | 0.00 |
| Package II Length, Km | | 42.40 | 15.40 | 0.00 |

3.2.3 Proposals from Traffic Police Department

Police department has prepared a corridor wise proposal for the works to be considered in Short Term, Mid Term and Long-Term measures to improve the Traffic discipline, reduce the congestion, and minimize the accidents and fatalities. the detailed report submitted by the department is annexed with this report and the prominent, short term measures, Midterm Measures, and long-Term measures, which are included in the project proposal are Summarized in the table below.

Table 3.4 Proposals considered as per Traffic Police Department

| SI No | Items Considered in Estimate as per Traffic Police Requirement | Quantity | | |
|-------|--|----------|---------|---------|
| | | HDC 03 | HDC 04 | HDC 12c |
| 1 | Junction Improvement | 10 Nos | 2 Nos | 6 Nos |
| 2 | High Raised Pedestrian Crossing | 21 Nos | 15 Nos | 30 Nos |
| 3 | Median Guard Railing | 15.45 Km | 7.5 Km | 12.5 Km |
| 4 | Bus Bay | 5 Nos | 1 No | 2 Nos |
| 5 | Widening of road | 70 m | Nil | 100 m |
| 6 | Traffic Sign Boards | 244 Nos | 107 Nos | 256 Nos |
| 7 | Traffic Umbrella/Kiosk | 8 Nos | 4 Nos | 6 Nos |
| 8 | Traffic Signals | 4 Nos | 1 No | 2Nos |
| 9 | Skywalks | 2 Nos | 4 Nos | 4 Nos |
| 10 | Surveillance and Enforcement Cameras installation | 58 Nos | 15 Nos | 24 Nos |

Various discussion held with ACS, CS on these issues concluded that the skyalks shall be

taken up on PPP basis separately and cameras will be taken up under separate head, hence these two items are excluded from the current scope of project.

3.2.4 Proposals from DULT

DULT suggested to provide bus lanes and cycle lanes in all roads as per the budgetary announcement made by Hon'ble CM. various discussions held on this at ACS, CS level and following suggested to include bus lanes at roads (preferable Outer Ring Road) where 6 lanes are more exists at present and any other stretches needed will be added alter with proper permission/approval from Govt. In Package 2 – length of ORR is around 16.5 Km, where Bus Priority lane is already executed, Hence no provision is made for creating Bus Priority lane in this Package.

Table 3.5 Proposals of DULT

| SI No | High Density Corridor | Length of Bus Priority Lane Considered, Km |
|-------|--|--|
| 1 | HDC 03 – Old Airport Road | Nil |
| 2 | HDC 04 – Sarjapur Road | Nil |
| 3 | HDC 12 C – ORR from KR Puram to Silk Board | Already Executed |
| | Total Length of Bus Lane in Package 2 | 0.00 Km |

3.3 Initial Improvement Works

Initial improvement works are proposed in the Balance length of the corridors which are not considered for improvement by BBMP / BMRCL. The summary of the initial improvement lengths of the 3 corridors under Package 1 is represented below.

Table 3.6 Table below shows the Length of Initial Improvement Works

| HDC No | Corridor Name | Length Considered for Initial Improvement, Km | Total Length of the corridor, Km | BBMP ongoing work length, Km | BMRCL ongoing work length, Km |
|-----------------------------|------------------------|---|----------------------------------|------------------------------|-------------------------------|
| 3 | Old Airport Road | 14.00 | 17.15 | 3.15 | 0.00 |
| 4 | Sarjapur Road | 1.10 | 8.75 | 7.65 | 0.00 |
| 12c | KR Puram to Silk Board | 11.9 | 16.5 | 4.6 | 0.00 |
| Package I Length, Km | | 27.0 | 42.4 | 15.40 | 0.00 |

The Proposals have been split into following Major Heads.

- (i) Where No works are taken up by BBMP or BMRCL, these stretches the project improvement proposals includes
- Carriageway Improvements
 - Junction Improvements
 - Footpath Improvement and Construction of Green Hedging
 - Median Improvements and Guardrail
 - Construction of Bus Bays & Road Widening
 - Drain Improvements
 - Traffic Signs, Road Markings and Other Appurtenances
- (ii) Whereas for the section where, works taken by BBMP / are under progress or already tendered, only the following works are provisioned.
- Median Guardrail Provisioned
 - Construction of Green Hedging
 - Missing Sign Boards installation
 - Selected Junction Improvements.

3.3.1 Preliminary Works:

Following works are considered under preliminary works along the project roads under Package 02, viz Old Airport Road, Sarjapura Road and Outer ring road from KR Puram to Silk Board. Clearing and grubbing is considered for removal and disposal of unwanted plants and waste materials from the project site. The damaged portion of Medians, Kerbs and Footpaths are proposed for Dismantling and refixing.

3.3.2 Carriageway Improvements: -


Uniform lanes: the carriageways are widened over a period of time and there's no standard lane widths at present, the outer lane widths varies and at few places, its less than the standard lane width. Based on tender sure experience the lane widths are standardized as below, the outer lane shall be of 3.5 m as buses move on this lane, center lane shall be 3.0 m as this is predominately LMV's for and inner lane shall be 3.25 m giving a shyness of 0.25 m for median. This is been done in discussion with DULT and BBMP as per the tender sure experience.

Resurfacing: Carriageway is proposed with functional overlay or strengthening and Overlay as per the pavement evaluation and overlay design. Prior to laying overlay, milling of existing bituminous surface is considered in order to achieve required camber and to reduce profile correction course. The carriage way is proposed

with uniform lane markings, and installation of raised pavement markers. Carriageway improvements are represented in volume 3 – Drawings.

Table 3.7 Table below shows resurfacing proposed

| Sl No | Corridor Name | Chainage | | Overlay Thickness, mm | |
|-------|---------------------------------------|----------|--------|-----------------------|----|
| | | From | To | DBM | BC |
| 1 | HDC 03: Old Airport Road | 0+000 | 3+800 | 0 | 40 |
| 2 | | 4+100 | 5+200 | | |
| 3 | | 5+500 | 10+800 | | |
| 4 | | 13+350 | 17+150 | | |
| 5 | HDC 04: Sarjapur Road | 3+000 | 4+100 | 0 | 40 |
| 6 | HDC 12c: ORR (KR Puram to Silk Board) | 0+000 | 11+900 | 0 | 40 |



3.3.3 Junction Improvements:

The selected junctions along the corridor are proposed with carriageway improvements, road markings, sign board installations, construction or modification of traffic channelizing islands. provision for precast new jersey barrier to guide the traffic. the junctions are redesigned in order to ensure safe maneuvering of vehicles and pedestrians. In coordination with police department few selected junctions which are not in initial improvement section are also considered for improvement. Junctions considered for improvement are tabulated below.


Old Airport Road: -

| SI No | Junction Chainage | Junction Name |
|-------|-------------------|-------------------------------|
| 1 | 0+150 | ASC Junction |
| 2 | 0+650 | Cambridge Road junction |
| 3 | 1+250 | ASC centre & College junction |

with uniform lane markings, and installation of raised pavement markers. Carriageway improvements are represented in volume 3 – Drawings.

Table 3.7 Table below shows resurfacing proposed

| SI No | Corridor Name | Chainage | | Overlay Thickness, mm | |
|-------|---------------------------------------|----------|--------|-----------------------|----|
| | | From | To | DBM | BC |
| 1 | HDC 03: Old Airport Road | 0+000 | 3+800 | 0 | 40 |
| 2 | | 4+100 | 5+200 | | |
| 3 | | 5+500 | 10+800 | | |
| 4 | | 13+350 | 17+150 | | |
| 5 | HDC 04: Sarjapur Road | 3+000 | 4+100 | 0 | 40 |
| 6 | HDC 12c: ORR (KR Puram to Silk Board) | 0+000 | 11+900 | 0 | 40 |



3.3.3 Junction Improvements:

The selected junctions along the corridor are proposed with carriageway improvements, road markings, sign board installations, construction or modification of traffic channelizing islands. provision for precast new jersey barrier to guide the traffic. the junctions are redesigned in order to ensure safe maneuvering of vehicles and pedestrians. In coordination with police department few selected junctions which are not in initial improvement section are also considered for improvement. Junctions considered for improvement are tabulated below.

Old Airport Road: -

| SI No | Junction Chainage | Junction Name |
|-------|-------------------|-------------------------------|
| 1 | 0+150 | ASC Junction |
| 2 | 0+650 | Cambridge Road junction |
| 3 | 1+250 | ASC centre & College junction |

| SI No | Junction Chainage | Junction Name |
|-------|-------------------|---------------------------------|
| 4 | 2+400 | Near Domlur flyover junction |
| 5 | 3+500 | 80feet road junction |
| 6 | 4+100 | NAL wind tunnel road junction |
| 7 | 8+000 | Yamalur Junction |
| 8 | 8+250 | Doddanekundi main road junction |
| 9 | 15+650 | Immadihalli junction |
| 10 | 16+500 | Ambedkar Nagar road junction |
| 11 | 0+150 | ASC Junction |
| 12 | 0+650 | Cambridge Road junction |

Sarjapur Road: -

| SI No | Junction Chainage | Junction Name |
|--------|-------------------|------------------------|
| Link-1 | | |
| 1 | 3+800 | Sarjapura-ORR junction |
| 2 | 3+000 | Cross road |

Outer Ring Road KR Puram to Silk Board: -

| SI No | Junction Chainage | Junction Name |
|-------|-------------------|------------------------------|
| 1 | 2+800 | Doddanekundi junction |
| 2 | 6+550 | Cross Road junction |
| 3 | 8+300 | New horizon college junction |
| 4 | 9+050 | Devarabeesanahalli Junction |
| 5 | 10+250 | Bellandur Junction |

3.3.4 Footpath and Kerb

Footpath proposal includes construction of new walkways with interlocking paver blocks, where space is available or where existing footpath is in poor condition. In addition, replacement of damaged Kerbs and paver blocks are also considered.

Old Airport Road: -

| SL No | From | To | Length in m (including both sides) |
|-------|--------|--------|------------------------------------|
| 1 | 10+600 | 10+800 | 200 |

Sarjapur Road: -


Provision is kept for 600m in the entire stretch for damaged or discontinued sections

Outer Ring Road KR Puram to Silk Board: -

| SL No | From | To | Length in m (including both sides) |
|-------|--------|--------|------------------------------------|
| 1 | 6+100 | 6+400 | 300 |
| 2 | 7+200 | 7+450 | 250 |
| 3 | 8+770 | 8+900 | 130 |
| 4 | 12+150 | 12+770 | 620 |
| 5 | 13+600 | 14+400 | 800 |
| 6 | 15+400 | 16+000 | 600 |
| 7 | 15+500 | 15+900 | 400 |

3.3.5 Green Hedging: -

With the intention to improve the aesthetics of the high-density corridors, Green Hedging is proposed on the footpath sides of the carriageway. the proposal includes installation of additional kerb line and supplying and spreading of farm yard Manure to support planting of permanent hedges. Green hedging is proposed at all feasible locations which are being improved by both BBMP or KRDCL. in addition, provision for chute drains is made along the Kerb line to guide the carriageway runoff to the drain. Cross sections indicating green hedging is represented below.



3.3.6 Median and Guard rail: -

Two types of median are considered for improvement one is the conventional median with both side Kerb with grassing and the other is 900mm standard new Jersey barrier. This is proposed in consultation with Traffic police department. The first type is considered where there is already existing convention median but in poor condition and the second type is considered as per the police requirement in places where there is existing low height concrete median or at specified places by the police department. Similarly, Guard rail is also proposed in two design, one is to install over conventional median and the second type is proposed to install over new jersey barrier in such a way to maintain uniform height. Typical section of median with guard rail is represented below.

Old Airport Road: -

| Sl No | From | To | Length in m |
|-------|-------|-------|-------------|
| 1 | 0+000 | 0+640 | 640 |
| 2 | 0+700 | 1+240 | 540 |
| 3 | 1+270 | 1+930 | 660 |
| 4 | 1+940 | 2+140 | 200 |
| 5 | 2+150 | 2+200 | 50 |
| 6 | 2+210 | 2+310 | 100 |
| 7 | 2+330 | 2+370 | 40 |
| 8 | 2+410 | 2+750 | 340 |
| 9 | 2+950 | 3+130 | 180 |
| 10 | 3+160 | 3+180 | 20 |
| 11 | 3+200 | 3+290 | 90 |
| 12 | 3+310 | 3+510 | 200 |
| 13 | 3+540 | 4+060 | 520 |
| 14 | 4+100 | 4+190 | 90 |
| 15 | 4+210 | 4+410 | 200 |
| 16 | 4+430 | 5+300 | 870 |
| 17 | 5+500 | 6+680 | 1180 |
| 18 | 6+720 | 6+950 | 230 |
| 19 | 6+990 | 7+220 | 230 |
| 20 | 7+230 | 7+840 | 610 |
| 21 | 7+860 | 8+000 | 140 |
| 22 | 8+030 | 8+250 | 220 |



| Sl No | From | To | Length in m |
|-------|--------|--------|-------------|
| 23 | 8+260 | 8+480 | 220 |
| 24 | 8+510 | 9+960 | 1450 |
| 25 | 10+200 | 10+760 | 560 |
| 26 | 10+810 | 11+050 | 240 |
| 27 | 11+070 | 11+540 | 470 |
| 28 | 11+560 | 12+540 | 980 |
| 29 | 12+560 | 13+080 | 520 |
| 30 | 13+100 | 13+580 | 480 |
| 31 | 13+605 | 13+740 | 135 |
| 32 | 13+760 | 14+050 | 290 |
| 33 | 14+160 | 14+315 | 155 |
| 34 | 14+340 | 14+660 | 320 |
| 35 | 14+690 | 15+215 | 525 |
| 36 | 15+235 | 15+400 | 165 |
| 37 | 15+420 | 15+635 | 215 |
| 38 | 15+655 | 15+770 | 115 |
| 39 | 15+790 | 15+800 | 10 |
| 40 | 15+820 | 15+900 | 80 |
| 41 | 15+920 | 16+090 | 170 |
| 42 | 16+110 | 16+470 | 360 |
| 43 | 16+490 | 16+775 | 285 |
| 44 | 16+795 | 17+150 | 355 |

Sarjapur Road:-

| Sl No | From | To | Length in m |
|-------|-------|--------|-------------|
| 1 | 0+100 | 0+600 | 500 |
| 2 | 1+650 | 4+000 | 2350 |
| 3 | 5+750 | 10+400 | 4650 |

Outer Ring Road KR Puram to Silk Board:-

| SI No | From | To | Length, m |
|-------|--------|--------|-----------|
| 1 | 0+300 | 1+150 | 850 |
| 2 | 1+600 | 2+810 | 1210 |
| 3 | 3+100 | 3+700 | 600 |
| 4 | 3+900 | 5+500 | 1600 |
| 5 | 5+800 | 7+600 | 1800 |
| 6 | 7+950 | 9+200 | 1250 |
| 7 | 9+500 | 10+100 | 600 |
| 8 | 10+400 | 11+300 | 900 |
| 9 | 11+700 | 12+800 | 1100 |
| 10 | 13+460 | 14+550 | 1090 |
| 11 | 15+150 | 16+650 | 1500 |



3.3.7 Bus Bays: -

Improvement proposal of Existing bus bays includes pavement overlay in case of Flexible Pavement, Pavement Markings, and Sign Board installations. in Bellary road Existing bus bays are proposed for improvements as discussed. But, with respect to Old Madras road and Outer ring road project reaches new bus bays are proposed as required by traffic police department.

Old Airport Road: -

| SI No | Bus bay Chainage | Location |
|--------|------------------------------|----------|
| 2+700 | Near Dommalur flyover | 2+700 |
| 4+620 | Rajeshwari Talkies | 4+620 |
| 6+600 | Near HAL Helicopter Division | 6+600 |
| 7+850 | Borewell Busstop | 7+850 |
| 10+550 | Kundalahalli Gate | 10+550 |

Sarjapur Road: -

| SI No | Bus Bay Chainage | Location |
|-------|------------------|-------------------------|
| 1 | 3+800 | Agara |
| 2 | 6+220 | Bellandur Gate |
| 3 | 7+250 | Kaikondanahalli Busstop |
| 4 | 8+080 | Junnasandra Gate |
| 5 | 9+320 | Doddakanahalli |

Outer Ring Road KR Puram to Silk Board: -

| SI No | Bus bay Chainage | Location |
|-------|------------------|-----------------------------|
| 1 | 5+560 | Near Marathahalli Underpass |
| 2 | 7+650 | Kadubeesanahalli |

3.3.8 Drainage and Structural Improvements: -

Existing Drainage facility is studied along the project corridors, for availability and functioning, based on which it is proposed for construction of New Drain with cover slab and replacement of damaged cover slab. in addition, it is also provisioned for any emergency repairs of RE Wall portions of the Grade Separators.

Old Airport Road:-

| Sl No | From | To | Length in m |
|-------|-------|-------|-------------|
| 1 | 0+900 | 1+400 | 500 |

Sarjapur Road:-

| Sl No | From | To | Length in m |
|-------|-------|-------|-------------|
| 1 | 3+000 | 3+200 | 400 |
| 2 | 3+270 | 3+440 | 170 (LHS) |
| 3 | 5+750 | 5+850 | 200 |

Outer Ring Road KR Puram to Silk Board:-

Provision has been made for 1.5Km length at damaged and discontinued section

3.3.9 Utility and Ducts

There are no proposals for shifting of utilities in these stretches, further the initial improvements are taken only for a part length of 191 kms, the provision of utility ducts is not considering as there will be no continuity of ducts if provided. Further it was decided in various meetings that the current project is of maintenance nature and utilities are in the scope of respective utility departments and KRDCL will focus on maintenance of road assets.

3.3.10 Road Markings, Traffic Signboards and other Appurtenances:-

Road Markings viz Edge lines, Centre lines, Pedestrian Crossings, Directional Arrows are proposed as per the standard requirements and as indicate in the drawings. Similarly raised pavement markers or Road studs are proposed along road markings, at Junctions, at HRPCs as per standards and as indicated in the Drawings. Different Type of Sign boards are provisioned for the project corridors and Appropriate Type & number of sign boards shall be Installed as per the Good for Construction Drawings. The provisions under this head also includes Road Delineators, Hazard markers, Bollards, Single arrow directional sign Boards, overhead gantry sign boards, Traffic Umbrella / KIOSK for Traffic Policemen, Traffic Signals, and Gratings at VUPs. Road Delineators are provided to demarcation of the Bus priority lane, turning demarcation and at edges of the islands. Hazard markers are provisioned for installation at approaches of all structures, at Median openings, etc. Single Arrow directional signboards are provisioned to aid in identification of cross roads, where the board is not available. Over Head Gantry Sign

Boards, Traffic KIOSKs and Traffic Signals are all included for costing as per the requirements of the traffic police department.

3.4 Annual Maintenance Proposals

As part of maintenance proposals, government has decided to go for a 5 years long term maintenance and during which the road has to be kept in the good condition for easy and safe movement of traffic and pedestrians at all time. **Road Maintenance** includes routine Maintenance, preventive Maintenance, periodic Maintenance, disaster Maintenance, exigencies and inspections.

- **Periodic Maintenance:** works such as re-surfacing of pavements may be required to restore the functional deficiencies that have developed over a time period. Which shall be decided based on functional and structural valuation studies.
- **Routine Maintenance:** Contractor shall carry out day-to-day site inspection of the designated road stretches and note down the damages that have occurred due to natural or artificial causes, they should take immediate steps to correct or rectify the damages. Routine Maintenance are undertaken by the maintenance staff almost round the year.
- **Preventive Maintenance:** The preventive maintenance is performed to improve or extend the functional life of pavement surface while in good condition. This may defer the need of periodic maintenance and rehabilitation
- **Disaster Maintenance:** Occasionally several damages are caused to roads cross drainage and other road assets. structures by floods or very heavy down pour or rains, though these may not occur every year. Under such circumstances works are to be completed as early as possible and the road infrastructure shall be restored so as to minimized the inconvenience to road users.
- **Safety & Traffic Management** – this includes enforcement of regulations together with the relevant authorities. Keep project roads safer, this also includes hazard response and Road patrols
- **Asset management** – this includes daily, routine and periodic inspections, Maintenance, repairs, housekeeping and emergency Maintenance

following are the maintenance activities suggested with Time limits for rectification.

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|---------|--|-------------------------------------|
| A | Carriageway/Road surface, Hard shoulders, Drains and | |

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|---------|--|--|
| | Cross Drainage works, Bridges / Interchanges / Grade Separators (Fly Overs/ RUB/ ROB/ Under Pass / any other Road structure). | |
| 1 | Maintaining a public relations unit to interface with and attend to suggestions from the Users, government agencies, media and other agencies and deploying the required staff. Equipment Installation and Office setup (Large TV, Computers, Printers and other equipment), deploying Three non-technical and two technical staff | On or before 30 days from LOA |
| 2 | all surplus construction machinery and materials, waste materials (including hazardous materials and waste water), rubbish and other debris (including, without limitation, accident debris) and keep the Project in a clean, tidy and orderly condition, and in conformity with Applicable Laws, Applicable Permits and Good Industry Practice. | Daily |
| 3 | Carriageway Sweeping using mechanical sweepers and footpath manual cleaning Minimum 4 vehicle mounted sweeping machines to be deployed all the debris/dust/litter shall be safely carried and disposed away at designated places. | Daily |
| 4 | Breach or blockade (the item of works shall be removal of fallen concrete wall, trees, electric pole etc. | Temporary restoration of traffic within 3 hours' permanent restoration within 7 days |
| 5 | Roughness not more than 2600mm/km for each lane in a km length (as measured by a standardized rough meter/bump integrator). | As indicated in the Work order, for this work. |
| 6 | Skid Resistance (Skid Number, SN; minimum Desirable shall be 55 SN | As indicated in the Work order, for this work |
| 7 | Potholes | 24 hours |
| 8 | Cracking all types in less than 5% of road surface for each lane in a km length | 3 (Three) days |
| 9 | Ravelling/Stripping of bitumen and all types in less than 5% of road surface for each lane in a km length | 3 (Three) days |
| 10 | Settlement all types in less than 5% of road surface for each lane in a km length | 3 (Three) days |
| 11 | Rutting exceeding 5 mm in more than 2% of road surface for each lane in a km length (measured ROMDAS or equivalent technology) | 7 (Seven) days |
| 12 | Bleeding | 3 (Three) days |
| 13 | Damage to pavement edges exceeding 100 mm | 24 hours |
| 14 | Painting of Kerb, railing, parapets, crash barriers, | Twice every year |

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|---------|---|---|
| 15 | All types of Road Marking | Retro reflectivity mcd/m ² /lux of 150 during the contract period / Twice every year |
| 16 | Joint Sealing in concrete pavement | 7 (Seven) days |
| 17 | Replacement of Pavement Quality Concrete slabs | 15 (fifteen) days |
| 18 | Rain cuts/gullies in slope | 3 (Three) days |
| 19 | Damage to or silting of culverts and side drains during and immediately preceding the rainy season | 3 (Three) days |
| 20 | Desilting of drains in Road side Drains | 3 (Three) days |
| 21 | Cracks - Temporary measures | Within 48 hours |
| 22 | Spalling/scaling | 3 (Three) days |
| 23 | Foundations-cavitation | 3 (Three) days |
| 24 | Piers, abutments, return walls, RE-walls Cracks and damages including settlement and tilting Temporary measures | 30 (Thirty) days |
| 25 | Bearings All type- Replacements | As indicated in the Work order, for this work |
| 26 | Joints in bridges: Loosening and malfunctioning of joints | As indicated in the Work order, for this work |
| 27 | Deforming of pads in elastomeric bearings | As indicated in the Work order, for this work |
| 28 | Gathering of dirt in bearings and joints or clogging of spouts, weep holes and vent-holes | 3 (Three) days |
| 29 | Damage or deterioration in parapets and handrails | 3 (Three) days |
| 30 | Rain-cuts or erosion of banks of the side slopes of approaches | 3 (Three) days |
| 31 | Resurfacing of wearing coat | As indicated in the Work order, for this work |
| 32 | Damage or deterioration in approach slabs | 3 (Three) days |
| 33 | Growth of vegetation affecting the structure or obstructing the waterway | 3 (Three) days |
| B | Foot Path/Medians/Drains | |
| 34 | Manual cleaning of footpaths, all the debris/dust/litter shall be safely carried and disposed away at designated places | Daily |
| 35 | Damage to paver blocks or concrete surface or tiles of footpath | 3 (Three) days |
| 36 | Damage to Kerbs, bollards, tree guards, pedestrian railings | 3 (Three) days |
| 37 | Road side Drains and inlets | Should be Clean at all times |
| 38 | Damage to drain cover, walls | 3 (Three) days |
| C | Road safety and furniture including all road sign boards | |

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|---------|--|---|
| | and pavement raised marking (road studs) | |
| 39 | Damage to shape or position, poor visibility or loss of retro-reflectivity | 48 hours |
| 40 | Damaged/missing road signs requiring replacement | 7 (seven) days |
| 41 | Painting of railing, parapets, crash barriers | Once every year |
| 42 | Reflective Pavement Markers (Road Studs) Numbers and Functionality as per specification in IRC :SP:84-2014 and IRC :35-2015, unless specified | At all times |
| 43 | Pedestrian Guard rail : Functionality: Functioning of guardrail as intended | At all times |
| 44 | Traffic Safety Barriers: Functionality: Functioning of Safety Barriers as intended | At all times |
| 45 | Overhead Sign Structures shall be structurally and functionally adequate | At all times |
| D | Miscellaneous Works (Trees and Plantation, Road Patrol, Road Cutting Restoration, Road lighting | |
| 46 | Obstruction in a minimum head-room of 5 m above carriageway or obstruction in visibility of road signs | 24 hours |
| 47 | Deterioration in health of trees and bushes | Timely watering and treatment |
| 48 | Replacement/replanting of plants and bushes on medians, islands, footpaths and green edges | 3 (Three) days |
| 49 | Removal of vegetation affecting sight line and road structures | 3 (Three) days |
| 50 | Patrolling of roads by a vehicle of Bolero or equivalent with a driver, assistant and a supervisor at all times - 2 vehicles and two teams | All through the day |
| 51 | Restoration of road cutting as per IRC specifications Temporary Permanent | As indicated in the Work order, for this work |
| 52 | Road lighting | Not Included. |
| E | Emergency Works | |
| 53 | Removal of Fallen Trees | 3 hours |
| 54 | Towing of Accident vehicle / Breakdown vehicle / Abandoned vehicle, mandatory deployment of: <ul style="list-style-type: none"> • LMV Towing vehicle –for towing of light commercial vehicles and below – 1 nos • HCV Towing vehicle –for towing of buses/ heavy commercial vehicles - 1 nos | 1 hour |
| 55 | Water logging / Ponding on road surface / grade separators, mandatory deployment of Tippers, pumps, sucking machines, etc., as needed | 1 hour |

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|---------|--|-------------------------------------|
| 56 | Fallen Street pole / Sign Boards / any other structure | 1 hour |

3.4.1 Traffic Incident Management

As a part of maintenance proposals, The Project corridors are required to Patrol continually through dedicated staff and Vehicle, to monitor any possible hindrance for the free flow of traffic and to ensure good condition of all Road Assets. Two patrol vehicles with staff are provided for each package of work

During the discussions with the police department, provision of cranes for toeing was asked to toe away the vehicles stranded, met in accident or illegally parked on HDC's. provision of two toeing vehicles one for heavy vehicles like buses and trucks and another for LMV's is proposed.

Water logging at selected locations is a perennial issue during rainy season, especially at underpasses. In the even of water logging, the provision of sucking machines, pumps and labour is also provisioned in the maintenance work.

CHAPTER 4: COST ESTIMATE

4.1 General

The Project cost is worked out based on estimated quantities from the detailed engineering design including road works, drainage works, pavement, culverts, road furniture, road safety appurtenances etc.

4.2 Construction Items

The following factors have been considered to arrive at the unit rates for various construction items.

The project cost estimates have been prepared separately for initial improvement works and Annual Maintenance works based on various items of works considered for the upgradation and annual maintenance of the project roads. The Major items rates are considered from **PWP IWTD SoR 2018-19, Bangalore Circle**, Govt. of Karnataka along with latest issue rates, and for few items derived rates are adopted.

Table 4.1 Adopted Unit Rates for Some of the Major Items (Excluding Area Weight Factor)

| Sl. No. | Items | Unit | Rate |
|---------|--|---------|----------|
| 1 | Milling of Existing Bituminous Layer | Sqm | 70.00 |
| 2 | Granular Sub base | Cum | 1882.00 |
| 3 | Wet Mix Macadam | Cum | 1888.00 |
| 4 | Dense Bituminous Macadam (DBM) | Cum | 6045.00 |
| 5 | Bituminous Concrete (BC) | Cum | 6939.00 |
| 6 | Interlocking Paver Blocks | Sqm | 1110.00 |
| 7 | M15 for Kerb Laying | Cum | 5422.00 |
| 8 | Kerb | Nos | 450.00 |
| 9 | Painting two Coats for Kerb | Sqm | 82.00 |
| 10 | Yard Manure | Cum | 204.00 |
| 11 | Planting permanent hedge | Mt | 296.00 |
| 12 | Tree Guard / Grating and Median guard Rail | Quintal | 7187.00 |
| 13 | Providing and Laying M20 for Drain | Cum | 6670.00 |
| 14 | Steel Reinforcement | Tonnes | 61365.00 |
| 15 | Road Marking- Thermoplastic | Sqm | 429.00 |
| 16 | Moulded Shank Raised Pavement Markers | Nos | 337.00 |

4.3 Project Costing

Quantification

The quantification of various items of work is based upon the proposals recommended in the previous chapters. The quantities have been worked out separately for different items of work. The construction cost has been sub - divided into Preliminary Works, Carriageway improvement, Junction Improvement, Footpath and Kerbs, Medians and guard rails, Bus bays and Road Widening Works, Drainage Improvement and other structural Works, Traffic signs, Marking and other Appurtenances.

The following are the Bill wise of works, which have been estimated:

Preliminary Works including Dismantling, Clearance and Earthworks: The area considered for Site Clearance is the area within the proposed Right of Way width. and the damaged portions of Median Kerbs, and Footpath are proposed for dismantling.

Carriageway Improvements: Carriageway improvements costs includes Milling of existing bituminous surface, Strengthening and overlay as per the structural evaluation and Pavement design.

Junction Improvements: Junction improvement cost includes overlay for carriageway, Road markings, installation of sign Boards, High raised pedestrian crossings, construction of channelization islands as per the requirement.

Footpath and Kerbs: Footpath works cost includes removal of damaged paver blocks, kerb stones, etc and replacement with the new ones. In addition, the costing also includes the Green Hedging provision along the footpath

Median and Guardrail: The estimation of quantities for Median construction were based on site inventory, and Median Guard rails for pedestrian safety as per police department instruction is considered .

Bus Bays and Road Widening Works: The estimation of quantities for Bus bays and road widening works were based on the police department requirements , detailed design and drawings.

Drainage Improvement and Structural Works: Provision under this sub-head has been made for cost for construction of side drains, and repairs of RE wall.

Traffic Sign, Markings and Other Appurtenances: Proper traffic signs were selected at required locations along the project corridor. It is reviewed considering the traffic, pedestrian safety, and modified if required. Centre line and edge markings required

from safety point of view were considered in the quantity estimate.

4.4 Total Project Cost

The total project cost of **package 2** is **111.86 Crores**, which includes Initial Improvement cost of **64.50 Crores**, Annual maintenance cost of **21.75 Crores**, 12% for GST, 5% Administration Charges, 3% for DPR and PMC charges, 10% Contingencies. The summary of the project is given in **Table 4.2** below for Total Project Cost along with Road Wise Cost Summary.

The detailed rate analysis and quantity estimation is given in Volume-3: Cost Estimate.

Table 4.2: Summary of Cost for the Project

| Sl. No | Description | HDC 03 | HDC 04 | HDC 12C | Package II |
|--------|---|-----------------|-----------------|-----------------|-----------------|
| | | Amount (Crores) | Amount (Crores) | Amount (Crores) | Amount (Crores) |
| 1 | Preliminary Works including Dismantling, Clearance and Earthworks | 0.16 | 0.03 | 0.27 | 0.45 |
| 2 | Carriageway Improvements | 11.56 | 1.03 | 10.02 | 22.61 |
| 3 | Junction Improvements | 1.71 | 0.64 | 1.53 | 3.88 |
| 4 | Footpath and Kerbs | 6.56 | 3.41 | 6.28 | 16.26 |
| 5 | Median and Guardrail | 4.87 | 2.37 | 3.98 | 11.21 |
| 6 | Bus Bays and Road Widening Works | 0.28 | 0.21 | 0.19 | 0.68 |
| 7 | Drainage Improvement and Structural Works | 0.72 | 0.94 | 2.03 | 3.69 |
| 8 | Traffic Sign, Markings and Other Appurtenances | 2.32 | 0.70 | 2.69 | 5.72 |
| A. | Initial Improvement Cost | 28.17 | 9.33 | 26.99 | 64.50 |
| B. | Annual Maintenance Cost | 7.38 | 4.04 | 10.34 | 21.75 |
| C. | GST @ 12% of (A+B) | 4.27 | 1.60 | 4.48 | 10.35 |
| D. | Administrative Charges @ 5% on (A+B) | 1.78 | 0.67 | 1.87 | 4.31 |
| E. | DPR & PMC Charges @ 3% on (A+B) | 0.93 | 0.48 | 1.08 | 2.49 |
| F. | Contingencies @ 10% | 3.13 | 1.44 | 3.84 | 8.42 |
| G. | Miscellaneous and Rounding off | 0.01 | 0.02 | 0.01 | 0.04 |
| H. | Total Project Cost (A+B+C+D+E+F+G) | 45.67 | 17.58 | 48.61 | 111.86 |

4.5 Implementation Plan

An implementation plan refers to a detailed description of actions that demonstrate how to implement an activity within the project in the context of achieving the objectives,

addressing the requirements, and meeting the expectations. The above project is to be implemented in two forms.

1. Initial Improvement and
2. Maintenance

Initial Improvement: Initial improvement is to be done within first nine months of the project tenure year for carriage way, Junctions improvements, Footpath and Drain improvements, Traffic lane markings and sign boards, median island improvements and providing green edge in ongoing BBMP Tender works.

Maintenance: The proposed project roads are to be maintained periodically by clearing of pavement, Repair of traffic signs and road markings, Repair of damage caused by traffic accidents. The project corridors are to be maintained for 5 years.

4.6 Packaging

The Total Length of the all the high-density corridor is 191 Km which is spreader over the entire Bengaluru city. this will make the task of maintaining the road very cumbersome, as it will be very difficult to accesses, Monitor and control the activities over entire length. Hence the Total 15 roads of high-density corridors are grouped in to four packages, such that it will be convenient to Access, Monitor and control the different activities running along the corridor within each package.

4.7 Time Schedule.

The duration for the initial improvement works is 270 days covering various stages of work. The time schedule of the Project along with work programme of activities is given below.

| Sl. No | Description | Duration | Start Date | End Date |
|--------|---|-----------------|-------------------|-------------------|
| A | Initial Improvement Works | 270 Days | 01-04-2021 | 31-12-2021 |
| 1 | Strengthening/Resurfacing, Road Marking, Traffic Signs for Priority Stretches | 90 Days | 01-04-2021 | 30-06-2021 |
| 2 | Drainage and Utility Works | 90 Days | 01-04-2021 | 30-06-2021 |
| 3 | Footpath and Kerbs | 90 Days | 01-05-2021 | 31-07-2021 |
| 4 | Median and Guardrails | 60 Days | 01-07-2021 | 31-08-2021 |

| Sl. No | Description | Duration | Start Date | End Date |
|--------|---|----------|------------|------------|
| 5 | Junction Improvements | 60 Days | 01-09-2021 | 31-10-2021 |
| 6 | Strengthening/Resurfacing, Road Marking, Traffic Signs Road Appurtenances for Other Stretches | 90 Days | 01-10-2021 | 31-12-2021 |

The Annual Maintenance works needs to be executed continually throughout the year for the project duration of 5 Years.

Design Traffic Calculation for overlay design - Old Airport Road

| YEAR | LCV | | BUS | | TWO AXLE | | THREE AXLE TRUCK | | MULTI AXLE | | Total Yearly Standar d Axle | Design Cumula tive Standar d Axle |
|------|-------------------|-----------------------------|-------------------|-----------------------------|-------------------|------------------------------|-------------------|-----------------------------|-------------------|------------------------------|--------------------------------------|---|
| | AADT (Veh/day) | Yearly Standard Axles | AADT (Veh/day) | Yearly Standard Axles | AADT (Veh/day) | Yearly Standar d Axles | AADT (Veh/day) | Yearly Standard Axles | AADT (Veh/day) | Yearly Standar d Axles | | |
| 2021 | 1656 | 0.453 | 1574 | 0.431 | 547 | 0.749 | 459 | 0.628 | 81 | 0.111 | 2 | |
| 2022 | 1739 | 0.476 | 1653 | 0.452 | 574 | 0.786 | 482 | 0.660 | 85 | 0.116 | 2 | 2 |
| 2023 | 1826 | 0.500 | 1735 | 0.475 | 603 | 0.825 | 506 | 0.693 | 89 | 0.122 | 3 | 5 |
| 2024 | 1917 | 0.525 | 1822 | 0.499 | 633 | 0.867 | 531 | 0.727 | 94 | 0.128 | 3 | 7 |
| 2025 | 2013 | 0.551 | 1913 | 0.524 | 665 | 0.910 | 558 | 0.764 | 98 | 0.135 | 3 | 10 |
| 2026 | 2114 | 0.579 | 2009 | 0.550 | 698 | 0.956 | 586 | 0.802 | 103 | 0.141 | 3 | 13 |

Design Traffic Calculation for overlay design - Sarjapura Road

| YEAR | LCV | | BUS | | TWO AXLE | | THREE AXLE TRUCK | | MULTI AXLE | | Total Yearly Standar d Axle | Design Cumula tive Standar d Axle |
|------|-------------------|-----------------------------|-------------------|-----------------------------|-------------------|------------------------------|-------------------|-----------------------------|-------------------|------------------------------|--------------------------------------|---|
| | AADT (Veh/day) | Yearly Standard Axles | AADT (Veh/day) | Yearly Standard Axles | AADT (Veh/day) | Yearly Standar d Axles | AADT (Veh/day) | Yearly Standard Axles | AADT (Veh/day) | Yearly Standar d Axles | | |
| 2021 | 1135 | 0.311 | 2200 | 0.602 | 299 | 0.409 | 286 | 0.391 | 6 | 0.008 | 2 | |
| 2022 | 1192 | 0.326 | 2310 | 0.632 | 314 | 0.430 | 300 | 0.411 | 6 | 0.009 | 2 | 2 |
| 2023 | 1251 | 0.343 | 2426 | 0.664 | 330 | 0.451 | 315 | 0.432 | 7 | 0.009 | 2 | 4 |
| 2024 | 1314 | 0.360 | 2547 | 0.697 | 346 | 0.474 | 331 | 0.453 | 7 | 0.010 | 2 | 5 |
| 2025 | 1380 | 0.378 | 2674 | 0.732 | 363 | 0.497 | 348 | 0.476 | 7 | 0.010 | 2 | 7 |
| 2026 | 1449 | 0.397 | 2808 | 0.769 | 382 | 0.522 | 365 | 0.500 | 8 | 0.010 | 2 | 10 |

Design Traffic Calculation for overlay design - ORR KR Puram to Silk Board

| YEAR | LCV | | BUS | | TWO AXLE | | THREE AXLE TRUCK | | MULTI AXLE | | Total Yearly Standar d Axle | Design Cumula tive Standar d Axle |
|------|-------------------|-----------------------------|-------------------|-----------------------------|-------------------|------------------------------|-------------------|-----------------------------|-------------------|------------------------------|--------------------------------------|---|
| | AADT (Veh/day) | Yearly Standard Axles | AADT (Veh/day) | Yearly Standard Axles | AADT (Veh/day) | Yearly Standar d Axles | AADT (Veh/day) | Yearly Standard Axles | AADT (Veh/day) | Yearly Standar d Axles | | |
| 2021 | 3614 | 0.791 | 3716 | 0.814 | 1455 | 1.593 | 746 | 0.817 | 207 | 0.227 | 4 | |
| 2022 | 3795 | 0.831 | 3902 | 0.854 | 1528 | 1.673 | 783 | 0.858 | 217 | 0.238 | 4 | 4 |
| 2023 | 3984 | 0.873 | 4097 | 0.897 | 1604 | 1.757 | 822 | 0.901 | 228 | 0.250 | 5 | 9 |
| 2024 | 4184 | 0.916 | 4302 | 0.942 | 1684 | 1.844 | 864 | 0.946 | 240 | 0.262 | 5 | 13 |
| 2025 | 4393 | 0.962 | 4517 | 0.989 | 1769 | 1.937 | 907 | 0.993 | 252 | 0.276 | 5 | 18 |
| 2026 | 4612 | 1.010 | 4743 | 1.039 | 1857 | 2.033 | 952 | 1.043 | 264 | 0.289 | 5 | 23 |

Consulting Services for Preparation of DPR and Project Management Consultancy
(Including Detailed Designs) for High Density Corridors(HDC) in Bengaluru, Karnataka


Design Traffic Calculation for overlay design - ORR KR Puram to Silk Board


| YEAR | LCV | | BUS | | TWO AXLE | | THREE AXLE TRUCK | | MULTI AXLE | | Total Yearly Standar rd Axle | Design Cumula tive Standar rd Axle |
|------|-------------------|-----------------------------|-------------------|-----------------------------|-------------------|------------------------------|-------------------|-----------------------------|-------------------|------------------------------|---------------------------------------|--|
| | AADT (Veh/day) | Yearly Standard Axles | AADT (Veh/day) | Yearly Standard Axles | AADT (Veh/day) | Yearly Standar d Axles | AADT (Veh/day) | Yearly Standard Axles | AADT (Veh/day) | Yearly Standar d Axles | | |
| 2021 | 3614 | 0.791 | 3716 | 0.814 | 1455 | 1.593 | 746 | 0.817 | 207 | 0.227 | 4 | |
| 2022 | 3795 | 0.831 | 3902 | 0.854 | 1528 | 1.673 | 783 | 0.858 | 217 | 0.238 | 4 | 4 |
| 2023 | 3984 | 0.873 | 4097 | 0.897 | 1604 | 1.757 | 822 | 0.901 | 228 | 0.250 | 5 | 9 |
| 2024 | 4184 | 0.916 | 4302 | 0.942 | 1684 | 1.844 | 864 | 0.946 | 240 | 0.262 | 5 | 13 |
| 2025 | 4393 | 0.962 | 4517 | 0.989 | 1769 | 1.937 | 907 | 0.993 | 252 | 0.276 | 5 | 18 |
| 2026 | 4612 | 1.010 | 4743 | 1.039 | 1857 | 2.033 | 952 | 1.043 | 264 | 0.289 | 5 | 23 |

Annexures 3.1

Details from BBMP

| MAINTENANCE OF HIGH DENSITY CORRIDORS IN BENGALURU CITY | | | | | | | | |
|---|----------------|-----------|-------------------|---------------------|------------------|--|---|--|
| HDC No-03 Old Airport Road Corridor | | | | | | | | |
| Sl No | Chainage to Km | | Location | | BBMP Department | Ongoing Works / Completed works implemented by | Works Considered by KRDCL for Initial Improvement | Maintainence Proposal |
| | From | to | From | to | | | | |
| Link 03- ASC Center to Hope farm Junction | | | | | | | | |
| 1 | Ch 0.00 | Ch 3.80 | ASC Center | HP Petrol Bunk | RI - East | . | Proposed Improvement by KRDCL | 1.. Routine Maintenance incl. Mechanical Sweeping of carriageways and Manual Cleaning of Footpath. 2. Removal debries, roadside silt, C&D Wastes & allied works using Tractor Labours. 3. Patrolling. 4. Maintenance of Carriageway. 5. Maintenance of Drain & Footpath. 6. Street Light Maintenance. 7. Other Allied Works on emergent days |
| | Ch 3.80 | Ch 4.10 | HP Petrol Bunk | Coffe day | | SFC in progress by Project Central BBMP | . | |
| | Ch 4.10 | Ch 5.20 | Coffe day | HAL Starting gate | | . | Proposed Improvement by KRDCL | |
| | Ch 5.20 | Ch 5.50 | HAL Starting gate | Suranjandas road | | SFC in progress by project central BBMP | . | |
| 2 | Ch 5.50 | Ch 6.90 | Suranjandas road | Yemalur Junction | RI-KR Puram | . | Proposed Improvement by KRDCL | |
| 3 | Ch 6.90 | Ch 10.80 | Yemalur Junction | ITPB | RI- Mahadevapura | . | Proposed Improvement by KRDCL | |
| | Ch 10.80 | Ch 11.10 | ITPB | Ganesh Juice Center | | SFC in progress by project central BBMP | . | |
| | Ch 11.10 | Ch 17.150 | Varthur Kodi | Hope Farm Junction | | . | Road Improvement taken up by KRDCL | |
| Length of Corridor | | | 17.150 Km | | | | | |


Assistant Executive Engineer-4
Project Office Bengaluru South
K.R.D.C.L., Bengaluru.


Executive Engineer
Project Office Bengaluru South
K.R.D.C.L., Bengaluru.

| MAINTENANCE OF HIGH DENSITY CORRIDORS IN BENGALURU CITY | | | | | | | | |
|--|----------------|---------|----------------|------------------|------------------|--|---|--|
| HDC No -04 Sarjapura Road Corridor | | | | | | | | |
| No | Chainage to Km | | Location | | BBMP Department | Ongoing Works / Completed works implemented by | Works Considered by KRDCL for Initial Improvement | Maintainence Proposal |
| | From | to | From | to | | | | |
| Link 04 St Johns Hospital to Agara, Iblur Junction to Carmelram Bridge | | | | | | | | |
| 1 | Ch 0.00 | Ch 3.00 | Hosur Road | Jakkasandra | RI - South | White topping work in progress by Project Central (BBMP) | | 1.. Routine Maintenance incl. Mechanical Sweeping of carriageways and Manual Cleaning of Footpath. 2. Removal debris, roadside silt, C&D Wastes & allied works using Tractor Labours. |
| 2 | Ch 3.00 | Ch 4.10 | Jakkasandra | Agara | RI- Bommanahalli | | Proposed Improvement by KRDCL | 3. Patrolling. 4. Maintenance of Carriageway. 5. Maintenance of Drain & Footpath. |
| 3 | Ch 0.00 | Ch 4.75 | Iblur Junction | Carmelram Bridge | RI- Mahadevapura | Proposed Improvement by RI- Mahadevapura (BBMP) <i>Road Widening</i> | | 6. Street Light Maintenance. 7. Other Allied Works on emergent days |
| Length of Corridor | | | 8.85 Km | | | | | |

M. S. S.


Executive Engineer
Infrastructure - South
Bengaluru Mahanagara Palike

U. S.
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ರಸ್ತೆ ಮೂಲಭೂತ ಸೌಕರ್ಯ, ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ


J. S.
Executive Engineer
Road Widening Division Project Office Bengaluru South
Bengaluru Mahanagara Palike K.R.D.C.L., Bengaluru.

A. S.
Executive Engineer
Project Office Bengaluru South
K.R.D.C.L., Bengaluru.


| MAINTENANCE OF HIGH DENSITY CORRIDORS IN BENGALURU CITY | | | | | | | | |
|--|--------------------|----------|------------|----------------|-------------------|---|---|---|
| Summary of Works Under HDC No -12 B KR Puram to Silk Board Road Corridor | | | | | | | | |
| Sl No | Chainage to Km | | Location | | BBMP Department | Ongoing Works / Completed works implemented by | Works Considered by KRDCL for Initial Improvement | Maintainence Proposal |
| | From | to | From | to | | | | |
| Silk Board to Lowry Junction | | | | | | | | |
| 1 | Ch 0.00 | Ch 3.20 | Silk Board | Agara | RI - Bommanahalli | Proposed improvement under RI-TEC ✓ | | 1.. Routine Maintenance incl. Mechanical Sweeping of carriageways and Manual Cleaning of Footpath. |
| 2 | Ch 3.20 | Ch 5.10 | Agara | Iblur junction | RI - Bommanahalli | Proposed improvement under RI-Bommanahalli | | 2. Removal debries, roadside silt, C&D Wastes & allied works using Tractor Labours. 3. Patrolling. 4. Maintenance of Carriageway. |
| 3 | Ch 5.10 | Ch 16.50 | Iblur | Lowry Junction | RI - Mahadevapura | This road has already developed by R.I Mahadevapura and it is under DLP | Proposed Improvement by KRDCL | 5. Maintenance of Drain & Footpath. 6. Street Light Maintenance. 7. Other Allied Works on emergent days |
| | Length of Corridor | | 16.50 Km | | | | | |



Executive Engineer
Road Infrastructure, Mahadevapura Division
B B M P Bangalore

(RI-BOMMANAHALLI)


Executive Engineer
Traffic Engineering Cell (RI)
B B M P Bangalore

EE (RI-MAHADEVAPURA)


Assistant Executive Engineer-4
Project Office Bengaluru South
K.R.D.C.L., Bengaluru.


Executive Engineer
Project Office Bengaluru South
K.R.D.C.L., Bengaluru.

EE (KRDCL-SOUTH)



ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಮೂಲಭೂತ ಸೌಕರ್ಯ, ಬೆಂಗಳೂರು ದಿ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Table of Content

| | |
|--|-----------|
| CHAPTER 1: INTRODUCTION | 1 |
| 1.1 Project Background | 1 |
| 1.2 Objective of the Project | 7 |
| 1.3 Scope of the Project | 8 |
| 1.4 Meetings with Clients and Stakeholders | 9 |
| 1.5 Structure of the Report | 9 |
| CHAPTER 2: SURVEYS AND INVESTIGATIONS | 11 |
| 2.1 Introduction | 11 |
| 2.2 Road Inventory and Condition Surveys | 11 |
| 2.3 Road Junctions | 52 |
| 2.4 Bus Shelters / Bus Bays / Bus Stop | 57 |
| 2.5 Pavement Condition Survey | 58 |
| 2.6 Traffic Survey | 64 |
| 2.7 Existing Pavement Structure | 65 |
| 2.8 Pavement structural Evaluation using Falling Weight Deflectometer Studies | 65 |
| 2.9 Inventory and Condition Survey of Culverts, Bridges, Grade Separators / VUPs / PUPs | 68 |
| 2.10 Topographic Survey | 68 |
| CHAPTER 3: IMPROVEMENT PROPOSALS | 70 |
| 3.1 General | 70 |
| 3.2 Discussions made with various Stake Holders | 70 |
| 3.3 Initial Improvement Works | 73 |
| 3.3.1 Preliminary Works: | 74 |
| 3.3.2 Carriageway Improvements: - | 75 |

| | | |
|---------------------------------------|--|-----------|
| 3.3.3 | Junction Improvements: | 75 |
| 3.3.4 | Footpath and Kerb | 76 |
| 3.3.5 | Green Hedging: - | 76 |
| 3.3.6 | Median and Guard rail: - | 77 |
| 3.3.7 | Bus Bays: - | 80 |
| 3.3.8 | Drainage and Structural Improvements: - | 80 |
| 3.3.9 | Road Markings, Traffic Signboards and other Appurtenances: - | 81 |
| 3.4 | Annual Maintenance Proposals | 81 |
| 3.4.1 | Traffic Incident Management | 86 |
| CHAPTER 4: COST ESTIMATE | | 87 |
| 4.1 | General | 87 |
| 4.2 | Construction Items | 87 |
| 4.3 | Project Costing | 87 |
| 4.4 | Total Project Cost | 89 |
| 4.5 | Implementation Plan | 90 |
| 4.6 | Packaging | 90 |
| 4.7 | Time Schedule. | 90 |

List of Tables

| | | |
|------------|---|----|
| Table 1.1: | Length of Project Corridors in Package 3..... | 2 |
| Table 2.1: | Table showing details of RoW along for HDC-05 Hosur Road | 12 |
| Table 2.2: | Table showing details of RoW along for HDC-06 Bannerugatta Road | 13 |
| Table 2.3: | Table showing details of RoW along for HDC-7 Kanakpura Road..... | 13 |
| Table 2.4: | Table showing details of RoW along for HDC-12d Silk Board to Mysore Road | 17 |
| Table 2.5: | Table showing details of RoW along for HDC-05 Hosur Road | 18 |
| Table 2.6: | Table showing details of Carriageway and shoulder along main carriage way for HDC-06 Bannerghatta Road. | 19 |

| | | |
|-------------|--|----|
| Table 2.7: | Table showing details of Carriageway and shoulder along main carriage way for HDC-7 Kanakpura Road..... | 26 |
| Table 2.8: | Table showing details of Carriageway and shoulder along main carriage way for HDC-12d Silk Board to Mysore Road..... | 32 |
| Table 2.9: | Table showing details of Carriageway and shoulder along service road for HDC-5 Hosur Road..... | 36 |
| Table 2.10: | Table showing details of Carriageway and shoulder along service road for HDC 6 Bannerghatta Road | 36 |
| Table 2.11: | Table showing details of Carriageway and shoulder along service road for HDC 7 Kanakpura Road | 36 |
| Table 2.12: | Table showing details of Carriageway and shoulder along service road for HDC 12d Silk Board to Mysore Road..... | 37 |
| Table 2.13: | Table showing details of drain for HDC-05 Hosur Road..... | 37 |
| Table 2.14: | Table showing details of drain for HDC-06 Bannerghatta Road..... | 38 |
| Table 2.15: | Table showing details of drain for HDC-7 Kanakpura Road | 42 |
| Table 2.16: | Table showing details of drain for HDC-12d Silk Board to Mysore Road | 45 |
| Table 2.17: | Table showing details of footpath for HDC-05 Hosur Road | 47 |
| Table 2.18: | Table showing details of footpath for HDC-06 Bannerghatta Road..... | 48 |
| Table 2.19: | Table showing details of footpath for HDC-7 Kanakpura Road | 52 |
| Table 2.20: | Table showing details of Junctions | 56 |
| Table 2.21: | Table showing Bus Bays / Bus Stops | 58 |
| Table 2.22: | Showing Summary of Structures along the Corridor..... | 68 |
| Table 3.1 | Lane Configuration..... | 70 |
| Table 3.2 | Below showing Table of Assets | 71 |
| Table 3.3 | Tendered length of BBMP and BMRCL | 72 |
| Table 3.4 | Proposals considered as per Traffic Police Department | 72 |
| Table 3.5 | Proposals of DULT..... | 73 |
| Table 3.6 | Table below shows the Length of Initial Improvement Works..... | 74 |
| Table 4.1: | Adopted Unit Rates for Some of the Major Items (Excluding Area Weight Factor) | 87 |
| Table 4.2: | : Summary of Cost for the Project..... | 89 |

List of Figures

| | | |
|-------------|---|---|
| Figure 1.1: | Key Plan of Alignment (Hosur Road)..... | 4 |
|-------------|---|---|

| | | |
|-------------|--|----|
| Figure 1.2 | Key Plan of Alignment (Bannerughatta Road) | 5 |
| Figure 1.3 | Key Plan of Alignment (Kanakapura Road) | 6 |
| Figure 1.4 | Key Plan of Alignment (Outer Ring Road) | 7 |
| Figure 2.1: | Summary of existing Pavement condition of HDC 07 Kanakapura Road..... | 64 |

1.1 Project Background

Bangalore is one of the fastest growing cities in Asia and also one of the most sought after cities in India by people, companies and multinationals. The massive growth that the city has witnessed in the last decade is a clear indication of this city being developed to be at par with the most modern cities in the world. The population of Bangalore has grown enormously on account of migration of people from all corners of India, neighboring countries and from countries in the West. Bengaluru's road network exceeds 3,000 km (1,800 mi) and consists of ring roads, arterial roads, sub-arterial roads and residential streets.

The main arterial roads of Bengaluru coming into the city include Bellary Road in the north, Tumkur Road and Mysore Road in the west, Kanakapura Road, Bannerghatta Road and Hosur Road in the south and Airport Road and Old Madras Road in the east, these high-volume traffic arterial roads are inter connected with Outer Ring Road. Bangalore Commissioner of Police notified these 12 Major Roads connecting inter-districts and inter-states as High Traffic Density Corridors vide Notification dated: 03-09-2016, and are named as High-Density Corridors.

Roads, and means of transport, make a crucial contribution to economic development and growth and bring important social benefits. Poorly maintained roads constrain mobility, significantly raise vehicle operating costs, increase accident rates and their associated human and property costs. Deterioration of constructed pavement is natural. It's natural because over time the materials that make up Bitumen begin to break down and become affected by elements such as rain, sunlight and chemicals that come into contact with the pavement surface. The liquid Bitumen binder that is the "glue" of the pavement begins to lose its natural resistance to water, allowing it to penetrate into and underneath the pavement. Once this happens, the surface can quickly fall prey to a number of different types of deterioration.

The construction and maintenance of roads to address the growing traffic in the city has been a challenge to the BDA and the BBMP. To reduce the pressure of hectic maintenance activities for BBMP and to ensure the effective maintenance of high-volume traffic arterial roads it has been proposed to handover the maintenance of High-density corridors to KRDC.

The decision has been taken in the meeting held on 06-11-2019 under the Chairmanship of Hon'ble Chief Minister, Govt. Of Karnataka for Upgradation and maintenance of 12 High Traffic Density Corridors as per IRC guidelines to be taken by Karnataka Road Development Corporation Ltd.


Karnataka Road Development Corporation Limited (KRDCL) was incorporated on 21st of July 1999 as a wholly owned Government of Karnataka Company as per the Provisions of the Company's Act, 1956. The company is managed by a Board of Directors chaired by Principal Secretary to Government, PWP and IWID with Members from other organizations.

KRDCL is a company under the Public Works, Ports & Inland Water Transport Department. This Company was established to promote surface infrastructure by taking up Road Works, Bridges etc., and to improve road network by taking up construction, widening and strengthening of roads, construction of bridges, maintenance of roads etc., and to take up projects on BOT, BOOT, BOLT. With the emerging industrial and economic development of the past few decades, there has been a tremendous growth in terms of the traffic on all the roads

Karnataka Road Development Corporation Limited (KRDCL) has appointed **M/s Infra Support Engineering Consultants Pvt Ltd** (ISECPL) as consultants for Preparation of DPR and Project Management Consultancy (Including Detailed Designs) for High Density Corridors (HDC) Package - 2 in Bengaluru, Karnataka comprising of the following roads: [HDC 5: Hosur Road, HDC 6: Bannerughatta Road, HDC 7: Kanakpura Road, HDC12d: Outer Ring Road. Total Length 91.85 Km (Approximate)].

Table 1.1: Length of Project Corridors in Package 3


| SL No | Name of the Road / Junction | Project length considered in km |
|---------------------------|---|---------------------------------|
| Package - 3 | | |
| 1 | HDC 5: Hosur Road - from Vellara Junction to Silk Board via Madiwala. | 6.45 |
| 2 | HDC 6: Bannerughatta Road - from Hosur Road to Bannerghatta via Jayadeva, Jedimara, Kolifarm. | 16.50 |
| 3 | HDC 7: Kanakpura Road – from KR Road to Nice Road via Banashankari, Konanakunte Cross | 14.50 |
| 4 | HDC 12d: Outer Ring Road – from Silk Board to Nayandanahalli via Jayadeva jn. Jedimara, Sarakki | 12.00 |
| Total length in Km | | 91.85 |



Index Map of Project Road

HDC 5: Hosur Road - from Vellara Junction to Silk Board via Madiwala.

The scope of work for the stretch HDC No. 5 starts at Vellara Junction on Hosur Road and ends at Silk Board via Madiwala with a total length of 6.45 Km. This road has 4 lane divided Carriageway. This stretch is the mix of commercial and residential layouts on both sides. This road experiences heavy commercial vehicles movement. A sketch indicating the alignment plan is shown below.,




| Index | | |
|-------|--|---------|
| | Work considered by KRDCCL for Initial Improvements | 0.00 Km |
| | Ongoing / Tendered works under BBMP | 6.45 Km |
| | Total Length | 6.45 Km |

Figure 2.1 Key Plan of Alignment (Hosur Road)

HDC 6: Bannerugatta Road - from Hosur Road to Bannerghatta via Jayadeva, Jedimara, Kolifarm.

The scope of work for the stretch HDC No.6 Bannerugatta Road from Hosur Road to Bannerghatta starts at Hosur Road and ends at Bannerghatta via Jayadeva, Jedimara, Kolifarm with a total length of 16.50 Km. This road has 4/6 lane divided Carriageway. This stretch is the mix of commercial and residential layouts on both sides. A sketch indicating the alignment plan is shown below




| Index | |
|---|----------------|
| Work considered by KRDCL for Initial Improvements | 0.00 Km |
| Ongoing / Tendered works under BBMP | 6.90 Km |
| Ongoing / Tendered works under BMRCL | 9.60 Km |
| Total Length | 16.5 Km |

Figure 2.2 Key Plan of Alignment (Bannerughatta Road)

HDC 7: Kanakpura Road - from KR Road to Nice Road via Banashankari, Konanakunte Cross

The scope of work for the stretch HDC No.7 Kanakpura Road from KR Road to Nice Road starts at KR Road and ends at Nice Road with a total length of 14.50 Km. This road has 4 lane divided Carriageway. This stretch is the mix of commercial and residential layouts on both sides. A sketch indicating the alignment plan is shown below.




| Index | |
|---|----------------|
| Work considered by KRDCL for Initial Improvements | 0.50 Km |
| Ongoing / Tendered works under BBMP | 8.30 Km |
| Ongoing / Tendered works under BMRCL | 5.70 Km |
| Total Length | 14.5 Km |

Figure 2.3 Key Plan of Alignment (Kanakapura Road)

HDC 12d: Outer Ring Road – from Silk Board to Nayandanahalli

The scope of work for the stretch HDC No.12d Outer Ring Road starts at Silkboard and ends at Nayandanahalli with a total length of 12.00 Km. This road has 4/6 lane divided Carriageway. This stretch is the mix of commercial and residential layouts on both sides. A sketch indicating the alignment plan is shown below.



| Index | | |
|--------------|---|----------|
| | Work considered by KRDCL for Initial Improvements | 0.00 Km |
| | Ongoing / Tendered works under BBMP | 9.80 Km |
| | Ongoing / Tendered works under BMRCL | 2.20 Km |
| Total Length | | 12.00 Km |

Figure 2.4 Key Plan of Alignment (Outer Ring Road – Silk Board to Mysore Road)

1.2 Objective of the Project

The objective of the consultancy Services is to provide the required technical services to KRDCL in preparation of Detailed designs, Drawings, Estimations, Assisting in Tender Processes, and Project Management including construction supervision, maintenance supervision of the High-Density Corridors.

The following works are intended to be carried out on the Project Road:

1. Identification of possible improvements in the existing alignment.
2. Improvement of drainage at poor drainage locations and clear identification of the same on the drawings.
3. Rehabilitation /Reconstruction of bridges and culverts where necessary,

4. Improvement to junctions/intersections
5. Improvement of sidewalks with all required appurtenances like bollards, chamber covers, landscaping, access to properties, lighting etc.
6. Improvements to Signage, road markings
7. Street lighting of the corridor
8. Requirement for Provision of pedestrian facilities
9. Requirement for Improvement of junctions/intersections.
10. Assessing the Provision of road furniture and adequate road markings.
11. Assessing the Provision of traffic control devices where appropriate.
12. Preparation of roadway plans, sidewalk, median and all required drawings to be issued for good for construction.
13. Preparation of BOQ, specifications, estimates.
14. Preparation of routine maintenance intervals and specifications.
15. Presentations, meetings and discussions with various stakeholders in city.
16. Assisting in Preparation of bidding documents (schedules, specifications and drawings).
17. Bid processing assistance.

1.3 Scope of the Project

The broad scope of work encompasses

Stage 1: Carrying out surveys, investigations, detailed designs on the project roads, estimation, costing and submission of good for construction drawings and

Stage 2: Project management including construction supervision, maintenance supervision, progress reports and PMS uploading.

Following is the brief scope of work as extracted from the RFP Document for Stage 1.

- Analysis of Available Reports and data's from KRDCL, BBMP and other departments.
- Survey and investigations of the Project Road
- Traffic Studies and Analysis
- Road safety assessment
- Pavement Structural Strength
- Topographic Survey

- Bridge / Structures Inventory and Condition Survey
- Hydrology and Drainage Investigations
- Pavement crust thickness
- Detailed Design
- Report and Drawings
- Bid process management

1.4 Meetings with Clients and Stakeholders

During the course of preparation of DPR meetings are held with client and Stakeholders for finalization of improvement proposals and other technical aspects. Following Meetings were held with various stakeholders for administration and Technical approval.

| Sl No | Meeting held on | Meeting Chaired by | Meeting Location |
|-------|-----------------|---|--------------------------|
| 1 | 30/11/2020 | Additional Chief Secretary, PWD | Vikasa Soudha |
| 2 | 1/12/2020 | Additional Commissioner, Bangalore Traffic Police | Bangalore Traffic Centre |
| 3 | 2/12/2020 | DULT Commissioner | DULT office |
| 4 | 11/12/2020 | Additional Commissioner, Bangalore Traffic Police | Bangalore Traffic Centre |
| 5 | 11/12/2020 | Additional Chief Secretary, PWD | Vikasa Soudha |
| 6 | 16/12/2020 | Managing Director, KRDCL | KRDCL Office |
| 7 | 24/12/2020 | Chief Secretary | Vidhana Soudha |
| 8 | 29/12/2020 | DULT Commissioner | Online |
| 9 | 4/1/2021 | Chairman, Technical committee | KRDCL Office |
| 10 | 8/1/2021 | ACS, UDD | Vikasa Soudha |
| 11 | 12/1/2021 | ACS, UDD | Vikasa Soudha |
| 12 | 13/1/2021 | ACS, UDD | Vikasa Soudha |
| 13 | 30/11/2020 | Additional Chief Secretary, PWD | Vikasa Soudha |

1.5 Structure of the Report

The Draft Project Report has been structured as follows.

Volume – 1: Main report

Chapter 1 : Project back ground

Chapter 2 : Surveys and investigations carried out and Interpretation of data

Chapter 3 : Improvement Proposals

Chapter 4 : Cost Estimation

Annexures

Volume – II: Drawings

Strip Plan

Plan with Sections

Standard Drawings

Volume – III: Cost Estimation

Bill of Quantities - Package 1

Bill of Quantities – Individual Roads in Package 1

Cost Estimation - Individual Roads in Package 1

Rate Analysis

Volume – IV: Schedules

Schedule A: Existing Features

Schedule B: Initial Improvement Proposals.

Schedule C: Specifications and Standards

Schedule D: Interim Milestones for Initial Improvement Works

Schedule E: Applicable Permits

Schedule F: Maintenance Requirements

Schedule G: Control and Command Centre

Schedule H: Payments Schedule

Schedule I: Safety Requirements

Schedule J: Inter-Departmental Coordination Standard Operating Procedure
(Sop) & Support Agreement

Schedule K: Format of Bank Guarantee for Performance Security.

Schedule L: Appointment of Project Management Consultant

Schedule M: Format of Bank Guarantee for Advance Payment

Schedule N: Change of Scope Formats

Schedule O: Work Order Format for Additional Works

CHAPTER 2: SURVEYS AND INVESTIGATIONS

2.1 Introduction

This chapter deals with various surveys and Investigations carried out as per the Terms of Reference and required for quality compliance of the Project design and report preparation.

Major surveys and Investigations carried out are as follows:

- Road Inventory
- Pavement condition survey
- Structural Inventory
- Traffic surveys
- Topographic surveys
- FWD Survey

2.2 Road Inventory and Condition Surveys

2.2.1 Road Inventory

Road Inventory surveys have been conducted. Surveys are carried out as per the standard methodology / IRC guidelines. However brief methodology is given below:

As per the ToR consultants have to propose improvement proposals for the existing roads along the project corridors. Hence, the road and bridge inventory and condition surveys were conducted accordingly.

The road inventory survey involves making visual estimates and actual measurements of geometric and cross-sectional elements of the road and its deficiencies. This survey involves the collection of the data pertaining to the existing road such as the pavement type, width of the carriageway, type of the shoulder and its width, condition of road, type and condition of drain, footpath, median islands, number of CD structures, available land widths etc. Road inventory has been recorded in a standard format.

The team has travelled and walked along the alignments and adjacent roads collected first-hand information on the width and type of carriage way, type and condition of road, junctions, traffic intensity, width of footpath cum drains, Median islands, cross drainage structures, Bus stops/Bus bays/Bus shelters and relevant details of Grade separators, Metro Rail crossings and skywalks comprising in the proposed High-Density corridor are noted.

2.2.2 Right of Way

The Right of way details for the project road is taken by measuring drain to drain or footpath outer edge at regular intervals, RoW vary from 12m to 60 m. Details of RoW is shown in below table

Table 2.1: Table showing details of RoW along for HDC-05 Hosur Road

| From in Kms | To in Kms | Length in m | ROW in m |
|-------------|-----------|-------------|----------|
| 0+000 | 000+230 | 230.00 | 18.3 |
| 0+230 | 000+330 | 100.00 | 18.4 |
| 0+330 | 000+450 | 120.00 | 16.4 |
| 0+450 | 000+520 | 70.00 | 18.3 |
| 0+520 | 000+780 | 260.00 | 23.0 |
| 0+780 | 000+830 | 50.00 | 22.2 |
| 0+830 | 000+960 | 130.00 | 14.7 |
| 0+960 | 001+090 | 130.00 | 14.7 |
| 1+090 | 001+150 | 60.00 | 16.9 |
| 1+150 | 001+280 | 130.00 | 16.9 |
| 1+280 | 001+440 | 160.00 | 22.8 |
| 1+440 | 001+490 | 50.00 | 31.1 |
| 1+490 | 001+600 | 110.00 | 26.9 |
| 1+600 | 001+620 | 20.00 | 25.0 |
| 1+620 | 001+780 | 160.00 | 16.5 |
| 1+780 | 001+910 | 130.00 | 32.5 |
| 1+910 | 002+270 | 360.00 | 29.2 |
| 2+270 | 002+330 | 60.00 | 31.0 |
| 2+330 | 002+500 | 170.00 | 27.6 |
| 2+500 | 002+530 | 30.00 | 18.8 |
| 2+530 | 002+670 | 140.00 | 31.5 |
| 2+670 | 002+700 | 30.00 | 28.6 |
| 2+700 | 002+800 | 100.00 | 29.0 |
| 2+800 | 003+230 | 430.00 | 29.5 |
| 3+230 | 003+690 | 460.00 | 31.3 |
| 3+690 | 003+940 | 250.00 | 25.8 |
| 3+940 | 004+020 | 80.00 | 29.3 |
| 4+020 | 004+070 | 50.00 | 33.1 |
| 4+070 | 004+130 | 60.00 | 32.00 |
| 4+130 | 004+280 | 150.00 | 29.2 |
| 4+280 | 004+300 | 20.00 | 29.4 |
| 4+300 | 004+410 | 110.00 | 33.1 |
| 4+410 | 004+540 | 130.00 | 29.6 |
| 4+540 | 004+770 | 230.00 | 29.5 |
| 4+770 | 005+020 | 250.00 | 19.25 |
| 5+020 | 005+390 | 370.00 | 34.9 |



2.2.6 Footpath

At some locations drain cum footpath is provided where land availability is limited where sufficient land is available footpaths are provided separately. Details are shown in below table.

Table 2.17: Table showing details of footpath for HDC-05 Hosur Road

| From in Kms | To in Kms | Length in m | Footpath | | | |
|----------------|--------------|----------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | RHS | |
| | | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 0+000 | 0+230 | 230.00 | Paved | 2.20 | | |
| 0+230 | 0+330 | 100.00 | Paved | 0.80 | Paved | 1.5 |
| 0+330 | 0+450 | 120.00 | Paved | 0.60 | Paved | 1.5 |
| 0+450 | 0+520 | 70.00 | Paved | 1.00 | Paved | 1.0 |
| 0+520 | 0+780 | 260.00 | Paved | 0.80 | Paved | 1.0 |
| 0+780 | 0+830 | 50.00 | | | Paved | 1.3 |
| 0+830 | 0+960 | 130.00 | | | Paved | 1.3 |
| 0+960 | 1+090 | 130.00 | | | Paved | 1.8 |
| 1+090 | 1+150 | 60.00 | | | Paved | 0.6 |
| 1+150 | 1+280 | 130.00 | | | Paved | 1.6 |
| 1+280 | 1+440 | 160.00 | | | Paved | 1.6 |
| 1+440 | 1+490 | 50.00 | Paved | 3.30 | Paved | 1.6 |
| 1+490 | 1+600 | 110.00 | Paved | 1.00 | Paved | 0.9 |
| 1+600 | 1+620 | 20.00 | | | Paved | 0.9 |
| 1+620 | 1+780 | 160.00 | | | Paved | 0.0 |
| 1+780 | 1+910 | 130.00 | Paved | 2.00 | Paved | 3.3 |
| 1+910 | 2+270 | 360.00 | Paved | 2.00 | Paved | 1.3 |

| From in Kms | To in Kms | Length in m | Footpath | | | |
|----------------|--------------|----------------|-------------------------|-------|-------------------------|-------|
| | | | LHS | | RHS | |
| | | | Type (Paved/Unpaved) | Width | Type (Paved/Unpaved) | Width |
| 2+270 | 2+330 | 60.00 | Paved | 2.00 | Paved | 1.3 |
| 2+330 | 2+500 | 170.00 | | | | |
| 2+500 | 2+530 | 30.00 | | | | |
| 2+530 | 2+670 | 140.00 | | | | |
| 2+670 | 2+700 | 30.00 | Paved | 1.30 | | |
| 2+700 | 2+800 | 100.00 | Paved | 1.30 | Paved | 1.3 |
| 2+800 | 3+230 | 430.00 | Paved | 1.30 | Paved | 1.8 |
| 3+230 | 3+690 | 460.00 | Paved | 1.50 | Paved | 1.8 |
| 3+690 | 3+940 | 250.00 | Paved | 1.30 | Paved | 1.3 |
| 3+940 | 4+020 | 80 | Paved | 3.30 | Paved | 2.5 |
| 4+020 | 4+070 | 50 | Paved | 1.80 | Paved | 2.5 |
| 4+070 | 4+130 | 60 | Paved | 1.60 | Paved | 2.5 |
| 4+130 | 4+280 | 150 | Paved | 1.80 | Paved | 1.0 |
| 4+280 | 4+300 | 20 | Paved | 2.80 | Paved | 1.3 |
| 4+300 | 4+410 | 110 | Paved | 2.80 | Paved | 1.3 |
| 4+410 | 4+540 | 130 | Paved | 2.80 | Paved | 1.3 |
| 4+540 | 4+770 | 230 | Paved | 2.80 | Paved | 1.3 |
| 4+770 | 5+020 | 250 | | | | |
| 5+020 | 5+390 | 370 | Paved | 3.60 | Paved | 0.9 |
| 5+390 | 5+580 | 190 | Paved | 0.90 | | |
| 5+580 | 5+830 | 250 | | | | |

Table 2.18: Table showing details of footpath for HDC-06 Bannerghatta Road

| From, Kms | To, Kms | Length in m | Footpath | | | |
|-----------|------------|----------------|----------------|-------|----------------|-------|
| | | | LHS | | RHS | |
| | | | Type (P/UP) | Width | Type (P/UP) | Width |
| 0+000 | 0+100 | 100.00 | Paved | 1.7 | Paved | 1.7 |
| 0+100 | 0+200 | 100.00 | Paved | 1.7 | Paved | 1.7 |
| 0+200 | 0+300 | 100.00 | Paved | 1.7 | Paved | 1.7 |
| 0+300 | 0+400 | 100.00 | Paved | 1.7 | Paved | 1.7 |
| 0+400 | 0+500 | 100.00 | Paved | 1.7 | Paved | 1.7 |
| 0+500 | 0+600 | 100.00 | Paved | 1.5 | Paved | 3.0 |
| 0+600 | 0+700 | 100.00 | Paved | 1.5 | Paved | 2.0 |
| 0+700 | 0+800 | 100.00 | Paved | 1.5 | Paved | 1.5 |

| From, Kms | To, Kms | Length in m | Footpath | | | |
|-----------|---------|-------------|-------------|-------|-------------|-------|
| | | | LHS | | RHS | |
| | | | Type (P/UP) | Width | Type (P/UP) | Width |
| 0+800 | 0+900 | 100.00 | Paved | 1.5 | Paved | 0.0 |
| 0+900 | 1+000 | 100.00 | Paved | 1.5 | Paved | 1.5 |
| 1+000 | 1+100 | 100.00 | Paved | 1.5 | Paved | 3.0 |
| 1+100 | 1+200 | 100.00 | Paved | 1.5 | Paved | 1.7 |
| 1+200 | 1+300 | 100.00 | Paved | 1.7 | Paved | 1.7 |
| 1+300 | 1+400 | 100.00 | Paved | 1.5 | Paved | 1.5 |
| 1+400 | 1+500 | 100.00 | Paved | 1.7 | Paved | 1.7 |
| 1+500 | 1+600 | 100.00 | Paved | 1.2 | Paved | 1.2 |
| 1+600 | 1+700 | 100.00 | Paved | 2.0 | Paved | 2.0 |
| 1+700 | 1+800 | 100.00 | Paved | 2.0 | Paved | 2.0 |
| 1+800 | 1+900 | 100.00 | Paved | 2.0 | Paved | 2.0 |
| 1+900 | 2+000 | 100.00 | Paved | 2.0 | Paved | 2.0 |
| 2+000 | 2+100 | 100.00 | Paved | 2.0 | Paved | 2.0 |
| 2+100 | 2+200 | 100.00 | Paved | 5.0 | Paved | 3.0 |
| 2+200 | 2+300 | 100.00 | Paved | 6.0 | Paved | 3.0 |
| 2+300 | 2+400 | 100.00 | Paved | 4.5 | Paved | 3.0 |
| 2+400 | 2+500 | 100.00 | Paved | 1.7 | Paved | 1.7 |
| 2+500 | 2+600 | 100.00 | Paved | 1.7 | Paved | 1.7 |
| 2+600 | 2+700 | 100.00 | Paved | 1.0 | Paved | 1.0 |
| 2+700 | 2+800 | 100.00 | Paved | 1.0 | Paved | 1.0 |
| 2+800 | 2+900 | 100.00 | Paved | 1.5 | Paved | |
| 2+900 | 3+000 | 100.00 | Paved | 1.5 | Paved | |
| 3+000 | 3+100 | 100.00 | Paved | 1.5 | Paved | |
| 3+100 | 3+200 | 100.00 | Paved | 1.5 | Paved | |
| 3+200 | 3+300 | 100.00 | Paved | 1.5 | Paved | |
| 3+300 | 3+400 | 100.00 | Paved | 1.2 | Paved | |
| 3+400 | 3+500 | 100.00 | Paved | 1.2 | Paved | |
| 3+500 | 3+600 | 100.00 | Paved | 3.0 | Paved | |
| 3+600 | 3+700 | 100.00 | Paved | | Paved | |
| 3+700 | 3+800 | 100.00 | Paved | 1.2 | Paved | 3.5 |
| 3+800 | 3+900 | 100.00 | Paved | 1.2 | Paved | 2.0 |
| 3+900 | 4+000 | 100.00 | Paved | 2.5 | Paved | 6.5 |
| 4+000 | 4+100 | 100.00 | Paved | 2.5 | Paved | 1.5 |
| 4+100 | 4+200 | 100.00 | Paved | 2.5 | Paved | 1.0 |
| 4+200 | 4+300 | 100.00 | Paved | 2.5 | Paved | 1.0 |
| 4+300 | 4+400 | 100.00 | Paved | 2.5 | Paved | 1.0 |
| 4+400 | 4+500 | 100.00 | Paved | 2.5 | Paved | 1.0 |
| 4+500 | 4+600 | 100.00 | Paved | 4.0 | Paved | 2.5 |
| 4+600 | 4+700 | 100.00 | Paved | 1.5 | Paved | 1.5 |
| 4+700 | 4+800 | 100.00 | Paved | 7.0 | Paved | 1.0 |
| 4+800 | 4+900 | 100.00 | Paved | 1.5 | Paved | 1.0 |

| From, Kms | To, Kms | Length in m | Footpath | | | |
|-----------|---------|-------------|-------------|-------|-------------|-------|
| | | | LHS | | RHS | |
| | | | Type (P/UP) | Width | Type (P/UP) | Width |
| 4+900 | 5+000 | 100.00 | Paved | 1.5 | Paved | 1.0 |
| 5+000 | 5+100 | 100.00 | Paved | 1.5 | Paved | 2.0 |
| 5+100 | 5+200 | 100.00 | Paved | 1.5 | Paved | 1.5 |
| 5+200 | 5+300 | 100.00 | Paved | 4.5 | Paved | 1.0 |
| 5+300 | 5+400 | 100.00 | Paved | 4.5 | Paved | 2.0 |
| 5+400 | 5+500 | 100.00 | Paved | 4.5 | Paved | 2.0 |
| 5+500 | 5+600 | 100.00 | Paved | 3.0 | Paved | 2.0 |
| 5+600 | 5+700 | 100.00 | Paved | 1.7 | Paved | 2.0 |
| 5+700 | 5+800 | 100.00 | Paved | 1.7 | Paved | 2.0 |
| 5+800 | 5+900 | 100.00 | Paved | 1.5 | Paved | 2.0 |
| 5+900 | 6+000 | 100.00 | Paved | 1.5 | Paved | 2.0 |
| 6+000 | 6+100 | 100.00 | Paved | 1.5 | Paved | 2.0 |
| 6+100 | 6+200 | 100.00 | Paved | 2.5 | Paved | 1.5 |
| 6+200 | 6+300 | 100.00 | Paved | 2.5 | Paved | 2.0 |
| 6+300 | 6+400 | 100.00 | Paved | 3.0 | Paved | 0.0 |
| 6+400 | 6+500 | 100.00 | Paved | 6.5 | Paved | 2.0 |
| 6+500 | 6+600 | 100.00 | Paved | 6.5 | Paved | 2.0 |
| 6+600 | 6+700 | 100.00 | Paved | 5.0 | Paved | 2.0 |
| 6+700 | 6+800 | 100.00 | Paved | 0.0 | Paved | 2.0 |
| 6+800 | 6+900 | 100.00 | Paved | 0.0 | Paved | 2.5 |
| 6+900 | 7+000 | 100.00 | Paved | 6.8 | Paved | 3.5 |
| 7+000 | 7+100 | 100.00 | Paved | 6.8 | Paved | 2.0 |
| 7+100 | 7+200 | 100.00 | Paved | 6.8 | Paved | 2.0 |
| 7+200 | 7+300 | 100.00 | Paved | 1.2 | Paved | 1.5 |
| 7+300 | 7+400 | 100.00 | Paved | 1.2 | Paved | 1.5 |
| 7+400 | 7+500 | 100.00 | Paved | 1.5 | Paved | 1.5 |
| 7+500 | 7+600 | 100.00 | Paved | 1.5 | Paved | 2.0 |
| 7+600 | 7+700 | 100.00 | Paved | 1.5 | Paved | 2.0 |
| 7+700 | 7+800 | 100.00 | Paved | 0.0 | Paved | 2.0 |
| 7+800 | 7+900 | 100.00 | Paved | 1.5 | Paved | 2.0 |
| 7+900 | 8+000 | 100.00 | Paved | 1.5 | Paved | 2.0 |
| 8+000 | 8+100 | 100.00 | Paved | 1.5 | Paved | 2.0 |
| 8+100 | 8+200 | 100.00 | Paved | 2.0 | Paved | 2.0 |
| 8+200 | 8+300 | 100.00 | Paved | 2.0 | Paved | 2.0 |
| 8+300 | 8+400 | 100.00 | Paved | 2.0 | Paved | 2.0 |
| 8+400 | 8+500 | 100.00 | Paved | 1.0 | Paved | 0.0 |
| 8+900 | 9+000 | 100.00 | Paved | 1.5 | Paved | 1.5 |
| 9+000 | 9+100 | 100.00 | Paved | 1.5 | Paved | 1.5 |
| 9+100 | 9+200 | 100.00 | Paved | 1.8 | Paved | 0.0 |
| 9+200 | 9+300 | 100.00 | Paved | 1.8 | Paved | 0.0 |
| 9+300 | 9+400 | 100.00 | Paved | 1.8 | Paved | 0.0 |

| From, Kms | To, Kms | Length in m | Footpath | | | |
|-----------|---------|-------------|-------------|-------|-------------|-------|
| | | | LHS | | RHS | |
| | | | Type (P/UP) | Width | Type (P/UP) | Width |
| 9+400 | 9+500 | 100.00 | Paved | 1.8 | Paved | 1.5 |
| 9+500 | 9+600 | 100.00 | Paved | 1.5 | Paved | 0.0 |
| 9+600 | 9+700 | 100.00 | Paved | 1.5 | Paved | 0.0 |
| 9+700 | 9+800 | 100.00 | Paved | 1.7 | Paved | 0.0 |
| 9+800 | 9+900 | 100.00 | Paved | 1.5 | Paved | 0.0 |
| 9+900 | 10+000 | 100.00 | Paved | 1.5 | Paved | 0.0 |
| 10+000 | 10+100 | 100.00 | Paved | 1.5 | Paved | 0.0 |
| 10+100 | 10+200 | 100.00 | Paved | 1.5 | Paved | 0.0 |
| 10+200 | 10+300 | 100.00 | Paved | 1.5 | Paved | 1.5 |
| 10+300 | 10+400 | 100.00 | Paved | 1.5 | Paved | 1.5 |
| 10+400 | 10+500 | 100.00 | | | Paved | 1.5 |
| 10+500 | 10+600 | 100.00 | | | Paved | 2.0 |
| 10+600 | 10+700 | 100.00 | | | | 0.0 |
| 10+700 | 10+800 | 100.00 | Closed | 1.5 | | 0.0 |
| 10+800 | 10+900 | 100.00 | Closed | 1.5 | Closed | 1.5 |
| 10+900 | 11+000 | 100.00 | Closed | 1.5 | | 0.0 |
| 11+000 | 11+100 | 100.00 | Closed | 1.5 | | 0.0 |
| 11+100 | 11+200 | 100.00 | Closed | 1.5 | Closed | 1.5 |
| 11+200 | 11+300 | 100.00 | Closed | 1.5 | Closed | 1.0 |
| 11+300 | 11+400 | 100.00 | | | | 0.0 |
| 11+400 | 11+500 | 100.00 | | | Closed | 1.5 |
| 11+600 | 11+700 | 100.00 | | | Closed | 2.5 |
| 11+700 | 11+800 | 100.00 | | | Closed | 1.5 |
| 11+800 | 11+900 | 100.00 | Closed | 1.7 | Closed | 1.8 |
| 11+900 | 12+000 | 100.00 | Closed | 1.7 | Closed | 1.5 |
| 12+000 | 12+100 | 100.00 | Closed | 1.7 | Closed | 1.5 |
| 12+300 | 12+400 | 100.00 | | | Closed | 1.8 |
| 12+400 | 12+500 | 100.00 | | | | |
| 12+500 | 12+600 | 100.00 | Closed | 1.4 | Closed | 1.4 |
| 12+600 | 12+700 | 100.00 | Closed | 1.4 | | |
| 12+700 | 12+800 | 100.00 | Closed | 1.4 | | |
| 12+800 | 12+900 | 100.00 | Closed | 1.5 | | |
| 12+900 | 13+000 | 100.00 | Closed | 1.5 | | |
| 14+900 | 15+000 | 100.00 | Closed | 1.5 | | |
| 15+300 | 15+400 | 100.00 | | | Closed | 1.0 |
| 15+400 | 15+500 | 100.00 | Closed | 1.0 | | |
| 15+500 | 15+600 | 100.00 | Closed | 1.0 | | |
| 15+800 | 15+900 | 100.00 | | | Closed | 1.0 |
| 16+000 | 16+100 | 100.00 | | | Closed | 1.0 |
| 16+100 | 16+200 | 100.00 | | | Closed | 1.0 |
| 16+200 | 16+300 | 100.00 | | | Closed | 1.2 |

| From, Kms | To, Kms | Length in m | Footpath | | | |
|-----------|---------|-------------|-------------|-------|-------------|-------|
| | | | LHS | | RHS | |
| | | | Type (P/UP) | Width | Type (P/UP) | Width |
| 16+300 | 16+400 | 100.00 | | | Closed | 1.2 |

Table 2.19: Table showing details of footpath for HDC-7 Kanakpura Road

| From, Kms | To, Kms | Length in m | Footpath | | | |
|-----------|---------|-------------|-------------|-------|-------------|-------|
| | | | LHS | | RHS | |
| | | | Type (P/UP) | Width | Type (P/UP) | Width |
| 0+000 | 0+100 | 100 | Paved | 3 | Paved | 2 |
| 0+100 | 0+200 | 100 | Paved | 3 | Paved | 2 |
| 0+200 | 0+300 | 100 | Paved | 3 | Paved | 3 |
| 0+300 | 0+400 | 100 | Paved | 3 | Paved | 3 |
| 0+400 | 0+500 | 100 | Paved | 3 | Paved | 4 |
| 0+500 | 0+600 | 100 | Paved | 5 | Paved | 3 |
| 0+600 | 0+700 | 100 | Paved | 2 | Paved | 3 |
| 0+700 | 0+800 | 100 | Paved | 3 | Paved | 0 |
| 0+800 | 0+900 | 100 | Paved | 3 | Paved | 3 |
| 0+900 | 1+000 | 100 | Paved | 3 | Paved | 3 |
| 1+000 | 1+100 | 100 | Paved | 4 | Paved | 5 |
| 1+100 | 1+200 | 100 | Paved | 4 | Paved | 5 |
| 1+200 | 1+300 | 100 | Paved | 1 | Paved | 3 |
| 1+300 | 1+400 | 100 | Paved | 3 | Paved | 2 |
| 1+400 | 1+500 | 100 | Paved | 3 | Paved | 2 |
| 1+500 | 1+600 | 100 | Paved | 3 | Paved | 2 |
| 1+600 | 1+700 | 100 | Paved | 2 | Paved | 3 |
| 1+700 | 1+800 | 100 | Paved | 2 | Paved | 4 |
| 1+800 | 1+900 | 100 | Paved | 3 | Paved | 4 |
| 1+900 | 2+000 | 100 | Paved | 3 | Paved | 4 |
| 2+000 | 2+100 | 100 | Paved | 3 | Paved | 4 |
| 2+100 | 2+200 | 100 | Paved | 3 | Paved | 4 |
| 2+200 | 2+300 | 100 | Paved | 3 | Paved | 3 |
| 2+300 | 2+400 | 100 | Paved | 3 | Paved | 3 |
| 2+400 | 2+500 | 100 | Paved | 2 | Paved | 2 |
| 2+500 | 2+600 | 100 | Paved | 2 | Paved | 2 |
| 2+600 | 2+700 | 100 | Paved | 2 | Paved | 2 |
| 2+700 | 2+800 | 100 | Paved | 3 | Paved | 2 |
| 2+800 | 2+900 | 100 | Paved | 3 | Paved | 3 |
| 2+900 | 3+000 | 100 | Paved | 3 | Paved | 3 |
| 3+000 | 3+100 | 100 | Paved | 2 | Paved | 2 |
| 3+100 | 3+200 | 100 | Paved | 3 | Paved | 2 |
| 3+200 | 3+300 | 100 | Paved | 3 | Paved | 2 |
| 3+300 | 3+400 | 100 | Paved | 3 | Paved | 2 |

| From, Kms | To, Kms | Length in m | Footpath | | | |
|-----------|---------|----------------|-------------|-------|-------------|-------|
| | | | LHS | | RHS | |
| | | | Type (P/UP) | Width | Type (P/UP) | Width |
| 3+400 | 3+500 | 100 | Paved | 3 | Paved | 2 |
| 3+500 | 3+600 | 100 | Paved | 3 | Paved | 2 |
| 3+600 | 3+700 | 100 | Paved | 3 | Paved | 3 |
| 3+700 | 3+800 | 100 | Paved | 3 | Paved | 3 |
| 3+800 | 3+900 | 100 | Paved | 3 | Paved | 2 |
| 3+900 | 4+000 | 100 | Paved | 3 | Paved | 2 |
| 4+000 | 4+100 | 100 | Paved | 3 | Paved | 2 |
| 4+100 | 4+200 | 100 | Paved | 3 | Paved | 3 |
| 4+200 | 4+300 | 100 | Paved | 3 | Paved | 3 |
| 4+300 | 4+400 | 100 | Paved | 2 | Paved | 2 |
| 4+400 | 4+500 | 100 | Paved | 2 | Paved | 2 |
| 4+500 | 4+600 | 100 | Paved | 1 | Paved | 1 |
| 4+600 | 4+650 | 50 | Paved | 1 | Paved | 1 |
| 4+650 | 4+700 | 50 | Paved | 0 | Paved | 0 |
| 4+700 | 4+800 | 100 | Paved | 0 | Paved | 0 |
| 4+800 | 4+900 | 100 | Paved | 4 | Paved | 6 |
| 4+900 | 5+000 | 100 | Paved | 4 | Paved | 2 |
| 5+000 | 5+100 | 100 | Paved | 4 | Paved | 2 |
| 5+100 | 5+200 | 100 | Paved | 2 | Paved | 2 |
| 5+200 | 5+300 | 100 | Paved | 2 | Paved | 3 |
| 5+300 | 5+400 | 100 | Paved | 2 | Paved | 2 |
| 5+400 | 5+500 | 100 | Paved | 2 | Paved | 2 |
| 5+500 | 5+600 | 100 | Paved | 2 | Paved | 2 |
| 5+600 | 5+700 | 100 | Paved | 2 | Paved | 3 |
| 5+700 | 5+800 | 100 | Paved | 2 | Paved | 2 |
| 5+800 | 5+900 | 100 | Paved | 3 | Paved | 3 |
| 5+900 | 6+000 | 100 | Paved | 3 | Paved | 3 |
| 6+000 | 6+100 | 100 | Paved | 2 | Paved | 3 |
| 6+100 | 6+200 | 100 | Paved | 2 | Paved | 2 |
| 6+200 | 6+300 | 100 | Paved | 2 | Paved | 2 |
| 6+300 | 6+400 | 100 | Paved | 2 | Paved | 2 |
| 6+400 | 6+500 | 100 | Paved | 2 | Paved | 3 |
| 6+500 | 6+600 | 100 | Paved | 2 | Paved | 3 |
| 6+600 | 6+700 | 100 | Paved | 3 | Paved | 3 |
| 6+700 | 6+800 | 100 | Paved | 2 | Paved | 2 |
| 6+800 | 6+900 | 100 | Paved | 2 | Paved | 2 |
| 6+900 | 7+000 | 100 | Paved | 2 | Paved | 2 |
| 7+000 | 7+100 | 100 | Paved | 2 | Paved | 2 |
| 7+100 | 7+200 | 100 | Paved | 2 | Paved | 2 |
| 7+200 | 7+300 | 100 | Paved | 3 | Paved | 4 |
| 7+300 | 7+400 | 100 | Paved | 1 | Paved | 0 |

| SI No | Chainage | Side | | Remarks |
|---------------------------------|----------|------|-----|-------------------------------------|
| | | LHS | RHS | |
| 71 | 12+680 | Yes | - | Koli Farm Gate |
| 72 | 12+690 | - | Yes | Viewers colony |
| HDC 07 - Kanakapura Road | | | | |
| 73 | 0+050 | Yes | - | Makkalakota Busstop |
| 74 | 0+390 | Yes | - | Mahila Seva Samaja Busstop |
| 75 | 0+450 | - | Yes | Mahila Seva Samaja Busstop |
| 76 | 0+860 | Yes | - | National college Busstop |
| 77 | 0+880 | - | Yes | National college Busstop |
| 78 | 0+960 | - | Yes | National college Busstop |
| 79 | 1+720 | Yes | - | Basavanagudi Police Station Busstop |
| 80 | 1+750 | - | Yes | Basavanagudi Police Station Busstop |
| 81 | 3+090 | Yes | - | Yediyur busstop |
| 82 | 3+150 | - | Yes | Yediyur busstop |
| 83 | 3+730 | - | Yes | Deepak Nursing Home Busstop |
| 84 | 3+750 | Yes | - | Deepak Nursing Home Busstop |
| 85 | 4+410 | - | Yes | Hunasemara Busstop |
| 86 | 4+420 | Yes | - | Hunasemara Busstop |
| 87 | 4+740 | Yes | - | Banashankari Busstation |
| 88 | 5+570 | Yes | - | Sarakki Busstop |
| 89 | 5+580 | - | Yes | Sarakki Busstop |
| 90 | 5+840 | Yes | - | Jaya Prakash Nagar Busstop |
| 91 | 5+890 | - | Yes | Sarakki Signal Busstop |
| 92 | 6+470 | Yes | - | Jaraganahalli Cross Busstop |
| 93 | 6+590 | - | Yes | Jaraganahalli Busstop |
| 94 | 6+940 | - | Yes | Yelachenahalli Busstop |
| 95 | 6+950 | Yes | - | Yelachenahalli Busstop |
| 96 | 7+200 | Yes | Yes | Yelachenahalli Metro Busstop |
| 97 | 7+360 | Yes | - | Yelachenahalli Metro Busstop |
| 98 | 7+600 | Yes | - | Metro Busstop |
| 99 | 7+620 | - | Yes | Metro Busstop |
| 100 | 8+000 | Yes | - | Konanakunte Cross Busstop |
| 101 | 8+060 | - | Yes | Konanakunte Cross Busstop |
| 102 | 8+180 | Yes | - | Konanakunte Cross Busstop |
| 103 | 8+200 | - | Yes | Konanakunte Cross Busstop |
| 104 | 9+090 | - | Yes | Doddakallasandra Busstop |
| 105 | 9+630 | - | Yes | Gubbalala Bustop |
| 106 | 9+680 | Yes | - | Gubbalala Bustop |
| 107 | 10+390 | Yes | - | Raguvanahalli Cross Busstop |

| Sl No | Chainage | Side | | Remarks |
|--|----------|------|-----|---|
| | | LHS | RHS | |
| 108 | 10+430 | - | Yes | Raguvaranahalli Cross Busstop |
| 109 | 11+040 | Yes | Yes | Bayyanapalya Busstop |
| 110 | 11+650 | Yes | Yes | Jyotipuram Busstop |
| 111 | 12+040 | Yes | - | Thalagattapura Busstop |
| 112 | 12+070 | - | Yes | Thalagattapura Busstop |
| 113 | 12+470 | Yes | - | CS- Towardssinkler School Thalagattapura Busstop |
| 114 | 12+730 | Yes | Yes | Vajramuneshwara gate Busstop |
| 115 | 13+430 | Yes | - | Jyothi Farm Busstop |
| 116 | 13+450 | - | Yes | Jyothi Farm Busstop |
| 117 | 13+750 | - | Yes | Nice Road Kanakapura Road Junction |
| HDC 12d - Mysore road to Silk Board | | | | |
| 118 | 0+030 | - | Yes | BMTC Bus Stop |
| 119 | 0+930 | - | Yes | Veerabhadra Nagara Bus Stop |
| 120 | 1+000 | Yes | - | Veerabhadra Nagara Bus Stop |
| 121 | 1+480 | Yes | - | PES Institute of Technology Bus Stop |
| 122 | 1+550 | - | Yes | PES Institute of Technology Bus Stop |
| 123 | 2+410 | - | Yes | Hosakerehalli Cross Bus Stand |
| 124 | 2+730 | Yes | Yes | Janatha Bazar Bus Stop |
| 125 | 3+220 | - | Yes | Kathriguppe Bus Stop |
| 126 | 3+660 | - | Yes | Kamakya Bus Stand |
| 127 | 4+360 | - | Yes | Deve Gowda Petrol Bunk Stop |
| 128 | 5+150 | - | Yes | Kadirenahalli Park Bus Stop |
| 129 | 6+780 | - | Yes | Ilas Nagar Bus Stop |
| 130 | 8+350 | Yes | - | J P Nagar 15th Cross Bus Stop |
| 131 | 8+800 | Yes | - | J P Nagar Bus Stop |
| 132 | 9+730 | Yes | - | J P Nagar 3rd Phase Bus Stop |
| 133 | 9+810 | Yes | - | J P Nagar Bus Stop |
| 134 | 9+880 | - | Yes | Jeedimara Bus Stop |
| 135 | 10+480 | Yes | - | Gopalan Innovation Mall Bus Stop |
| 136 | 10+520 | - | Yes | Mico Layout Bus Stop |
| 137 | 11+160 | Yes | - | Mico Layout Bus Stop |
| 138 | 11+570 | Yes | - | BTM Water Tank Bus Stop |
| 139 | 11+780 | - | Yes | Udupi Garden Bus Stop |
| 140 | 11+800 | Yes | - | Udupi Garden Bus Stop |
| 141 | 12+515 | Yes | - | BTM Bus Stop |
| 142 | 13+200 | - | Yes | Silk Board Bus Stop |

| Sl No | Chainage | Side | | Remarks |
|-------|----------|------|-----|------------------------|
| | | LHS | RHS | |
| 143 | 13+470 | - | Yes | Silk Board Bus Stop |
| 144 | 14+050 | Yes | - | HSR Apartment Bus Stop |
| 145 | 14+970 | Yes | - | HSR 14th Main Bus Stop |
| 146 | 14+990 | - | Yes | HSR 14th Main Bus Stop |
| 147 | 15+700 | - | Yes | HSR Mantri Bus Stop |

2.5 Pavement Condition Survey

The survey regarding road inventory and pavement condition was carried out along the project corridor. The width of the carriageway along the project road varies from 4 lane divided carriage way to six lane divided carriageway. Visual inspection is conducted at improvement length of the project road, the study showed a Fair surface condition.

The condition of the pavement has been evaluated based on the field measurements of primary pavement surface distress of cracking (narrow and wide), patching, raveling and potholes, noted for each kilometer length. The extent of each distress has been visually estimated for every kilometer length of the road in terms of percentage area affected and then averaged for one-kilometer road length.

The distress conditions are measured under the following sub-heads:

- Cracking (%)
- Potholes (%)
- Raveling (%)
- Patching (%)
- Settlement & Upheaval (%)

2.4.1 Cracks

Pavement cracking is a typical failure commonly observed in flexible / bituminous pavements occurring predominantly due to the higher number of repetitions of heavier axle loads. Pavement Cracks (%) details along the existing project corridor are in **Annexure 2.2**. The average values of minimum, maximum and average percentage of cracks in the project roads are 3.5%, 3.95%, 3.73% respectively for Kanakpura road.

2.4.2 Patching

The variation of Pavement Patching (%) with length is shown in Figure 2.2. Pavement patching (%) details along project corridor is in **Annexure 2.1**. No significant patching is noticed except at few localized spots. The average values of minimum, maximum and

average percentage of patching area in the project roads are 3.25%, 4.20%, 3.73% respectively for Kanakpura road.

2.4.3 Raveling

Disintegration of the pavement surface caused due to failure of binder to hold the material together causing blowing off of fine aggregates leaving behind pock marks and when larger particles are broken free with stripping of aggregates is termed as Raveling. Pavement raveling (%) details along the project corridor is in **Annexure2.1**. The average values of minimum, maximum and average percentage of raveling in the project roads are 3.3%, 4.0%, 3.65% respectively for Kanakpura road.

2.4.4 Potholes

Potholes are bowl-shaped holes of varying sizes in the surface layer extending into the base course. Potholes are mainly formed due of loose base course or base course not covered properly with wearing course or due to inadequate bonding between base course and subsequent top layers. Pavement Potholes (%) details along the project corridor are in **Annexure2.1**. The average values of minimum, maximum and average percentage of potholes in the project roads are 2.5%, 2.0%, 2.25% respectively for Kanakpura road.

2.4.5 Rutting

Rutting is a surface depression in the wheel path. Pavement uplift (shearing) may occur along the sides of the rut. Ruts are particularly evident after a rain when they are filled with water. There are two basic types of rutting: mix rutting and subgrade rutting. Mix rutting occurs when the subgrade does not rut yet the pavement surface exhibits wheel path depressions as a result of compaction/mix design problems. Subgrade rutting occurs when the subgrade exhibits wheel path depressions due to loading. In this case, the pavement settles into the subgrade ruts causing surface depressions in the wheel path. Pavement Rutting (%) details along the project corridor are in **Annexure2. 1**. The average values of minimum, maximum and average percentage of potholes in the project roads 0.0%, 0.0%, 0.0% respectively for Kanakpura road.

2.4.6 Summary of Observations on Pavement Condition

The overall condition of the pavement is in fair to Good condition with around 87.0 % of the pavement area in fair condition for Kanakpura Road. Since there is no improvement length in Hosur Road, Bannerughatta Road and Outer Ring Road (Silk Board to Nayandahalli) this data is not reported.




Figure 2.1:- Summary of existing Pavement condition of HDC 03 Kanakapura Road

2.6 Camber

Carriageway camber is checked at intervals to assess the camber at site, the camber is very important for effective drainage of rain water. The standard camber is 2.5% on our roads, but quite often the camber reduces or becomes non uniform during the course of life of road in urban roads due to distress, frequent overlays. Following table represents the camber on the existing roads. Since this package contains negligible improvement length the data is not reported.

2.7 Traffic Survey

Traffic surveys are an integral component of any transport study where appreciation of existing traffic and travel characteristics of the study area are extremely important. However, Traffic surveys are not required in this assignment as no additional widening is proposed beyond available ROW. However, the traffic survey details available with KRDCL are collected for Analysis of pavement Evaluation and overlay design.

At the outset, ISECPL has collated available traffic survey details to establish the base line data for the study.

The classified traffic volume count data available was processed and compiled using Spread Sheet software packages to get Commercial Vehicles per day, which is further utilized to compute the design traffic. Since this package contains negligible improvement length the data is not reported.

2.8 Existing Pavement Structure

The bituminous layers contribute the major part of the strength of the flexible pavement structure. Hence pavement investigation is carried out to know the Existing Bituminous Thickness without disturbing the surrounding area of test pit, the existing bituminous layer thickness is measured by cutting a bituminous core cutting equipment. The core samples are taken on all the project roads at an effective interval of 2 Km. The photographs taken during core cutting in project stretch are given in following paragraphs. Since the package contains negligible improvement length the data is not reported.

2.9 Pavement structural Evaluation using Falling Weight Deflectometer Studies

Falling Weight Deflectometer (FWD) applies dynamic load on the pavement, which closely simulates the duration and amplitude of the load pulses produced by moving wheel loads. The FWD test was carried out in accordance with IRC: 115-2014 "Guidelines for structural evaluation and strengthening of flexible road pavements using Falling Weight Deflectometer (FWD) Technique. FWD readings were taken along the wheel path. Readings were taken at 250m interval, with test points staggered on both sides. Adjustments to reading locations were made to avoid culverts, bridge decks and locally damaged areas. Pavement and air temperatures were recorded for the purpose of temperature correction. Subgrade moisture data was also obtained from field moisture

measurements for applying seasonal corrections to deflection measurements.

Principle of Pavement evaluation using FWD

Performance of flexible pavements can be evaluated by applying loads on the pavements that simulate the traffic loading, recording the response to such loading by measuring the elastic deflection under such loads, and analyzing these data duly considering the factors influencing the performance such as subgrade strength, pavement thickness and quality of each of the pavement layers, drainage conditions, pavement surface temperature etc.

Among the equipment available for structural evaluation of pavements, the Falling Weight Deflectometer (FWD) is extensively used world-wide because it simulates, to a large extent, the actual loading conditions of the pavement. When a moving wheel load passes over the pavement it produces load pulses. The resulting load-deflection data can be interpreted through appropriate analytical techniques, such as back calculation technique, to estimate the elastic moduli of the pavement layers. The computed moduli are, in turn, used for (i) the strength evaluation of different layers of in-service pavements (ii) the estimation of the remaining life of in-service pavement (iii) determination of strengthening requirement, if any and (iv) evaluation of different rehabilitation alternatives (overlay, recycling, partial reconstruction, etc).

Falling Weight Deflectometer (FWD) is an impulse-loading device in which a transient load is applied to the pavement and the deflected shape of the pavement surface is measured. Impulse load is applied by means of a falling mass, which is allowed to drop vertically on a system of springs placed over a circular loading plate. The deflected shape of the pavement surface is measured using displacement sensors which are placed at different radial distances starting with the center of the load plate. Trailer mounted as well as vehicle mounted FWD models are available commercially. The working principle of all these FWD models is essentially the same. A mass of weights is dropped from a pre-determined height onto a series of springs/ buffers placed on top of a loading plate. The corresponding peak load and peak vertical surface deflections at different radial locations are measured and recorded.

FWD is non-destructive test equipment for pavements. It applies a dynamic load to a pavement structure which simulates a moving load, unlike in case of BBD where static load is applied, which does not simulate moving load. FWD provides fast, non-destructive evaluation of pavements and is safe in operating with traffic. It evaluates the condition of

underlying pavement layers and can trace the complete shape of bowl formed under dynamic loading.

The survey has been carried out by conducting deflection studies over the existing carriageway along the wheel paths at an effective interval of 250 m alternatively on both lanes of carriageway on each side. The deflections are measured by lowering the loading plate in proper contact with the pavement surface along with the required number of geophones placed at known distance from the loading plate. A target load of 40KN is achieved by dropping the mass from predetermined height. At each study point the load is applied once as seating load and the corresponding deflection is need not be recorded. After seating load, Raise the mass and drop minimum 3 times and record load and deflection data into the computer through data acquisition system on all 3 drops. While peak load and peak deflections at different selected radial positions must be recorded. After that the loading plate and Geophone frames are raised to original position and vehicle is moved to next test point. Temperatures are recorded at an interval of half hour and it has ensured FWD studies are not carried with pavement temperature greater than 45°C.

Temperature Correction

Back calculated moduli values of the bituminous layers evaluated by FWD survey are influenced by the pavement temperature. Hence the back calculated moduli obtained at temperatures other than the identified standard temperature will have to be corrected. For areas in India having a tropical climate, the standard pavement temperature is recommended as 35°C.

Correction for Seasonal Variation

Moisture content affects the strength of subgrade and granular subbase/base layers. The extent to which the strength is affected will depend on the nature of subgrade soil, gradation and nature of fines in the granular layers, etc. For applying these guidelines, it is intended that the pavement layer moduli values should pertain to the period when the subgrade is at its weakest condition. In India, this period occurs during the recession of monsoon. It is, therefore, desirable to conduct deflection measurements during this period. Where the same is not feasible, a correction procedure should be adopted.

The deflection measurement results with due temperature, seasonal corrections and characteristic deflections are presented in **Annexure 2.2**.

The Summar of Normalized deflection are presented in Table 2.17 to Table 2.20 and the summary for FWD analysis and pavement overlay design is presented in Table 2.21 to the completed details of FWD analysis and overlay design is Annexed with this report. Since the package contains negligible improvement length the data is not reported.

2.10 Inventory and Condition Survey of Culverts, Bridges, Grade Separators / VUPs / PUPs

A detailed reconnaissance and inventory of Bridges / Grade Separators / CD structures / VUPs / PUPs inventory were carried out along the project road corridor, in order to collect the relevant information w.r.to the following parameters to assess the condition of existing structures.

- Structure location in km
- Type of Structures (Culverts, Bridges, Grade Separators / VUPs / PUPs)
- Carriageway Width (m) and other general arrangements of footpath, handrails, etc.

Table 2.22: Showing Summary of Structures along the Corridor

| Sl. No | Type of Structure | No of Structures | | | | Total |
|--------|-------------------|------------------|--------|--------|---------|-------|
| | | HDC 05 | HDC 06 | HDC 07 | HDC 12d | |
| 1 | Bridges | 1 | 1 | - | - | 2 |
| 2 | Culverts | - | - | 13 | - | 13 |
| 3 | Flyover | 1 | - | - | 3 | 4 |
| 4 | ROB/RUB | - | - | - | - | - |
| 5 | VUP/PUP/CUP/VOP | 1 | 3 | 2 | 4 | 10 |
| 6 | Subways | - | - | - | - | - |
| 7 | Skywalks | 4 | - | - | - | 4 |

2.11 Topographic Survey

As per ToR, topographic survey has to be conducted along the project stretches. The main purpose of the topographical survey was to produce digital 3d base maps showing the existing terrain including all existing road features including houses, telephone line, OFC, electric line, monuments, place of worship, cremation ground, utility line, trees, hand pumps and other features covering the entire right of way of the road. The digital 3d base maps are the basis for preparation of the digital terrain models (dtm) required for the road design.

The methodology as per terms of reference (ToR) was adopted for topographical survey by the consultants for capturing all the physical features along the project corridor for facilitating proposals for the final center line of the proposed 2/4-lane road, keeping in view the possible local realignments. The corridor for survey is at least 30 m beyond either side of the center line of the proposed divided carriageway or land boundary and additional width for interchanges and intersections, toll plazas, wayside amenities and at high embankment locations such as approaches to bridges / Rob's. This survey includes reading spot levels along L-section at every 25m interval, cross sections at every 50m interval, fixing GPS/ Benchmarks at every 5 Km interval and the Reference Benchmark Pillars at every 250m interval connected to GTS Benchmarks as specified in TOR.

The project road alignment was surveyed and Reference / Bench Mark pillars for horizontal and vertical control were fixed on the ground along the project road as per TOR. The scope of Consultancy was to carry out the topographic survey to cover following aspects:

- Control Surveys
- GPS Control
- Total Station Traverse
- Height Control

CHAPTER 3: IMPROVEMENT PROPOSALS

3.1 General

The project corridors are studied thoroughly with respect to the existing features on the project roads viz No of lanes, carriageway details, Drains and CDs, Footpaths, Medians, Junctions, Bus bays, sign Boards and other traffic Appurtenances as discussed in Chapter 2. the project corridors under package 3 i.e., HDC 05: Hosur Road, HDC 06: Bannerghatta Road, HDC 07: Kanakapura Road, and HDC 12d: Outer Ring Road from Mysore Road to Silk Board comprise carriageway varying from 4 lane to 6 lanes.

Table 3.1 Lane Configuration

| SI No | Road Name | Lane Km | | | |
|-------|--|-----------|----------|-------------|---------------|
| | | 4 Lane | 6 Lane | For SR Lane | Total Lane Km |
| 1 | Hosur Road | 12.24 Km | 20.34 Km | 0 | 33 Km |
| 2 | Bannerghatta Road | 66 Km | 0 | 0 | 66 Km |
| 3 | Kanakapura Road | 58 Km | 0 | 0 | 58 Km |
| 4 | Outer Ring Road (Mysore road to Silk Board) | 40 Km | 12 Km | 6.4 Km | 59 Km |
| Total | | 176.24 Km | 32.34 Km | 6.4 Km | 216 Km |

Since the project corridors are under control of BBMP, there are already various improvement works have been carrying out or already tendered by BBMP and BMRCL in the project corridors. Improvement proposals are made for the remaining length which has not been considered for improvement works under BBMP / BMRCL. In Package 3, about 99% length of the project corridor is being under construction / tendered by BBMP or BMRCL, except for a very minimal length of 0.5 Km in Kanakapura road, and ORR where provisions made for emergency pavement treatment, the initial improvement works in the package is very minimum.

The Project Proposals are Prepared in 2 Parts

1. Initial Improvement Proposals
2. Annual maintenance Proposal

3.2 Discussions made with various Stake Holders

3.2.1 Assets to be included as part of the maintenance project

KRDCL has informed that several meetings were held on this project at various levels of

ACS, CS and it was concluded to include and exclude the following assets as part of maintenance by KRDCL

Table 3.2 Below showing Table of Assets

| SL No | Assets Proposed for Maintenance |
|---|--|
| Assets Included for Maintenance by KRDCL | |
| 1 | Carriageway |
| 2 | Median |
| 3 | Junctions |
| 4 | Grade Separators (Flyovers/Underpasses/RoB/RUB) |
| 5 | Bus Bays |
| 6 | Service Roads / Slip Roads / Parking Lanes |
| 7 | Road Markings |
| 8 | Sign Boards |
| 9 | Footpath |
| 10 | Pedestrian Guard Rails |
| 11 | Bollards |
| 12 | High Raised Pedestrian Crossings |
| 13 | Traffic Signals at Junctions |
| 14 | Installation of Traffic KIOSK / Umbrella for Policemen |
| 15 | Side Drains |
| 16 | Cross Drainage Structures |
| 17 | Road Sweeping |
| 18 | Manhole chamber Improvements |
| 19 | Tree Guards |
| 20 | Tree pruning |
| 21 | Road Cutting and Restoration |
| 23 | Removal of Construction and Demolition Debris |
| Assets Excluded for Maintenance by KRDCL | |
| 1 | Bus Shelters |
| 2 | Sky Walks |
| 3 | Solid Waste Management |
| 4 | Encroachment Clearance |
| 5 | Street Lighting |
| 6 | Land Acquisition for improvements |
| 7 | Water Supply and Sanitary lines leakages by BWSSB |
| 8 | Faulty Power Lines by BESCOM/KPTCL |
| 9 | Gas Leakages in Gas Lines by GAIL |

3.2.2 Bruhat Bengaluru Mahanagara Palike (BBMP)

Meetings and Discussions are held with BBMP officials regarding the ongoing improvement works or tendered works along the project length of the High-Density corridors. The details of the works which are already considered by BBMP and BMRL are collected and summary of the same is tabulated below. The stretch wise details of the

works considered by BBMP / BMRCL are annexed with the report.

Table 3.3 Tendered length of BBMP and BMRCL

| HDC No | Corridor Name | Total Length of the corridor, Km | BBMP ongoing work length, Km | BMRCL ongoing work length, Km |
|-------------------------------|---|----------------------------------|------------------------------|-------------------------------|
| 5 | Hosur Road | 6.45 | 6.45 | 0 |
| 6 | Bannerughatta Road | 16.5 | 6.9 | 9.6 |
| 7 | Kanakapura Road | 14.5 | 8.3 | 5.7 |
| 12 d | Outer Ring Road (Mysore road to Silk Board) | 12 | 9.8 | 2.2 |
| Package III Length, Km | | 49.45 | 31.45 | 17.5 |

3.2.3 Traffic Police Department

Police department has prepared a corridor wise proposal for the works to be considered in Short Term, Mid Term and Long-Term measures to improve the Traffic discipline, reduce the congestion, and minimize the accidents and fatalities. the detailed report submitted by the department is annexed with this report and the prominent, short term measures, Midterm Measures, and long-Term measures, which are included in the project proposal are Summarized in the table below.

Table 3.4 Proposals considered as per Traffic Police Department

| SI No | Items Considered in Estimate as per Traffic Police Requirement | Quantity | | | |
|-------|--|----------|----------|----------|---------|
| | | HDC 05 | HDC 06 | HDC 07 | HDC 12d |
| 1 | Junction Improvement | 2 Nos | Nil | 3 Nos | 6 Nos |
| 2 | High Raised Pedestrian Crossing | 9 Nos | 20 Nos | 11 Nos | 16 Nos |
| 3 | Median Guard Railing | 5.8 Km | 14.85 Km | 13.05 Km | 10.8 Km |
| 4 | Bus Bay | 1 No | Nil | 2 Nos | 6 Nos |
| 5 | Widening of road | Nil | Nil | 60 m | Nil |
| 6 | Traffic Sign Boards | 112 Nos | 77 Nos | 113 Nos | 86 Nos |
| 7 | Traffic Umbrella/Kiosk | 4 Nos | 5 Nos | 8 Nos | 5 Nos |
| 8 | Traffic Signals | 1 Nos | 2 Nos | 2 Nos | 2 Nos |
| 9 | Skywalks | 02 Nos | 03 Nos | 04 Nos | 05 Nos |

| SI No | Items Considered in Estimate as per Traffic Police Requirement | Quantity | | | |
|-------|--|----------|--------|--------|---------|
| | | HDC 05 | HDC 06 | HDC 07 | HDC 12d |
| 10 | Surveillance and Enforcement Cameras installation | 12 Nos | 24 Nos | 22 Nos | 24 Nos |

Various discussion held with ACS, CS on these issues concluded that the skywalks shall be taken up on PPP basis separately and cameras will be taken up under separate head, hence these two items are excluded from the current scope of project.

3.2.4 Proposals from DULT

DULT suggested to provide bus lanes and cycle lanes in all roads as per the budgetary announcement made by Hon'ble CM. various discussions held on this at ACS, CS level and following suggested to include bus lanes at roads (preferable Outer Ring Road) where 6 lanes are more exists at present and any other stretches needed will be added alter with proper permission/approval from Govt.

Table 3.5 Proposals of DULT

| SI No | High Density Corridor | Length of Bus Priority Lane Considered, Km |
|-------|--|--|
| 1 | HDC 05 – Hosur Road | Nil |
| 2 | HDC 06 –Bannerghatta Road | Nil |
| 3 | HDC 07 –Kanakpura Road | Nil |
| 4 | HDC 12 D Silk Board to Mysore Road | 2.0 Km |
| | Total Length of Bus Lane in Package 3 | 2.0 Km |

3.3 Initial Improvement Works

Initial improvement works are proposed in the Balance length of the corridors which are not considered for improvement by BBMP / BMRCL. The summary of the initial improvement lengths of the 4 corridors under Package 3 is represented below.

Table 3.6 Table below shows the Length of Initial Improvement Works

| HDC No | Corridor Name | Length Considered for Initial Improvement, Km | Total Length of the corridor, Km | BBMP ongoing work length, Km | BMRL ongoing work length, Km |
|-----------------------------|---|---|----------------------------------|------------------------------|------------------------------|
| 5 | Hosur Road | 0.00 | 6.45 | 6.45 | 0.00 |
| 6 | Bannerghatta Road | 0.00 | 16.5 | 6.9 | 9.6 |
| 7 | Kanakpura Road | 0.5 | 14.5 | 8.3 | 5.7 |
| 12d | Outer Ring Road (Mysore road to Silk Board) | 0.0 | 12.0 | 9.8 | 2.2 |
| Package I Length, Km | | 0.5 | 49.45 | 31.45 | 17.5 |

The Proposals have been split into following Major Heads.

(i) Where No works are taken up by BBMP or BMRL, these stretches the project improvement proposals includes

- Carriageway Improvements
- Junction Improvements
- Footpath Improvement and Construction of Green Hedging
- Median Improvements and Guardrail
- Construction of Bus Bays & Road Widening
- Drain Improvements
- Traffic Signs, Road Markings and Other Appurtenances

(ii) Whereas for the section where, works taken up by BBMP / are under progress or already tendered, only the following works are provisioned.

- Service road improvement as per police requirement.
- Median Guardrail Provisioned
- Construction of Green Hedging
- Missing Sign Boards installation
- Selected Junction Improvements.

3.3.1 Preliminary Works:


Following works are considered under preliminary works along the project roads under Package 03, viz Hosur Road, Bannerghatta Road, Kanakpura Road and Silk Board to Mysore Road. Clearing and grubbing is considered for removal and disposal of unwanted plants and waste materials from the project site. The damaged portion of Medians, Kerbs

and Footpaths in the improvement lengths are proposed for Dismantling and refixing.

3.3.2 Carriageway Improvements: -

Uniform lanes: the carriageways are widened over a period of time and there's no standard lane widths at present, the outer lane widths varies and at few places, its less than the standard lane width. Based on tender sure experience the lane widths are standardized as below, the outer lane shall be of 3.5 m as buses move on this lane, center lane shall be 3.0 m as this is predominately LMV's for and inner lane shall be 3.25 m giving a shyness of 0.25 m for median. This is been done in discussion with DULT and BBMP as per the tender sure experience.

Resurfacing: Carriageway in the initial improvement length is proposed with functional overlay as per the pavement evaluation and overlay design. Prior to laying overlay, **milling of existing bituminous surface is considered in order to achieve required camber and to reduce profile correction course.** The carriage way is proposed with uniform lane markings, and installation of raised pavement markers. Carriageway improvements are represented in Volume 3 – Drawings. Since the package contains negligible improvement length the data is not reported.



3.3.3 Junction Improvements:

The selected junctions along the corridor are proposed with carriageway improvements, road markings, sign board installations, construction or modification of traffic channelizing islands. provision for precast new jersey barrier to guide the traffic. the junctions are redesigned in order to ensure safe maneuvering of vehicles and pedestrians. In coordination with police department few selected junctions which are not in initial improvement section are also considered for improvement. Junctions considered for improvement are tabulated below.

Hosur Road: -

| SI No | Junction Chainage | Junction Name |
|-------|-------------------|------------------|
| 1 | 2+500 | Adugodi junction |

Bannerghatta Road: -

| SI No | Junction Chainage | Junction Name |
|-------|-------------------|---------------|
| Nil | | |

Kanakpura Road: -

| SI No | Junction Chainage | Junction Name |
|-------|-------------------|-----------------------|
| 1 | 4+750 | Banashankari Junction |
| 2 | 5+680 | Sarakki Junction |

Silk Board to Mysore Road: -

| SI No | Junction Chainage | Junction Name |
|-------|-------------------|---------------------|
| 1 | 1+500 | Devegowda circle |
| 2 | 3+500 | Kamakya junction |
| 3 | 5+650 | K S layout junction |

3.3.4 Footpath and Kerb

Footpath proposal includes construction of new walkways with interlocking paver blocks, where space is available or where existing footpath is in poor condition. In addition, replacement of damaged Kerbs and paver blocks are also considered.

Hosur Road: -

Provision of 200 m is kept in the entire length for damaged or discontinued section as per police requirement.

Bannerghatta Road: - Nil

Kanakpura Road: -


Provision of 1.0 km is considered in the for damaged or unattended section between saarakki junction and Nice Road Junction.

Silk Board to Mysore Road: -

Provision of 1.3 km is kept in the entire length for damaged or unattended section.

3.3.5 Green Hedging: -

With the intention to improve the aesthetics of the high-density corridors, Green Hedging is proposed on the footpath sides of the carriageway. the proposal includes installation of additional kerb line and supplying and spreading of farm yard Manure to support planting of permanent hedges. Green hedging is proposed at all feasible locations which are being improved by both BBMP or KRDCL. in addition, provision for chute drains is made along the Kerb line to guide the carriageway runoff to the drain. Cross sections indicating green hedging is represented below.



3.3.6 Median and Guard rail: -

Two types of median are considered for improvement one is the conventional median with both side Kerb with grassing and the other is 900mm standard new Jersey barrier. This is proposed in consultation with Traffic police department. The first type is considered where there is already existing convention median but in poor condition and the second type is considered as per the police requirement in places where there is existing low height concrete median or at specified places by the police department. Similarly, Guard rail is also proposed in two design, one is to install over conventional median and the second type is proposed to install over new jersey barrier in such a way to maintain uniform height. Typical section of median with guard rail is represented below.

Hosur Road: -

| Sl. No | From | To | Length of Guard rail, in m |
|--------|-------|-------|----------------------------|
| 1 | 0+000 | 0+625 | 625 |
| 2 | 0+960 | 3+590 | 2630 |
| 3 | 3+720 | 5+420 | 1700 |
| 4 | 5+600 | 6+450 | 850 |

Bannerghatta Road: -

| Sl No | From | To | Length in m |
|-------|--------|--------|-------------|
| 1 | 0+000 | 0+550 | 550 |
| 2 | 0+600 | 0+800 | 200 |
| 3 | 0+850 | 1+000 | 150 |
| 4 | 1+030 | 1+800 | 770 |
| 5 | 1+870 | 2+780 | 910 |
| 6 | 2+820 | 3+280 | 460 |
| 7 | 3+300 | 3+650 | 350 |
| 8 | 3+700 | 5+120 | 1420 |
| 9 | 5+180 | 5+600 | 420 |
| 10 | 5+670 | 5+770 | 100 |
| 11 | 5+800 | 6+900 | 1100 |
| 12 | 6+960 | 7+800 | 840 |
| 13 | 7+870 | 8+680 | 810 |
| 14 | 8+720 | 9+070 | 350 |
| 15 | 9+120 | 9+310 | 190 |
| 16 | 9+380 | 9+800 | 420 |
| 17 | 9+900 | 11+600 | 1700 |
| 18 | 11+900 | 16+000 | 4100 |



Kanakapura Road :-

| Sl No | From | To | Length of Guard rail, in m |
|-------|-------|-------|----------------------------|
| 1 | 0+400 | 0+880 | 480 |
| 2 | 0+900 | 0+950 | 50 |

| Sl No | From | To | Length of Guard rail, in m |
|-------|--------|--------|-------------------------------|
| 3 | 1+000 | 1+800 | 800 |
| 4 | 1+840 | 1+870 | 30 |
| 5 | 2+010 | 2+080 | 70 |
| 6 | 2+100 | 2+380 | 280 |
| 7 | 3+100 | 3+470 | 370 |
| 8 | 3+500 | 3+900 | 400 |
| 9 | 4+000 | 4+280 | 280 |
| 10 | 4+320 | 4+640 | 320 |
| 11 | 4+800 | 5+900 | 1100 |
| 12 | 5+950 | 8+150 | 2200 |
| 13 | 8+500 | 9+400 | 900 |
| 14 | 9+800 | 9+950 | 150 |
| 15 | 10+050 | 10+120 | 70 |

Silk Board to Mysore Road: -

| SI No | From | To | Length, m |
|-------|--------|--------|-----------|
| 1 | 0+000 | 0+700 | 700 |
| 2 | 0+780 | 3+060 | 2280 |
| 3 | 3+110 | 4+150 | 1040 |
| 4 | 4+500 | 6+250 | 1750 |
| 5 | 6+300 | 6+540 | 240 |
| 6 | 6+600 | 6+850 | 250 |
| 7 | 6+900 | 8+750 | 1850 |
| 8 | 9+100 | 9+520 | 420 |
| 9 | 10+650 | 11+650 | 1000 |
| 10 | 11+750 | 12+240 | 490 |
| 11 | 12+320 | 13+090 | 770 |
| 12 | 0+000 | 0+700 | 700 |



Hosur Road: -

| SI No | Bus bay Chainage | Location |
|-------|------------------|----------|
| 1 | 2+700 | Adugodi |

Bannerghatta Road: - Nil

Kanakpura Road: -

| SI No | Bus bay Chainage | Location |
|-------|------------------|--|
| 1 | 2+900 | Yadiyur lake |
| 2 | 6+600 | Jaraganahalli |
| 3 | 8+150 | Konankunte Cross |
| 4 | 11+600 | Jothipuram |
| 5 | 12+530 | CS-Towardsinkler School Thalagattapura |

Silk Board to Mysore Road: -

| SI No | Bus bay Chainage | Location |
|-------|------------------|---------------------|
| 1 | 0+950 | Veerabhadranagar |
| 2 | 3+150 | Katriguppe Bus stop |

| SI No | Bus bay Chainage | Location |
|-------|------------------|----------------------|
| 3 | 7+000 | J P Nagar 6th Phase |
| 4 | 8+550 | J P Nagar 5th Phase |
| 5 | 11+800 | BTM Layout 16th Main |
| 6 | 12+900 | Slik Board |

3.3.8 Drainage and Structural Improvements: -

Existing Drainage facility is studied along the project corridors, for availability and functioning, based on which it is proposed for construction of New Drain with cover slab and replacement of damaged cover slab. in addition, it is also provisioned for any emergency repairs of RE Wall portions of the Grade Separators.

Hosur Road: -

| Sl No | From | To | Length in m |
|-------|-------|-------|-------------|
| 1 | 1+620 | 1+750 | 260 |

Bannerghatta Road: - Nil

Kanakapura Road: -

Provision has been made for damaged and discontinued sections

Outer Ring Road KR Puram to Silk Board: -

Provision has been made for 200m length at damaged and discontinued section.

3.3.9 Utility and Ducts

There are no proposals for shifting of utilities in these stretches, further the initial improvements are taken only for a part length of 191 kms, the provision of utility ducts is not considering as there will be no continuity of ducts if provided. Further it was decided in various meetings that the current project is of maintenance nature and utilities are in the scope of respective utility departments and KRDCL will focus on maintenance of road assets.

3.3.10 Road Markings, Traffic Signboards and other Appurtenances: -

Road Markings viz Edge lines, Centre lines, Pedestrian Crossings, Directional Arrows are proposed as per the standard requirements and as indicate in the drawings. Similarly raised pavement markers or Road studs are proposed along road markings, at Junctions, at HRPCs as per standards and as indicated in the Drawings. Different Type of Sign

boards are provisioned for the project corridors and Appropriate Type & number of sign boards shall be Installed as per the Good for Construction Drawings. The provisions under this head also includes Road Delineators, Hazard markers, Bollards, Single arrow directional sign Boards, overhead gantry sign boards, Traffic Umbrella / KIOSK for Traffic Policemen, Traffic Signals, and Gratings at VUPs. Road Delineators are provided to demarcation of the Bus priority lane, turning demarcation and at edges of the islands. Hazard markers are provisioned for installation at approaches of all structures, at Median openings, etc. Single Arrow directional signboards are provisioned to aid in identification of cross roads, where the board is not available. Over Head Gantry Sign Boards, Traffic KIOSKs and Traffic Signals are all included for costing as per the requirements of the traffic police department.

3.4 Annual Maintenance Proposals

As part of maintenance proposals, government has decided to go for a 5 years long term maintenance and during which the road has to be kept in the good condition for easy and safe movement of traffic and pedestrians at all time. **Road Maintenance** includes routine Maintenance, preventive Maintenance, periodic Maintenance, disaster Maintenance, exigencies and inspections.

- **Periodic Maintenance:** works such as re-surfacing of pavements may be required to restore the functional deficiencies that have developed over a time period. Which shall be decided based on functional and structural valuation studies.
- **Routine Maintenance:** Contractor shall carry out day-to-day site inspection of the designated road stretches and note down the damages that have occurred due to natural or artificial causes, they should take immediate steps to correct or rectify the damages. Routine Maintenance are undertaken by the maintenance staff almost round the year.
- **Preventive Maintenance:** The preventive maintenance is performed to improve or extend the functional life of pavement surface while in good condition. This may defer the need of periodic maintenance and rehabilitation
- **Disaster Maintenance:** Occasionally several damages are caused to roads cross drainage and other road assets. structures by floods or very heavy down pour or rains, though these may not occur every year. Under such circumstances works are to be completed as early as possible and the road infrastructure shall be restored so as to minimised the inconvenience to road users.

- **Safety & Traffic Management** – this includes enforcement of regulations together with the relevant authorities. Keep project roads safer, this also includes hazard response and Road patrols
- **Asset management** – this includes daily, routine and periodic inspections, Maintenance, repairs, housekeeping and emergency Maintenance

following are the maintenance activities suggested with Time limits for rectification.

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|---------|--|--|
| A | Carriageway/Road surface, Hard shoulders, Drains and Cross Drainage works, Bridges / Interchanges / Grade Separators (Fly Overs/ RUB/ ROB/ Under Pass / any other Road structure). | |
| 1 | Maintaining a public relations unit to interface with and attend to suggestions from the Users, government agencies, media and other agencies and deploying the required staff. Equipment Installation and Office setup (Large TV, Computers, Printers and other equipment), deploying Three non-technical and two technical staff | On or before 30 days from LOA |
| 2 | all surplus construction machinery and materials, waste materials (including hazardous materials and waste water), rubbish and other debris (including, without limitation, accident debris) and keep the Project in a clean, tidy and orderly condition, and in conformity with Applicable Laws, Applicable Permits and Good Industry Practice. | Daily |
| 3 | Carriageway Sweeping using mechanical sweepers and footpath manual cleaning Minimum 4 vehicle mounted sweeping machines to be deployed all the debris/dust/litter shall be safely carried and disposed away at designated places. | Daily |
| 4 | Breach or blockade (the item of works shall be removal of fallen concrete wall, trees, electric pole etc. | Temporary restoration of traffic within 3 hours' permanent restoration within 7 days |
| 5 | Roughness not more than 2600mm/km for each lane in a km length (as measured by a standardized rough meter/bump integrator). | As indicated in the Work order, for this work. |
| 6 | Skid Resistance (Skid Number, SN, minimum Desirable shall be 55 SN | As indicated in the Work order, for this work |
| 7 | Potholes | 24 hours |
| 8 | Cracking all types in less than 5% of road surface for each lane in a km length | 3 (Three) days |

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|---------|--|---|
| 9 | Ravelling/Stripping of bitumen and all types in less than 5% of road surface for each lane in a km length | 3 (Three) days |
| 10 | Settlement all types in less than 5% of road surface for each lane in a km length | 3 (Three) days |
| 11 | Rutting exceeding 5 mm in more than 2% of road surface for each lane in a km length (measured ROMDAS or equivalent technology) | 7 (Seven) days |
| 12 | Bleeding | 3 (Three) days |
| 13 | Damage to pavement edges exceeding 100 mm | 24 hours |
| 14 | Painting of Kerb, railing, parapets, crash barriers, | Twice every year |
| 15 | All types of Road Marking | Retro reflectivity mcd/m ² /lux of 150 during the contract period / Twice every year |
| 16 | Joint Sealing in concrete pavement | 7 (Seven) days |
| 17 | Replacement of Pavement Quality Concrete slabs | 15 (fifteen) days |
| 18 | Rain cuts/gullies in slope | 3 (Three) days |
| 19 | Damage to or silting of culverts and side drains during and immediately preceding the rainy season | 3 (Three) days |
| 20 | Desilting of drains in Road side Drains | 3 (Three) days |
| 21 | Cracks - Temporary measures | Within 48 hours |
| 22 | Spalling/scaling | 3 (Three) days |
| 23 | Foundations-cavitation | 3 (Three) days |
| 24 | Piers, abutments, return walls, RE-walls Cracks and damages including settlement and tilting Temporary measures | 30 (Thirty) days |
| 25 | Bearings All type- Replacements | As indicated in the Work order, for this work |
| 26 | Joints in bridges: Loosening and malfunctioning of joints | As indicated in the Work order, for this work |
| 27 | Deforming of pads in elastomeric bearings | As indicated in the Work order, for this work |
| 28 | Gathering of dirt in bearings and joints or clogging of spouts, weep holes and vent-holes | 3 (Three) days |
| 29 | Damage or deterioration in parapets and handrails | 3 (Three) days |
| 30 | Rain-cuts or erosion of banks of the side slopes of approaches | 3 (Three) days |
| 31 | Resurfacing of wearing coat | As indicated in the Work order, for this work |
| 32 | Damage or deterioration in approach slabs | 3 (Three) days |
| 33 | Growth of vegetation affecting the structure or obstructing | 3 (Three) days |

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|----------|---|---|
| | the waterway | |
| B | Foot Path/Medians/Drains | |
| 34 | Manual cleaning of footpaths, all the debris/dust/litter shall be safely carried and disposed away at designated places | Daily |
| 35 | Damage to paver blocks or concrete surface or tiles of footpath | 3 (Three) days |
| 36 | Damage to Kerbs, bollards, tree guards, pedestrian railings | 3 (Three) days |
| 37 | Road side Drains and inlets | Should be Clean at all times |
| 38 | Damage to drain cover, walls | 3 (Three) days |
| C | Road safety and furniture including all road sign boards and pavement raised marking (road studs) | |
| 39 | Damage to shape or position, poor visibility or loss of retro-reflectivity | 48 hours |
| 40 | Damaged/missing road signs requiring replacement | 7 (seven) days |
| 41 | Painting of railing, parapets, crash barriers | Once every year |
| 42 | Reflective Pavement Markers (Road Studs) Numbers and Functionality as per specification in IRC :SP:84-2014 and IRC :35-2015, unless specified | At all times |
| 43 | Pedestrian Guard rail : Functionality: Functioning of guardrail as intended | At all times |
| 44 | Traffic Safety Barriers: Functionality: Functioning of Safety Barriers as intended | At all times |
| 45 | Overhead Sign Structures shall be structurally and functionally adequate | At all times |
| D | Miscellaneous Works (Trees and Plantation, Road Patrol, Road Cutting Restoration, Road lighting | |
| 46 | Obstruction in a minimum head-room of 5 m above carriageway or obstruction in visibility of road signs | 24 hours |
| 47 | Deterioration in health of trees and bushes | Timely watering and treatment |
| 48 | Replacement/replanting of plants and bushes on medians, islands, footpaths and green edges | 3 (Three) days |
| 49 | Removal of vegetation affecting sight line and road structures | 3 (Three) days |
| 50 | Patrolling of roads by a vehicle of Bolero or equivalent with a driver, assistant and a supervisor at all times - 2 vehicles and two teams | All through the day |
| 51 | Restoration of road cutting as per IRC specifications Temporary Permanent | As indicated in the Work order, for this work |
| 52 | Road lighting | Not Included. |

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|----------|--|-------------------------------------|
| E | Emergency Works | |
| 53 | Removal of Fallen Trees | 3 hours |
| 54 | Towing of Accident vehicle / Breakdown vehicle / Abandoned vehicle, mandatory deployment of: <ul style="list-style-type: none"> • LMV Towing vehicle –for towing of light commercial vehicles and below – 1 nos • HCV Towing vehicle –for towing of buses/ heavy commercial vehicles · 1 nos | 1 hour |
| 55 | Water logging / Ponding on road surface / grade separators, mandatory deployment of Tippers, pumps, sucking machines, etc., as needed | 1 hour |
| 56 | Fallen Street pole / Sign Boards / any other structure | 1 hour |

3.4.1 Traffic Incident Management

As a part of maintenance proposals, The Project corridors are required to Patrol continually through dedicated staff and Vehicle, to monitor any possible hindrance for the free flow of traffic and to ensure good condition of all Road Assets. Two patrol vehicles with staff are provided for each package of work

During the discussions with the police department, provision of cranes for toeing was asked to toe away the vehicles stranded, met in accident or illegally parked on HDC's. provision of two toeing vehicles one for heavy vehicles like buses and trucks and another for LMV's is proposed.

Water logging at selected locations is a perennial issue during rainy season, especially at underpasses. In the even of water logging, the provision of sucking machines, pumps and Labour is also provisioned in the maintenance work.

CHAPTER 4: COST ESTIMATE

4.1 General

The Project cost is worked out based on estimated quantities from the detailed engineering design including road works, drainage works, pavement, culverts, road furniture, road safety appurtenances etc.

4.2 Construction Items

The following factors have been considered to arrive at the unit rates for various construction items.

The project cost estimates have been prepared separately for initial improvement works and Annual Maintenance works based on various items of works considered for the upgradation and annual maintenance of the project roads. The Major items rates are considered from **PWP IWTD SoR 2018-19, Bangalore Circle, Govt. of Karnataka** along with latest issue rates, and for few items derived rates are adopted.

Table 4.1: Adopted Unit Rates for Some of the Major Items (Excluding Area Weight Factor)

| Sl. No. | Items | Unit | Rate |
|---------|--|---------|----------|
| 1 | Milling of Existing Bituminous Layer | Sqm | 70.00 |
| 2 | Granular Sub base | Cum | 1882.00 |
| 3 | Wet Mix Macadam | Cum | 1888.00 |
| 4 | Dense Bituminous Macadam (DBM) | Cum | 6045.00 |
| 5 | Bituminous Concrete (BC) | Cum | 6939.00 |
| 6 | Interlocking Paver Blocks | Sqm | 1110.00 |
| 7 | M15 for Kerb Laying | Cum | 5422.00 |
| 8 | Kerb | Nos | 450.00 |
| 9 | Painting two Coats for Kerb | Sqm | 82.00 |
| 10 | Yard Manure | Cum | 204.00 |
| 11 | Planting permanent hedge | Mt | 296.00 |
| 12 | Tree Guard / Grating and Median guard Rail | Quintal | 7187.00 |
| 13 | Providing and Laying M20 for Drain | Cum | 6670.00 |
| 14 | Steel Reinforcement | Tonnes | 61365.00 |
| 15 | Road Marking- Thermoplastic | Sqm | 429.00 |
| 16 | Moulded Shank Raised Pavement Markers | Nos | 337.00 |

4.3 Project Costing

Quantification

The quantification of various items of work is based upon the proposals recommended in the previous chapters. The quantities have been worked out separately for different items of work. The construction cost has been sub - divided into Preliminary Works, Carriageway improvement, Junction Improvement, Footpath and Kerbs, Medians and guard rails, Bus bays and Road Widening Works, Drainage Improvement and other structural Works, Traffic signs, Marking and other Appurtenances.

The following are the Bill wise of works, which have been estimated:

Preliminary Works including Dismantling, Clearance and Earthworks: The area considered for Site Clearance is the area within the proposed Right of Way width. and the damaged portions of Median Kerbs, and Footpath are proposed for dismantling.

Carriageway Improvements: Carriageway improvements costs includes Milling of existing bituminous surface, Strengthening and overlay as per the structural evaluation and Pavement design.

Junction Improvements: Junction improvement cost includes overlay for carriageway, Road markings, installation of sign Boards, High raised pedestrian crossings, construction of channelization islands as per the requirement.

Footpath and Kerbs: Footpath works cost includes removal of damaged paver blocks, kerb stones, etc and replacement with the new ones. In addition, the costing also includes the Green Hedging provision along the footpath

Median and Guardrail: The estimation of quantities for Median construction were based on site inventory, and Median Guard rails for pedestrian safety as per police department instruction is considered .

Bus Bays and Road Widening Works: The estimation of quantities for Bus bays and road widening works were based on the police department requirements , detailed design and drawings.

Drainage Improvement and Structural Works: Provision under this sub-head has been made for cost for construction of side drains, and repairs of RE wall.

Traffic Sign, Markings and Other Appurtenances: Proper traffic signs were selected at required locations along the project corridor. It is reviewed considering the traffic, pedestrian safety, and modified if required. Centre line and edge markings required from safety point of view were considered in the quantity estimate.

4.4 Total Project Cost

The total project cost of **package 3** is **81.66 Crores**, which includes Initial Improvement cost of **39.35 Crores**, Annual maintenance cost of **21.88 Crores**, 12% for GST, 5% Administration Charges, 3% for DPR and PMC charges, 10% Contingencies. The summary of the project is given in **Table 4.2** below for Total Project Cost along with Road Wise Cost Summary.

The detailed rate analysis and quantity estimation is given in Volume-3: Cost Estimate.

Table 4.2: : Summary of Cost for the Project

| SL No | Description | HDC 05 | HDC 06 | HDC 07 | HDC 12D | Package III |
|-----------|---|-----------------|-----------------|-----------------|-----------------|-----------------|
| | | Amount (Crores) | Amount (Crores) | Amount (Crores) | Amount (Crores) | Amount (Crores) |
| 1 | Preliminary Works including Dismantling, Clearance and Earthworks | 0.00 | 0.00 | 0.02 | 0.19 | 0.20 |
| 2 | Carriageway Improvements | 0.10 | 0.26 | 0.58 | 4.37 | 5.31 |
| 3 | Junction Improvements | 0.10 | 0.03 | 0.23 | 0.34 | 0.71 |
| 4 | Footpath and Kerbs | 2.42 | 0.00 | 4.74 | 5.11 | 12.27 |
| 5 | Median and Guardrail | 1.83 | 4.67 | 4.11 | 3.41 | 14.03 |
| 6 | Bus Bays and Road Widening Works | 0.05 | 0.00 | 0.15 | 0.27 | 0.48 |
| 7 | Drainage Improvement and Structural Works | 0.55 | 0.25 | 0.72 | 0.45 | 1.96 |
| 8 | Traffic Sign, Markings and Other Appurtenances | 0.51 | 0.95 | 1.03 | 1.89 | 4.38 |
| A. | Initial Improvement Cost | 5.57 | 6.17 | 11.58 | 16.03 | 39.35 |
| B. | Annual Maintenance Cost | 3.12 | 6.94 | 6.16 | 5.67 | 21.88 |
| C. | GST @ 12% of (A+B) | 1.04 | 1.57 | 2.13 | 2.60 | 7.35 |
| D. | Administrative Charges @ 5% on (A+B) | 0.43 | 0.66 | 0.89 | 1.08 | 3.06 |
| E. | DPR & PMC Charges @ 3% on (A+B) | 0.35 | 0.90 | 0.79 | 0.65 | 2.69 |
| F. | Contingencies @ 10% | 1.04 | 2.04 | 2.08 | 2.14 | 7.31 |
| G. | Miscellaneous and Rounding off | 0.00 | 0.01 | 0.01 | 0.01 | 0.03 |
| H. | Total Project Cost (A+B+C+D+E+F+G) | 11.56 | 18.28 | 23.63 | 28.19 | 81.66 |

4.5 Implementation Plan

An implementation plan refers to a detailed description of actions that demonstrate how to implement an activity within the project in the context of achieving the objectives, addressing the requirements, and meeting the expectations. The above project is to be implemented in two forms.

1. Initial Improvement and
2. Maintenance

Initial Improvement: Initial improvement is to be done within first nine months of the project tenure year for carriage way, Junctions improvements, Footpath and Drain improvements, Traffic lane markings and sign boards, median island improvements and providing green edge in ongoing BBMP Tender works.

Maintenance: The proposed project roads are to be maintained periodically by clearing of pavement, Repair of traffic signs and road markings, Repair of damage caused by traffic accidents. The project corridors are to be maintained for 5 years.

4.6 Packaging

The Total Length of the all the high-density corridor is 191 Km which is spreader over the entire Bengaluru city. this will make the task of maintaining the road very cumbersome, as it will be very difficult to accesses, Monitor and control the activities over entire length. Hence the Total 15 roads of high-density corridors are grouped in to four packages, such that it will be convenient to Access, Monitor and control the different activities running along the corridor within each package.

4.7 Time Schedule.

The duration for the initial improvement works is 270 days covering various stages of work. The time schedule of the Project along with work Programme of activities is given below.

| Sl. No | Description | Duration | Start Date | End Date |
|--------|---|-----------------|-------------------|-------------------|
| A | Initial Improvement Works | 270 Days | 01-04-2021 | 31-12-2021 |
| 1 | Strengthening/Resurfacing, Road Marking, Traffic Signs for Priority Stretches | 90 Days | 01-04-2021 | 30-06-2021 |
| | | | | |

| Sl. No | Description | Duration | Start Date | End Date |
|--------|---|----------|------------|------------|
| 2 | Drainage and Utility Works | 90 Days | 01-04-2021 | 30-06-2021 |
| 3 | Footpath and Kerbs | 90 Days | 01-05-2021 | 31-07-2021 |
| 4 | Median and Guardrails | 60 Days | 01-07-2021 | 31-08-2021 |
| 5 | Junction Improvements | 60 Days | 01-09-2021 | 31-10-2021 |
| 6 | Strengthening/Resurfacing, Road Marking, Traffic Signs Road Appurtenances for Other Stretches | 90 Days | 01-10-2021 | 31-12-2021 |

The Annual Maintenance works needs to be executed continually throughout the year for the project duration of 5 Years.

MAINTENANCE OF HIGH DENSITY CORRIDORS IN BENGALURU CITY.

Summary of Works Under HDC No. 5 - Hosur Road Corridor

| Sl. No. | Chainage in km | | Location | | BBMP Department | Ongoing Works / Completed Works Implemented By | Works Considered by KRDCL for Initial Improvement | Maintenance Proposal |
|---------|----------------|----------|--|--|-----------------|--|---|---|
| | From | To | From | To | | | | |
| 1 | Ch.0.000 | Ch.1.950 | Vellara Junction | Church Near Storm Water Drain crossing | RI-East | Proposed Widening and White Topping Work by Central Project (BBMP) | - | 1. Routine Maintenance incl. Mechanical Sweeping of carriageways and Manual Cleaning of Footpath. 2. Removal debries, roadside silt, C&D Wastes & allied works using Tractor Labours. 3. Patrolling. 4. Maintenance of Carriageway. 5. Maintenance of Drain & Footpath. 6. Street Light Maintenance. 7. Other Allied Works on emergent days |
| 2 | Ch.1.950 | Ch.5.050 | Church Near Storm Water Drain crossing | Madivala Underpass | RI-South | Proposed White Topping Work by Central Project (BBMP) | - | |
| 3 | Ch.5.050 | Ch.5.600 | Madivala Underpass | Silk Board Fly Over Start <i>in</i> | RI-South | Proposed Improvement by RI South | - | |
| 4 | Ch.5.600 | Ch.6.450 | Silk Board Fly Over Start | Start of NH Limit | RI-Bommanahalli | Work under progress by RI-TEC not considered. | - | |

[Signature]
EE (RI-East)

[Signature]
EE (RI-South)

[Signature]
EE (RI-TEC)

[Signature]
EE (Project-Central)

EE (KRDCL-SOUTH)

[Signature]
Assistant Executive Engineer-3
Project Office Bengaluru South
K.R.D.C.L., Bengaluru.

[Signature]
Executive Engineer
Project Office Bengaluru South
K.R.D.C.L., Bengaluru.

| | | | | | | | | |
|------------------------------|-----------|-----------|---------------|----------------------------|-------------|---------------------------------|---|-----------------------|
| 4 | Ch.13.000 | Ch.16.500 | Koliform Gate | Bannerghatta National Park | PWD | Overlay work in progress by PWD | - | |
| Length of Corridor: 16.50 Km | | | | | Total Cost: | | - | Rs.9.56 Crores / year |

S. Bilal
 EE (RI-South)
 Executive Engineer
 Roads In-charge, South Division
 Municipal Corporation, Mahanagar Palik

EE (RI-Road Widening)
 Roads In-charge, South Division
 Municipal Corporation, Mahanagar Palik

| MAINTENANCE OF HIGH DENSITY CORRIDORS IN BENGALURU CITY | | | | | | | | |
|--|--------------------|---------|---|-------------|-----------------|---|---|--|
| Summary of Works Under HDC No -12 C Silk Board to Mysore Road Corridor | | | | | | | | |
| SL No | Chainage to Km | | Location | | BBMP Department | Ongoing Works / Completed works implemented by | Works Considered by KRDCL for Initial Improvement | Maintainence Proposal |
| | From | to | From | to | | | | |
| Link 1: Mysore road to Jedi Mara | | | | | | | | 1. Routine Maintenance incl. Mechanical Sweeping of carriageways and Manual Cleaning of Footpath. 2. Removal debris, roadside silt, C&D Wastes & allied works using Tractor Labours. 3. Patrolling. 4. Maintenance of Carriageway. 5. Maintenance of Drain & Footpath. 6. Street Light Maintenance. 7. Other Allied Works on emergent days |
| 1 | Ch 0.00 | Ch 1.40 | Mysore Road (Nayanda halli junction) | PES college | RI - South | Proposed improvement under RI-TEC ✓ | | |
| 2 | Ch 1.40 | Ch 9.50 | PES college | Jedi Mara | RI - South | SFC work under progress by Project Central (BBMP) | | |
| Link 2: Jayadeva to Silk Board | | | | | | | | |
| 3 | Ch 0.00 | Ch 2.50 | Jayadeva | Silk Board | RI - South | Proposed improvement under RI-South & Metro Corridor. | | |
| | Length of Corridor | | 12.00 Km | | | | | |

S. B. Mahesh
Executive Engineer
 Road Infrastructure - South
 Bangalore Mahanagara Palike

EE (RI-South)

Quintus V.
Executive Engineer
 Traffic Engineering Cell (RI)
 Bangalore Mahanagara Palike
 Bangalore-560 002

J. S. Sankar
Assistant Executive Engineer-4
 Project Office Bengaluru South
 K.R.D.C.L., Bengaluru.

Ans
Executive Engineer
 Project Office Bengaluru South
 K.R.D.C.L., Bengaluru.

EE (KRDCL-SOUTH)

Table of Contents

| | |
|---|----|
| CHAPTER 1 | 4 |
| INTRODUCTION | 4 |
| 1.1 General | 4 |
| 1.2 Classification of Roads in India | 4 |
| Figure 1.1 Classification of Roads in India | 5 |
| 1.3 Classification of Urban Roads in India | 5 |
| Figure 1.2 Classification of Urban Roads in India | 5 |
| 1.4 Project Background | 6 |
| 1.4.1 Location and Terrain condition | 6 |
| Table 1.1 Details of Road | 6 |
| Figure 1.3 Map Showing Road Network | 7 |
| 1.5 Objective | 8 |
| 1.4 Structure of the Report | 8 |
| CHAPTER 2 | 8 |
| METHODOLOGY ADOPTED FOR STUDY | 9 |
| 2.1 General | 9 |
| 2.2 Engineering Surveys and Investigations | 9 |
| 2.2.1 Reconnaissance Survey | 9 |
| 2.2.2 Road Inventory and Road Condition | 10 |
| 2.2.3 Pavement Structural Evaluation | 10 |
| 2.2.4 Topographical Survey | 11 |
| 2.2.4.1 Block Level Survey | 11 |
| 2.2.4.2 Office Processing | 11 |
| 2.2.5 Hydrology and Drainage Investigations | 12 |
| 2.2.6 Engineering Design | 12 |
| 2.2.6.1 Pavement Design | 12 |
| 2.2.7 Preliminary Cost Estimates | 12 |
| CHAPTER 3 | 14 |
| SCHEDULES | 14 |
| 3.1 The Site | 14 |
| Table 3.1 Details of Road | 14 |
| Figure 3.1 Map Showing Road Network | 15 |

| | |
|---|----|
| 3.2 Land | 16 |
| 3.3 Carriageway | 16 |
| 3.4 Road Side Drain | 17 |
| 3.5 Footpath | 17 |
| 3.6 Service Roads | 18 |
| 3.7 Structures | 18 |
| 3.8 Bus Shelters / Bus Bays / BusStop | 19 |
| 3.9 Junctions | 22 |
| 3.10 Road Furnitures | 24 |
| 3.11 Pavement Type | 25 |
| CHAPTER 4 | 27 |
| DESIGN STANDARDS, METHODOLOGIES AND SPECIFICATIONS | 27 |
| 4.1 Project Corridors | 27 |
| 4.2 Classification of Urban Roads | 27 |
| 4.3 Guiding Principles | 27 |
| 4.4 Traffic Design | 27 |
| 4.4.1 General | 27 |
| 4.4.2 Definition and Concepts | 28 |
| 4.4.3 Level of Service (Clause 5.1 of IRC 106 of 1990) | 28 |
| Figure 3.1 Map Showing Various Levels of Service in the form of indicative Volume-Flow Relationship | 29 |
| 4.4.3.1 Equivalency Factors | 29 |
| 4.4.4 Recommended Design Service Volumes for Two Lane Roads | 30 |
| Table 4.1 Design service volumes for Two lane roads | 30 |
| 4.4.5 Traffic Signs and Road Markings | 30 |
| 4.5 Indicative Design Standards for Road | 31 |
| Table 4.2 Indicative Design Standards for Main Carriageway | 31 |
| 4.6 Road Markings | 32 |
| 4.7 Specifications | 32 |
| CHAPTER - 5 | 33 |
| CONCLUSIONS | 33 |
| 5.1 Roads | 33 |
| Table 5.1 Details of Road | 33 |
| 5.1.1 Milling | 33 |

| | | |
|---|---|-------------------------------------|
| 5.1.2 | Cleaning | 33 |
| 5.1.4 | Overlay..... | 33 |
| Table 5.2 Details of Stretches where Overlay or Strengthening Layer is Proposed..... | | 34 |
| 5.2 | Roadside Drainage | 35 |
| 5.3 | Median Improvement and Guard Rail | 35 |
| 5.4 | Footpath Improvement..... | 35 |
| 5.5 | Green Hedging..... | 36 |
| 5.6 | Traffic signs | 36 |
| Table 5.3 Details of Traffic Signs, Road Markings, Road Safety and Road Furnitures and Other Appurtenances..... | | 36 |
| 5.7 | Annual Maintenance Proposals includes | 37 |
| Table 5.4 Maintenance timelines proposed | | 37 |
| CHAPTER - 6 | | 41 |
| PRELIMINARY COST ESTIMATES | | 41 |
| 6.1 | General..... | 41 |
| 6.2 | Methodology | 41 |
| 6.2.1 | Basic rates | 41 |
| 6.2.2 | Quantification of Items | 41 |
| Table of Contents..... | | Error! Bookmark not defined. |

INTRODUCTION

CHAPTER 1

INTRODUCTION

1.1 General

India has a road network of over 4,689,842 kilometres (2,914,133 mi) in 2013, the second largest road network in the world. At 0.66 km of roads per square kilometre of land, the quantitative density of India's road network is like that of the United States (0.65) and far higher than that of China (0.16) or Brazil (0.20). However, qualitatively India's roads are a mix of modern highways and narrow, unpaved roads, and are being improved. As of 2011, 54 percent – about 2.53 million kilometres – of Indian roads were paved.

Adjusted for its large population, India has less than 3.8 kilometres of roads per 1000 people, including all its paved and unpaved roads. In terms of quality, all season, 4 or more lane highways, India has less than 0.07 kilometres of highways per 1000 people, as of 2010. These are some of the lowest road and highway densities in the world. For context, United States has 21 kilometres of roads per 1000 people, while France about 15 kilometres per 1000 people – predominantly paved and high quality in both cases. In terms of all season, 4 or more lane highways, developed countries such as United States and France have a highway density per 1000 people that is over 15 times as India.

1.2 Classification of Roads in India

As per Indian Road Congress (IRC) and Ministry of Road Transport & Highways, Indian Roads are classified into three classes i.e. Primary, Secondary and Tertiary Systems, for the purposed of transport planning, functional identification, earmarking administrative jurisdictions and assigning priorities on a road network.






Figure 1.1 Classification of Roads in India

1.3 Classification of Urban Roads in India

The road systems within urban areas are classified as Urban Roads and will form a separate category of roads to be taken care by the representative urban authorities. Further urban roads are classified as



Figure 1.2 Classification of Urban Roads in India



1.4 Project Background

Bengaluru's road network exceeds 3,000 km (1,800 mi) and consists of ring roads, arterial roads, sub-arterial roads and residential streets.

The main arterial roads of Bengaluru coming into the city include Bellary Road in the north, Tumkur Road and Mysore Road in the west, Kanakpura Road, Bannerghatta Road and Hosur Road in the south and Airport Road and Old Madras Road in the east, and all these roads are inter connected with Outer Ring road.

Bangalore Commissioner of Police notified 12 Major Roads connecting inter-districts and inter-states as High Traffic Density Corridors vide Notification dated:03-09-2019

Bengaluru 's vehicular traffic has increased manifold, with 1.6 million registered vehicles in the city – the second highest for an Indian city, after New Delhi.

The construction and maintenance of roads to address the growing traffic in the city has been a challenge to the BDA and the BBMP. To reduce the pressure of hectic maintenance activities for BBMP and to ensure the effective maintenance of high-volume traffic arterial roads it has been proposed to handover the maintenance of High-density corridors to Karnataka Road Development Corporation Limited (KRDCL).


A decision has been taken in the meeting held on 06/11/2019 under the Chairmanship of Hon'ble Chief Minister, Govt. Of Karnataka for Upgradation and maintenance of 12 High Traffic Density Corridors as per IRC guidelines to be taken by Karnataka Road Development Corporation Ltd. side drains, Construction of Pedestrian footpaths.

1.4.1 Location and Terrain condition

Table 1.1 Details of Road

| Sl. No | Name of the Road | Length in Km |
|--------|--|--------------|
| 1 | HDC 8: Mysore Road | 15.40 |
| 2 | HDC 9: Magadi Road | 12.00 |
| 3 | HDC 10: Tumkur Road | 7.90 |
| 4 | HDC 11: West of Chord Road | 8.40 |
| 5 | HDC 12a: ORR (From Mysore Road to Gorguntepalya) | 10.90 |
| | Total | 54.60 |





1.5 Objective

The objective of the consultancy services is to recommend an optimal proposal for implementation, which comprises of:

- *Reconnaissance Survey.*
- *Inventory and Pavement Condition Survey.*
- *Pavement Structural Evaluation*
- *Topographical Surveys.*
- *Hydrological and Drainage Investigation.*
- *Provision of road and CD Works to meet functional and structural requirements;*
- *Adequate road side drainage to preserve the road assets; and*
- *Highest safety of road users achieved through improvement to road & junction geometrics, appropriate street furniture, road signs and illumination.*
- *Preparation of cost estimate.*

1.4 Structure of the Report

This report includes following:

- ❖ *Chapter 1 : Introduction*
- ❖ *Chapter 2 : Methodology Adopted for Study*
- ❖ *Chapter 3 : Engineering Surveys and Investigations*
- ❖ *Chapter 4 : Preliminary Alignment Study*
- ❖ *Chapter 5 : Pavement Design*
- ❖ *Chapter 6 : Conclusions*



CHAPTER 2

METHODOLOGY ADOPTED FOR STUDY

2.1 General

Various engineering surveys and investigations that are essential inputs for the preparation of detailed project report have been carried out along the Project Road section conforming to IRC Specifications/Codes to generate adequate database for preparing the most appropriate and optimal improvement proposal for rehabilitation, widening/strengthening and upgrading the existing road section. All the relevant maps/data/details available with the concerned departments have been collected, compiled and reviewed. Particular attention has been given to past/historical data. A review of the past data available in the various studies has been made use of, after updating/augmenting the data wherever necessary. The activities were performed on several fronts fully complying with the requirements. The activities carried out with specific reference to the present project are succinctly brought out hereunder. All the investigation/surveys have been carried out on a priority basis. The various engineering surveys/investigations, which have been carried out include:


- ❖ *Reconnaissance Survey*
- ❖ *Pavement Condition Survey*
- ❖ *Material Survey*
- ❖ *Pavement Structural Evaluation*
- ❖ *Topographic/Levelling Survey*
- ❖ *Traffic Surveys*
- ❖ *Inventory and Condition Survey of Bridges and CD Structures*
- ❖ *Engineering Design*
- ❖ *Cost Estimates*

The basic data collected from different engineering surveys along with the results of the survey / investigations, data analyses are compiled.

2.2 Engineering Surveys and Investigations

2.2.1 Reconnaissance Survey

The consultants made an in-depth study of the available land width (ROW), topographic survey maps of the project area and other relevant information were collected.



A detailed reconnaissance survey was conducted on the total project area and an assessment of possible alignment change at places, if required, was also made. Detailed features such as land-use, habitation, water routes, utilities such as electrical lines (HT / LT), etc. were also noted down. This enabled the Consultants to visualize the possible problems likely to be encountered with in the execution of the project. The detailed ground reconnaissance of project influence area was utilized for planning and programming the detailed surveys and investigations.

2.2.2 Road Inventory and Road Condition


An inventory of the project road has been carried out by visual observations supplemented with sample measurements using tape etc. Kilometre wise features like terrain, land-use, pavement surfacing type and width, shoulder surfacing type & width, Subgrade, local soil type, curve details, retaining structures details, location of water bodies, height of embankment or depth of cut, ROW, CD structures, road side arboriculture, existing utility services and general drainage conditions etc., were recorded. Also Crust Thickness of the existing pavement were recorded by core cutting. The road inventory has been referenced to the existing km posts established along the roadside. A detailed road inventory, Crust Thickness and condition survey are presented in the **Appendix**

2.2.3 Pavement Structural Evaluation

Principle of Pavement Evaluation using FWD

The structural strength evaluation of the existing pavements was carried out as per IRC 115: 2014. Performance of Flexible Pavements can be evaluated by applying loads on the pavements that simulate the traffic loading, recording the response to such loading by measuring the elastic deflection under such loads and analyzing these data duly considering the factors influencing the performance such as subgrade strength, thickness and quality of each of the pavement layers, drainage conditions, pavement surface temperature etc.

Falling weight Deflectometer (FWD) is extensively used worldwide because it simulates, to a large extent, the actual loading conditions of the pavement. When a moving wheel load passes over the pavement it produces load pulses. Normal stresses at a location in the pavement will increase in magnitude from zero to a peak value as the moving load approaches the location. The time taken for the stress pulses to vary from zero to peak value is termed as 'rise time of pulse'. As the wheel moves away from the location, magnitude of stress reduces from peak value to zero. The time period during which the magnitude of stress



pulse varies from 'zero-to-peak-to-zero' is the pulse duration. Peak load and the corresponding pavement responses are of interest for pavement evaluation.

The resulting load deflection data can be interpreted through appropriate analytical techniques, such as back calculation technique, to estimate the elastic moduli of the pavement layers. The computed moduli are in turn used for

- The strength evaluation of different layers of in-service pavements
- The estimation of the remaining life of in-service pavement
- Determination of strengthening requirement, if any
- Evaluation of different rehabilitation alternatives (Overlay, recycling, partial reconstruction, etc)

2.2.4 Topographical Survey

Topographic survey using total station equipment was conducted and a contour map shall be prepared showing contour line drawn at an interval of 0.5m, it also indicates all the prominent existing features such as roads, railway tracks, colonies, (independent houses also), power lines, water bodies, farms, gardens, fields etc. Few reference stones were marked on the survey map and their levels were enlisted (smaller to larger scales). Providing and fixing of boundary stones at an interval of 50m and additionally wherever bends occurs was done as per the directions of Engineer In charge.

2.2.4.1 Block Level Survey

Block level survey was taken up and a contour map was prepared showing contours at intervals of 0.5m. It also indicates land use and all the prominent existing features such as roads, railway tracks, colonies, independent houses, water bodies, farms, gardens, fields, fences etc., cardinal points was marked with reference stones on the ground and marked on the survey map. The RL was indicated based on either an established PBM, if available, or with reference to a TBM established.

2.2.4.2 Office Processing

The field survey will be processed in the office to provide a digital output file for the design engineers. The Surveyor will arrange for a proof survey for a statistical sample to check the digital maps in the field.

The data will be structured so that the vertical profile of the proposed alignment can be produced automatically. The format of the resulting data will be such as will readily promote the calculations of earthworks (if any) and other quantities required for the evaluation of

detailed cost estimates.

2.2.5 Hydrology and Drainage Investigations

A detailed inventory and condition survey carried out to determine the High flood levels (HFL's) in the project area.

Some of the major features collected were:

- Information was collected about the soils vegetation and drainage pattern along the project area.
- All necessary hydrological and other data for storm water and sub-surface drainage systems were collected.
- Characteristics of water crossings and hydrological structures were collected.

2.2.6 Engineering Design

Based on the existing road conditions, present Right-of-way (ROW) and traffic movement, we have developed designs and roadway plans necessary for the project. The improved HDC's will look aesthetically pleasing, efficient in traffic movement, uniform lanes, pedestrian friendly sidewalks, pleasing medians, adequate lighting and landscaping where possible.

We have considered all the current improvements undertaken by BBMP, BDA and designed further needed improvements.

2.2.6.1 Pavement Design

The pavement design includes Overlay design of the existing pavement

Falling weight Deflectometer Test Results and Pavement Condition Survey data as well as close reconnaissance by experts were used to determine the strengthening requirement of existing pavement. The thickness of overlay was proposed judiciously considering the provisions of IRC: 115-2014.

New pavement design is in accordance with IRC:37-2018.

2.2.7 Preliminary Cost Estimates

The rate of materials adopted in the preliminary cost estimate is based on the basic rates of PW, P & IWT D S.O.R. (Bengaluru Circle). For items where these rates are not available, the rates were adopted as per Market rates. For the working out of preliminary cost estimate, work items are split into the following sub-heads:

- Site Clearance and earthworks
- Granular Pavement Courses

- Flexible Pavement Overlays
- Culverts, Retaining Walls and other structures
- Drainage and other Protective works
- Road Furniture and Road Safety Works
- Traffic Management and maintenance during construction



CHAPTER 3

SCHEDULES

3.1 The Site

Site of the Project Road shall include the Road works, Parking lots, Bus bays, land, Drains and structures as described in table 3.1.

An inventory of the Site including the road works, land, buildings, structures, trees and any other immovable property on, or attached to, the Site shall be prepared jointly by the Authority Representative and the Contractor, and such inventory shall form part of the memorandum referred to in the Agreement.

The Master plan of the project road is specified in Map attached below (Fig 3.1). The proposed improvement of the project Roads shall be followed by the contractor with not less than the minimum proposal as per the Schedule. The contractor, however, may improve/upgrade the proposal as indicated in Annexure-II based on site/design requirement.

Table 3.1 Details of Road

| Sl. No | Name of the Road | Length in Km |
|--------|--|--------------|
| 1 | HDC 8: Mysore Road | 15.40 |
| 2 | HDC 9: Magadi Road | 12.00 |
| 3 | HDC 10: Tumkur Road | 7.90 |
| 4 | HDC 11: West of Chord Road | 8.40 |
| 5 | HDC 12a: ORR (From Mysore Road to Gorguntepalya) | 10.90 |
| | Total | 54.60 |






Figure 3.1 Map Showing Road Network



3.2 Land

The Site of the Project Road comprises the land, existing right of way as described below:

| Sl. no | Name of Place | | Existing Chainage in Km | | Length in (Km) | Existing ROW(m) |
|----------------------------|-------------------------|-------------------------|-------------------------|-------|----------------|--------------------|
| | From | To | From | To | | |
| HDC 08– Mysore Road | | | | | | |
| 1 | Hudson Circle | Nice Road | 0.00 | 15.40 | 15.40 | 13.50 m to 59.05 m |
| HDC 09 – Magadi Road | | | | | | |
| 2 | Leprosy Hospital | Nice Road | 0.00 | 12.00 | 12.00 | 15.00 m to 45.00 m |
| HDC 10 – Tumkur Road | | | | | | |
| 3 | Sangolli Rayanna Circle | Gorguntepal ya junction | 0.00 | 7.90 | 7.90 | 16.30 m to 81.93 m |
| HDC 11– West Of Chord Road | | | | | | |
| 4 | Sandal Soap Factory | Deepanjalina gar | 0.00 | 8.40 | 8.40 | 22.30 m to 67.47m |
| HDC 12a – Outer Ring Road | | | | | | |
| 5 | Nayadanahalli Junction | Gorguntepal ya Junction | 0.00 | 10.90 | 10.90 | 24.47 m to 62.30m |
| Total Length in Km | | | | | 54.60 | |

3.3 Carriageway

The present carriageway of the Project Road varies from Two lane Single carriageway to Six lane divided carriageway. The type of the existing pavement is both Flexible and Rigid pavement. Details of the existing carriageway is given in the following table.

| Existing Chainage in Km | | Length in (Km) | One Way / Two Way Traffic Movement | Divided/ Undivided Carriageway | Carriageway Width | | | Pavemen t type |
|----------------------------|-------|-------------------|---|--------------------------------------|-----------------------|--------------------|----------------------|-------------------|
| From | To | | | | LHS | Media n | RHS | |
| HDC 08– Mysore Road | | | | | | | | |
| 0.00 | 15.40 | 15.40 | One Way and Two Way | Divided and Undivided | 5.48m to 21.15m | 0.45 m to 3.0 m | 5.15 m to 7.62 m | CC and BC |
| HDC 09 – Magadi Road | | | | | | | | |
| 0.00 | 12.00 | 12.00 | Two Way | Divided | 6.00 m to 16.50 m | 0.60 m to 2.50m | 5.30 m to 23.60 m | BC |

| Existing Chainage in Km | | Length in (Km) | One Way / Two Way | Divided/ Undivided Carriageway | Carriageway Width | | | Pavemen |
|----------------------------|-------|----------------|-------------------|--------------------------------|-------------------|------------------|-------------------|----------------------|
| HDC 10 – Tumkur Road | | | | | | | | |
| 0.00 | 7.90 | 7.90 | Two Way | Divided | 6.50 m to 25.50 m | 0.35 m to 3.00m | 5.50 m to 42.85 m | BC and White Topping |
| HDC 11– West Of Chord Road | | | | | | | | |
| 0.00 | 8.40 | 8.40 | Two Way | Divided | 6.30 m to 13.00 m | 0.50 m to 3.00m | 2.30 m to 14.00 m | CC and BC |
| HDC 12a – Outer Ring Road | | | | | | | | |
| 0.00 | 10.90 | 10.90 | Two way | Divided | 7.25m to 11.0m | 0.60 m to 2.50 m | 7.25m to 11.0m | CC and BC |

3.4 Road Side Drain

The details of the side drain along the Project Corridors are as follows

| Sl. No | Existing chainage in km | | Length in km | Side | Total Length |
|----------------------------|-------------------------|-------|--------------|------|--------------|
| | From | To | | | |
| HDC 08– Mysore Road | | | | | |
| 1 | 0.00 | 15400 | 15.40 | Both | 18.70 |
| HDC 09 – Magadi Road | | | | | |
| 2 | 0.00 | 11000 | 11.00 | Both | 22.00 |
| HDC 10 – Tumkur Road | | | | | |
| 3 | 0.00 | 7700 | 7.70 | Both | 15.40 |
| HDC 11– West of Chord Road | | | | | |
| 4 | 0.00 | 8300 | 8.30 | Both | 16.60 |
| HDC 12a – Outer Ring Road | | | | | |
| 5 | 0.00 | 10827 | 10.827 | Both | 21.654 |
| Total Length of Drain | | | | | 94.354 |

3.5 Footpath

The details of the Existing Footpath along the Project Road are as follows.

| Existing Chainage in Km | | Length in (Km) | Paved / Unpaved | Footpath | | | |
|-------------------------|-------|----------------|-----------------|-----------|-----------------|-----------|-----------------|
| | | | | LHS | | RHS | |
| From | To | | | Length km | Width in m | Length km | Width in m |
| HDC 08– Mysore Road | | | | | | | |
| 0.00 | 15400 | 15.40 | Paved | 15.40 | 0.3 m to 8.62 m | 9.40 | 0.26 m to 6.0 m |
| HDC 09 – Magadi Road | | | | | | | |
| 0.00 | 11000 | 11.00 | Paved | 11.00 | 0.0 m to 5.10 m | 11.00 | 0.9 m to 5.0 m |

| HDC 10 – Tumkur Road | | | | | | | |
|--------------------------------|-------|--------|-------|--------|------------------|--------|------------------|
| 0.00 | 7700 | 7.70 | Paved | 7.70 | 0.36 m to 5.30m | 7.70 | 0.93 m to 5.68 m |
| HDC 11– West of Chord Road | | | | | | | |
| 0.00 | 8300 | 8.30 | Paved | 8.30 | 0.79 m to 6.10 m | 8.30 | 0.9 m to 3.5 m |
| HDC 12a – Outer Ring Road | | | | | | | |
| 0.00 | 10827 | 10.827 | Paved | 10.827 | 1.0 m to 4.8 m | 10.827 | 1.0 m to 9.5 m |
| Total Length of Footpath in Km | | | | | | 58.98 | |

3.6 Service Roads

The Existing Service Road Detail is in the following table.

| Sl. No | Existing chainage in Km | | LHS | | | RHS | | |
|------------------------------------|-------------------------|--------|------------|-----------------|------------------|------------|-----------------|------------------|
| | From | To | Length, Km | Width, m | Type of Pavement | Length, Km | Width, m | Type of Pavement |
| HDC 09– Magadi Road | | | | | | | | |
| 1 | 3.199 | 3.532 | 0.333 | 7.4m | Flexible | 0.333 | 7.65 m | Flexible |
| HDC 10 – Tumkur Road | | | | | | | | |
| 2 | 5.100 | 7.600 | 2.50 | 7.5m | Flexible | 0.1 | 2.9m | Flexible |
| HDC 11– West of Chord Road | | | | | | | | |
| 3 | 0.900 | 8.25 | 7.15 | 4.5 m to 15.0m | Flexible | 7.35 | 4.5 m to 9.0m | Flexible |
| HDC 12a – Outer Ring Road | | | | | | | | |
| 4 | 0.650 | 10.827 | 10.027 | 3.8 m to 14.10m | Flexible | 10.127 | 4.4 m to 14.30m | Flexible |
| Total Length of Service Road in Km | | | | | | 37.920 | | |

3.7 Structures

The Existing Structure Detail is in the following table.

| Sl No | Type of Structure | No of Structures | | | | | Total |
|-------|-------------------|------------------|--------|--------|--------|---------|-------|
| | | HDC 08 | HDC 09 | HDC 10 | HDC 11 | HDC 12a | |
| 1 | Bridges | 2 | 1 | 2 | 1 | 3 | 9 |
| 2 | Culverts | 6 | 4 | - | - | - | 10 |
| 3 | Flyover | 2 | - | 1 | 3 | 7 | 13 |
| 4 | ROB/RUB | - | - | 2 | 1 | - | 3 |
| 5 | VUP/PUP/CUP/VOP | - | 1 | 3 | 2 | 9 | 15 |



3.8 Bus Shelters / Bus Bays / BusStop

In this project road there are 115 No. of bus stops the details are shown below:

| Sl No | Chainage | Side | | Remarks |
|---------------------|----------|------|-----|-----------------------------|
| | | LHS | RHS | |
| HDC 08– Mysore Road | | | | |
| 1 | 0.00 | Yes | - | Hudson circle |
| 2 | 690.0 | Yes | - | State Gun House |
| 3 | 1200 | - | Yes | BMTC bus stop |
| 4 | 2380 | Yes | - | Murthi Cycle Shop |
| 5 | 2430 | - | Yes | Vetarinary Hospital |
| 6 | 3200 | - | Yes | RK Bar &Restaure |
| 7 | 3620 | - | Yes | Bharath Petroleum |
| 8 | 3980 | - | Yes | 1st Main Cross Road |
| 9 | 4030 | - | Yes | Bus Stop |
| 10 | 4050 | Yes | - | GSPH (Lift) |
| 11 | 4750 | - | Yes | VPL Pvt.Ltd |
| 12 | 4950 | - | Yes | New Master Piece |
| 13 | 5250 | Yes | - | Satallite Bus Stand |
| 14 | 6120 | - | Yes | Deepanjali Nagar Junction |
| 15 | 7000 | Yes | - | Rajalakshmi weigh bridge |
| 16 | 7500 | - | Yes | 2nd cross |
| 17 | 8010 | - | Yes | B.P Petrol bunk |
| 18 | 11150 | - | Yes | RV College Bus Stop |
| 19 | 11200 | Yes | - | RV College Bus Stop |
| 20 | 13000 | - | Yes | Kengeri Main Bus Station |
| 21 | 13650 | - | Yes | Kengeri police station |
| 22 | 13700 | Yes | - | KSRTC Ticket booking centre |
| HDC 09– Magadi Road | | | | |
| 23 | 200.00 | - | Yes | Gopalapura 1st cross |
| 24 | 800.00 | - | Yes | Jana Jyothi Building |
| 25 | 830.00 | Yes | - | Jyoti motors |
| 26 | 1330.00 | - | Yes | Saptagiri complex |
| 27 | 1450.00 | Yes | - | M.S Complex |
| 28 | 1630.00 | Yes | - | Cholurpalya Cross |
| 29 | 1800.00 | Yes | - | Ganapati temple |
| 30 | 1830.00 | - | Yes | Indian oil Petrol Bunk |
| 31 | 2563.00 | - | Yes | Sri Shiradisai fashions |
| 32 | 2860.00 | Yes | - | DasarahalliBusstop |
| 33 | 2997.00 | - | Yes | whirpool service centre |
| 34 | 3233.00 | Yes | - | Indian oil Petrol Bunk |
| 35 | 3423.00 | - | Yes | UCO Bank |
| 36 | 3530.00 | Yes | - | Leonardo Automation |

| SI No | Chainage | Side | | Remarks |
|----------------------|----------|------|-----|------------------------------|
| | | LHS | RHS | |
| 37 | 3600.00 | - | Yes | Sri revannasiddeshvara mess |
| 38 | 4195.00 | - | Yes | Dananjaya palace |
| 39 | 4211.00 | - | Yes | AthreyaAyurvedha pharm |
| 40 | 4941.00 | Yes | - | Sri manjunatha creations |
| 41 | 5290.00 | - | Yes | Gajananan Xerox centre |
| 42 | 5950.00 | Yes | - | UdupiUpahaar |
| 43 | 6200.00 | - | Yes | Bank Of Baroda |
| 44 | 7130.00 | - | Yes | Sangeetha Mobiles |
| 45 | 7200.00 | Yes | - | Sri Murthy Comlex |
| 46 | 7400.00 | - | Yes | Star Furnitures |
| 47 | 7850.00 | Yes | - | Sri VinayakaTilor |
| 48 | 7900.00 | - | Yes | Adishwara |
| 49 | 8450.00 | Yes | - | Govt. School |
| 50 | 8550.00 | - | Yes | Shankar Nag Auto stand |
| 51 | 9050.00 | Yes | - | AnjanaNagara Junction |
| 52 | 9100.00 | - | Yes | Mamata Bangles |
| 53 | 9750.00 | Yes | - | KPTCL |
| 54 | 9850.00 | - | Yes | Kiran Wines |
| 55 | 10150.00 | Yes | - | Indian oil Petrol Bunk |
| 56 | 10250.00 | Yes | - | ManjunathCandimantes |
| 57 | 10350.00 | - | Yes | Home Style Furniture |
| 58 | 10850.00 | - | Yes | Sri Ranganatha Auto Mobiles |
| 59 | 10900.00 | Yes | - | Junction |
| HDC 10 – Tumkur Road | | | | |
| 60 | 468.00 | - | Yes | RRR Kalyanamantapa |
| 61 | 560.00 | Yes | - | Jain heights palace |
| 62 | 1120.00 | Yes | - | Big tree |
| 63 | 1150.00 | - | Yes | Sujatha talkies |
| 64 | 1156.00 | - | Yes | SKT tyres |
| 65 | 1165.00 | Yes | - | Planet Honda service station |
| 66 | 3010.00 | - | Yes | Sagarsima 1960 |
| 67 | 4110.00 | Yes | - | Karmikarajyavimanigama |
| 68 | 4140.00 | Yes | - | Indian oil Petrol bunk |
| 69 | 4800.000 | - | Yes | Sandal Soap metro station |
| 70 | 4900.00 | - | Yes | Statue |
| 71 | 5500.00 | Yes | - | Yeshwanthpura |
| 72 | 6300.00 | - | Yes | APMC Yard |
| 73 | 6400.00 | - | Yes | Vaishnavi sapphaire center |
| 74 | 6600.00 | Yes | - | ICICI Bank |
| 75 | 6900.00 | - | Yes | IOC Namratha Agency |

| Sl No | Chainage | Side | | Remarks |
|----------------------------|----------|------|-----|----------------------------|
| | | LHS | RHS | |
| 76 | 7100.00 | Yes | - | Sparsh Hospitals |
| 77 | 7500.00 | - | Yes | People tree Hospital |
| HDC 11- West Of Chord Road | | | | |
| 78 | 170.00 | Yes | - | Mysore Sandal soap factory |
| 79 | 180.00 | - | Yes | Ravindu Toyota Show Room |
| 80 | 192.00 | - | Yes | Ravindu Toyota Show Room |
| 81 | 830.00 | Yes | - | Iskcon Temple |
| 82 | 1200.00 | Yes | - | Aram Hotel |
| 83 | 1750.00 | - | Yes | Metro Building |
| 84 | 1760.00 | Yes | - | Metro Building |
| 85 | 2170.00 | Yes | - | Sindhu Hotel |
| 86 | 2580.00 | - | Yes | Ananya Hospital |
| 87 | 2870.00 | Yes | - | Nandana Palace |
| 88 | 3273.00 | Yes | - | J.P lights |
| 89 | 3280.00 | - | Yes | Car decorators |
| 90 | 3330.00 | - | Yes | G.D cars |
| 91 | 3330.00 | Yes | - | G.D cars |
| 92 | 5600.00 | Yes | - | KSRTC Dispensary |
| 93 | 5700.00 | Yes | - | Falcon Foot Wear |
| 94 | 5700.00 | - | Yes | Falcon Foot Wear |
| 95 | 6000.00 | Yes | - | Mini Corner Stores |
| 96 | 6200.00 | - | Yes | Maruthi Complex |
| 97 | 6200.00 | - | Yes | Maruthi Complex |
| 98 | 6450.00 | - | Yes | Vacant Land |
| 99 | 6650.00 | Yes | - | Prasad Enterprises |
| HDC 12a - Outer Ring Road | | | | |
| 100 | 120 | Yes | - | Mandovi Motors |
| 101 | 620 | - | Yes | Modern Bakery |
| 102 | 700 | Yes | - | Disha Designs |
| 103 | 1450 | Yes | - | Manish Food |
| 104 | 1450 | - | Yes | Manish Food |
| 105 | 2230 | - | Yes | Sai Ganesh Hotel |
| 106 | 2300 | Yes | - | Nandini Layout Bus stop |
| 107 | 2700 | - | Yes | To Nandini layout |
| 108 | 2700 | Yes | - | To Nandini layout |
| 109 | 3300 | Yes | - | GM Tours Travels |
| 110 | 3500 | - | Yes | Popular Finance |
| 111 | 3950 | - | Yes | CMH Bar |
| 112 | 3950 | Yes | - | CMH Bar |
| 113 | 6400 | Yes | - | Sri Plaza |
| 114 | 7600 | Yes | - | Open land |

| Sl No | Chainage | Side | | Remarks |
|-------|----------|------|-----|-----------------------------|
| | | LHS | RHS | |
| 115 | 9950 | Yes | - | Sri Maruthi Modular Kitchen |

3.9 Junctions

In the project road, there are 94 major junctions and 09 minor junctions. Details of all the junctions are given below:

Major Junction

| Sl. No | Existing chainage | Type of Junction | Road Type | Side |
|----------------------------|-------------------|------------------|-----------|------|
| HDC 08- Mysore Road | | | | |
| 1 | 30.00 | + | BT | Both |
| 2 | 200.0 | + | BT | Both |
| 3 | 500.0 | Y | BT | Both |
| 4 | 575.0 | Y | BT | Both |
| 5 | 810.0 | T | BT | Both |
| 6 | 1150.0 | + | BT | Both |
| 7 | 1350.0 | + | BT | Both |
| 8 | 1740.0 | T | BT | Both |
| 9 | 1910.0 | T | BT | Both |
| 10 | 2170.0 | + | BT | Both |
| 11 | 2330.0 | + | BT | Both |
| 12 | 2440.0 | + | BT | Both |
| 13 | 2610.0 | T | BT | Both |
| 14 | 2790.0 | T | BT | Both |
| 15 | 3060.0 | T | BT | Both |
| 16 | 3350.0 | + | BT | Both |
| 17 | 3770.0 | + | BT | Both |
| 18 | 4270.0 | T | BT | Both |
| 19 | 4930.0 | T | BT | Both |
| 20 | 5230.0 | T | BT | Both |
| 21 | 5520.0 | Circle | BT | Both |
| 22 | 5760.0 | T | BT | Both |
| 23 | 6050.0 | Circle | BT | Both |
| 24 | 7260.0 | + | BT | Both |
| 25 | 7350.0 | + | BT | Both |
| 26 | 7500.0 | + | BT | Both |
| 27 | 7840.0 | + | BT | Both |
| 28 | 8300.0 | + | BT | Both |
| 29 | 8750.0 | T | BT | Both |
| 30 | 9350.0 | T | BT | Both |
| 31 | 10150.0 | T | BT | Both |

| Sl. No | Existing chainage | Type of Junction | Road Type | Side |
|------------------------------------|-------------------|-----------------------|-----------|------|
| 32 | 12500.0 | T | BT | Both |
| 33 | 13200.0 | + | BT | Both |
| 34 | 13600.0 | + | BT | Both |
| 35 | 15000.0 | Y | BT | Both |
| HDC 09 – Magadi Road | | | | |
| 36 | 0.00 | T | BT | RHS |
| 37 | 1350.0 | Y | BT | RHS |
| 38 | 1850.0 | + | BT | BOTH |
| 39 | 2280.0 | T | BT | LHS |
| 40 | 2635.0 | + | BT | BOTH |
| 41 | 3020.0 | T | BT | LHS |
| 42 | 3300.0 | + | BT | BOTH |
| 43 | 3760.0 | + | BT | BOTH |
| 44 | 4036.0 | Y | BT | RHS |
| 45 | 4620.0 | + | BT | BOTH |
| 46 | 4690.0 | Y | BT | RHS |
| 47 | 4940.0 | Y | BT | LHS |
| 48 | 5430.0 | + | BT | - |
| 49 | 6261.0 | T | BT | LHS |
| 50 | 8400.0 | T | BT | RHS |
| 51 | 8600.0 | T | BT | RHS |
| 52 | 9080.0 | + | BT | BOTH |
| 53 | 9300.0 | T | BT | LHS |
| 54 | 9450.0 | T | BT | RHS |
| 55 | 10080.0 | T | BT | LHS |
| 56 | 10090.0 | + | BT | BOTH |
| HDC 10 – Tumkur Road | | | | |
| 57 | 0.00 | Skewed Y | BT | LHS |
| 58 | 610.0 | Skewed Y | BT | LHS |
| 59 | 1250.0 | + | BT | Both |
| 60 | 1850.0 | T | BT | RHS |
| 61 | 2030.0 | + | BT | Both |
| 62 | 2200.0 | + | BT | Both |
| 63 | 2350.0 | T | BT | Both |
| 64 | 2750.0 | + | BT | Both |
| 65 | 3100.0 | + | BT | Both |
| 66 | 3400.0 | + | BT | Both |
| 67 | 3550.0 | Multiple Intersection | BT | Both |
| 68 | 3810.0 | + | BT | Both |
| 69 | 4050.0 | T | BT | Both |
| 70 | 5050.0 | Y | BT | Both |
| 71 | 6750.0 | + | BT | Both |
| 72 | 7300.0 | + | cc | Both |
| HDC 11 – West Of Chord Road | | | | |

| Sl. No | Existing chainage | Type of Junction | Road Type | Side |
|----------------------------------|-------------------|------------------|-----------|------|
| | 815.00 | T | BT | RHS |
| 74 | 1200.0 | + | BT | Both |
| 75 | 1950.0 | + | BT | Both |
| 76 | 2450.0 | + | BT | Both |
| 77 | 3136.0 | + | BT | Both |
| 78 | 3435.0 | + | BT | Both |
| 79 | 4490.0 | + | BT | Both |
| 80 | 4900.0 | + | BT | Both |
| 81 | 5200.0 | T | BT | RHS |
| 82 | 5600.0 | + | BT | Both |
| 83 | 6100.0 | T | BT | RHS |
| 84 | 6250.0 | + | BT | Both |
| 85 | 6450.0 | + | BT | Both |
| 86 | 7150.0 | T | BT | RHS |
| 87 | 7450.0 | + | BT | Both |
| HDC 12a – Outer Ring Road | | | | |
| 88 | 1030.0 | + | BT | Both |
| 89 | 1890.0 | + | BT | Both |
| 90 | 5180.0 | + | BT | Both |
| 91 | 6760.0 | + | BT | Both |
| 92 | 8300.0 | T | BT | RHS |
| 93 | 9020.0 | + | BT | Both |
| 94 | 10580.0 | + | BT | Both |

Minor Junction

From the inventory, it is found that there are 02 minor junctions in Mysore Road, 01 minor junction in Magadi Road, 02 minor junctions in Tumkur road, 01 minor junction in West Of Chord Road and 03 minor junctions in Outer Ring Road.

3.10 Road Furnitures

| Sl No | Description | Unit | Quantity | | | | | Total |
|-------|------------------------|------|----------|--------|--------|--------|---------|-------|
| | | | HDC 08 | HDC 09 | HDC 10 | HDC 11 | HDC 12a | |
| 1 | Street lights | No | 514 | 322 | 144 | 559 | 558 | 2097 |
| 2 | Highmast | No | - | 3.00 | - | - | - | 3.00 |
| 3 | Pedestrian guard rails | km | 1.55 | 0.45 | 0.60 | 0.48 | - | 3.08 |
| 4 | Kerb | km | 7.75 | 5.90 | 5.40 | 7.30 | 9.60 | 35.95 |
| 5 | Pavement marking | | | | | | | |
| 5.1 | Edge Lane Marking | km | 2.70 | 7.10 | 3.20 | 6.20 | 4.70 | 23.90 |
| 5.2 | Centre Lane | km | 2.70 | 7.10 | 2.35 | 4.20 | 4.70 | 21.05 |

| SI No | Description | Unit | Quantity | | | | | Total |
|-------|--------------------|------|----------|--------|--------|--------|---------|--------|
| | | | HDC 08 | HDC 09 | HDC 10 | HDC 11 | HDC 12a | |
| | Marking | | | | | | | |
| 6 | New jersey barrier | km | 2.45 | 0.60 | 2.40 | 2.30 | 0.60 | 8.35 |
| 7 | Road studs | km | 2.70 | 3.50 | 1.50 | 1.00 | - | 8.70 |
| 8 | Sign boards | No | 151 | 260 | 275 | 245 | 288 | 1219 |
| 9 | Land scaping | km | 2.15 | 3.20 | 2.40 | 5.54 | 9.90 | 23.19 |
| 10 | Bollards | No | - | - | 65.00 | 51.00 | - | 116.00 |

3.11 Pavement Type

| SI No | Chainage | | Length | Pavement type | |
|---------------------|----------|-------|--------|---------------|----------|
| | From | To | | LHS | RHS |
| HDC 08– Mysore Road | | | | | |
| 1 | 0.00 | 600 | 0.60 | BT | BT |
| 2 | 600 | 1150 | 0.55 | BT | CC+BT |
| 3 | 1150 | 1350 | 0.20 | BT | CC |
| 4 | 1350 | 2100 | 0.75 | BT | BT |
| 5 | 2100 | 2200 | 0.10 | CC | BT |
| 6 | 2200 | 2350 | 0.15 | BT | CC+Paver |
| 7 | 2350 | 2450 | 0.10 | BT | CC |
| 8 | 2450 | 3300 | 0.85 | BT | CC+Paver |
| 9 | 3300 | 3600 | 0.30 | BT | BT |
| 10 | 3600 | 3650 | 0.05 | BT | CC+Paver |
| 11 | 3650 | 3800 | 0.15 | BT | CC+BT |
| 12 | 3800 | 3850 | 0.05 | CC+BT | CC+BT |
| 13 | 3850 | 3950 | 0.10 | CC+BT | CC |
| 14 | 3950 | 4100 | 0.15 | CC+BT | CC+Paver |
| 15 | 4100 | 4150 | 0.05 | CC+BT | CC |
| 16 | 4150 | 4250 | 0.10 | CC+BT | CC+Paver |
| 17 | 4250 | 4300 | 0.05 | CC+BT | CC+BT |
| 18 | 4300 | 4400 | 0.10 | CC+BT | CC+Paver |
| 19 | 4400 | 4450 | 0.05 | CC+BT | CC+BT |
| 20 | 4450 | 4500 | 0.05 | CC | CC+Paver |
| 21 | 4500 | 4650 | 0.15 | CC+BT | CC+Paver |
| 22 | 4650 | 4850 | 0.20 | CC+BT | CC+BT |
| 23 | 4850 | 4950 | 0.10 | CC | CC |
| 24 | 4950 | 5600 | 0.65 | CC+BT | CC+BT |
| 25 | 5600 | 5700 | 0.10 | BT | BT |
| 26 | 5700 | 5900 | 0.20 | CC+BT | CC+BT |
| 27 | 5900 | 15400 | 9.50 | BT | BT |

| SI No | Chainage | | Length | Pavement type | |
|--|----------|-------|--------|---------------|---------------|
| | From | To | | LHS | RHS |
| HDC 09 – Magadi Road | | | | | |
| 1 | 0.00 | 11000 | 11.00 | BT | BT |
| HDC 10 – Tumkur Road | | | | | |
| 1 | 0 | 7000 | 7.00 | BT | BT |
| 2 | 7000 | 7700 | 0.70 | White Topping | White Topping |
| HDC 11 – West of Chord Road | | | | | |
| 1 | 0.00 | 200 | 0.20 | CC | CC |
| 2 | 200 | 300 | 0.10 | BT | BT |
| 3 | 300 | 500 | 0.20 | CC | CC |
| 4 | 500 | 600 | 0.10 | BT | BT |
| 5 | 600 | 1300 | 0.70 | CC | CC |
| 6 | 1300 | 1400 | 0.10 | BT | BT |
| 7 | 1400 | 1800 | 0.40 | CC | CC |
| 8 | 1800 | 6600 | 4.80 | BT | BT |
| 9 | 6600 | 8250 | 1.65 | CC | CC |
| HDC 12a – Outer Ring Road | | | | | |
| 1 | 0.00 | 1600 | 1.60 | BT | BT |
| 2 | 1600 | 2250 | 0.65 | CC | BT |
| 3 | 2250 | 2600 | 0.35 | BT | BT |
| 4 | 2600 | 2750 | 0.15 | BT | CC |
| 5 | 2750 | 3700 | 0.95 | CC | CC |
| 6 | 3700 | 3900 | 0.20 | BT | CC |
| 7 | 3900 | 4000 | 0.10 | BT | BT |
| 8 | 4000 | 4050 | 0.05 | BT | CC |
| 9 | 4050 | 4900 | 0.85 | CC | CC |
| 10 | 4900 | 4950 | 0.05 | CC | BT |
| 11 | 4950 | 5350 | 0.40 | BT | BT |
| 12 | 5350 | 5800 | 0.45 | BT | CC |
| 13 | 5800 | 5850 | 0.05 | BT | BT |
| 14 | 5850 | 7200 | 1.35 | BT | CC |
| 15 | 7200 | 7600 | 0.40 | CC | CC |
| 16 | 7600 | 8050 | 0.45 | BT | CC |
| 17 | 8050 | 8550 | 0.50 | CC | CC |
| 18 | 8550 | 8600 | 0.05 | CC | BT |
| 19 | 8600 | 10800 | 2.20 | BT | BT |
| Total Length of Flexible Road:- 44.55 Km | | | | | |
| Total Length of Concrete Road:- 11.50 Km | | | | | |
| Total Length of Concrete and Flexible Road:- 3.50 Km | | | | | |



CHAPTER 4

DESIGN STANDARDS, METHODOLOGIES AND SPECIFICATIONS

4.1 Project Corridors

The proposed improvement is to be carried out to make it a good infrastructure for improvement of residential and commercial configuration in all respects. The terrain on this stretch is plain.

This section describes the standards and principles based on which various designs will be carried out. These proposed standards are consistent with the parameters recommended in the relevant standards of the Indian Roads Congress (IRC). The aim of this chapter is to evolve design standards and material specifications for the study, which is primarily based on IRC publications and MoRTH circulars and relevant standards.

4.2 Classification of Urban Roads

The following classification of urban roads has been recommended in IRC-86:1983

- Arterial Roads
- Sub-arterial roads
- Collector Streets
- Local streets

4.3 Guiding Principles

While carrying out the geometric design, the following points will be taken into consideration:

The designed facility shall not become obsolescent before the design year.

Design shall be consistent and the standards followed for different elements shall be compatible with one another.

The design shall cover all geometric aspects of the road including signage.

The design will be worked out, aiming at minimizing the vehicle operating cost, including initial cost and cost of maintenance etc.

The design will take into consideration the environmental and landscaping aspects of the project road

4.4 Traffic Design

4.4.1 General

IRC has, however, published highway capacity standards for rural / urban highways.

Capacity analysis is fundamental to the planning, design and operation of roads, and provides, among other things, the basis for determining the carriageway width to be provided at any point in a road network with respect to the volume and composition of traffic. Moreover it is a valuable tool for evaluation of the investments needed for future road constructions and improvements.

4.4.2 Definition and Concepts

Volume (or Flow) is the number of vehicles that pass through a given point on the road during a designated time interval. Since roads have a certain width and numbers of lanes are accommodated in that width. Flow is always expressed in relation to the given width (i.e., per lane or per two lane etc.). The time unit selected is an hour or a day. ADT is the volume of average Daily Traffic when the measurements are taken for a few days. AADT is the volume of the Annual Average Daily Traffic when measurements are taken for 365 days of the year and averaged out. (Clause 4.5 of IRC 106 of 1990)

Density (or Concentration) is the number of vehicles occupying a unit length of road at an instant of time. The unit length is generally one Kilometre. Density is expressed in relation to the width of the road (i.e. per lane or per two lanes etc.).

When vehicles are in jammed condition, the density is the maximum. It is then termed as the jamming density. (Clause 4.6 of IRC 106 of 1990)

Capacity is defined as the maximum hourly volume (vehicles per hour) at which vehicles can reasonably be expected to traverse a point or uniform section of a lane or roadway during a given time period under the prevailing road way, traffic and control conditions. (Clause 4.7 of IRC 106 of 1990)

Design Service Volume is defined as the maximum hourly volume at which vehicles can reasonably be expected to traverse a point or uniform section of a lane or road way during the given time period under the prevailing roadway, traffic and control conditions while maintaining a designated level of service. (Clause 3.5 of IRC 64 of 1990)

Peak Hours Factor is defined as the traffic volume during peak hour expressed as percentage of the AADT. The peak hour volume in this case is taken as the thirtieth hourly Volume (i.e., volume of traffic which is expected only during 30 hours in a year).

4.4.3 Level of Service (Clause 5.1 of IRC 106 of 1990)

Capacity standards are fixed normally in relation to the Level of Service (LOS) adopted for

A handwritten signature in blue ink is written over a circular blue stamp. The stamp contains the text "Engineers (India)" around its perimeter.

the design. Level of Service is defined as a qualitative measure describing operational conditions

Level of Service definition generally describes these conditions in terms of factors such as speed and travel time, freedom to manoeuvre, traffic interruptions, comfort, convenience and safety. Six levels of service are recognised commonly, designated from A to F, with Level of Service A representing the best operating condition (i.e. free flow and Level of Service F the worst (i.e. forced or break-down flow). On urban roads, the Level of Service is affected strongly by factors like the heterogeneity of traffic, speed regulations, strongly by factors like the heterogeneity of traffic, speed regulations strongly by factors like the heterogeneity of traffic, speed regulations, frequency of intersections, presence of bus stops, on-street parking, roadside commercial activities, pedestrian volumes etc. This renders the Level of Service concept




Figure 3.1 Map Showing Various Levels of Service in the form of indicative Volume-Flow Relationship

4.4.3.1 Equivalency Factors

The need of expressing capacity in passenger car units has triggered off many studies for establishing appropriate Passenger Car Equivalency (PCE) values for different types of vehicles. Notable among the studies carried out in India are the Road User Cost Studies (RUCS) by the CRRI and the MoRT&H. It has been recognised that the PCE values vary under different traffic and roadway conditions for any given type of vehicle.

Equivalency Factor is a factor to convert the mixed flow of traffic in to single unit to express the capacity of road. The unit generally employed is the Passenger Car Unit (PCU).

The maximum service flow in terms of PCUs per day in rolling and hilly terrain will depend upon the extent of trucks and buses present in the traffic stream, their PCU equivalent and the grades of the alignment, PCU for commercial vehicles vary with the magnitude of grade. Further, the passenger car equivalent factor decreases for the same grade with the increase in the percentage of commercial vehicles.

Tentative equivalency factor for conversion of different types of vehicles in to equivalent passenger car units based on their relative interference value are considered.

4.4.4 Recommended Design Service Volumes for Two Lane Roads

Design service volumes as given in Table 3.1 assume, that the functional classification of roads into arterial, sub-arterial and collector categories.

Table 4.1 Design service volumes for Two lane roads

| Sl. No. | Type of Carriageway | Total Design Service Volumes for Different Categories of Urban Roads | | |
|---------|-----------------------------|--|--------------|-----------|
| | | Arterial | Sub-Arterial | Collector |
| 1 | 2-Lane (One Way) | 2400 | 1900 | 1400 |
| 2 | 2-Lane (Two Way) | 1500 | 1200 | 900 |
| 3 | 3-Lane (One Way) | 3600 | 2900 | 2200 |
| 4 | 4-Lane Undivided (Two Way) | 3000 | 2400 | 1800 |
| 5 | 4-Lane Divided (Two Way) | 3600 | 2900 | - |
| 6 | 6- Lane Undivided (Two Way) | 4800 | 3800 | - |
| 7 | 6- Lane Divided (Two Way) | 5400 | 4300 | - |
| 8 | 8- Lane Divided (Two Way) | 7200 | - | - |

4.4.5 Traffic Signs and Road Markings

The design of traffic signs and road marking shall be done according to the IRC standards. Where necessary, AASHTO standards will be used to augment the IRC standards.

Following is the list of IRC standards, which are being followed:

- IRC: 35-2015 - Code of practice for Road markings
- IRC: 67-2012 - Code of practice for Road Signs
- IRC: SP: 55-2014 - Guidelines for Safety in Construction Zones

Adequate safety measures have been considered for the design of the project road.

These are indicated as below:

Crash barriers

Reflectors

Proper super elevation and radii of curvature

Traffic signage

Drainage

The safety during construction shall be achieved by providing;

Signs (regulatory, warning and direction)

Delineators

Traffic cones and cylinders

Drums

Barricades

Flagmen

4.5 Indicative Design Standards for Road

The indicative design standards for geometric design of road are illustrated in the **Tables 3.2** as Indicative Design Standards for main Carriageway and geometric standards

Table 4.2 Indicative Design Standards for Main Carriageway

| Sl. No. | Parameter | Value | Standard / Code Reference |
|---------|----------------------|------------------|---------------------------|
| 1 | Design Speed | | IRC: 86-2018 |
| | Arterial | 60 kmph | |
| | Sub-arterial | 60 kmph | |
| | Collector Street | 40 kmph | |
| | Local Street | 30 kmph | |
| 2 | Cross Section | | IRC: 86-2018 |
| | (i) Carriageway | 3.50m with Kerbs | |
| | (ii) Footpath | Minimum 1.8m | |
| | (iii) Cross slope: | | |

| Sl. No. | Parameter | Value | Standard / Code Reference |
|---------|---------------------------------------|-------------|---------------------------|
| | - Main carriageway and Paved shoulder | 2.0 to 2.5% | |
| | - Footpath | 2.5 to 3.0% | |

4.6 Road Markings

Road markings shall be as per IRC: 35-2015. These markings shall be applied to road center lines, edge lines, continuity line, stop lines, give-way lines, diagonal/chevron markings, zebra crossing and at parking areas by means of an approved self-propelled machine which has a satisfactory cut-off value capable of applying broken lines automatically.

Road markings shall be of hot applied thermoplastic paints with glass reflectorizing beads conforming to MoRTH Specifications for Road and Bridge works (5th Revision).

4.7 Specifications

The materials to be used in the Project work and the specifications for execution of work shall conform to "MORTH Specifications for Road and Bridge Works 5th Rev. 2013". However special Technical Specifications shall be framed wherever MORTH specifications need change / amendments. Where these specifications are silent with regard to certain specifications for the material in question, in that case, specifications under Bureau of Indian Standards / AASHTO / ASTM / BS or any other international standard shall apply.



CHAPTER - 5

CONCLUSIONS

5.1 Roads

A total length of km of existing road is been designed to be overlayed using thin white topping and is been detailed in Table No. 5.1.

Table 5.1 Details of Road

| Sl. No | Name of the Road | Length in Km |
|--------------|--|--------------|
| 1 | HDC 8: Mysore Road | 15.40 |
| 2 | HDC 9: Magadi Road | 12.00 |
| 3 | HDC 10: Tumkur Road | 7.90 |
| 4 | HDC 11: West of Chord Road | 8.40 |
| 5 | HDC 12a: ORR (From Mysore Road to Gorguntepalya) | 10.90 |
| Total | | 54.60 |

5.1.1 Milling

The milling of the existing asphalt pavement provides removal of rutting, a roughened surface to enhance the bonding between the new concrete overlay and the existing asphalt pavement. The depth of milling (25-50 mm) depends upon the types and severity of distress especially the depth of rutting or other surface distortions and the available thickness of asphalt pavement. Hand grinding/Light Chiselling may also be used gently for making the roughness in top surface of asphalt pavement at difficult locations.

5.1.2 Cleaning

After milling or providing the profile correction course, atop the existing asphalt pavement, the top surface is cleaned to ensure bonding between the existing asphalt pavement and the new concrete overlay. Different methods of cleaning to remove foreign particles are given as:

- Air blasting/vacuum cleaner
- Power brooming
- Water blasting
- Sand blasting
- Chiseling

5.1.4 Overlay

The carriageway is proposed with overlay (wearing course-Bituminous Concrete) or strengthening with overlay (Binder + wearing course – Dense Bituminous Macadam + Bituminous Concrete) as per IRC:115-2014. For rigid pavements joint maintenance is

considered, and since, white Topping roads are under DLP / maintenance hence not considered for Initial Improvements. Service road carriageways shall be improved similar to main carriageway. The improvement of carriageway is valued with proper Road Markings, Road Studs, Speed Calming Measures and adequate sign Board installations. Following are chainages where overlay or strengthening is proposed

Table 5.2 Details of Stretches where Overlay or Strengthening Layer is Proposed

| Sl No | Road name | Stretch/Chainage (m) | No of Lanes | Lane width (m) | Length (m) | Overlay Thickness in mm | |
|-------|-------------|----------------------|---|---|------------|-------------------------|----|
| | | | | | | DBM | BC |
| 1 | Mysore Road | 7700-8200 | 4 Lane Divided Carriageway | 7.5 | 500 | 50 | 40 |
| 2 | | 13250-13750 | 4 Lane Divided Carriageway | 7.5 | 500 | 50 | 40 |
| 3 | | 6650-7750 | 4 Lane Divided Carriageway | 7.5 | 1100 | - | 40 |
| 4 | | 8700-9500 | 4 Lane Divided Carriageway | 7.5 | 800 | - | 40 |
| 5 | | 9500-11500 | 4 Lane Divided Carriageway and 6 Lane Divided Carriageway | 9500-9600 (10.5m), 9600-10100 (7.5m), 10100-10300 (10.5m), 10300-11500 (7.5m) | 2000 | - | 40 |
| 6 | | 11600-12550 | 4 Lane Divided Carriageway | 7.5 | 950 | - | 40 |
| 7 | | 12600-14250 | 4 Lane Divided Carriageway and 6 Lane Divided Carriageway | 12600-13400 (7.5m), 13400-14300 (10.5m) | 1650 | - | 40 |
| 8 | | 14300-15300 | 4 Lane Divided Carriageway | 7.5 | 1000 | - | 40 |
| 9 | Magadi Road | 670-2500 | 4 Lane Divided Carriageway and 6 Lane Divided Carriageway | 670-1300 (7m), 1300-2000 (10.5m), 2000-2500 (7m) | 1830 | 50 | 40 |
| 10 | | 7100-11570 | 6 Lane Divided Carriageway | 10.5 | 4470 | 50 | 40 |

[Signature]


| Sl No | Road name | Stretch/Chainage (m) | No of Lanes | Lane width (m) | Length (m) | Overlay Thickness in mm | |
|-------|-------------|----------------------|----------------------------|----------------|------------|-------------------------|----|
| | | | | | | DBM | BC |
| 11 | Tumkur Road | 5500-6800 | 6 Lane Divided Carriageway | 10.5 | 1300 | 50 | 40 |
| 12 | | 3300-3900 | 4 Lane Divided Carriageway | 7.5 | 600 | 50 | 40 |
| 13 | | 4200-5000 | 4 Lane Divided Carriageway | 7.5 | 800 | 50 | 40 |
| 14 | WOC Road | 7000-7500 | 4 Lane Divided Carriageway | 7.5 | 500 | 50 | 40 |
| 15 | | 7550-8400 | 4 Lane Divided Carriageway | 7.5 | 850 | - | 40 |

5.2 Roadside Drainage

Where, the existing condition of drain is found not functioning and structurally inadequate, maintenance is proposed by clearing of clogged drain and reconstruction is proposed to replace the damaged portion. Wherever, construction of new drain or upgradation of existing masonry / BS slab drain to RCC is envisaged, design of drain should be done as per applicable standards and approval should be taken from the relevant authority. De silting is considered for entire length and reconstruction of damaged portion is proposed

5.3 Median Improvement and Guard Rail

The improvement proposal includes replacing of broken new jersey barrier, pedestrian guard rails and kerb stones with the new ones and painting of the kerb for the entire stretch of the corridors.

To avoid the random road crossing of Pedestrians and to enhance the Pedestrian safety Median Guard rails are installed for entire length of the corridor

5.4 Footpath Improvement

Damaged and missing Portion is proposed with reconstruction of footpath with paver blocks and Kerb stones. RCC Bollards are proposed for Entry and Exit

For Magadi Road, HDPE lines of 2 numbers of 200mm dia and 2 numbers of 100mm dia pipes on both sides of the road are provided to carry the utility lines such as BESCO lines and OFC cables. Also, dual cross ducts of 300mm dia at every 100m interval is provided in order to cross over the utility lines with cross duct chamber of 2.0m x 1.0m is provided on both side of the roads.

5.5 Green Hedging

To Improve the Aesthetics of HDCs Green Hedging on outer edge of the carriageways is considered. Work includes dismantling of exiting concrete/paver blocks, installation of Landscape kerbs, spreading of yard manure and planting of Plants

5.6 Traffic signs

Traffic signs are important features of traffic control devices and transmit visually vital information to drivers and ensure increased safety and efficiency in free flow of traffic. IRC: 67 has standardized patterns for delineating the traffic signs which give information about highway routes, directions and destinations. These also give information on special obligations, prohibitions and restrictions and caution about the existence of any hazardous conditions on or adjacent to the roadway. Thermoplastic paint mixed with retro-reflective beads has long life, night visibility and its drying period is very short. In view of these advantages, retro-reflective thermoplastic paint is proposed for use. The major advantage of retro-reflectorized plastic sheet is that the colour and legend is as legible at night as during the day time.

High Raised Pedestrian Crossing at suitable locations are proposed in order to facilitate the Pedestrian/Non-Motorised Traffic to cross the road section with Refuge Islands

Following are the type of Traffic Signs, Road Markings, Road Safety and Road Furnitures and Other Appurtenances proposed

Table 5.3 Details of Traffic Signs, Road Markings, Road Safety and Road Furnitures and Other Appurtenances

| Sl. No. | Items |
|---------|--|
| 1 | Road Marking- Thermoplastic |
| 2 | Sign boards |
| 2.1 | (900mm Equilateral Triangle) |
| 2.2 | 600mm Circle (Speed limit and Go slow) |
| 2.3 | 600 x 450mm Chevron Signs |
| 2.4 | Informatory sign board 600x800mm (Petrol Pumps, hospitals police stations) |
| 2.5 | Road Delineator |
| 2.6 | Retro- reflective Hazard Marker signboards |
| 2.7 | Moulded Shank Raised Pavement Markers |
| 3 | High Raised Pedestrian Crossing |
| 4 | RCC Circular Bollards |
| 5 | RCC Crash Barrier |
| 6 | Provision of Traffic signal at Junctions |

[Handwritten signature and circular stamp of an Engineer]

| | |
|---|---|
| 7 | Provision of Traffic Umbrella/Kiosk for Traffic Police man |
| 8 | Overhead signs (Truss and Vertical Support) |
| 9 | Overhead sign board installation of retro reflective sheeting |

5.7 Annual Maintenance Proposals includes

Annual Maintenance includes the activities required to maintain these road assets regularly to ensure the safety and hassle free movement of traffic along these roads. annual maintenance activities include, regular cleaning of carriageways and footpaths, seasonal clearing of blockages in drains and culverts, painting of Kerbs and medians as and when required, ensuring road markings and signboards, to be intact over the maintenance period.

When roads are regularly maintained, the city is able to keep them in a safe condition and generally will only need to replace the top layer of asphalt in its Periodic overlay program. If a road is neglected for too long, all of the old asphalt must be removed, and then replaced by new asphalt depending on the roadways type and level of use. This complete rebuild can cost up to three times as much as an overlay. The goal of the program is to “do the right maintenance at the right time.”

Routine road maintenance works are usually non-structural in nature and are meant to extend the life of the pavement, to enhance the performance and to reduce user delays in road use. Non-preventive maintenance can also be described as routine. Where routine refers to the “fixed-cost” activities such as grass cutting, drainage maintenance and road markings and sign maintenance; along with activities required throughout the year such as pothole patching, crack sealing, and grading. Maintenance timelines proposed to follow for various parameters is tabulated below.

Table 5.4 Maintenance timelines proposed

| Repair/ Rectification of Defects and Deficiencies | | |
|--|--|--|
| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
| A | Carriageway/Road surface | |
| 1 | Maintaining a public relations unit to interface with and attend to suggestions from the Users, government agencies, media and other agencies | On or before 45 days from LOA |
| 2 | all surplus construction machinery and materials, waste materials (including hazardous materials and waste water), rubbish and other debris (including, without limitation, accident debris) and keep the Project in a clean, tidy and orderly condition, and in conformity with Applicable Laws, Applicable Permits and Good Industry Practice. | Daily |
| 3 | Carriageway Sweeping using mechanical sweepers, manual | Daily |

Repair/ Rectification of Defects and Deficiencies

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|----------|--|---|
| | cleaning of footpaths | |
| 4 | Breach or blockade | Temporary restoration of traffic within 3 hours' permanent restoration within 7 days |
| 5 | Roughness value exceeding 2600mm (Fair) in a stretch of 1 km (as measured by a standardized rough meter/bump integrator) | 7 days |
| 6 | Potholes | 24 hours |
| 7 | Cracking all types in less than 5% of road surface in a stretch of 1 km | 3 (Three) days |
| 8 | Raveling/Stripping of bitumen and all types in less than 5% of road surface in a stretch of 1 km | 3 (Three) days |
| 9 | Settlement all types in less than 5% of road surface in a stretch of 1 km | 3 (Three) days |
| 10 | Rutting exceeding 10 mm in more than 2% of road surface in a stretch of 1 km (measured with 3 m straight edge) | 7 (Seven) days |
| 11 | Bleeding/skidding | 3 (Three) days |
| 12 | Damage to pavement edges exceeding 100 mm | 24 hours |
| 13 | Painting of kerb, railing, parapets, crash barriers, | As and when required / Twice every year |
| 14 | All types of Road Marking | Retro reflectivity mcd/m ² /lux of 150 during the contract period / Twice every year |
| 15 | Joint Sealing in concrete pavement | 7 (Seven) days |
| 16 | Replacement of Pavement Quality Concrete slabs | 15 (fifteen) days |
| B | Hard shoulders, Drains and Cross Drainage works | |
| 17 | Rain cuts/gullies in slope | 3 (Three) days |
| 18 | Damage to or silting of culverts and side drains during and immediately preceding the rainy season | 3 (Three) days |
| 19 | Desilting of drains in Road side Drains | 3 (Three) days |
| C | Bridges / Interchanges / Grade Separators (Fly Overs/ RUB/ ROB/ Under Pass / any other Road structure) | |
| 20 | Cracks Temporary measures Permanent measures | Within 48 hours Within 3 days |
| 21 | Spalling/scaling | 3 (Three) days |
| 22 | Foundations-cavitation | 3 (Three) days |
| 23 | Piers, abutments, return walls, RE-walls Cracks and damages including settlement and tilting | 10 (Ten) days |

Repair/ Rectification of Defects and Deficiencies

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|----------|---|---------------------------------------|
| 24 | Bearings All type- Deformation | 30 (Thirty) days |
| 25 | Joints in bridges: Loosening and malfunctioning of joints | 30 (Thirty) days |
| 26 | Deforming of pads in elastomeric bearings | 30 (Thirty) days |
| 27 | Gathering of dirt in bearings and joints or clogging of spouts, weep holes and vent-holes | 3 (Three) days |
| 28 | Damage or deterioration in parapets and handrails | 3 (Three) days |
| 29 | Rain-cuts or erosion of banks of the side slopes of approaches | 3 (Three) days |
| 30 | Damage to wearing coat / Resurfacing | 10 (Ten) days |
| 31 | Damage or deterioration in approach slabs | 3 (Three) days |
| 32 | Growth of vegetation affecting the structure or obstructing the waterway | 3 (Three) days |
| D | Trees and Plantation | |
| 33 | Obstruction in a minimum head-room of 5 m above carriageway or obstruction in visibility of road signs | 24 hours |
| 34 | Deterioration in health of trees and bushes | Timely watering and treatment |
| 35 | Replacement of trees and bushes | 3 (Three) days |
| 36 | Removal of vegetation affecting sight line and road structures | 3 (Three) days |
| E | Other Project Facilities and Approach roads | |
| 37 | Manual cleaning of footpaths | Daily |
| 38 | Damage to paver blocks or concrete surface or tiles of footpath | 3 (Three) days |
| 39 | Damage to Kerbs, bollards, tree guards, pedestrian railings | 3 (Three) days |
| 40 | Road side Drains and inlets | Should be Clean at all times |
| 41 | Damage to drain cover, walls | 3 (Three) days |
| F | Road safety and furniture including all road sign boards and pavement raised marking (road studs) | |
| 42 | Damage to shape or position, poor visibility or loss of retro-reflectivity | 48 hours |
| 43 | Damaged/missing road signs requiring replacement | 7 (seven) days |
| 44 | Painting of railing, parapets, crash barriers | As and when required/ Once every year |
| 45 | Reflective Pavement Markers (Road Studs) Numbers and Functionality as per specification in IRC: SP:84-2014 and IRC :35-2015, unless specified | At all times |
| 46 | Pedestrian Guard rail: Functionality: Functioning of guardrail as intended | At all times |
| 47 | Traffic Safety Barriers: Functionality: Functioning of Safety Barriers as intended | At all times |
| 48 | Overhead Sign Structures shall be structurally and | At all times |

Repair/ Rectification of Defects and Deficiencies

| Sl. No. | Nature of Defect or Deficiency | Time limit for Repair/Rectification |
|----------|--|-------------------------------------|
| | functionally adequate | |
| G | Road lighting | |
| 49 | Any major failure of the system | 24 hours |
| 50 | Replacement of bulbs, LED's, damaged light arms, poles | 8 hours |
| H | Emergency Works | |
| 51 | Removal of Fallen Trees | 3 hours |
| 52 | Towing of Accident vehicle / Breakdown vehicle / Abandoned vehicle | 1 hour |
| 53 | Water logging / Ponding on road surface / grade separators | 1 hour |
| 54 | Fallen Street pole / Sign Boards / any other structure | 1 hour |



CHAPTER - 6**PRELIMINARY COST ESTIMATES****6.1 General**

Cost estimation is important for the feasibility study as it provides vital input to the economic and financial evaluation of the project. The cost estimates have been prepared the project corridor separately for improvements to the existing road including reconstruction/widening of few cross-drainage structures, longitudinal drains, etc.

6.2 Methodology

Estimation of Preliminary cost, a primary pre-requisite for Economic and Financial evaluation, has been carried out. The process involved in the preliminary cost estimation has been described under the following sections.

6.2.1 Basic rates

The basic rates for each construction items were analyzed on the basis of MORTH Standard Data Book and Karnataka PW,P&IWTD Standard Schedule of Rates 2018-19 of Bengaluru Circle adopted.

6.2.2 Quantification of Items

The quantification of most of the items that are uniformly occurring is calculated per km, based on the typical cross sections. The construction items covered in cost estimates are: site clearance; earthwork cutting, Loosening and recomposing, Pavement in carriageways and shoulders; culverts; Drainage and Miscellaneous items which includes Pavement markings, Signage's, Guard Rails, etc. Special consideration was given for the stretches passing through hazardous conditions.

