

Bruhath Bengaluru Mahanagara Palike

Narashima Raja Square Bengaluru

Remodeling of Primary & Secondary Storm Water Drains in Bengaluru Under JNNURM Scheme

Chalaghatta Valley

Feasibility & Detailed Project Report

Volume – I

December 2006



STUP Consultants P. Limited

Remodelling of Primary and Secondary Storm Water Drains In Bangalore City

LIST OF FIGURES FOR CHALLAGHATTA VALLEY

SI. No.	Figure No.	Description	Page No.
1.	2.1	Study Area Boundary	25
2.	2.2	Major and Minor Valleys of Bangalore Storm Water Drains	26
3.	2.3	Additional Drains Considered for Remodelling Studies	28
4.	2.4	Challaghatta Valley Primary and Secondary Storm Water Drains	31
5.	2.5	Challaghatta Valley - Low Lying Areas	102
6.	3.1	Challaghatta Valley – Sub Catchments	119
7.	3.2	Ulsoor Valley – Sub Catchments	120
8.	3.3	Challaghatta Valley – Land Use Map	124
9.	3.4	Ulsoor Valley – Land Use Map	125
10.	3.5	Intensity V/s Duration - One Year Storms	143
11.	3.6	Intensity V/s Duration - Two Year Storms	144
12.	3.7	Intensity V/s Duration - Five Year Storms	145
13.	3.8	Intensity V/s Duration - Ten Year Storms	146
14.	3.9	Intensity V/s Duration - Twenty Year Storms	147
15.	3.10	Duration V/s Rainfall Intensity	151
16.	3.11	Duration V/s Runoff Coefficients	152
17.	4.1	Challaghatta Valley – Culverts Considered for Remodelling	or 169
18.	4.2	Plan showing Location of Tertiary Drain Improvement Locations Near Vasanthanagar & Shivajinagar	187

Feasibility Report – Challghatta Valley

LIST OF FIGURES (Contd.)

SI. No.	Figure No.	Description	Page No.
19.	4.3	Plan showing Location of Tertiary Drain Improvement Locations Near Anandanagar	189
20.	4.4	Plan showing Location of Tertiary Drain Improvement Locations Near Munireddypalya & Chinnappa Garden	190
21	4.5	Diversion of Drainage Channel near Airport	191
22.	4.6	Plan showing proposed Airport Compound V location	Vall 192
23.	4.7	Plan showing proposed location for construction of RCC Box drain near S.K. Garden	193
24.	4.8	Strip Plan showing locations for Storm Drain Improvements In Challaghatta Valley	195
25.	4.9	Strip Plan showing locations for Storm Drain Improvements In Ulsoor Valley	202
26.	5.1	Potential Locations for Construction of Detention Ponds In Challaghatta Valley	288
27	10.1	Out line Methodology flow chart for Phase-1 -Feasibility Report	
28	10.2	Out line Methodology flow chart for Phase-1 -Detailed Engineering	1
29	10.3	Activity Bar Chart	
30	10.4	Package Details	

Remodelling of Primary and Secondary Storm Water Drains In Bangalore City

LIST OF TABLES FOR CHALLAGHATTA VALLEY

SI. No.	Table	No. I	Description	Page No.
1.	2.1	Summary of Sto	orm Water Drainage Catchment	27
2.	2.2	Abstract of Drai	ins Considered for Remodelling Stud	lies 29
3.	2.3	Drain Details of	Challaghatta Valley	30
4.	2.4	List of Critical L	ow Lying Areas In Challaghatta Valle	ey 101
5.	3.1	Challaghatta M	ain Valley Micro Catchment Code	121
6.	3.2	Challaghatta M	ain Valley Flow Region Code	121
7.	3.3	Ulsoor Valley N	licro Catchment Code	122
8.	3.4	Ulsoor Valley F	low Region Code	122
9.	3.5	Challaghatta M	ain Valley Land Cover Characteristic	s 123
10.	3.6	Ulsoor Valley L	and Cover Characteristics	126
11.	3.7	Table of CPHE	EO Manuel – Runoff Coefficients	133
12.	3.8	Analysis of Free	quency of Storms	141
13.	3.9	Time Intensity	Values of Storms	142
14.	3.10	Intensity V/s Du	uration	149
15.	4.1	Abstract of Ade	quacy Analysis For C Main Valley	158
16.	4.2	Abstract of Ade	quacy Analysis For Ulsoor Valley	159
17.	4.3		quacy Analysis Results of Culverts atta Main Valley	165
18.	4.4	Abstract of Ade – For Ulsoor Va	quacy Analysis Results of Culverts alley	166
19.	4.5	List of Bridges (in Challaghatta	Considered for Reconstruction Valley	168

Feasibility Report – Challghatta Valley

LIST OF TABLES (Contd.)

SI. No.	Figur	e No. I	Description	Page No.
20.	5.1		s Identified for Construction of Is in Challaghatta Valley	287
21.	6.1		proving the Carrying Capacity of Drain in Challaghatta Main Valley	298
22.	6.2		oviding Rehabilitation to Existing Drain in Challaghatta Main Valley	301
23.	6.3		proving the Carrying Capacity of m Drains in Challaghatta Main Valle	y 304
24.	6.4		oviding Rehabilitation to Existing m Drains in Challaghatta Main Valle	y 305
25.	6.5		proving the Carrying Capacity of Drain in Ulsoor Valley	306
26.	6.6		oviding Rehabilitation to Existing Drain in Ulsoor Valley	307
27.	6.7		proving the Carrying Capacity of m Drains in Ulsoor Valley	309
28.	6.8		oviding Rehabilitation to Existing m Drains in Ulsoor Valley	311
29.	6.9		t For Bridges / Culverts Remodelling in Challaghatta Valley	313
30.	6.10	Abstract of Cos in Challaghatta	t For Improving the Existing Tertiary Valley	Drains 314
31.	6.11		t For Operational And Maintenance age System in Challaghatta Valley	317

Remodelling of Primary and Secondary Storm Water Drains In Bangalore City

LIST OF FIGURES FOR CHALLAGHATTA VALLEY

SI. No.	Figure No.	Description	Page No.
1.	2.1	Study Area Boundary	25
2.	2.2	Major and Minor Valleys of Bangalore Storm Water Drains	26
3.	2.3	Additional Drains Considered for Remodelling Studies	28
4.	2.4	Challaghatta Valley Primary and Secondary Storm Water Drains	31
5.	2.5	Challaghatta Valley - Low Lying Areas	102
6.	3.1	Challaghatta Valley – Sub Catchments	119
7.	3.2	Ulsoor Valley – Sub Catchments	120
8.	3.3	Challaghatta Valley – Land Use Map	124
9.	3.4	Ulsoor Valley – Land Use Map	125
10.	3.5	Intensity V/s Duration - One Year Storms	143
11.	3.6	Intensity V/s Duration - Two Year Storms	144
12.	3.7	Intensity V/s Duration - Five Year Storms	145
13.	3.8	Intensity V/s Duration - Ten Year Storms	146
14.	3.9	Intensity V/s Duration - Twenty Year Storms	147
15.	3.10	Duration V/s Rainfall Intensity	151
16.	3.11	Duration V/s Runoff Coefficients	152
17.	4.1	Challaghatta Valley – Culverts Considered for Remodelling	or 169
18.	4.2	Plan showing Location of Tertiary Drain Improvement Locations Near Vasanthanagar & Shivajinagar	187

Feasibility Report – Challghatta Valley

LIST OF FIGURES (Contd.)

SI. No.	Figure No.	Description	Page No.
19.	4.3	Plan showing Location of Tertiary Drain Improvement Locations Near Anandanagar	189
20.	4.4	Plan showing Location of Tertiary Drain Improvement Locations Near Munireddypalya & Chinnappa Garden	190
21	4.5	Diversion of Drainage Channel near Airport	191
22.	4.6	Plan showing proposed Airport Compound V location	Vall 192
23.	4.7	Plan showing proposed location for construction of RCC Box drain near S.K. Garden	193
24.	4.8	Strip Plan showing locations for Storm Drain Improvements In Challaghatta Valley	195
25.	4.9	Strip Plan showing locations for Storm Drain Improvements In Ulsoor Valley	202
26.	5.1	Potential Locations for Construction of Detention Ponds In Challaghatta Valley	288
27	10.1	Out line Methodology flow chart for Phase-1 -Feasibility Report	
28	10.2	Out line Methodology flow chart for Phase-1 -Detailed Engineering	1
29	10.3	Activity Bar Chart	
30	10.4	Package Details	

EXECUTIVE SUMMARY

INTRODUCTION

The total area of Bangalore city is approximately 225 Sq.m. and is divided by 4 major valleys namely Vrishabhavathy, Koramangala, Challaghatta and Hebbal valley with total length of primary and secondary drains more than 220 Km. Challaghatta main valley originates from palace ground in Jayamahal and join Bellandur lake. Hebbal main valley starts from Mathikere and joins Hebbal Lake. Koramangala main valley originates from Subhashnagar and joins Bellandur lake and Vrishabhavathy main valley originates from Sankey tank and joins Vrishabhavathy valley near Mysore road.

Due to rapid urbanization, the rate of growth of population in Bangalore has been explosive during the last two decades. Bangalore being a chosen destination for software, Biotech and other industrial entrepreneurs has further escalated the population rise. This has obviously caused additional strain on the already overloaded city infrastructure. The large scale construction of Office premises, residential accommodation and other similar construction, to meet the demands of the rising population has resulted in :

i)Increased ground coverage and pavements

ii)Developments inside the buffer storage areas and tanks

iii)Encroachments into the storm water drain

- iv)Uncontrolled discharge of sewage and effluents inside the Storm water drain
- v)Constructions inside the drain to facilitate running of other utilities.

Bangalore Mahanagara Palike, agency responsible for the maintenance of the city's infrastructure has taken up the project of remodelling the entire storm water drain to improve the efficiency of the storm water drainage system and entrusted the work to M/s. STUP Consultants P. Limited.

The scope of work includes;

- I) Preparation of:
 - a) Feasibility Report
 - b) Detailed Project Report
 - c) Construction Management for 4 valleys :
 - i. Vrishabhavathy Valley
 - ii.Koramangala Valley
 - iii.Chellaghatta
 - iv.Hebbal
- II) Detailed scope of services includes;
 - Detailed topographical and geo-technical survey
 - Assessment of quantity and quality of drainage discharge
 - Analysis of the existing system
 - Prevention of sewerage entering drains (to the possible extent)
 - Hydraulic and structural designs and drawings
 - Cost estimation and Bill of Quantities
 - Technical specifications
 - Cost benefit analysis
 - Bid documents
 - Slicing and Packing (Phasing for Implementation)
 - Assistance inviting and evaluating Bids
 - Project management and Quality assurance
 - Training of BMP staff

While Remodeling proposals on the entire Storm water drain system is in progress, the report on Challagatta valley remodeling is being submitted as a first part in 2 Volumes namely :

Volume 1	-	Main Report
Volume 2	-	Drain Alignment Plan, Longitudinal Section, Cross Section &
		General Arrangement Drawings for Challaghatta Valley.

WORK METHODOLOGY:

To asses the existing condition of the drain a detailed topographical survey has been carried out using total stations in which the alignment of the drain, length of the drain, adjoining buildings, culverts / bridges, cross section of the drain etc are identified.

Condition survey of the drain and bridges were also carried out in which the bed condition of the drain, walls, level of silting in the drains, obstructions, sewage entry points to the drain, pipe crossings, manholes etc., were also identified and listed in the formats. The condition of bridges and culverts have also been assessed. Various low lying areas are identified during reconnaissance survey which are prone to flooding and the bottle necks and reason causing flooding were identified.

It is an established fact that the high intensity, high volume rainfall follows laws of probability which can be established for a place like Bangalore where rainfall data for over 25 – 30 years is available. These mathematical laws generally called as "extreme value distributions" enable one to correlate the intensity of rainfall and the chances (probability) of that rainfall taking place within a given time frame (1 hour, 12 hours, 24 hours, etc.) when such precipitation takes place, the amount of water that will flow from various parts of the catchment area to the drains can be calculated based on knowledge of the type and characteristics of terrain (in terms of its absorption and runoff) type of drains, sectional areas of drains and their slopes, etc.

This method, (Called Rational Method) being logical and incorporating various actual physical characteristics is considered to be a powerful method for predicting the maximum expected floods. However, to evaluate and fix various physical parameters of catchment

areas (i.e. properties) and to fit rainfall data is a difficult task. Even when carried out, it needs to be "confirmed" by observation of actual water discharge against the calculated discharge., A set of catchment parameters need to be consistently chosen and adjusted in prediction model whose predictions shall match with the actual observations of flood. This stage is termed as the "Calibration of the System".

The rational method is a very powerful method for design of a "Greenfield" project (i.e new towns, new development areas, etc.). However, this method is not adequate on its own for studying the existing systems which have been developed over a period of time without having any systematic design philosophy behind its design.

Therefore, as a first step in improving the existing system it is necessary to take following steps :

- a)Repair and rehabilitation of damaged portion of existing drains.
- b)Cleaning and clearing of waterway by removal of debris, artificial constrictions, blockages, etc.
- c)Making the entire drain system internally consistent over its full length.

Once the above is achieved, the probabilistic predictions of discharge, velocity and capacity can be compared with those of actually observed floods. This will enable one to establish correct mathematical model which is then used for optimizing the design for other portions of drainage channels (i.e. primary, secondary and tertiary drains) and make the whole system internally consistent and cost effective.

At present, the mathematic model for rainfall in Bangalore has been established based on rainfall data of part several years. Also, the parameters of catchment have been evaluated and the first order prediction model is prepared.

This model has been used to make first predictions of the expected flood. This is found to yield higher flood levels than those actually observed and will need second stage corrections. This can be effectively done after completing three stages of repair/rehabilitation mentioned above. Meanwhile, these first order results, have been

used as a guideline in preparing proposals of widening / additional capacity of drains at local portions in such a way as to make the system internally consistent.

DESIGN PHILOSOPHY:

The data required for adequacy analysis of drain like rainfall data, topography and land use from satellite imagery are collected. The detailed technical and hydraulic analysis have been carried out to assess the hydraulic capacity of the drain and bridges. Various statistical analysis were studied for rainfall and the method which is best suited to the site condition, i.e. CPHEEO method has been selected and analysed.

RECOMMENDATIONS:

To improve the section of the drain and to minimize the flooding, various drain improvement methods are suggested are :-

- 1.Provision of gratings for closed drain for allowing water to the drain with openings for cleaning the drain.
- 2.Plugging of all openings to the drain made for draining ground water to the main drain where the drain wall top is higher than the ground level/road level and construct side drain leading off storm water to the down stream end.
- 3. Provision of pointing to inside of existing stone masonry drain wall.
- 4. Provision of bed to drain to improve the flow
- 5. Provision of bed and wall for drain wherever they do not exist to improve the drain hydraulics.
- 6.Removal and reconstruction of drain wall wherever the drain wall is in dilapidated conditions.

- 7.Provision of embankment in the pitching and lined bed for drain where enough land is available.
- 8. Provision of Byepass drains to reduce the load on the existing drain.
- 9.Provision of cut off drain around the low lying area to prevent outside water entering the low lying area and construction of sump for pumping out water at a location closer to the main drains (downstream end) and easily accessible to reach the truck mounted pump.
- 10. The improvement shall be taken up from the down stream of the valley. If remodeling is commenced from upstream side, situation at the downstream end would further get aggravated.
- 11.Increase the drain wall height to increase the carrying capacity of the drain wherever required. Provide parallel drain adjacent to the raised drain wall to dispose the ground water to down stream of drain.
- 12.All obstructions like bridges/culverts, utility lines, manholes, etc. shall be removed and rebuilt wherever required.
- 13.All silt/debris from the drain shall be removed.
- 14. Regading of drain from Shivaji Nagar to down steam of Gurudwara bridge
- 15. Reconstruction of Gurudwara bridge.
- 16.Remodeling of Bridges near Ulsoor lake, Indiranagar and Airport road.
- 17.Set-up a vigilance squad to prevent debris dumping, encroaching of drain, local obstruction, such as, pipe crossing, construction inside the drain, any construction other than required for storm water in drainage.
- 18. Encourage rain water harvesting in institutions, public parks, open grounds, etc.,

ENVIRONMENTAL AND SOCIAL IMPACTS

Storm drains carrying sewage and solid wastes are causing environmental hazards such as :

- 1.Pollution of ground water source.
- 2.Odour problem
- 3. Mosquito menace
- 4. Unhygienic conditions are causing health hazards

The inadequate size of the drains causes flooding of the areas which includes low lying areas such as, Millars tank, Shivaji Nagar, Munireddy Palya, Jogupalya etc, causing damage to properties, affecting social life of local residents.

Therefore, to minimize flooding, proposals for both immediate and long term are prepared for Challagatta valley.

Cost Estimation

For implementation of the various recommendations a detailed cost estimation has been prepared, and is shown as below;

Sl.No.	Description	Amount	
51.190.	Description	(Rs. In Lakhs)	
	Cost for Remodeling of Primary & Secondary Storm Water		
1	Drains, Construction of New Drains near low lying areas,	10,046.76	
	Formation of Service Roads etc.,		
2	Cost for Remodeling of Bridges / Culverts constructed across		
2	Primary & Secondary Storm Water Drains.	1,333.40	
3	Cost for shifting utility lines, footpath improvement works,	EC0.01	
5	barricading, traffic diversion, strengthening of diversion routes etc.	569.01	
4	Construction of Detention Ponds / Retarding Basins	150.00	
5	Construction of Wells with pumping arrangement in low lying areas	200.00	
6	Procurement of desilting machine	0.00	
7	Miscellaneous and rounding off	0.02	
8	Advisory, Project Management & Establishment Charges		
0	(1.5 % of Item 1 to 7)	184.50	
	TOTAL	12,483.69	
9	Annual Operation & Maintenance Cost	100.00	
	(1.0 % of Item 1 to 7)	123.00	

For effective functioning of any system, requires maintenance. The operation and maintenance requirement have been identified and costing is indicated.

CHAPTER – 1

INTRODUCTION AND BACKGROUND

1.1 GENERAL:

Bangalore, the capital of Karnataka, is one of the fastest growing cities in India with a current estimated population of 5.8 million souls, spread over an area of about 225 Sq.km. and is situated at an altitude of about 894 m. above MSL.

Bangalore was once well known for its open parkland environment with significant number of large traditional tanks with a good network of waterways and thick vegetative cover. Rapid increase in population, industrialization and migration of people from rural Karnataka and rest of the country in a relatively short span of time has put more pressure on the utilities and services, which are already loaded beyond their capacities. Storm water drains are one of the most affected services in the city. The problem is aggravated by uncontrolled urbanisation, infringement by other utilities, encroachments and indiscriminate dumping of solid wastes and over flowing of sewers in drain. Other secondary problems includes sedimentation, vegetation growth and sewage outlets into the drains, etc. Due to the above, there is reduction in carrying capacity of the drains causing localized flooding to the settlements adjacent to the drains and tanks, in low lying areas. Many tank beds have been converted into residential layouts causing disappearance of water body which otherwise would have acted as detention ponds / retarding basins. The damage caused by the floods, are very serious in terms of life and property. Therefore, there is an urgent need to examine the status of existing storm water drainage system, the reasons for the frequent flooding and devise possible remedial measures to alleviate the damage.

1.2 **PROJECT BACKGROUND**:

The stated goal for remodeling of existing storm water drain project is to improve the carrying capacity of the existing system, for the delivery of storm water without flooding the low lying areas of the city and also to provide improvised environmental sanitation services to the city of Bangalore, with emphasis on the urban poor and vulnerable groups and within a process of long term environmental, economic, social and institutional sustainability.

In August 1988 and May 2002, Bangalore city had experienced unusually high intensity rainfall which resulted in substantial damage to both life and property. Bangalore Mahanagara Palike (BMP), the agency responsible for maintenance of the city's infrastructure with an endeavour to obviate the problems faced by the city, therefore took up the project including preliminary investigations, detailed survey, system analysis and proposals for improvements and capacity augmentations of the existing drainage system in Bangalore.

Bangalore Mahanagara Palike invited proposals from competent consultants based on the approach document prepared by BMP and entrusted the work to M/s. STUP Consultants Private Limited, Bangalore to provide necessary direction and set priorities on existing drainage system rehabilitation needs, and to explore the potential options, considering future hydraulic design requirements, for drainage system rehabilitation and other technical services for remodelling the existing drainage system in Bangalore City.

Further, the outputs of this study will provide the basis for developing a comprehensive plan for the drainage system and detailed proposals for selected improvement projects to be implemented by BMP.

Bangalore city topography is marked by the presence of Four Primary valleys, viz.,

1.Vrishabhavathy Valley

2.Koramangala Valley

3.Challaghatta Valley

4.Hebbal Valley

Based on the Survey conducted, the lengths of the main valleys are as shown in the table below:

SI.No.	Name of the Valley	Primary Drain Length (m)		
1.	Vrishabhavathi Valley	32,150		
2.	Koramangala Valley	19,625		
3.	Challaghatta Valley	16,150		
4.	Hebbal Valley	25,800		
	Total length of drain	93,725		

This report forms the feasibility study for Challaghatta Valley.

1.3 OBJECTIVES OF THE PROJECT:

The objectives, defined in broad terms are:

- •To study the main reasons for failure of the existing storm water drains to dispose the storm water without flooding the areas of the city.
- •To study the carrying capacity of the existing primary and secondary drains.
- •To suggest modifications to the main and secondary drains in respect of improvement in flow characteristics and capacity.
- •To study the feasibility of segregating sewage from storm water and the extent practicable.
- •To provide rehabilitation of bridges across Storm Water Drains which are hindrances to the carrying capacity of drain.

1.4 **REPORT OBJECTIVES**:

This report provides, details of existing storm water drains in Challaghatta Valley,, wherein it also provides a strategic framework to ensure better management of drainage assets in Bangalore which also has significant implications in:

•Future management of storm drainage system in Challaghatta Valley.

•Strategies to be follow for implementation of improvement measures.

•Resources generation to achieve the stated objectives and targets.

For the report purpose the studies made are:

- •Identifying the low lying area and reasons for flooding
- •Assessment of existing condition of drainage system

•Evaluation of development options for existing system.

•Examining option / strategies for the preferred options for local applications.

• Preparation of cost estimates for works and associated operation and maintenance.

- Review of existing management of drainage system and the recommendations for institutional improvements.
- Identification of further studies and investigation required for refinement.

Further, for the preparation of this report, supplementary sources are considered at a macro level and also the results of those studies and investigations are integrated into this report.

This report has the following structure:

VOLUME I	Main Report
VOLUME II	Drain Alignment Plan, Longitudinal Section, Cross Section &
	General Arrangement Drawings for Challaghatta Valley.

1.5 SCOPE OF ASSIGNMENT:

A Brief scope of assignment to be rendered by the Consultants as defined in the TOR is given below:

- Detailed topographical and geo-technical survey
- Assessment of quantity of runoff
- Adequacy analysis of existing drains
- Hydraulic and structural designs and drawings
- Cost estimation and Bill of Quantities
- Technical specifications.
- Bid Documents
- Slicing and Packaging (Phasing for Implementation)
- Assistance in Inviting and evaluating Bids
- Project management and Quality assurance

1.6 PHASES OF THE PROGRAMME

The consultancy services which is to be carried out in three (3) phases are as given below:

- **Phase 1:** Technical, Economical and Environmental Feasibility Study of the Project of Remodeling of the Storm Water Drain System.
- Phase 2: Detailed Engineering Design, preparation of tender documents, cost estimates for the remodeling work, Preparation of Bid document and assist BMP to entrust the work to experienced, competent and successful agency.
- **Phase 3:** Supervision of the construction works.

This report is presented for Phase - 1 and Phase - 2 works of Challaghatta Valley.

1.7 PREAMBLE TO INCEPTION REPORT:

Reference is made to the inception report, which identifies the different valleys and conditions of existing storm drains, new drains (i.e., not considered in TOR) and low lying areas in different drainage zones in this report. The details from previous data, recommendation made during past initiatives, current approach, methodology, design procedure and work plan adopted for preparation of detailed project report, narrated in detail.

CHAPTER - 2

ASSESSMENT OF EXISTING STORM WATER DRAINAGE SYSTEM

2.1 INTRODUCTION:

Bangalore city is at an altitude of 894 m. above MSL. and has the general advantage of natural valleys offering good drainage arrangement for storm water. However, misuse and inappropriate planning of drainage network in these valleys have resulted in flooding. The main factors responsible for failure of the system in Bangalore are :

- •A general neglect of the basic functions of the major drains which has allowed numerous channel restrictions to occur and caused a general down grading of the channel capacities, without having adequate provision for flood discharge to meet the design requirement.
- •The apparent acceptance of a design standard for the existing main drains in the core area, for a large city like Bangalore with a rolling topography is extremely low.
- •Lack of planning, design standard and maintenance of tertiary drains which is not upto the acceptable standards for a large city.
- Lack of good management practices like adoption of sediment control measures, effective solid waste management, development of land in low lying areas/ tank beds etc.
- •Laying of sewer lines inside drainage channels in an unacceptable manner.

In the present study, the functionality of tertiary drains is not considered because it is outside the current scope of work.

The area covered under this study is basically the area administered by Bangalore Mahanagara Palike. Map showing the extent of study area is shown as Figure 2.1.

2.2 DESCRIPTION OF CATCHMENTS:


Bangalore is situated on the divide between the Cauvery Basin and the Ponnaiyar Basin, at an elevation of approximately 894 m. above MSL and also with nearly 40% of the projected future population living within the Cauvery Basin. There are four major valleys and five minor drainage valleys. Three of the four major valleys namely, Vrishabhavathy (V-Valley), Koramangala (K-Valley) and Challaghatta (C-Valley), run generally from North to South direction dividing the greater part of the metropolitan area into three separate and distinct drainage zones. A fourth major valley, referred to as the Hebbal series (H-valley), forms the drainage zone to the North of the ridge and runs in Northeast direction.


Five minor valleys, the Kathriguppe and the Tavarekere lie to the South, the Kethamaranahalli and Arkavathi lie to the North-West, Hebbal minor valleys 1 & 2 lie to the North-East. Further, all these minor valleys lie outside the tributary areas of the major valleys and drain independently. The catchment boundaries of major and minor valleys are shown in Figure 2.2.

Details of these catchments are as given in Table 2.1.

TABLE – 2.1 SUMMARY OF STORM WATER DRAINAGE CATCHMENT

Valley Major & Minor Drop Pri. Drain Names Valleys (m.) Origin Poin	Pri. Drain Terminal Point (Ha.)	
--	--	--





Valley Names	Major & Minor Valleys	Drop (m.)	Pri. Drain Origin Point	Pri. Drain Terminal Point	Catchmen t Area (Ha.)	Length of Primary Drain (m.)	Munici palities in catchment
Vrishabhavat hi Valley	Vrishabhavathi Main Valley	120	Sankey tank	Kenchanahalli Near Mysore Road	4,070	13,888	BMP, Kengeri & Patanagere
Valley	Kethamaranahalli & Arkavathi Valley		Near Peenya Indl. area	Kenchanahalli Near Mysore Road	3,045	13,250	
	Kathariguppe Valley		Near Srinivasnagar	Rajarajeshwarin agar	1,819	4,750	-
Koramangala Valley	Koramangala Main Valley	20	Near Majestic Area	Bellandur lake	3,548	10,900	BMP, Bommanah alli &
	Tavarekere Valley		Near NIMHANS Hospital	Agara lake	2,690	6,075	Mahadevep ura
Challaghatta Valley	Challaghatta Main Valley	30	Near Vasanthanagar	Bellandur lake	3,168	10,275	BMP, Krishnarajap Jura
	Ulsoor Valley		Near Jayamahal Extn.	Ulsoor lake	710	4,150	
Hebbal Valley	Hebbal Main Valley	30	Near Matadahalli	Nagavara lake	1,096	4,375	BMP, Dasarahalli &
	a) Hebbal Main Valley – 1		Near I.I.S.C	Hebbal lake	2,348	7,775	Bayatarayan apura
	b) Hebbal Minor Valley – 1		Near Jaibharathnag ar	Kalkere lake	2,230	7,375	
	c) Hebbal Minor Valley – 2		Near Chikka Banasawadi	Kalkere lake	764	2,875	

Bomodolling of Brimory and Soconda	ry Storm Water Drains in Bangalore City	Feasibility Report - Challaghatta Valley - Chapter.2
Relification of Filling V and Seconda		reasinilly reput - Chanaunalla valley - Chanlen.2

Note: Catchment areas indicated in the table is inclusive of portion of CMC/TMC areas coming within respective catchment boundaries.

The total length of primary and secondary drain mentioned in the TOR in all the valleys was 179.30 kms. But during reconnaissance survey, it was observed that, the length of secondary drains in all the valleys were exceeding by about 41.85 kms. apart from this few more additional drains have been proposed for reducing the flooding problems which requiring BMP's approval for additional length has also been included in the present study. An abstract of drain lengths considered for remodelling studies is given in Table 2.2 and the same is shown in Figure 2.3. In addition to the drain length mentioned, additional new drains are also designed to cutoff the runoff to the low lying areas.

Table 2.2 Abstract of Drains considered for Remodelling Studies

Name of the Valley	Primary D	rains (leng	th in Kms.)	Secondary Drains (length in Kms.)					
	As per Actual Survey	As per TOR	Difference in length	As per Actual Survey	As per TOR	Difference in length			
Vrishabhavathi	31.88	29.7	2.18	58.6	48	10.6			
Koramanagala	16.98	16.5	0.48	28.9	23.8	5.1			
Challaghatta	14.6	14.6	0	18.05	8	10.05			
Hebbal	22.4	12.6	9.8	29.74	26.1	3.64			
Total length (Kms.)	85.86	73.4	12.46	135.29	105.9	29.39			
Total length of additional drains (Kms.) 41.85									

Remodelling of Primary and Secondary Storm Water Drains in Bangalore City Feasibility Report - Challaghatta Valley - Chapter.2

Since, Koramangala Valley being the most critical valley, it has been taken up on priority for the preparation of feasibility report and further, followed by Challaghatta, Hebbal & Vrishabhavathi Valley.

2.3 DESCRIPTION OF CHALLAGHATTA VALLEY:

2.3.1 Challaghatta Valley:

Challaghatta valley comprises of two main drains known as Challaghatta main drain and Ulsoor drain (i.e., Munnireddypalya drain), the first of which starts from Vasanthnagar and flows through Miller tank area, Jasma Bhavana Road, Rajiv Gandhi Colony, Nehrupuram, Corporation Colony, Shivajinagar, Nala Road, Anna Swamy Mudaliar Street, RBAMNS College, Gangadhar Chetty Road, Adjacent to Ulsoor lake, Ulsoor, Munivenkatappa garden, Guptha layout, L.B. Shastrinagar, Cambridge layout, Indiranagar, Domlur Layout, Airport Road and joins at Bellandur tank.

Challaghatta main valley comprises of one primary drain and four secondary drains, details of these drains is as mentioned in Table 2.3 and the same is shown in Figure 2.4.

The second main drain known as Ulsoor valley drain starts from J.C. Nagar near Munireddypalya and runs through Kempiah Block, Krishnamma nagar, Chinnappa Garden, S.K. Garden, Pottery town, Frazer town, Sindhi Colony, Wheelers Road and terminates at Ulsoor lake. Another sub main drain covering rest of the Ulsoor valley, flows independently from Jeevanahalli area and flows through East Railway station area, M.E.G. Centre and terminates at Ulsoor lake.


Ulsoor valley drain comprises one primary drain and four secondary drains and also one sub main drain. Details of these drains is as mentioned in Table 2.3 and the same is shown in Figure 2.4.

Sr.	Drain ID	Name	Туре	Start	End	Length			
No.	Brainib	Humo	.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Otart	2.1.0	(Mts.)			
Challaghatta Main Valley (C1):									
1	C100	Challaghata Valley	Pri.	Vasanthanagar	Bellandur Tank	12,000			
2	C100	Murugesh Palya	Sec.	Anandanagar	Challaghatta	1.875			
3	C102	Shastrinagar	Sec.	Sweepers Colony	Shastrinagar	1,600			
4	* C102	Krishnamurthy nagar	Sec.	Krishnamurthy nagar	Kadariyanapalya	1,000			
7	0103	intra indititi y hagai	060.	Kiisiinamuruny nagai	Tank	1,600			
5	* C104	Kadariyanapalya	Sec.	Kadariyanapalya	Kadariyanapalya	1,000			
5	0104	Radanyanapaiya	060.	Radanyanapaiya	Tank	2,500			
6	C105	ISRO Complex	Sec.	Jeevanbhimanagar	Kodihalli	3,000			
7	* C105	Thippasandra	Sec.	New Thippasandra	ISRO Complex	650			
8	C100	Malleshappanapalya	Sec.	Garmantakanapalya	Dodda Nekundi Tank				
9				Airport S.E Corner		600			
-		HAL Airport - 1	Sec.		Upto NAL Road	600			
10	* C109	HAL Airport - 2	Sec.	Adj. To Airport	Bellandur tank	075			
				compound wall		675			
Total Length of Primary Drains						12,000			
Total Length of Secondary Drains						13,400			
Ulsoor Valley (C2) :									
1	C200	Ulsoor	Pri.	Jayamahal Extn.	Ulsoor Tank	4,150			
2	C201	Ganesh Temple	Sec.	Ganesh Temple	MEG Center	250			
3	C202	Cox Town	Sec.	Richard's Town	Gymkhana Ground	1,170			
4	C203	Sagayapuram	Sec.	Sagayapuram	Cleveland Town	750			
5	* C204	Jeevanahalli	Sec.	Jeevanahalli	Ulsoor Tank	2,000			
Total Length of Primary Drains									
Total Length of Secondary Drains									

TABLE 2.3

CHALLAGHATTA VALLEY DRAINS

* - Storm Drains, exists inside Defence area



2.4 **RECONNAISSANCE SURVEY**:

Reconnaissance survey has been carried out in Challaghatta main valley and Ulsoor valley. The critical locations which were prone for flooding even for small intensity of rainfall due to various reasons have been identified and also photographed.

Reconnaissance survey has been carried out with a view :

- •For describing the contributory areas of the valley i.e., contributing to the existing drains.
- Investigate the condition of drains, cross drains, type of construction, extent of rehabilitation to be provided, possibility of creating new drains, change of alignment, upgradation of drains etc.
- •Examine feasibility of widening/deepening of the drain to carry the design flow.
- •Status of land use pattern / type and density of development, adjoining the drains (i.e., residential, commercial, industrial or vacant land)
- •and other key issues which have bearing for smooth functioning of the drainage system.

2.5 REPORT ON FIELD SURVEY OF DRAINS IN CHALLAGHATTA VALLEY:

•METHODOLOGY:

Having identified the drains, the chainages were marked all along the drains, after measuring the length of the drain starting from `0' m chainage at the upper reaches i.e., starting point and the chainage increasing towards the terminal point i.e., down stream direction.

based on local coordinate system. Total stations were used for surveying of details in and around the drain. Every point is surveyed for its planimetry and height. For heights inside the drain, this was necessary, since conventional levelling was not feasible as the drain bottom is at a very low level at some places compared to the sides of the drain. By resorting to Total station, the names of the roads, localities and important land marks, features adjacent to drains were picked up at site and incorporated along with others details.

The heights were given to points with the help of Total stations based on T.B.Ms established all along the drains at strategic locations, on permanent objects such as culverts etc. Before that, the existing Survey of India GTS B.Ms were checked for stability and after ensuring the stability of these B.Ms the levelling was done to establish T.B.Ms all along the drain.

•Methodology adopted in representing the drains in the drawing:

Plan showing details of drains, land marks, bench marks, encroachments, locations where sewage entering into storm water drain, condition of retaining walls, location of bridges and cross drainages and utility crossing are identified in the drawing to a scale of 1:1000 and longitudinal section details of drains in 1:1000 / 1:100 are proposed in the same drawing.

As per TOR, each primary and secondary drains in all the valleys are to be identified with respect to their respective predominant locality names and correspondingly numbering has been made.

For ease of identification, sub drains in all the valleys have been identified from down stream end, accordingly numbers have been assigned for each secondary drains in the respective valleys and the same are to be read as follows.

Eg.: 1) C100 = C1 represents Challaghatta main valley first primary storm drain.

2) C101 = C1 represents Challaghatta main valley, first primary storm drain and 01 indicates first secondary storm drain in Challaghatta valley.

•Elevation drawings of Culverts / Bridges:

The data required to ascertain the condition of existing cross drainage were collected at site. From the data obtained, the type of construction, condition of culvert, details about vent way, approach slab, support piers, parapet walls, carriage way, foot paths, intensity of traffic, obstructions for flow of water at the culvert location etc. has been assessed and appropriate mitigative measures has been suggested. These culverts were serially numbered and each culvert has an identical number both in strip map and in elevation drawing and the same is enclosed as part of this report in the condition survey volume.

•Longitudinal Section:

Longitudinal sections showing drain top levels (Both right side and left side) and bed levels at every 25 m. apart on a horizontal scale of 1:1000 and on vertical scale of 1:100 has been made for every drain and the same is enclosed as part of this report in the drawing volume.

•Cross-section:

Drain cross section at every 25 m. interval has been made, showing drain depths, levels at top of the silt, bed level and also at the edges of the drain. Heights were given on top of drain wall and also at the adjoining land. The section also indicate whether the walls/buildings or road edge that rests on the drain, at that particular section.

•Silt Volume:

From the drain cross section, silt volume is calculated using Prismoidal formula and the quantity is considered for estimation.

•Other Items:

Locations where indiscriminate dumping of debris, garbage and solid waste materials noticed inside the storm drain and also breakage in the drain walls along with its measurements were identified during reconnaissance survey.

2.6 DETAILS OF EXISTING STORM DRAINS IN CHALLAGHATTA VALLEY :

Challaghatta Valley comprises of two main drains known as Challaghatta main drain and Ulsoor drain, the first of which starts from Vasanthnagar and terminates at Bellandur tank. The second main drain known as Ulsoor drain starts from Munireddypalya and terminates at Ulsoor Lake. The details of these primary and secondary storm drains is as mentioned in earlier sections of this chapter.

2.6.1 OBSERVATIONS DURING SITE INVESTIGATION OF CHALLAGHATTA MAIN VALLEY PRIMARY STORM DRAIN (C100):

For ease of assessment Challaghatta valley nalla is divided into 11 segments. The details of each segment is as discussed below :

Segment - 1 (Chainage length 0.00 to 1000.00 m.): (Vasanthanagar Upto Queens Road):

Starts from a very congested residential area near Vasanthnagar and continues upto Queens Road. As per the preliminary investigations made by the consultants, it was noticed that localities surrounding Bangalore Palace grounds, Vasanthnagar, Millers tank area and also area adjoining to Cunningham road forms the part of contributory areas for this section.

The width of drainage channel varies from 2.5 m to 5 m & depth varies from 1.5 to 2.0 m. and is having masonry walls on either sides, the condition of the side walls is in good to moderate condition.

- •The drainage channel is covered with RCC deck slab from 1st Cross Vasanthanagar upto Corporation. dobhi ghat and with B.S. Slabs from Millers road upto Millers tank bund road.
- •The drain reach inside dobhi ghat is very narrow and inadequate to cater, even for present hydraulic design flow.
- •The existing tertiary drains connecting to the primary drain near Vasanthanagar are not designed and constructed as per standards.
- •Large quantity of sewage is being contributed to this primary drain through the existing tertiary drains.
- •The drainage channel inside Ambedkar bhavan is covered with RCC Slab with reduced drain section.
- •Large quantity of construction debris have been dumped over the drain and also vegetal growth is observed behind Mahaveer Jain hospital.
- •The existing culverts constructed across storm drain near Millers road and Millers tank bund road are obstructing free flow of water due to inadequate vent space.
- •Sewage/waste water generated from badminton association is being directly discharged into the drain and also the approach bridges constructed across the drain for the stadium and also its adjoining property i.e., Indian Council for Social welfare is drastically obstructing the flow.
- •Sewer line of 450 mm dia. has been laid and manholes of 1.2 m. dia. which are above drain bed level are noticed inside the drainage channel in this reach.

- •The existing drain bed in this reach is in natural condition, and also there is scope for regrading the bed in this reach.
- •Dumping of solid waste, garbage, silt deposition and vegetation growth is noticed at many places inside the channel, and also near the vents of cross drains, thereby causing obstruction for the free flow of water in the channel.
- •The nalla throughout its stretch has service road on either sides or on one side and residential / commercial buildings on the other side of the channel.

•The drainage channel has 3 culverts in this reach.

Segment - 2 (Change length 1000.00 m. to 2000.00 m.) (Queens Road upto Juma Masjid Road):

This part of the drain starts from Queen's road and continues upto Juma Masjid road. As per the preliminary investigations made by the consultants, it was noticed that the localities surrounding Rajiv Gandhi colony, corporation colony, part of Shivajinagar, part of Nehrupuram, Part of Bamboo Bazar area forms the contributory areas for this section.

The width of drainage channel varies from 4.5 m to 7.5 m & depth varies from 1.8 to 2.2 m. and is having masonry walls on either sides, the condition of the side walls is in good to moderate condition.

- •This reach of drain is an open drain upto Russell market area and further shops have been constructed over the drain, which intern is obstructing free flow of water.
- •The condition of side walls near St. Xavier high school is in moderate condition, which requires rehabilitation .

•The drain reach near Broadway Road upto Seppings Road is very narrow

and inadequate to cater even for present hydraulic design flow.

- •Large number of openings have been made to the parapet wall to allow rain water to enter into the main drain.
- •The existing tertiary drains connecting to the primary drain near Shivajinagar area is not designed and constructed as per standards.
- •Large quantity of sewage is being contributed to this primary drain through the existing tertiary drains.
- •The existing culverts constructed across storm drain near Old bamboo bazar road, Charminar Road, Juma Masjid Road are obstructing free flow of water due to inadequate vent space.
- •Sewer line of 450 mm dia. has been laid and manholes of 1.2 m. dia. which are above drain bed level are noticed inside the drainage channel in this reach.
- •The existing drain bed in this reach is in natural condition, and also there is scope for regrading the bed in this reach.
- •Dumping of solid waste, garbage, silt deposition and vegetation growth is noticed at many places inside the channel and also near the vents of cross drains, thereby causing obstruction for the free flow of water in the channel.
- •The nalla throughout its stretch has service road on either side of the channel.
- •The drainage channel has 7 culverts and number of foot bridges in this reach and as such these foot bridges are not obstructing free flow of water.
- •At few places the condition of wall is in poor condition and which requires

reconstruction and also at some places rehabilatation.

•Large number of utility crossing are observed in this reach of drain.

•The tertiary drains near Police guarters and corporation colony are discharging large quantity of sewage into storm drain.

Segment - 3 (Chainage length 2000.00 m to 3000.00 m.) (Juma Masjid Road upto A.S.M. Road near Ajantha theatre)

This part of the drain starts from Juma Masjid Road and continues upto A.S.M. Road near Ajantha theatre. As per the preliminary investigations made by the consultants, it has been noticed that localities surrounding Russel market, part of Shivajinagar, part of Nehrupuram, Part of Bamboo Bazar, Bharathi nagar, Shivanchetti Garden, Commercial Street area forms the part of contributory areas for this section.

The width of drainage channel varies from 5 m to 10 m and depth 1.8 to 2.4 m. and is having masonry walls on both the sides. The condition of the side walls is in good to moderate condition.

- In the initial stretch of this drain, shops have been constructed over the drain and further it is an open drain.
- •The drain reach near Kamaraj Road and St. Johns Road is narrow and there is scope for widening the drain in this reach.

•The existing tertiary drains connecting to the primary drain near Narayan Pillai street, old post office road, Jewellers street are not designed and constructed as per standards.

•The existing culverts constructed across storm drain near Sepping's Road, STUP Consultants P. Ltd.

Kamaraj Road and St. Johns Road are obstructing free flow of water due to inadequate vent space.

- •Few temporary shops, which are abutting to the drain wall have been constructed near Makkan Road.
- •Large number of toilet blocks have been constructed over the drain and intern raw sewage from these toilet blocks are being discharged into this storm drain
- •Large quantity of garbage and solid waste materials are stacked adjacent to storm drain near Seppings road and intern these waste materials find their way into storm drain and obstructs free flow of water.
- •Sewer line of 600 mm dia. has been laid and manholes of 1.4 m. dia. which are above drain bed level are noticed inside the drainage channel in this reach.
- •The existing drain bed in this reach is in natural condition and there is scope for deepening the drain bed in this reach.
- •Large number of openings have been made in the parapet wall to allow storm water from road to enter into the main drain.
- •Dumping of solid waste, garbage, silt deposition and vegetation growth is noticed at many places inside the channel, and also near the vents of cross drains, thereby causing obstruction for the free flow of water in the channel.
- •The nalla throughout its stretch has service road on either side of the channel.
- •At few places, the walls are in poor condition and which requires reconstruction and also at some places rehabilitation.

•Large number of utility crossing are observed in this reach of drain.

- •Large quantity of sewage is being contributed to this primary drain through the existing tertiary drains.
- •The drainage channel has 6 culverts and number of foot bridges in this reach.

Segment - 4 (Chainage length 3000.00 m to 4000.00 m.) (A.S.M. Road near Ajantha theatre upto Kensington Road)

This reach of storm water drain starts from A.S.M. Road near Ajantha theatre and continues upto Kensington Road. As per the preliminary investigations made by the consultants, it was noticed that localities surrounding Dickinson Road, A.S.M. street, RBAMNS College, Gangadar shetty Road area forms the part of contributory areas for this section.

The width of drainage channel approximately varies from 8 m to 12 m & depth varies from 2.4 to 2.6 m. Masonry walls are constructed on either side of the channel and it is in good to moderate condition. Further, waste weir of Ulsoor tank is situated opposite to Gurudwara and overflow from Ulsoor tank to Challaghata valley is also noticed at that location.

- •This reach of drain is an open drain.
- •The drain reach near RBANMS College is narrow and there is scope for widening the drain in this reach.
- •The existing tertiary drains connecting to the primary drain near ASM Road and Gangadar shetty Road are not designed and constructed as per standards.
- •The existing weir constructed across storm drain near RBANMS college is obstructing free flow of water and also causing accumulation of solid waste materials.

•The existing culverts constructed across storm drain near A.S.M Road is

obstructing free flow of water due to inadequate vent space.

- •Accumulation of large quantity of silt, garbage and solid waste materials can be noticed near RBANMS College.
- •Sewer line of 900 mm dia. has been laid and manholes of 1.6 m. dia. which are above drain bed level are noticed inside the drainage channel in this reach.
- •The existing drain bed in this reach is almost flat and also in natural condition, there is scope for deepening the drain bed in this reach.
- •Large quantity of vegetation growth is noticed at many places inside the channel i.e., opposite to Ajantha theatre and also near RBANMS college.,
- •The nalla throughout its stretch has service road on one side and tank bund on the other side.
- •At few places, the wall is in poor condition and which requires reconstruction and also at some places rehabilitation.
- •Large quantity of debris are being dumped into drainage channel near Ulsoor lake
- •Large number of utility crossing are observed in this reach of drain.
- •The drainage channel has 2 culverts in this reach.

Segment - 5 (Chainage length 4000.00 m to 5000.00 m.) (Kensington Road upto Old Madras Road)

This section of the reach starts from Kensinton Road and continues upto Old Madras Road. As per the preliminary investigations made by the consultants, it was noticed that localities surrounding Sweepers colony, Murphy town, Munivenkatappa garden, Gupta layout, Hoysala nagar, and part of Ulsoor area forms the part of contributory areas for this section.

The width of drainage channel approximately varies from 11 m. to 15 m. & depth varies from 2 to 2.5 m. Masonry walls have been constructed on either side of the channel, the condition of the side walls is in good to moderate condition.

- •This reach of drain is an open drain.
- •The drain reach behind Gurudwara is having a rocky strata, due to which water/sewage is stagnating in the storm drain and also large quantity of vegetal growth and solid waste accumulation can be noticed opposite to Gurudwara.
- •The drain reach adjacent to Gurudwara is covered and a school is being run over the drain by Gurudwara association.
- •The existing bridge constructed across Kensington road has been constructed in 2 different stages. Where portion of the bridge i.e, towards Gangadar chetty road is having RCC columns and the other portion of the bridge i.e., main carriage way is resting on masonry piers. The arrangement of columns and piers are obstructing free flow of water and also causing hindrance for the maintenance of drain near the bridge portion.
- •Slum development is noticed adjacent to drain near Munivenkapappa Garden and also both liquid and solid wastes generated by the slum dwellers are being discharged into storm drain.
- •The existing drain bed in this reach is almost flat and also in natural condition, there is scope for deepening the drain bed in this reach.
- •Large quantity of silt accumulation and vegetation growth is noticed near the fringe of the drain at many places.

- •The width of the drainage channel opposite to Murphy town market is reduced, and which needs to be widened.
- •The nalla throughout its stretch has service road on one side (i.e, left hand side) and densely built residential building, which are abutting to drain wall on the other side (right hand side).
- •At few places, the wall is in poor condition and which requires reconstruction and also at some places rehabilitation.
- •Large quantity of garbage dumpings are noticed at foot bridge locations near Guptha layout.
- •Large number of utility crossing and also few manhole are observed in this reach.
- •Large number of sewer outlets are noticed from residential buildings in this reach.

•The drainage channel has 3 culverts and 4 foot bridges in this reach.

Segment - 6 (Chainage length 5000.00 m to 6000.00 m.) (Old Madras Road upto Saraswathipura)

This section of the drain starts from Old Madras Road and continues upto Saraswathipura. As per the preliminary investigations made by the consultant, it is noticed that localities surrounding Shammana Gowda layout, Doddaiah layout, Lakshmipura, Lal Bahadur Shastrinagar and Jogupalya area forms part of contributory areas for this section.

The width of drainage channel approximately varies from 15 m to 18 m. & depth varies from 2.5 to 2.8 m. Masonry walls have been constructed on both sides and the condition of the side walls are in good to moderate condition.

•This reach of drain is an open drain.

- •Large quantity of silt accumulation and vegetation growth is noticed near the fringe of the drain at many places.
- •The width of the drainage channel near Lakshmipura is reduced, and which needs to be widened.
- •The nalla throughout its stretch has service road on one side (i.e, Right hand side) and densely built residential building, which are abutting to drain wall on the other side.
- •In general condition of drain wall is in good condition. Except at few places, it requires minor rehabilitation.
- •The existing drain bed in this reach is almost flat and also in natural condition, there is scope for deepening the drain bed in this reach.
- •Large number of utility crossing and also few manholes are observed in this reach.
- •The drainage channel has 1 foot bridges near Lakshmipura in this reach.
- •A secondary drain (C105) from Indiranagar 1st Stage confluence with this primary drain near Lakshmipura.
- •The existing tertiary drains at Jogupalya area are having inadequate size, silted and also not properly networked, hence it is causing localized flooding problems.
- •Large number of sewer outlets from residential and commercial establishments are noticed in this reach.

Segment - 7 (Chainage length 6000.00 m to 7000.00 m.) (Saraswathipura upto Domlur II nd Stage)

This reach of the drain starts from Saraswathipura and continues upto Domlur II Stage near TERI. As per the preliminary investigations made by the consultant, it is noticed that localities surrounding Cambridge layout, Gouthampura, Jeevankendra layout, Mottappapalya, Someshwarapura, part of Domlur and Indiranagar area forms the part of contributory areas for this section.

The width of drainage channel approximately varies from 18 m to 24 m. & depth varies from 2.2 to 3.0 m. Masonry walls have been constructed on both the sides and the condition of the side walls is in good to moderate condition.

-In this stretch the drain is in open condition.

- Slum development is noticed adjacent to drain near Cambridge layout bridge and also both liquid and solid wastes generated by the slum dwellers are being discharged into storm drain.
- •Manholes constructed below the existing low level bridge (adjacent to cambridge layout bridge) is obstructing free flow of water.
- •The existing drain bed in this reach is almost flat and also in natural condition. There is a scope for deepening the drain bed in this reach.
- ·Large quantity of silt accumulation and vegetation growth is noticed near the fringe of the drain at many places.
- •The width of the drainage channel near Domlur 2nd Stage bridge location (RCC hume pipe location) is reduced, and which needs to be widened.
- •The nalla throughout its stretch has few open lands on one side and residential building and appartments, which are abutting to drain wall on the other side (i.e., right hand side).
- •The existing RCC hume pipe culverts constructed across the drain is obstructing free flow of water near Domlur 2nd Stage

Large number of utility crossing and also few manholes are observed in this STUP Consultants P. Ltd. Page No.

reach.

•The drainage channel has 2 culverts in this reach.

Segment - 8 (Chainage length 7000.00 m to 8000.00 m.)

(Domlur II Stage upto Diamond District Apartments)

This section of the drain starts from Domlur II Stage and continues upto Diamond District Appartments near Royal Orchid park plaza hotel. As per the preliminary investigations made by the consultant, it is noticed that localities surrounding part of Indiranagar, Domlur 2nd Stage, Airport Road area, Kodihalli forms the part of contributory areas for this section.

The width of drainage channel approximately varies from 16 m to 26 m. & depth varies from 2.6m to 3.0 m. Masonry walls have been constructed on both the sides and the condition of the side walls is in good to moderate.

- •The existing drain bed in this reach is having gentle slope and also in natural condition. There is a scope for deepening the drain bed in this reach.
- •Large quantity of silt accumulation and vegetation growth is noticed near the fringe of the drain at many places.
- •The width of the drainage channel near Indiranagar bridge location is reduced and which needs to be widened.
- •The nalla throughout its stretch has open lands on either side of the channel upto Airport road and further residential apartments buildings have been constructed on either side of the channel.
- •Large number of utility crossing and few manholes are observed in this reach.

•The drainage channel has 2 culverts in this reach.

•1800 mm dia. CI sewer pipe line is crossing the drain behind Diamond district apartment and also it is obstructing free flow of water.

Segment - 9 (Chainage length 8000.00 m to 9000.00 m.)

(Diamond District Apartments upto K.G.A. Golf Club)

This section of the drain starts from Diamond District apartments and continues upto K.G.A. Golf Club near Texas instruments.

Stone pitching is done on either side of the drain for a height of 1.5 m. The condition of the side walls is in good to moderate. The width of drainage channel approx. varies from 16 m to 28 m. & depth varies from 2.2 to 2.6 m.

•This reach of drain is in open condition.

•The natural coarse of drain has been altered in this reach.

- •The existing drain bed in this reach is having gentle slope and also in natural condition. There is a scope for deepening the drain bed in this reach.
- •Large quantity of silt accumulation and vegetation growth is noticed near the fringe of the drain at many places.
- •Few tertiary drains (i.e, from Ring Road Side) join this primary drain near Park plaza hotel, which needs to be desilted and widened for proper functionality.
- •Large quantity of desilted materials has been stacked in the middle of the drain and left without removing near K.G.A. Club.
- •The width of the drainage channel adjacent to K.G.A golf club is reduced and which needs to be widened.

•The drainage channel has 2 culverts in this reach.

Segment - 10 (Chainage length 9000.00 m to 10000.00 m.) (K.G.A. Golf Club upto Challaghatta Main Road)

This section of the drain starts from K.G.A. Golf Club near Texas instruments and further it flows inside Airport premises and also under the existing runway and continues upto Challaghatta main road i.e., behind Airport compound.

As per the preliminary investigation Jeevanbhimanagar, K.R. Garden, KGA Golf club and Challaghatta village forms part of contributory areas for this reach of drain.

This reach of the drain is in natural condition. The width of drainage channel approximately varies from 16 m to 30 m. & depth varies from 2.0 to 2.8 m.

•The natural coarse of drain has been altered in this reach.

- •The existing culvert constructed under the runway is silted and size is also very much inadequate.
- •The existing drain bed in this reach is almost flat and also in natural condition and there is a scope for deepening the drain bed in this reach.
- •New bypass drain has been constructed by the Airport authorities to divert the flow from the runway area. But, due to silt accumulation, vegetal growth and moderate slope there is very small flow of water is flowing in this drain.
- •Secondary drain (C101) from Jeevanbhimanagar and tertiary drains from K.R. Garden area are joining this primary drain inside the Airport area.
- •Large quantity of silt, solid waste accumulation and vegetation growth is noticed near the fringe of the drain at many places.

•The drainage channel has 1 culverts in this reach.

- •Large number of utility crossings are noticed near Wind tunnel road bridge location.
- •A large size grating screen has been placed in the compound wall of Airport across the drain where floating matters getting collected obstructs the free flow of water.

Segment - 11 (Chainage length 10,000.00 m to 12,000.00 m.) (Challaghatta Main Road upto Bellandur tank)

This section of the drain starts from Challaghatta Main Road and continues upto a location near Bellandur tank.

These is no defined drain available in these reach and also it is situated in marshy land.

2.6.2 OBSERVATIONS DURING SITE INVESTIGATION OF SECONDARY DRAINS IN CHALLAGHATTA MAIN VALLEY:

2.6.2.1 Murugeshpalya Drain (C101):

(Anandanagar upto Challaghatta), (Chainage length of about 1896.00 m.)

This section of the drain starts from a place near Anandanagar and flows through HAL Airport before confluenceing with the main drain. As per the

Anandanagar, Sudhamanagar, Shivalingaiah colony, Nanjareddy colony, BDA colony, Airport Road, Murugeshpalya, Konen Agrahara, Cauverynagar, Manjunatha layout, Vinayakanagar and K.R. Garden forms part of contributory areas for this section.

The width of drainage channel is about 1.5 m to 3 m & depth varies from 1.2 m to 2 m in this section.

- •This reach of drain is a covered drain except near Airport Road.
- •Slum development is noticed adjacent to drain near Sudhamanagar and Sreeramnagar. Further, both liquid and solid wastes generated by the slum dwellers are being discharged into storm drain.
- •The existing drain bed near the slum areas are silted heavily.
- •The width of the drainage channel near Muniswamy layout, Papaiah layout, Airport road and near Sreeramnagar is drastically reduced and which needs to be widened.
- •The nalla throughout its stretch has densely built residential building which are abutting to drain wall on the either side.
- •At few places, the condition of wall is poor which requires reconstruction and also at some places rehabilitation.
- •Large number of utility crossings and also few manholes are observed in this reach.
- •Large number of sewer outlets are noticed from residential buildings in this reach.
- •The locality adjacent to SWD (i.e., K.R. Garden) has been developed well below the HFL level of the SWD and intern causing localized flooding and

natural condition.

But as a part of this remodelling project, BMP has taken up construction of RCC box drain with provisions like desilting openings, inspection openings, manholes for house/lateral sewer connections and also for small dia. utility crossings across the drain in this reach.

- •Sewer line of about 450 mm dia. and manholes at regular intervals has been constructed all along SWD near Sir. M. Vishveshwariah Composite college upto Airport compound.
- •Further the drain flows inside Airport premises and also under existing runway.

Due to silt accumulation, dense vegetal growth and also due to inadequate vent size of existing culvert (i.e., under the runway) flow is being drastically obstructed.

•600 mm. dia. C.I. sewer pipe line is proposed to be laid across storm drain near Airport compound.

2.6.2.2 Shastrinagar Drain (C102)

(Sweepers colony upto Shastrinagar), (Chainage length of about 1600.00 m.)

This section of the drain starts from a place near Kadariyanapalya and flows Shastrinagar before confluenceing with the challaghatta main drain. As per the preliminary investigations, it is noticed that localities surrounding Part of Indiranagar, Shastarinagar and Lakshmipura forms part of contributory areas for this section.

The width of drainage channel is about 1.2 m to 2 m & depth varies from 1.2 to 1.6 m in this section. Masonry wall has been constructed in this reach. The condition of the wall is in good to moderate.

-Initial reaches of this drain lies within defence area (i.e., near Vivekananda

- •This section of the drain is an open drain upto Lakshmipura and beyond Lakshmipura upto primary drain location is a covered drain.
- •Large quantity of silt accumulation and vegetal growth is observed inside the drain near C.M.H. road.
- •At few places the condition of wall is in moderate and which requires reconstruction and also at some other places only minor rehabilitation.
- •This stretch has residential buildings and apartments on either side of the channel. Large quantity of sewage flow, silt and garbage dump is noticed at many places.

2.6.2.3 Krishnamurthynagar Drain (C103)

(Krishnamurthynagar to Kadariyanapalya tank),(Chainage length of 1600 m.)

This section of the drain starts from a place near Kadarayanapalya and confluence's with the Shastarinagar drain near Kadariyanapalya tank. As per the preliminary investigations it is noticed that this reach of drain lies within defence area.

2.6.2.4 Kadariyanapalya Drain (C104)

(Kadariyanapalya upto Kadariyanapalya tank),(Chainage length of 2500 m.)

This section of the drain starts from a place near N.G.E.F and confluence's with the Shastarinagar drain near Kadariyanapalya tank. As per the preliminary investigations made by the consultant, it is noticed that localities surrounding Kadariyanapalya and part of Krishanmurthynagar forms part of contributory areas for this section. But this reach of drain lies within defence area.

2.6.2.5 ISRO Complex Drain (C105)

(Jeevanbhimanagar upto Kodihalli), (Chainage length of about 3500.00 m.)

This section of the drain starts from a place near Jeevanbhimanagar and flows through ISRO complex before confluenceing with the main drain near Airport road.

As per the preliminary investigations, it is noticed that localities surrounding Jeevanbhimanagar, HAL 2nd & 3rd Stage, ISRO Complex and Kodihalli forms part of contributory areas for this section.

The width of drainage channel is about 2.5 m to 6 m & depth varies from 1.2 to 1.8 m. in this section. This stretch has residential buildings and apartments on either side of the channel. The drain reach inside ISRO complex is maintained by ISRO.

•This reach of drain is an open drain.

•The natural coarse of drain has been altered in this reach.

- •The existing drain bed in this reach is in natural condition and there is scope for deepening the drain bed in this reach.
- •Further, the drain flows inside I.S.R.O. Complex, where it is in lined condition. A trash barrier/steel grating has been installation by I.S.R.O. authorities due to this all the solid waste and water gets accumulated and cause localised flooding problems in the adjacent locality.
- •Large quantity of silt, vegetal growth and debris dumps are observed inside the drain i.e., behind I.S.R.O. Complex.
- •The drain flows between residential buildings where the drain size is reduced, but there is some scope for deepening the drain bed.

•Large quantity of raw sewage is being discharged into this storm drain from the nearby slum and Kodihalli village.

- •Further the drain reach near Kodihalli Village / Domlur, RCC drain walls have been constructed and these walls require minor rehabilitation works.
- •Large quantity of silt, solid waste accumulation and vegetation growth is noticed near the fringe of the drain at many places.
- •Large number of utility crossings are noticed near Airport road bridge location.
- •Large quantity of sewage flow, silt and garbage dump is noticed at many places.

2.6.2.6 Thippasandra Drain (C106)

(New Thippasandra upto ISRO Complex), (Chainage length of 650.00 m.)

This section of the drain starts from a place near New Thippasandra and joins the secondary drain C105 near ISRO complex. As per the preliminary investigations made by the consultants, it was noticed that localities surrounding New Thippasandra and part of Jeevanbhimanagar forms part of contributory areas for this section.

The width of drainage channel is about 2 m to 4 m & depth varies from 1.4 to 1.6 m. in this section. This stretch has residential buildings and apartments on one side and Thippasandra main road on the other.

•This drain reach near Thippasandra main road is covered by BS slab.

•Large quantity of silt and garbage dump is noticed at many places.

•Masonry sidewall have been constructed all along the channel on either side. The condition of the side walls is in good condition.

2.6.2.7 Malleshappanapalya Drain (C107)

(Garmantakanapalya upto Doddanekundi Tank),(Chainage length of 900.00 m.)

This section of the drain starts from a place near Garmanthanapalya and confluences with the Doddanekundi tank. As per the preliminary investigations made by the consultant, it is noticed that localities surrounding Garmanthanapalya, Malleshappanapalya and part of Doddenakundi forms part of contributory areas for this section. But during reconnaissance survey it is observed that this reach of drain lies beyond BMP boundary.

2.6.3 OBSERVATIONS DURING SITE INVESTIGATION OF ULSOOR VALLEY PRIMARY STORM DRAIN (C200):

For ease of assessment Ulsoor valley nalla is divided into 4 segments. The details of each segment is as discussed below :

Segment - 1 (Chainage length 0.00 to 1000.00 m.): (J.C. Nagar Main Road Upto Ramakka Block Main Road):

This stretch starts from a very congested residential area near J.C. Nagar and continues upto Ramakka Block main road. As per the preliminary investigations made by the consultant, it is noticed that localities surrounding Anchappa Garden, Kempaiah Block, Anjanappa Garden, Marappa Garden, Muddamma Garden, Gundappa Garden, Chinnappa Garden, Munireddypalya and Krishnappa Garden forms the part of contributory areas for this section.

The width of drainage channel varies from 4.0 m to 6 m & depth varies from 1.8 to 2.0 m. and is having masonry walls on either sides, the condition of the side walls is in good to moderate condition.

- •The drainage channel is covered with RCC deck slab near J.C. Nagar main road and provision for construction of shops over the drain has been made.
- •The drain reach near Ramgeetha block and Krishnammanagar is very narrow and needs to be widened.
- •Existing drain wall at few places are in moderate condition and it requires reconstruction.

- •BWSSB manholes have been constructed exactly at the vent locations of culverts at many locations near Krishnammanagar.
- •Drain reach near Kempiah block (i.e., near Mosque) is covered with RCC slab.
- •The existing tertiary drains connecting to the primary drain near Kempaiah Block, Anjanappa Garden, Marappa Garden, Muddamma Garden, Gundappa Garden, Chinnappa Garden, Munireddypalya and Krishnappa Garden are not designed and constructed as per standards.
- •The existing culverts constructed across storm drain near Krishnammanagar and Muddammanagar are obstructing free flow of water due to inadequate vent space.
- •Large quantity of construction debris have been dumped inside the drainage channel can be noticed at many places.
- •Near Aiyappa Swamy temple, a portion of the residential building has been constructed inside the drain area. Further, a KPTCL transformer also has been installed in the drain area.
- •Sewer line of 300 & 450 mm dia. has been laid and manholes of 1.2 m. dia. which are above drain bed level (upto a height of about 1.2 to 1.8 m.) are noticed inside the drainage channel in this reach.
- •The existing drain bed in this reach is in natural condition, and also there is scope for regrading the bed in this reach.
- •Dumping of solid waste, garbage, silt deposition and vegetation growth is noticed at many places inside the channel and also near the vents of cross drains thereby causing obstruction for the free flow of water in the channel.
- •The nalla throughout its stretch has residential / commercial buildings on either side of the channel.

•Large number of sewer outlets on either side have been connected to sewer pipe lines which are laid inside the drainage channel in this reach.

This reach of drain has 12 culverts

Segment - 2 (Chainage length 1000.00 to 2000.00 m.): (Ramakka Block Main Road upto S.K. Garden):

Starts from Ramakka Block Main Road and continues upto S.K. Garden main road near Pottery town. As per the preliminary investigations made by the consultant, it is noticed that localities surrounding S.K. Garden, I.T.I. Colony and adjoining defence area forms the part of contributory areas for this section.

The width of drainage channel varies from 5 m. to 8 m. & depth varies from 2.0 to 2.4 m. and is having masonry walls on either side, the condition of the side walls is in good to moderate.

•This reach of drain is in open condition.

- •The drain reach near Muddamma garden and I.T.I. Colony is narrow and needs to be widened. But, there is scope for construction of new drain at 13th cross Muddamma garden Extention.
- •Existing drain wall at few places are in moderate condition and it requires reconstruction.
- •The existing tertiary drains connecting to the primary drain near Muddamma Garden, I.T.I Colony and S.K. Garden are not designed and constructed as per standards.
- •The existing culverts constructed across storm drain near S.K. Garden and Pottery town are obstructing free flow of water due to inadequate vent space.

- •The drain reach adjacent to defence land near S.K. Garden main road is narrow and also large quantity of debris and garbage dumps are noticed.
- •Large quantity of construction debris have been dumped inside the drainage channel can be noticed at many places.
- •Sewer line of 300 & 450 mm dia. has been laid and manholes of 1.2 m. dia. which are above drain bed level (upto a height of about 1.2 to 1.8 m.) are noticed inside the drainage channel in this reach.
- •The existing drain bed in this reach is in natural condition and also there is a scope for regrading the bed in this reach.
- •Dumping of solid waste, garbage, silt deposition and vegetation growth is noticed at many places inside the channel, and also near the vents of cross drains, thereby causing obstruction for the free flow of water in the channel.
- •The nalla throughout the stretch has residential buildings on either side of the channel.
- •Large number of sewer outlets on either side have been connected to sewer pipe lines which are laid inside the drainage channel in this reach.

•This reach of drain has 8 culverts.

Segment - 3 (Chainage length 2000.00 to 3000.00 m.): (S.K. Garden Main Road upto Stephen's cross road):

Starts from S.K. Garden Main Road and continues upto Stephen's cross road near Frazer town. As per the preliminary investigations made by the consultant, it is noticed that localities surrounding part of Pulikeshi nagar, Frazer town, Cleveland town, and Richards town forms the part of contributory areas for this section. The width of drainage channel varies from 8 m. to 12 m & depth varies from 2.0 to 2.2 m. and is having masonry walls on either sides, the condition of the side walls is in good to moderate condition.

- •This reach of drain is in open condition.
- •The drain reach near Bore bank road (near Railway bridge) is narrow and needs to be widened.
- •Existing drain wall at few places are in moderate condition and it requires reconstruction.
- •The existing tertiary drains connecting to the primary drain near Frazer town not designed and constructed as per standards.
- •Large quantity of construction debris have been dumped inside the drainage channel can be noticed at many places near tannery road.

Sewer lines of 300 & 450 mm dia. has been laid and manholes of 1.2 m. dia. which are above drain bed level (upto a height of about 1.2 to 1.8 m.) are noticed inside the drainage channel in this reach.

- •Some section of the drain wall in this reach is in moderate condition and it requires minor rehabilitation.
- •The existing drain bed in this reach is in natural condition and also there is scope for regrading the bed in this reach.
- •Dumping of solid waste, garbage, silt deposition and vegetation growth is noticed at many places inside the channel and also near cross drains, thereby causing obstruction for the free flow of water in the channel.
- •The nalla throughout its stretch has residential buildings on either side of the channel.

- •Large number of sewer outlets on either side have been connected to sewer pipe lines which are laid inside the drainage channel in this reach.
- •Silt trap has been constructed near Mosque road and it is totally silted and causing stagnation of water and intern causing unhygenic situation to the adjoining residential areas.

•Large number of utility crossing are noticed at many places in this reach

•This reach of drain has 5 culverts.

Segment - 4 (Chainage length 3000.00 to 4100.00 m.): (Stephen's cross road upto Ulsoor tank):

Starts from Stephen's cross Road and continues upto Ulsoor lake. As per the preliminary investigations made by the consultant, it was noticed that localities surrounding part of Frazer town, Sindhi colony and Cox town forms the part of contributory areas for this section.

The width of drainage channel varies from 10 m. to 14 m & depth varies from 2.0 to 2.2 m. and is having masonry walls on either sides, the condition of the side walls is in good to moderate condition.

•This reach of drain is an open drain.

- •The drain reach near Sindhi colony is narrow and needs to be widened.
- •Existing drain wall at few places are in moderate condition and it requires reconstruction.
- •The existing tertiary drains connecting to the primary drain near Frazer town are not designed and constructed as per standards.
- •Sewer line of 450 mm dia. has been laid and manholes of 1.2 m. dia. which are above drain bed level (upto a height of about 1.2 to 1.8 m.) are noticed inside the drainage channel in this reach.

•The existing drain bed is almost flat and also it is in natural condition.

- •Dumping of solid waste, garbage, silt deposition and vegetation growth is noticed at many places inside the channel, and also near the vents of cross drains, thereby causing obstruction for the free flow of water in the channel.
- •The nalla throughout its stretch has service road on one side and open ground on the other side of the channel.
- •Some section of the drain wall in this reach is in moderate condition and it requires minor rehabilitation.
- •Silt trap has been constructed near Asseye road and it is totally silted and causing stagnation of water and also intern causing unhygenic situation to the adjoining residential areas.
- •Large number of utility crossing are noticed at many places in this reach.
- •This reach of drain has 4 culverts.
- •Large quantity of debris have been dumped inside the drain by the military authorities, behind corporation ward office near Ulsoor lake.

2.6.4 OBSERVATIONS DURING SITE INVESTIGATION OF SECONDARY STORM DRAINS IN ULSOOR VALLEY:

2.6.4.1 Ganesh temple Drain (C201):

(Ganesh temple upto MEG Centre), (Chainage length of about 250.00 m.)

This section of the drain starts from the back side of Ulsoor lake near Ganesh temple and continues upto MEG Centre. Since the vent size of the bridge near the temple is inadequate and the excess water from the main drain is diverted through this drain near the temple and further joins Ulsoor lake.

•The width of drainage channel is about 4 m. to 6 m. & depth varies from 1.6 to 1.8 m. in this section.

•Stone revetment has been provided on either side and it is in moderate condition.

•This section of the drain bed is in natural condition.

•This stretch has residential buildings and commercial establishments on one side and military grounds on the other side of the drain.

2.6.4.2 Cox Town Drain (C202):

(Richard's Town upto Gymkhana Ground), (Chainage length of about 1150.00 m.)

This reach of the drain starts from Richard's Town and continues upto Gymkhana Ground near Assaya road. As per the preliminary investigations made by the consultants, it was noticed that localities surrounding Richard's Town, part of Frazer town, Cox town and Cooke town forms the part of contributory areas for this section.

The width of drainage channel varies from 1.5 m to 4.2 m & depth varies from 2 to 2.2 m. and is having masonry walls on either sides of the drain. The condition of the side walls is in moderate condition.

- •This reach of drain is an open drain except near Frazer town police station (Lazer Road).
- •The drain reach opposite to Frazer town police station is covered and also narrow. It needs to be widened.
- •Sewer line of 300 mm dia. and construction of manholes of 1.2 m. dia. is noticed at many places inside the drain.

·Large quantity of debris have been dumped inside the drain near KPTCL

- •The nalla throughout its stretch has open space, residential and commercial establishments on either side of the drain.
- •Silt trap has been constructed near Asseye road, and it is totally silted and causing stagnation of water and also intern causing unhygenic situation to the adjoining residential areas.
- •Some section of the drain wall in this reach is in moderate condition and it requires minor rehabilitation.
- •The drain bed in this reach is in natural condition, and also there is some scope for regrading the drain bed.

•Large number of utility crossing are noticed at many places in this reach

2.6.4.3 Sagayapuram Drain (C203):

(Sagayapuram upto Cleveland town), (Chainage length of about 725.00 m.)

This reach of the drain starts from Sagayapuram and continues upto Cleveland town, before confluenceing with the main drain. As per the preliminary investigations made by the consultants, it was noticed that localities surrounding Sagayapuram, Tannery road, part of Richard's town and Cleveland town, forms the part of contributory areas for this section.

The drain reach between Davis road and Viviani road is covered with BS slab. The width of drainage channel varies from 1.5 m. to 4 m. & depth varies from 1.6 to 2 m. and is having masonry walls on either sides of the drain. The condition of the side walls is in moderate condition.

•This reach of drain is an open drain, except near Tannery Road.

•The drain reach, opposite to K.M.F.C. market, (near Tannery Road) upto railway bridge is covered and also narrow. It needs to be widened.

- •Sewer line of 250 mm dia. and construction of manholes of 1.2 m. dia. is noticed at many places inside the drain.
- •Large quantity of silt and garbage accumulation can be noticed inside the drain near Roger's road and its adjoining slum area.
- •The nalla throughout its stretch has residential buildings on either side of the drain.
- •Some section of the drain wall in this reach is in moderate condition and it requires minor rehabilitation.
- •The drain bed in this reach is in natural condition, and also there is some scope for regrading the drain bed.

Large number of utility crossings are noticed at many places in this reach
Large quantity of sewage flow is noticed inside the drain near Tannery road slum area.

2.6.4.4 Jeevanahalli Drain (C204)

(Jeevanahalli upto Ulsoor Lake), (Chainage length of about 2000.00 m.)

This reach of the drain starts from a place near Jeevanahalli and continues upto M.E.G. centre before confluencing into Ulsoor lake. As per the preliminary investigations made by the consultants, it is noticed that localities surrounding Sanjeevappa layout, Kandaswamy garden, BDA Qtrs. I.T.C Colony, K.H.B. Colony, Jeevanahalli and M.E.G. defence area forms the part of contributory areas for this section.

Recently as part of B.M.P's Ulsoor lake cleaning programme, a steel grating has been installed inside the drain by BMP near MEG centre and also near Ganesh temple to prevent entry of solid waste into Ulsoor lake,. The width of drainage channel varies from 1.5 m to 4.2 m & depth varies from 1.4 to 2.2 m. and is having masonry walls on either sides of the drain only in the initial reaches. The condition of the side walls is in moderate condition.

•This reach of drain is an open drain.

- •The drain reach near B.D.A. quarters road, east railway station and M.E.G centre is narrow and it needs to be widened.
- •Large quantity of silt and thick vegetal growth is noticed inside the drain at many places.
- •Sewer line of 250 mm dia. and construction of manholes of 1.2 m. dia. is noticed at many places inside the drain.
- •The nalla throughout its stretch has play grounds and residential and commercial establishments on either side of the drain i.e., upto railway track from railway track onwards it enters into M.E.G centre.
- •Some section of the drain wall in this reach is in moderate condition and it requires minor rehabilitation.
- •The drain reach inside M.E.G. Centre is in natural condition, and also it is narrow but, there is scope for widening and regrading the drain.
- •Large number of utility crossing are noticed at many places in this reach

2.7 Condition Survey of Cross Drains :

During reconnaissance survey, the existing cross drains constructed across both primary and secondary storm drains, has been assessed for its structural and hydrological conditions. The details of these existing culverts/bridges is enclosed in Volume 2 - Condition Survey.


2.8 OBSERVATIONS DURING SITE INVESTIGATION OF LOW LYING AREAS IN CHALLAGHATTA VALLEY:

During reconnaissance survey of Challaghatta valley a detailed assessment of site conditions, reason for flooding and possible mitigative measures to overcome the flooding problems in low lying areas have been identified and the same is discussed in the subsequent sections.

The list of critical low lying areas identified in Challaghatta valley is as mentioned in Table -2.4 and the same is depicted in Figure 2.5

SI.No.	Location	Valley	BMP Division

 Table 2.4
 List of Critical Low Lying Areas in Challaghatta Valley



1	Vasanthanagar, near Millers Tank	Challaghatta Main Valley	East
2.	Shivajinagar	Challaghatta Main Valley	East
3.	Jogupalya - Saraswathipuram	Challaghatta Main Valley	East
4.	Murgeshpalya - K.R. Garden	Challaghatta Main Valley	East
5.	Munireddypalya	Ulsoor Valley	East
6.	Chinnappa Garden	Ulsoor Valley	East

2.8.1 Vasanthanagar, Miller tank & Shivajinagar (Ward No. 78 & 79):

Miller tank & Shivajinagar area is situated in Challaghatta valley. Challaghatta valley primary storm drain (C100) which flows through these localities, and due to the reasons mentioned below, it is causing localised flooding problems in these regions.

These localities are situated at the lower most portion of the valley and also comprises of dense residential buildings and commercial establishments on either side of the drain. The establishments which are situated close to the drain are severely affected even for small intensity of rainfall in these regions.

Reasons for flooding:

- •Due to large scale encroachment, natural alignment of existing primary storm drain has been altered at many places.
- •Due to conversion of Millers tank area into builtup / commercial area.
- •Foundation/Floor level of residential buildings in this layout is much below the existing drain bed level.
- •Existing storm water drain size inside dobhi ghat is inadequate to cater for both sewage and storm water.
- •The existing culvert near Miller's Road is inadequate (near Mount Carmal College Play Ground on Millers Road)

•Existing tertiary drains opposite to Aiyappa swamy temple and Thimmiah Road are not properly networked and also portion of the drain has been encroached.

•At some places tertiary drain does not exists in Vasanthanagar.

- •Large quantity of debris has been dumped into SWD near Ambedkar Bhavan, Mahaveer Jain hospital upto Millers tank bund Road and intern it is causing drastic reduction in the carrying capacity of the drain.
- •The approach bridge constructed across SWD by Karnataka Badminton Association & Indian Council of social welfare is obstructing free flow of water and also raw sewage that is generated is being discharged into SWD by Karnataka Badminton Association.
- •Construction of commercial shops over the drainage channel in Shivajinagar area has restricted the carrying capacity of the drain and also obstructing free flow of water.
- •Large Nos. of non functional sewer manholes and utility crossings which are noticed inside the drainage channel in Shivajinagar area is obstructing free flow of water.
- •Large Nos. of toilet blocks which have been constructed over SWD in Shivajinagar area is obstructing free flow of water and also discharging raw sewage into SWD.
- •Drain Size is drastically reduced near Shivajinagar Nala road and Market area.
- •Large quantity of sewage flow is noticed in the existing storm drain.
- •Large quantity of debris and garbage dump is noticed at many places inside the existing SWD.

2.8.2 Murgeshpalya - K.R. Garden Area (Ward No. 73):

K.R. Garden is located in Murgueshpalya near H.A.L. Airport in Challaghatta Valley. Where as, this Secondary drain (C101) starts from Jeevanbhimanagar and further traverses through Jagadeshnagar, Airport Road and Murgeshpalya before confluencing with Challaghatta Valley Primary Storm drain (C100) inside H.A.L. Airport premises. And also this locality is situated at the lower most portion of the valley.

This locality was recently developed by private land developers, without allowing, adequate space for providing basic amenities. This locality is a newly added ward to Bangalore Mahanagara Palike.

The existing secondary drain (C101) was flowing through this locality in natural condition, and also due to various reasons mentioned below it resulted in localised flooding of this locality and inturn causing sever inconvenience to the residents.

Reasons for flooding:

•Foundation/Floor level of residential buildings in this layout is much below the drain bed level.

•Improper drainage facilities.

- •Sewerage system has not been extended to the entire area.
- •Existing tertiary drains in Nanjareddy colony and Cauvery pura and K.R. garden area are inadequate.
- •Large quantity of debris and garbage dump is noticed at many places inside the existing SWD.

•Providing inadequate vent way in the compound wall of Airport for drain.

•Improper drainage arrangement inside Airport premises.

2.8.3 Jogupalya and Someshwarapura (Ward No.):

Jogupalya and Someshwarapura area are situated in Challaghatta valley. These localities are situated at the lower most portion of the valley and also comprises of dense residential buildings and commercial establishments on either side of the drain. The establishments which are situated close to the drain are severely affecting even small intensity of rainfall in these regions.

Reasons for flooding:

- •Due to large scale encroachment, natural alignment of existing storm drain has been altered at many places.
- •Existing tertiary drains at Jogupalya main road, and Someshwara pura are not properly networked and also inadequate.
- •Large quantity of debris has been dumped and siltation has occurred in tertiary drains and intern it is causing drastic reduction in the carrying capacity of the drain.

2.8.4 Munireddypalya and Chinnappa Garden (Ward No.):

Munireddypalya and Chinnappa garden area are situated in Ulsoor valley. Ulsoor valley primary storm drain (C200) flows through these localities. These localities are situated at the lower most portion of the valley and also comprises of dense residential buildings and commercial establishments on either side of the drain. The establishments which are situated close to the drain are severely affected even for small intensity of rainfall in these regions.

Reasons for flooding:

- •Due to large scale encroachment, natural alignment of existing storm drain has been altered at many places.
- •Sewerline and Manholes that are constructed inside the drainage channel are obstructing free flow of water.
- •The existing culverts near Krishnammanagar are inadequate and intern causing obstructing free flow of water..
- •Existing tertiary drains at Pemme gowda road, church street, chinnappa garden and Coles road in Frazer town are inadequate.
- •At some places tertiary drain does not exists in Munnireddy playa and Chinnappa garden.
- •Large quantity of debris has been dumped and siltation has occurred in tertiary drains and intern it is causing drastic reduction in the carrying capacity of the drain.
- •Large quantity of debris and garbage dump is noticed at many places inside the existing SWD.

2.9 Existing Operation and Maintenance Practice

During the last two years, BMP has undertaken desilting work of storm water drains on a large scale basis. BMP has set up an emergency squads at the central control room and service of this arrangement is made to be available round the clock. Further, this squad is equipped with truck mounted pumping arrangements and also at each zonal office an emergency telephone connections has been established for public connivence incase of any eventuality.

BMP has also improved the existing solid waste management system and intern this aspect has minimised the load on maintenance of storm drains to a certain extent and also increased the aesthetic appearance of drains at many locations.

BMP has also taken up projects like improvement of conservancies, foot paths, rejuvenation of parks, Swacha Bangalore and Nirmala Bangalore etc. this intern minimise the load of silt accumulation at tertiary drain level and also increase the aesthetic appearance of the city.

2.10 Quantity and Quality of Sewage

The watershed area within the city is having the major problem of domestic sewage and sullage getting into storm water drains contributing to the pollution of the Bellandur lake. Indescriminate dumping of solid waste on the land and also in the storm water drains is yet another cause for the pollution of the Bellandur lake.

The dry weather flow of sewage flow in Challaghatta main valley and Ulsoor valley is as mentioned in the table below Table:

Name of Valley	Min flow (MLD.)	Avg. Flow (MLD.)	Max. Flow (MLD.)
Challaghatta Valley	31.72	46.64	58.28

Results of Dry Weather Flow Measurements in Open Drains

Source: M/s. Pai Enron Technologies systems limited Bangalore, April 2002.

Parameters (mg/l.)	Challaghatta Valley
BOD ₅	780
SS	200
NO3	0.33

Concentration of Pollutants in Dry Weather Flow Drains

Remodelling of Primary and Secondary Storm Water Drains in Bangalore City Feasibility Report - Challaghatta Valley - Chapter.2

Parameters (mg/l.)	Challaghatta Valley
Р	8.835

CHAPTER 3

STORM WATER DRAINAGE SYSTEM DESIGN AND ANALYSIS

3.1 INTRODUCTION:

Application of concepts and methodologies of drainage design requires establishment of design parameters of the system considered for the design. Such parameters specifies the system performance with regard to various inputs. While the design concepts and methodologies are fairly general, design parameters are site specific.. Depending on the design objectives and the availability of supporting data, different design parameters may apply to each region, location and project. Various parameters that are considered and analysed are discussed here under:

3.2 DESIGN CRITERIA:

These include planning horizon, design period, catchment physical parameters, process parameters and meteorological parameters.

3.2.1 PLANNING HORIZON:

Ideally planning of storm drainage works may be implemented in two levels – planning for short term and the long term. Planning for short term considers the proposed development plans for immediate mitigative measure. Information pertaining to development plan includes population trends, comprehensive land use and zoning plan, location of future roads, airports, and industrial area which may affect the drainage design as well as jurisdictional division and financial arrangement. The long term planning process reflects the ultimate development anticipated over a period of time which may be as long as 25 to 50 years. But, these may not be feasible for well developed cities, to accommodate higher size drains in already developed layouts. Therefore, best alternate is to backfit the drain capacity with respect to the ground conditions and arrive at the suitable return period, which is acceptable.

3.2.2 **DESIGN PERIOD**:

Planning horizon reflects the envisaged land use projected for a certain number of years, the design period of drainage system indicates the expected levels of protection against such phenomena as flooding, health hazard or deterioration in the quality of receiving waters. Besides the desired level of protection, the design period depends on construction cost and damage (losses) resulting from system failures. The planning horizon may be linked to the longest design life of structures under design. Thus, while there is only one planning horizon for a drainage area, the design period may differ for the individual system components.

The TOR specifies that the acceptable design standards commensurate with the anticipated runoff volume in the next 20 years be determined in Phase-I. Thus, it is considered that the adequacy of the existing primary and secondary storm drains be studied, for the anticipated runoff rate over the next 20 years. This needs review in the context of the good conditions.

3.2.3 PHYSICAL PARAMETERS OF CATCHMENT:

Base maps showing the project area, topographical details like contour, water courses, tanks, wooded areas, rocky outcrops, marshes, etc., details of existing and proposed land uses, existing and proposed drains for establishing the study area drainage boundaries, general drainage pattern in these areas, surface slopes and total catchment area are developed. The catchment area is divided into pervious and impervious areas. In addition, the existing drainage channels in the catchment need to be characterized in terms of the cross sections, slopes, lengths, and linkages. The extent of development of the catchment has significant bearing on the runoff calculations.

3.2.4 PROCESS PARAMETERS:

These include infiltration rates, depression storage, roughness of transport elements and runoff coefficient. Generally, these parameters will be considered together as a lumped aggregate parameter.

3.2.5 METEOROLOGICAL DATA:

Important input for runoff computation is rainfall data. Rainfall data processing may be carried out by many approaches. Some of the methods are as listed and explained here under,

- 1. CPHEEO MANUAL
- 2. CALIFORNIA METHOD OF RANKING
- 3. GUMBEL'S DISTRIBUTION METHOD
- 4. LOG PEARSON TYPE III DISTRIBUTION

3.2.5.1 RAIN FALL ANALYSIS USING CPHEEO METHOD:

The analysis of frequency of storms of stated intensities and duration will be computed from the available rainfall data, for the period of past 25 years (i.e., from 1976 to 2001) and the same will be tabulated.

From the tabulated values, storm occurrences for the different years will be computed and time intensity values for these frequencies will be obtained by interpolation for storm occurring once a year, once in 2 years, once in 5 years, once in 10 years and once in 20 years.

Using log-log sheet, a graph has been plotted using the values of intensity (i), and duration (t) from the above tabulated values for calculating the storm occurrences for different return periods i.e., once a year, once in 2 years, once in 5 years, once in 10 years and once in 20 years respectively. From the best fit line, values a & n are obtained. Further the same is substituted in the equation below.

			а
	i	=	
			t ⁿ
where,	i	=	intensity of rainfall in mm/hr
	t	=	duration of storm in minutes
	a,b,n	=	constants as appropriate

After substituting values of a and n, different values of " i " for a various values of " t " are calculated and tabulated. A curve is plotted using an ordinary graph paper.

Another graph of runoff coefficients (c) v/s duration time (t) is plotted as per the values given in Horner's table (Table 3.3, Pg. No. 45 of CPHEEO Manuel).

3.2.5.2 RAIN FALL ANALYSIS USING RANKING METHOD:

The rainfall data for a period of 25 years is collected from Indian Meteorological Department (IMD). From the rainfall data, intensity of highest rainfall is considered in that particular duration and year which is arranged in descending order and the rank is assigned with a rank one to the highest value, a rank of two to the next highest value and so on. Whenever a particular value occurs more then once, all the values should have the same rank as they are equal. Further, recurrence interval or frequency corresponding to each rank can be calculated using a formula

$$N = T \times m$$

Where m is the number of times, given rain is equalled or exceeded and is known as the ranking of the storm or ranking number

Extracting rainfall of various duration for desired frequency further calculation of rainfall intensity in mm/hour has been done.

Using log-log sheet, graphs have been plotted using the values of intensity (i), and duration (t) from the above tabulated values for calculating the storm occurrences for different return periods i.e., once a year, once in 2 years, once in 5 years, once in 10 years and once in 20 years respectively. From the best fit curve, values a & n are obtained. Further, the same are substituted in the equation below.

			а
	i	=	 t ⁿ
where,	i	=	intensity of rainfall in mm/hr
	t	=	duration of storm in minutes
	a,b,n	=	constants as appropriate

After substituting values of a & n different values of 'i' for a various values of 't' are calculated and tabulated. A curve is plotted using an ordinary graph paper.

3.2.5.3 RAIN FALL ANALYSIS USING GUMBEL'S DISTRIBUTION METHOD:

The rainfall data for a period of 25 years is collected from IMD and the highest rainfall

intensity in that particular duration and year is considered and it is arranged in a sequential order. For each duration, the mean and standard deviation are calculated. Subsequently, the amount of rainfall for various duration and return period is calculated using the below equation.

$$X T = X + K Sx$$

- Where, X is the mean.
 - Sx is the standard deviation of the sample of extreme rainfall.
 - X_T is the rainfall amount which is equalled or exceeded on an average once in T years.
 - K is the frequency factor which can be expressed in terms of the return period T and the number of years of record N,The value of K can be obtained from standard table.

By substituting the values of X, Sx and K. The value of K can be obtained from standard table (from S.K Garg, Table 10.6) for N = 25 and return periods varying from 1 to 20 years.

Amount of rainfall obtained will be tabulated and further the same is converted into rainfall intensities and tabulated.

Using log-log sheet, a graph is plotted using the values of intensity (i), and duration (t) from the above tabulated values for calculating the storm occurrences for different return periods i.e., once a year, once in 2 years, once in 5 years, once in 10 years and once in 20 years. From the best fit curve, values a & n are obtained. Further the same is substituted in the equation below.

			а
	i	=	
			t ⁿ
where,	i	=	intensity of rainfall in mm/hr
	t	=	duration of storm in minutes
	a,b,n	=	constants as appropriate

After substituting values of a & n, different values of i for various values of 't' are calculated and tabulated, a graph is plotted on an ordinary graph sheet.

Values obtained from the above three methods are compared with other design parameters which is suitable for the present site conditions and that method is adopted for computing storm water runoff.

3.2.6 STRUCTURAL DESIGN PARAMETERS :

Parameters and standards considered for design of sub structures, super structures and cross drainage works are as follows;

- 1.The structures are categorized as per Table-5B of IRC : 21-2000. Since the materials used are RCC, PCC and Stone masonry and in case of bridges total length is generally less than 60 m. In case the total length of the bridge is more than 60 m or any innovative design approach is adopted the same is categorized as per Table-5A of IRC : 21-2000.
- 2.For design purposes the condition of exposure is considered as SEVERE. Since the structures are in contact with untreated sewage and drainage effluent.
- 3. The following materials are proposed to be used in the structures.

i.Minimum Grades of Concretes used are as below

- •M15 In levelling course below RCC, PCC & Stone masonry foundations, pile caps, approach slabs and in footpath fillings.
- •M20 In PCC structural elements like retaining walls & abutments
- •M25 In kerbs, hand rail, and posts, approach slab, retaining walls, piers, pile caps and abutments.
- •M35 In crash barriers, super structures, box culverts & piles etc.

•Maximum water cement ratio shall be 0.45.

- ii.Grade of steel to be used is Fe 415.
- iii.Course rubble stone masonry for bridge works such as abutments.
- iv.Random rubble stone masonry for retaining structures other than bridge abutments.
- v.CM 1:3 for stone masonry.
- vi.PVC pipes for weep holes in retaining walls and provision for service lines in superstructure.

vii.Elastomeric bearings for beam and slab type superstructure.

- viii.Compression seal expansion joint for joints along longitudinal direction in carriage way portion of superstructure.
- ix.PVC water bar type expansion joint for superstructures with beam and slab arrangement.
- x.Premoulded bitumen filling joint for solid slab type superstructures covering full depth.
- xi.Premoulded bitumen filling joint for retaining walls.
- xii.Asphalted concrete wearing coat over mastic asphalt.
- xiii.Back filling behind abutments, returns and retaining walls shall be with granular materials with soil as per Appendix-6 of IRC : 78-2000.
- xiv.GI drainage spouts as per drawings.
- 4. Minimum dimensional requirements:
- i.Levelling course 100 mm. thick below RCC / PCC foundations.
 - 300 mm. thick below stone masonry foundations on soil base.
 - 150 mm. thick below stone masonry foundations on rock base
 - 150 mm. thick below approach slabs.
- ii.Walls 200 mm. thick for RCC / PCC walls.
 - 500 mm. thick for stone masonry walls.
- iii.Wearing coat on deck slabs shall be 50 mm. thick asphalted concrete in two layers of 25 mm. each over 6 mm. thick mastic asphalt. Thickness of asphalted concrete shall be varied suitably to achieve the slopes for camber or super elevation.
- iv.Normal camber considered is 2.5 %.
- v.Weep holes with PVC pipes (100 mm. dia. in RCC and 150 mm. dia. in stone masonry) shall be used in retaining structures including abutments and retaining walls. The spacing of weep holes shall be 1.0 m. in either direction in staggered way, with lowest at about 150 mm. above the low water level or ground level which ever is higher. (MOST Spec. : 2706).
- 5.Loading :

Density of PCC	=	2.2 t/m ³
RCC	=	2.4 t/m ³

Stone masonry		=	2.21	t/m ³	
Back filling		=	2.0 t/m ³		
	i.Load due to wearing coat	=	0.21	t/m ²	
	ii.Load due to crash barrier	=	0.8	t/m O	n each side.
	iii.Load due to hand rail and kerb		=		0.95 t/m On each side.
	iv.Load due to services in footpath	ı	=		0.1 t/m On each side.
	v.Foot path live load		=		0.5 t/m ² On each side.

vi.Vehicle live loads are as per clause 207.4, Table-2 of IRC:6-2000 for different carriage ways.

vii.Load due to water current as per clause 213 of IRC : 6 -2000.

viii.Live load surcharge is 1.2 m height of back fill.

ix.Buoyancy force as per clause 216 of IRC : 6-2000.

- x.One span dislodged condition is not considered in the case of slab bridges not provided with bearings. (As per clause 221.1 of IRC : 6-2000.)
- xi.Seismic forces are not considered as the structures are located in Seismic Zone-1. (As per clause 222.1 of IRC : 6-2000.)

6.Miscellaneous details :

- i.Bridges or culverts with out footpath are provided with crash barrier / Hand rail.
- ii.Bridges or culverts with footpath are provided with hand rails as per SD/202 of MOST STD drawing with or with out crash barrier at the edge of carriage way.
- iii.Drainage spouts in the superstructure of the bridge or culverts are as per SD/205 of MOST STD drawing.


3.3 CATCHMENT ANALYSIS:


To study the hydrological conditions and drainage characteristics of the Challaghatta valley catchment the following analysis procedure has been adopted

- Identification of ridge line and demarcation of catchment boundary.
- Demarcation of primary and secondary valleys.
- Demarcation of entire catchment into micro/sub catchments.
- Identification of flow regions within micro catchments.
- Codification of flow regions.
- Characterization of the entire catchment in terms of landuse categories.
- Identification of open and closed reach of drains.
- Assignment of the degree of imperviousness to rainfall for the above categories.
- · Computation of weighted average imperviousness for each of the flow region.

The ridge lines of the Challaghatta valley catchment are demarcated based on the available 10 m. interval elevation contour information in the survey of India 1:20,000 scale topo map for Bangalore city. On which the valley lines and the local ridge lines are identified to demarcate the sub catchments and flow regions. These details prepared on 1: 20000 scale map are digitized to generate a vector layer in Arcview GIS as line coverage as well as polygons coverage. After the transformation of the coverages with reference to the map used for digitization, various attribute details on length of arcs and area of polygons are analyzed to obtain the length both primary and secondary drains and area of catchment, sub catchment and micro catchment and the same is also indicated in Figure 3.1 & 3.2.

Further, to calculate the inlet time and time of concentration the sub/micro catchments are segmented into different flow regions based on terrain slope and other aspect derived from contour information. The area details of the micro catchments codes, flow regions, land use characteristics in Challaghatta main valley and Ulsoor valley are provided in Table – 3.1 to Table - 3.4.





SI. No.	Micro Catchment Code	Area (Ha.)
1	A 1	144.60
2	A 2	159.57
3	A 3	384.25
4	A 4	591.41
5	A 5	402.70
6	A 6	396.39
7	Α7	526.52
8	A 8	561.38
	TOTAL	3166.82

Table 3.1 CHALLAGHATTA VALLEY MICRO CATCHMENT CODE

Table 3.2 CHALLAGHATTA VALLEY FLOW REGION CODE

SI.No.	Flow Region Code	Area (ha.)
1.	A1 (a)	95.38
2.	A1 (b)	49.22
3.	A2 (a)	59.93
4.	A2 (b)	99.64
5.	A3 (a)	217.10
6.	A3 (b)	167.15
7.	A4 (a)	105.52
8.	A4 (b)	239.34
9.	A4 (c)	87.64
10.	A4 (d)	158.91
11.	A5 (a)	129.91
12.	A5 (b)	272.79
13.	A6 (a)	133.90
14.	A6 (b)	62.70
15.	A6 (c)	199.79
16.	A7 (a)	174.05
17.	A7 (b)	189.04
18.	A7 (c)	163.44
19.	A8 (a)	165.60
20.	A8 (b)	143.42
21.	A8 (c)	105.20
22.	A8 (d)	147.17
	TOTAL	3166.82

SI.No.	Micro Catchment Code	Area (ha.)
1.	A 1	238.27
2.	A 2	68.53
3.	A 3	46.46
4.	A 4	78.01
5.	A 5	38.00
6.	A 6	162.42
7.	A 7	78.06
	TOTAL	709.74

Table 3.3 ULSOOR VALLEY MICRO CATCHMENT CODE

Table 3.4 ULSOOR VALLEY FLOW REGION CODE

SI.No.	Flow Region Code	Area (ha.)	
1.	A 1 (a)	26.26	
2.	A 1 (b)	171.15	
3.	A 1 (c)	40.85	
4.	A 2	68.53	
5.	A 3 (a)	29.53	
6.	A 3 (b)	16.93	
7.	A 4	78.01	
8.	A 5	38.00	
9.	A 6	162.42	
10.	A 7	78.06	
	TOTAL	709.74	

Using digital image processing technique and also by visual interpretation, satellite image is used to analyze the catchments and categorise the same for various landuse categories as listed below and further at strategic locations the processed results are cross verified at site and accordingly range of percent imperviousness is assigned for each category.

- 1. Highly / Dense built up area with sparse vegetal cover
- 2. Dense built up area with medium / thick vegetal cover
- 3. Built up area with more open space as well as fairly dense vegetal cover
- 4. Open space with no vegetal cover / Open space with scrubs and other vegetation
- 5. Parks
- 6. Water bodies

Further, in order to compute the weighted average percent imperviousness for each, the highest runoff percent imperviousness assigned is 80 - 95 % for the land where settlement density is very high (>90%) and all roads are paved. The lowest runoff percent imperviousness assigned is 5 -20 % for parks with medium dense vegetation. The details of area and assigned percent imperviousness is shown in Table - 3.5.& 3.6.

In order to compute the weighted average percent imperviousness for each flow region, intersection of flow region boundaries with settlement density boundaries is done. A composite plans for Challagatta main valley and Ulsoor valley are generated by incorporating the drainage lines, ridge lines, flow region boundaries and the landuse and land cover categories and the same is indicated in Figure 3.3 & 3.4.

The weighted average percent imperviousness (IW) for each flow region is computed and is given by


$$IW = \frac{I_1 A_1 + I_2 A_2 + I_3 A_3 + I_4 A_4 \dots}{A_1 + A_2 + A_3 + A_4 \dots}$$


where, I_1 , I_2 , I_3 , I_4 are assigned imperviousness (%) for each of the land cover category within the flow region and A_1 , A_2 , A_3 , A_4 are the corresponding areas.

TABLE 3.5 CHALLAGHATTA VALLEY LAND COVER CHARACTERISTICS

SI.No.	Land Cover Characteristics	Area (ha)	Assigned % Imperviousness
1.	Highly / Dense built up area with sparse vegetal cover	1548.96	75 – 90
2.	Dense built up area with medium / thick vegetal cover	328.62	65 – 80
3.	Built up area with more open space as well as fairly dense vegetal cover	606.70	45 – 60
4.	Open space with no vegetal cover / Open space with scrubs and other vegetation	212.58	10 – 25
5	Parks	405.57	05 – 20
6	Water Bodies	64.40	
	Total	3166.82	

Table 3.6 ULSOOR VALLEY LAND COVER CHARACTERISTICS





SI.No.	Land Cover Characteristics	Area (ha)	Assigned % Imperviousness
1.	Highly / Dense built up area with sparse vegetal cover	333.96	75 – 90
2.	Dense built up area with medium / thick vegetal cover	91.82	65 – 80
3.	Built up area with more open space as well as fairly dense vegetal cover	135.00	45 – 60
4.	Open space with no vegetal cover / Open space with scrubs and other vegetation	119.72	10 – 25
5	Parks	23.55	05 – 20
6	Water Bodies	5.70	
	Total	709.74	

3.4 DESIGN PROCEDURE:

3.4.1 GENERAL:

Having understood the site conditions and terms of reference it is proposed to adopt the approach, philosophy of which revolves around 4 cardinal points viz.:

- 1. Understanding the project requirements and the accomplishment of the overall objective of the project.
- 2. Appreciation of the various factors that help or hinder the overall objective of the project both from the review of available documents and a field visit to support the overall objective.
- Ensuring ways and means of assuring quality of the contract deliverables taking into considerations the factors – efficiency of function, economy of implementation, ease of construction and recognising the link of designsoperations interactions.
- 4. Ensuring quality assurance in the materials and methods of execution including modern methods of construction for early completion of the works.

And also review of available data through site appreciation leads us to formulate the method of working to ensure:

•High degree of professional standards in designing the components.

•Clear detailing that will facilitate working and

•Quality assurance in the contract deliverables.

•Quality assurance in execution of contract.

In order to accomplish these objectives, following issues need to be addressed, as applicable for each of the three stages of the project Viz. Feasibility report, Detailed Project Report and Construction Supervision.

3.4.2 STORM WATER RUNOFF:

The storm water run off is the balance of rain water precipitation on the ground which flows in drains after a part of storm water getting infiltration into the soil, retention in surface depressions and evaporated. The rate of storm water run off to be used for design of storm sewers is complex to evaluate accurately. The rate of precipitation which causes the runoff is highly variable from place to place even within a smaller region of the City. The rainfall recording stations from which the intensity of precipitation and duration of rain fall is obtained for the design of storm water drains in many instances are remotely located from the area where the storm water drain has to be designed. The geological formation of the sub-surface will also be varying and estimations of these losses are complex. Numerous empirical runoff formulae had been used for estimation of storm water runoff. Some of the methods adopted are:

1.1.Rational method (Lloyd-Davis method evolved in the United Kingdom).

1.2.Hydrographs {Over-land Flow) method.

1.3.Inlet Method.

1.4.Unit Hydrograph method.

Out of the above methods, the rational method is widely used throughout the World. More than 90% of the Engineering offices through out the United States have confirmed in a questionnaire in the year 1956 with the rational method of design has given satisfactory results for urban drainage areas. The Ministry of Urban Development, Government of India, New Delhi, Central Public Health and Environmental Engineering Organization, has also recommended the estimation of storm water runoff by rational method.

3.4.2.1. RATIONAL METHOD:

The entire precipitation over the drainage district does not reach the storm water drains. The characteristics of the drainage district such as imperviousness, topography including depressions and water pockets, shape of the drainage basin and duration of the precipitation determine the function of the precipitation, which will reach the drain. This fraction known as the coefficient of runoff needs to be determined for each drainage district. The runoff reaching the drain is given by the expression,

Where, 'Q' is the runoff in m³/hr;

'C' is the coefficient of runoff;

- 'i' is the intensity of rainfall in mm/hr. and
- 'A' is the area of drainage district in hectares.

3.4.3. STORM FREQUENCY:

Urban storm drains are generally designed based on the concept of the design storm of a selected return period. In general the selection of the design event return period is affected by the design life of structures involved, construction cost and damage cost resulting from the system failure. Drainage structures are typically characterized by long design life and so the ideal design period should be one for which the total annual drainage costs, defined as the sum of annual construction and drainage failure costs are minimal.

While the foregoing may be true for major system, urban storm drainage system being minor system does not warrant a detailed analysis of construction and failure costs but must evaluate acceptable risk caused by the failure of the system, depending on whether it is a major or minor drainage system.

Major drainage system comprises natural streams and valleys as well as man made elements such as swales, channels, and ponds. The system should accommodate runoff from infrequent storms with long return periods. Damage caused by the failure of a major drainage system and the associated risks are loss of agricultural yield, damage to properties and even loss of life. Minor drainage system consists of swales, streets gutters, catch basis, storm sewers and surface and subsurface detention facilities. The minor system, designed to convey runoff from frequent storms with return periods i.e. from one to two years, primarily reduces the frequency of inconvenience caused by storm water ponding to both pedestrians and motorists. The consequences of failure of minor drainage are often insignificant provided the connected major drainage system is properly functioning.

Thus the selection of design return period for urban storm drain depends on the importance of area to be drained. Commercial and industrial areas have to be subjected to less frequent flooding. Manual on Sewerage and Sewage Treatment by the Ministry of Urban Development recommend the following:


•Residential area and Peripheral areas	Twice a year
 Central and high priced areas 	Once a year
 Commercial and high period areas 	Once in two years.

3.4.4 INTENSITY OF PRECIPITATION:

The intensity of rainfall decreases with duration. Analysis of the observed data on intensity duration of rainfall of past records over a. period of years in the area is necessary to arrive at a fair estimate of intensity - duration for given frequencies. The longer record available, the more dependable is the forecast. In Indian conditions, intensity of rainfall adopted in design is usually in the range of 12 mm./hr. to 20 mm./hr. Rainfall data over a period of 25 years is collected and considered.

Frequency of storms of intensities 10 mm./hr to 120 mm./hr. for duration of 5 min. to 120 min. are tabulated, and the number of storms that had occurred for the stated intensities and duration for the desired frequency of storms (once in a year and once in two years) are considered.

The relationship between intensity and duration of storm may be expressed by a suitable, mathematical formula, several forms of which are available. The following two equations are commonly used.



The available data on 'i' and 't' are plotted and the values of the intensity (i) can be determined for any given time of consideration, (t_c).

3.4.5. TIME OF CONCENTRATION:

It is the time required for the rain water to flow over the ground surface from the farthest point of the drainage basin to reach the point under consideration. Time of concentration (t_c) is equal to inlet time (t) plus the time of flow in the drain (t). The inlet time is dependent. on the distance of the farthest point in the drainage basin to the inlet of the drain, the shape, characteristics and .topography of the basin may generally vary. The time of flow is determined by the length of SWD and the velocity of flow in the SWD. It is to be computed for each length of SWD to be designed.

3.4.6. COEFFICIENT OF RUNOFF:

The portion of rainfall which finds its way to the drain is dependent on the imperviousness and the shape of tributary area, apart from the duration of storm.

1) Imperviousness:

The percent imperviousness of the drainage area can be obtained from the records of a particular district. In absence of such data, the following may be serve as a guide.

Type of Area

Percentage of Imperviousness

Feasibility Report - Challaghatta Valley - Chapter.3

Commercial and industrial area	70 to 90
Residential area:	
•High density	60 to 75
•Low density	35 to 60
Parks and undeveloped areas	10 to 20

The weighted average imperviousness of drainage basin for the flow concentrating at a point may be estimated using

 $I = (A_1I_1 + A_2I_2 + \dots) / (A1 + A2 + \dots)$

Where, A_1 , A_2 =	Drainage areas tributary to the section under
	consideration

 I_1, I_2 = Imperviousness respective areas and

I = Weighted average imperviousness of the total drainage basin.

3.4.7. TRIBUTARY AREA:

For each length of storm sewer, the drainage area should be indicated clearly on the map and measured. The boundaries of each tributary are dependent on topography, land use, nature of development and shape of the drainage basins. The incremental area may be indicated separately on the compilation sheet and the total area computed.

3.4.8. DURATION OF STORM:

The concept of design storm is developed to account for the time varying rainfall input as against the constant intensity design rainfalls. The assumption made in this concept is that the return period of the calculated runoff event is identical to the design storm.

For selected return period, the design storm is characterized by the duration, total amount of rainfall, the maximum rainfall intensity of a certain short duration, the timing of peak intensity and temporal storm rainfall distribution.

Continuously long light rain saturates the soil and produces higher coefficient than that of heavy rainfall for shorter duration. But intermittent rains in the same area causes lesser saturation in the latter case. Runoff from an area is significantly influenced by the saturation of the surface nearest the point of concentration, rather than the flow from the distant area. The runoff coefficient of a larger area has to be adjusted by dividing the area into zones of concentration and by suitably decreasing the coefficient with the distance of the zones.

3.4.9. COMPUTATION OF RUNOFF COEFFICIENTS:

The weighted average runoff coefficients for rectangular areas of length four times the. width as well as for sector shaped areas with varying percentages of impervious surface for different times of concentration are given in Table 3.7. Although these are applicable to particular shapes of areas, they also apply in a general way to the areas which are usually encountered in practice. Errors due to difference in shape of drainage are within the limits of accuracy of the rational method and of the assumption on which it is based.

Duration t,	10	20	30	45	60	75	90	100	120	135	150	185
minutes												
Weighted												
average												
coefficients												
1. Sector												
concentrating												
in stated time												
a) Impervious	.525	.588	.642	.700	.740	.711	.795	.813	.828	.840	.850	.865
b)60%	.365	.427	.477	.531	.569	.598	.622	.641	.656	670	.682	.701
impervious												
c)40%	.285	.346	.395	.446	.482	.512	.535	.554	.571	.585	.597	.618
Impervious												
d) Pervious	.125	.185	.230	.312	.312	.330	.362	.382	.399	.414	.429	.454
2. Rectangle												

TABLE – 3.7 Table of CPHEEO Manual - Runoff Coefficient

STUP Consultants P. Ltd.

(length = 4 x width) Concentrating in stated time												
a) Impervious	.550	.648	.711	.768	.808	.837	.856	.869	.879	.887	.892	.903
b)50% Impervious	.350	.442	.499	.551	.590	.618	.639	.657	.671	.683	.694	.713
c)30% Impervious	.269	.360	.414	.464	.502	.530	.552	.572	.588	.601	.614	.636
d) Pervious	.149	.236	.287	.334	.371	.398	.422	.445	.463	.479	.49	.522

3.5. HYDRAULICS OF STORM DRAIN:

Flow capacity of open channels is calculated for each stretch of drain of different bed slope using Manning's formula.

$$V = [(I/n)] \times [R^{2/3} S^{1/2}]$$

The Mannings co-efficient 'n' for various drain surfaces are Masonry;

0.013
0.015
0.014
0.015
0.017
0.020

Stone work;(a) Smooth, dressed ashlar	0.015
(b) Rubble set in cement	0.017
(c) Fine, well packed gravel	0.020

Earth;	(a) Regular surface in good condition		0.020
(b) In-o	rdinary condition	0.025	
(c) With	stones and weeds	0.030	
(d) ln p	oor condition	0.035	
(e) Par	ially obstructed with debris or weeds	0.050	

3.5.1 RATIONAL METHOD:

The Rational method is based on the following assumptions :

- 1)The peak rate of runoff at any point is a direct function of the average rainfall intensity during the time of concentration to that point.
- 2)The frequency of the peak discharge is the same as the frequency of the average rainfall intensity. The time of concentration is the time required for the runoff to become established and flow from the most remote part of the drainage area to the point under design.

The later assumption applies to the part most remote in time, not necessarily in distance. In the rational method, average intensities have no time sequence relation to the actual rainfall pattern during the storm. The intensity duration curve used in this method is not a time sequence curve of precipitation.

The determination of values for the coefficient of runoff is difficult because this factor must represent many variable including infiltration, ground slope, ground cover, surface and depression storage, antecedent precipitation and soil moisture, shape of drainage area, overland flow velocity, etc.

AREA;

The area of tributary to any point under consideration in a storm-sewer system must be determined.

Boundaries of the drainage area may be established by field surveys or from suitable maps or aerial photographs.

The complete drainage area is subdivided into sub-catchments and further into micro catchments for each tributary upto the point of inlet. This requires a preliminary layout of the system and tentative location of inlet point. Rearrangement of the system layout or of inlet location often is indicated as design proceeds. This requires reorganisation of component parts of the main drainage area to conform to the system layout and inlet scheme finally adopted.

3.5.2RAINFALL:

(a) Rainfall intensity factor, Determination of rainfall intensity, ' i ' for storm-sewer design involves consideration of the following factor:

- 1. Average frequency of occurrence
- 2.Intensity duration characteristic of rainfall for selected average frequency of occurrence.
- 3. Time of concentration.

b) Rainfall frequency: The average frequency of rainfall occurrence used for design determines the degree of protection afforded by a given storm drain system. This protection should be consistent with the amount of damage prevented. But in practice, cost-benefit studies usually are not conducted for the ordinary urban storm drainage project. Judgement supported by records of performance in other similar areas is usually basis of selected frequency.

The range of rainfall frequency used in engineering practices is as follows:

- 1)For storm drains in residential areas, 2 to 15 years with 5 year most commonly reported.
- 2)For storm drains in commercial and high value districts, 10 to 50 years, depending on economic justifications.
- 3)For flood protection works, 50 years or more

In the analysis of point rainfall intensity-duration data, there are two approaches, the annual duration and partial-duration series. In the annual duration series, for each duration selected, the heaviest rainfall that occurred in each year is listed, with no tabulation of lesser intensities during the same calendar year, even though some of them might be greater than rainfall intensities that occurred in other years of record. The first of these methods gives the probability of occurrence that the maximum rainfall in anyone year for a specified duration will equal or exceed in given intensity. In the other treatment of the data, partial duration series, all rainfall intensities above a practical minimum for each duration for the entire period of record are included. The second method gives the frequency or the number of occurrences in a given period of time that a rainfall of given intensity and duration will be equal or exceeded.

Sherman has injected the concept of "extended duration" which has been used widely and is recommended for developing rainfall intensity frequency data. In this method, if the total precipitation in a storm is sufficient to show significant average rates for periods longer than the actual duration of the rainfall, such storms are included in the data compilations as multiple events as though they had continued for the longer times. For example, a rainfall amount for an actual 50 min storm would be listed not only as a 50-min storm with its corresponding intensity, but also as a 60-min or 90-min, or longer duration storm with a corresponding lesser intensity.

Table -	Empirical Factors for Converting Annual-Duration Series to
	Partial-Duration Series

Return Period (Years)	Multiplier
2	1.14
5	1.04
10	1.01

Time of Concentration - An estimate of the time of concentration to the point under consideration is made so that the average rainfall rate may be determined. For urban storm sewer the time of concentration consists of the inlet time plus the time of flow in the sewer from the most remote inlet to the point under consideration.

Time of flow in the sewer may be estimated closely from the hydraulic properties of the conduit. Inlet time is the overland flow time for runoff to reach established surface drainage channels such as street gutters and ditches and travel through them to the point of inlet.

Inlet time will vary with surface slope, nature of surplus cover, and length of path of surface flow, as well with the variables influenced by antecedent rainfall intensity and duration such as infiltration capacity.

3.5.3 RUNOFF COEFFICIENTS:

General Considerations.- The run coefficient, C, is the variable of. the rational method least susceptible to precise determination. Its use in the formula implies a fixed ratio for any given drainage area, whereas, in reality, the coefficient accounts for abstractions or losses between rainfall and runoff which may vary for a given drainage area as influenced by differing climatological and seasonal conditions.

These losses, together. with their order of magnitude as observed by various investigators include:

- 1)Interception by vegetation. This is not usually significant in urban drainage but may range from 0.01 to 0.5 in. (0.03 to 0.13 cm.) in forest areas, depending on type of cover.
- 2)Infiltration into permeable soils. The ability of a soil to absorb water and percolate it to deeper groundwater is affected by certain events before and during a given storm, such as compaction of the surface, in-washing of finer sediments, and swelling of clays or colloidal soils. The Hydrology Handbook gives the following range of value of infiltration capacity. If various types of bare soils after 1 hr. of continuous rainfall.

Soil Group	Infiltration (In./hr.)
High (sandy, open structured)	0.50 to 1.00
Intermediate (loam)	0.10 to 0.50
Low (clay, dense structured)	0.01 to 0.10

Note: In. x 2.54 = cm.

The hand book also notes the profound influence of ground cover showing that bare-soil infiltration capacity can be increased from 3 to 7.5 times with good permanent forest or grass cover, ranging down. to little or no increase with poor row crops. Antecedent precipitation also affects soil infiltration capacity, but few quantitative data are available to evaluate this factor.

Retention in Surface Depressions.- The excess rainfall fills depressions essentially present in all surfaces. Retention in forest litter may be as much as 0.3 in. (0.08 cm.): in good pasture, 0.2 in. (0.05 cm.): and in smooth cultivated land, 0.05 to 0.10 in. (0.13 to 0:3 cm.). In urban areas of moderate grade, recent gauging shows retention to be about 0.05 in. (0.13 cm.) for impervious surfaces. Retention has been assumed to be 0.10 in. (0.3 cm) for surfaces such as lawns and normal urban pervious surfaces.

Evaporation and Transpiration - These are of little significance for the short rainfall duration encountered in urban storm drainage design.

Average Coefficients.- The use of average coefficients for various surface types, which are assumed not to vary through the duration of the storm is common.

The range of coefficient, classified with respect to the general character of the tributary area reported in use is :

Description of Area	Runoff coefficients
Business	
Down Town	0.70 to 0.95
Neighbourhood	0.50 to 0.70
Residential	
Single Family	0.30 to 0.50
Multi-Units, detached	0.40 to 0.60
Multi-Units, attached	0.60 to 0.75
Residential (Suburban)	0.25 to 0.40
Apartment	0.50 to 0.70
Industrial	
Light	0.50 to 0.80
Heavy	0.60 to 0.90
Parks, Cemeteries	0.10 to 0.25
Playgrounds	0.20 to 0.35
Railroad yards	0.20 to 0.35
Unimproved lands	0.10 to 0.30

It often is desirable to develop a composite runoff coefficient based on the percentage of different types of surface in the drainage area. This procedure often is applied to typical "sample" blocks as a guide to selection of reasonable values of the coefficient for an entire area. Coefficients with respect to surface type currently in use are:

Character of Surface	Runoff Coefficients
Pavement	
Asphaltic and Concrete	0.70 to 0.95
Brick	0.70 to 0.85
Roofs	0.75 to 0.95
Lawns, sandy soil	
Flat, 2 percent	0.05 to 0.10
Average, 2 to 7 percent	0.10 to 0.15
Steep, 7 percent	0.15 to 0.20
Lawns, heavy soil	
Flat, 2 percent	0.13 to 0.17
Average, 2 to 7 percent	0.18 to 0.22
Steep, 7 percent	0.25 to 0.35

The coefficient in these two tabulations are applicable for Storms of 5 to 10 years frequencies. Less frequent, higher intensity storms will require the use of higher

coefficients because infiltration and other losses have a proportionally smaller effect on runoff. The coefficient based on the assumption that the designs storm does not occur when the ground surface is frozen.

3.6. APPLICATION OF RATIONAL METHOD:

After the items discussed in the proceeding sections have been determined or estimated, a tentative arrangement of the proposed system including the location of inlets is made to permit division of the whole drainage area into sub districts tributary to sections of the storm sewer system.

Coefficients are selected or estimated which are appropriate for the land use and development expected at the end of the period of design.

Rainfall frequency consistent with degree of protection desired is selected and intensityduration curves for the locality are developed from available rainfall records or from such other data as may be available (6).

Many designers find it convenient to reduce the rainfall – intensity relationship to a family of curves of runoff for rainfall intensities of selected frequencies. Such curves indicate the product of the runoff coefficient and average rain intensity (18). Other designers suggest weighing the size of the areas to reflect the variation imperviousness of individual sub areas from the average imperviousness of the project area. The weighted area size then is applied to the runoff curve developed for the average degree of imperviousness.

3.7 PROCESSING OF RAINFALL DATA:

Estimation of storm run-off depends on many factors and is difficult to evaluate accurately. It however demands a study of rainfall data for the past few years with regard to intensity and duration of each spell etc. Indian Meteorological Department, (IMD) Bangalore was contacted to furnish the rainfall data and they made available rainfall data i.e. intensity and duration at 15 minutes intervals for the years 1976 to 2001 (25 years) and it was possible to carry out the analysis of the frequency of storms of stated intensities and durations. In general there are two approaches in the analysis of rainfall intensity - duration data viz., (1) Annual - duration. series and (2) Partial - duration series. In partial - duration series, all rainfall intensities above a practical

minimum for each duration for the entire period of record are included and hence this series is adopted for the analysis with the concept of "extended duration" as recommended by American Society of Civil Engineers manual. Due to practical limitations IMD have not been able to give the amount of spells less than 15 minutes for longer duration of rainfalls i.e. for 5 and 10 minutes durations, having higher intensities. As this is an essential data, corresponding higher intensity rainfall for lesser duration of 5 and 10 minutes was computed, from the available heaviest rainfall. in 15 minutes. The occurrence values thus arrived at are plotted on a graph paper against the time duration for various intensities of rainfall viz. 15 mm/hr to 240 mm/hr., are plotted on graphs, and the line of best fit is drawn for each curve of Occurrence vs. Duration. From these lines of best fit marked in the graphs of each intensities, the frequency of storms for different stated duration are finally derived.

Table – 3.8 gives the analysis of the frequency of storms of stated intensities anddurationduringthepast25years.

Table 3.8

	Duration (t) in minutes						
Intensity (i) mm/hr.	One year storm	Two year storm	Five year storm	Ten year storm	Twenty year storm		
	(i.e. 25 times)	(i.e. 12.5 times)	(i.e. 5 times)	(i.e. 2.5 times)	(i.e.1.25 times)		
15	123.75	202.50	-	-	-		
20	101.25	155.63	202.50	-	-		
25	65.63	106.88	165.00	217.50	236.25		
30	51.00	77.50	120.00	187.50	206.25		
35	39.38	69.38	112.50	157.50	176.25		
40	30.00	57.50	97.50	127.50	146.25		
50	23.75	55.86	75.00	108.75	118.13		
60	-	34.39	67.50	92.50	98.75		
70	-	16.00	30.00	48.75	58.13		
80	-	-	24.00	37.50	51.63		
90	-	-	18.75	28.00	41.25		
100	-	-	-	18.75	28.13		
120	-	-	-	-	-		

Table 3.9 Time intensity values of storms

The time intensity values for these frequencies are obtained by interpolation and given in Table 3.9, for storm occurring once a year, once in 2 year, once in 5 year, once in 10 year & once in 20 years.

A graph (Fig. 3.5 to 3.9) is plotted using the values of 'i' and 't' from Table-3.9 for once a year, once in two years and once in five years storms on a log-log paper. As per central Public Health and Environmental Engineering organisation (CPHEEO) manual guidelines, once a year frequency of storm is considered for central and comparatively high priced areas, for commercial areas once in two years frequency of storm is to be considered. In addition once in five years, ten year and twenty year frequency is also considered for checking, the adequacy of culverts and the adequacy of drain reach near flood prone areas.

The generalised formula adopted for intensity and duration is :

		i	a = t ⁿ	
Where,	i	=	intensity of	f rainfall in mm/hr
	t	=	duration of	f storm in minutes
a,b,n	=	constants as appropriate		

From the line of best fit marked in the graph (Fig. 3.5 to 3.9) the values of 'a' and 'n' are found out for one, two, five, ten and twenty year storms. From the plotted best fit line, values of 'a' and 'n' are obtained:

- (i) a = 414.25 and n = 0.673 for storm once a year.
- (ii) a = 511.91 and n = 0.6399 for storm once in two years,
- (iii) a = 570.75 and n = 0.5987 for storm once in five years.
- (iv) a = 568.72 and n = 0.5476 for storm once in ten years.
- (v) a = 976.47 and n = 0.6442 for storm once in twenty years.

Now using the above equation and substituting, the values of 'a' and 'n', different values of 'i' for various values of 't' are calculated and tabulated in Table 3.10.

Duration "t"	Intensity (i) = a / t ⁿ (mm/hour)							
in minutes	One year storm	Two year storm	Five year storm	Ten year storm	Twenty year storm			
	(i.e. 25 times)	(i.e. 12.5 times)	(i.e. 5 times)	(i.e. 2.5 times)	(i.e. 1.25 times)			
	a = 414.25	a = 511.91	a = 570.75	a = 568.72	a = 976.47			
	n = 0.673	n = 0.6399	n = 0.5989	n = 0.5474	n = 0.6442			
5	140.23	182.78	217.69	235.66	346.24			
10	87.96	117.30	143.73	161.25	221.54			
15	66.95	90.49	112.74	129.15	170.62			
20	55.17	75.28	94.90	110.34	141.75			
25	47.47	65.26	83.03	97.65	122.77			
30	41.99	58.07	74.44	88.37	109.17			
45	31.96	44.80	58.39	70.78	84.07			
60	26.34	37.27	49.15	60.47	69.85			
75	22.66	32.31	43.00	53.52	60.50			
90	20.05	28.75	38.55	48.43	53.79			
105	18.07	26.05	35.15	44.51	48.71			
120	16.52	23.92	32.45	41.38	44.69			
135	15.26	22.18	30.24	38.79	41.43			
150	14.22	20.74	28.39	36.62	38.71			
165	13.33	19.51	26.82	34.76	36.40			
180	12.57	18.45	25.45	33.14	34.42			
195	11.91	17.53	24.26	31.72	32.69			
210	11.33	16.72	23.21	30.46	31.17			
225	10.82	16.00	22.27	29.33	29.81			
240	10.36	15.35	21.43	28.31	28.60			

TABLE – 3.10

A curve is plotted on an ordinary graph paper (Fig 3.10) and from this graph or from loglog paper (Fig. 3.5 to 3.9), value of intensity of storm for any given duration can be worked out for return period of one, two, five, ten and twenty years.

Another graph (Fig.3.11), run-off coefficient 'c' vs duration time 't' is plotted as per : values given in Homer's table (Table 3.3, Pg. No. 45 of CPHEEO Manuel).

3.8 COMPUTATION OF STORM WATER RUN-OFF:

Quantity of storm water run-off is calculated using the rational formula:

Where, Q = run-off in m3/hr

c. = coefficient of run-off

- i. = intensity of rainfall in mm/hr
- A = area of drainage segment in hectares

Coefficient of run-off (c) is arrived at by interpolation of values given in Homer's table with respect to time of concentration (t_c) and for weighted imperviousness. Refer Graph (Fig. 3.11).

As per CPHEEO guide lines, the inlet time which depends on the distance of the farthest point in the drainage basin to the inlet drain, the shape, characteristics and topography of the basin and this may generally vary from 5 to 20 minutes. The inlet time in the present case will be the time taken for the storm water to flow through a network of roadside drains (roads parallel to the main drain and perpendicular to the main drain) till it reaches either a secondary drain or a primary drain. The range of velocities obtained for the secondary/primary drains considering the ground slope and the drain sections as per the existing uncleaned / silted condition of drain, works out to 0.5 to 4.5 m/sec. The mean velocity of flow in the primary drain for 0 to 1000 m distance for clean condition of drain and silted up condition of drain is found to be 5.5 m/sec and 2.25 m/sec respectively. Keeping this velocities in view, a velocity of flow of 1.2 m/sec for terrain and maximum of 3.0 m/sec in drain was chosen to estimate the time of flow (considering cleaned drain with moderate siltation / vegetation).

To arrive at a realistic time of concentration, surface flow velocity of rainwater is taken as 2 m/sec as stated above and the time of flow from the farthest point of the contributory area is worked out, The inlet time varying from 5 to 20 minutes depending on various factors. The time thus derived are used to compute design run-off of each segment.

The weighted imperviousness of the drainage area segment-wise, was worked out as stated in earlier section. Due to non-availability of 0.5 m. or 1.0 m. contour map, the entire tributary area has been divided into various segments with respect to the ridge line and flow patterns, using the area map developed from the satellite imagery.

The identification of roadside drains/ feeder drains leading to primary or secondary drains and adequacy check of such drains is not under the scope of work. However, multiple number of small drains existing in reality by the side of roads in each segment of catchment area (to be drained into main valley) is assumed to be replaced by centrally placed storm drain.

Intensity of rainfall (i) is arrived at from the Graphs (Fig. 3.5 to 3.9 or 3.10) with respect to time of concentration (t _c).

Area of each drainage segment for the entire watershed area has been arrived from the micro catchment area map enclosed in Section 3.3 of this chapter.

Quantity of storm water run-off, worked out segment-wise are furnished for Challaghatta main valley and Ulsoor valley in Table 4.1 & 4.2 is as enclosed in the section 4.2 of Chapter-4 in this report.

CHAPTER - 4

REVIEW OF ASSESSMENT AND RECOMMENDATIONS ON EXISTING STORM WATER DRAINAGE SYSTEM

4.1 **INTRODUCTION:**

This chapter on review of assessment has been prepared to identify the reasons for the failure of the system components. Depending on the nature and extent of the system failure, the approach for the system rehabilitation will vary accordingly. A Generic groupings of rehabilitation methodologies for different applications are therefore needed.

To identify and prioritise rehabilitation needs a systematic approach is needed in planning and investigating the most problematic areas. This will involve the establishment of guidelines on levels of service and asset performance, from which decisions can be consistently based and gaining an understanding of existing flooding problems through fieldwork investigations.

As the implementation of a systematic approach to planning and investigation of rehabilitation works can involve significant resource commitments, both in personnel and financial terms, it is proposed that the BMP progressively improve towards this long-term objective.

Further, Improvements to the existing storm drainage system, which is serving the core area is considered to be on priority for five key reasons:

•To rectify current localised flooding problems in the critical low lying areas.

- •To cope with additional areas being included into the BMP administered area.
- •To improve and extend the security of services in vulnerable areas of the current BMP administered area.
- •To improve and protect the quality of environmental attributes including aesthetic appearance of city's environs.
- •To minimise cost implication on operation and maintenance of the system.

4.2 **REPORT ON ADEQUACY ANALYSIS:**

An assessment of the existing system for its adequacy has been made using computer modelling. The adequacy of the existing system has been analysed and correlated for different year return periods.

Further, these analysis results have been once again correlated with the situation and specific site condition to verify the accuracy of the results and to suggest the strategic improvements required at that particular location.

The focus of this section is solely on

 Storm drains Cross drains

>Storm Water Drains:

The total catchment area of the Challaghatta valley is 3878 Ha. The localities which contribute and the existing condition of this drain is detailed in Section 2.3 & Section 2.6 of Chapter 2.

Cross section data of the existing drains at every 25 m. apart was collected and spread sheets were developed to analyse for their carrying capacity. The analysis has been done for different year return periods. The calculations and results of these analysis is enclosed in Table 4.1 & 4.2.

These tables show the discharge (Q) in the existing drain at that particular chainage. The procedure adopted to work out the required data are furnished below.

- 1.Bed levels on either side of the existing drain differ marginally and hence the average of these levels are considered for computation.
- 2.Top levels of the existing drain side also differ and hence the lower wall/ground level heights are considered for the depth of the drain.
- 3. Free board is taken as 300 mm. for one and two year storms and 100 mm. for five, ten & twenty year storms.
- 4.Coefficient of roughness (n) considered as 0.035 and 0.025 for unclean and clean condition respectively for analysis of existing drains and 0.02 - 0.025 for remodeled drain.

5.Design runoff (Q required) are worked out for respective chainages based

on the runoff calculated segment wise. An abstract of the analysis for Challaghatta main valley & Ulsoor valley is presented in Table – 4.1 & 4.2.

From the analysis and the assessment carried out, following outcomes are highlighted:

→ Challaghatta Main Valley:

- •Near Vasanthanagar the existing storm drain is having a wider catchment area, less time of concentration, drain depth and width is very less, gentle slope is available, severely silted, bed is in natural condition, max. obstructions and also drain walls are in moderate condition. Hence the capacity is adequate only for one year return period.
- •Near Shivajinagar the existing storm drain is having a wider catchment area, less time of concentration, drain depth and width is very less, shallow depth, moderate bed slope is available, silted, bed is in natural condition, number of obstructions and also drain walls are in moderate condition. The drain capacity is adequate for two year return period.
- •Near Bharathinagar the existing storm drain is having a wider catchment area, less time of concentration, drain depth and width is very less, shallow depth, moderate bed slope is available, silted, bed is in natural condition, max. obstructions and also drain walls are in moderate condition. The drain capacity in this stretch is adequate for five year return period.
- •Near Guptha layout the existing storm drain is having a smaller catchment area, more time of concentration, sufficient drain width and depth, good bed slope is available, silted, bed is in natural condition, min. obstructions and also drain walls are in good condition. The drain capacity is adequate for twenty year return period.

- •Near Old Madras road / Saraswathipura the existing storm drain is having a smaller catchment area, less time of concentration, sufficient drain width and depth except near Murphy town market, good bed slope is available, silted, bed is in natural condition, min. obstructions and also drain walls are in moderate condition. The drain capacity is adequate for ten year return period.
- •Near Shammana Gowda layout the existing storm drain is having a wider catchment area, less time of concentration, sufficient drain width and depth except at few places width gets reduced, moderate bed slope is available, silted, bed is in natural condition, min. obstructions and also drain walls are in good condition. The drain capacity is adequate for five year return period.
- •Near Cambridge layout the existing storm drain is having a lesser catchment area, less time of concentration, reduced drain width and depth, moderate bed slope is available, silted, bed is in natural condition, max. obstructions, and also drain walls are in good condition. The drain capacity is adequate for one year return period.
- •Near Domlur 2nd Stage the existing storm drain is having a lesser catchment area, less time of concentration, reduced drain width and depth, moderate bed slope is available, silted, bed is in natural condition, min. obstructions, and also drain walls are in good condition. The drain capacity is adequate for two year return period.
- •Near Diamond District Apartment the existing storm drain is having a lesser catchment area, more time of concentration, sufficient drain width and depth, moderate bed slope is available, silted, bed is in natural condition, min. obstructions, and also drain walls are in moderate condition. The drain capacity is adequate for five year return period.
- •Near Karnataka Golf Club the existing storm drain is having a more catchment area, more time of concentration, reduced drain width and depth, min. bed slope is available, silted, bed is in natural condition, min. obstructions, and also drain walls are in moderate condition. Hence, it is

very inadequate.

- Inside Airport complex the existing storm drain is having a more catchment area, more time of concentration, reduced drain width and depth, moderate bed slope is available, silted, bed is in natural condition, max. obstructions, and also drain walls are in natural condition. Hence, it is very inadequate.
- •Near Anandanagar the existing storm drain is having a more catchment area, less time of concentration, reduced drain width and depth, moderate. bed slope is available, silted, bed is in natural condition, max. obstructions, and also drain walls are in moderate condition. Hence, it is very inadequate.
- •Near Kodihalli Village the existing storm drain is having a more catchment area, less time of concentration, reduced drain width and depth, min. bed slope is available, silted, bed is in natural condition, min. obstructions, and also drain walls are in moderate condition. The drain capacity is adequate for one year return period.

→Ulsoor Valley:

- •Near J.C. Nagar the existing storm drain is having a smaller catchment area, less time of concentration, sufficient drain width and depth, good bed slope is available, silted, bed is in natural condition, few obstructions and also drain walls are in good condition. The drain capacity is adequate for twenty year return period.
- •Near S.K. Garden the existing storm drain is having a smaller catchment area, less time of concentration, sufficient drain width and depth, good bed slope is available, silted, bed is in natural condition, few obstructions and also drain walls are in good condition. The drain capacity is adequate for twenty year return period.

- •Near Frazer town the existing storm drain is having a smaller catchment area, less time of concentration, sufficient drain width and depth, good bed slope is available, silted, bed is in natural condition, few obstructions and also drain walls are in good condition. The drain capacity is adequate for twenty year return period.
- •Near Wheelers Road the existing storm drain is having a smaller catchment area, more time of concentration, sufficient drain width and depth, good bed slope is available, silted, bed is in natural condition, few obstructions and also drain walls are in good condition. The drain capacity is adequate for twenty year return period.
- •Near Sindhi colony the existing storm drain is having a smaller catchment area, more time of concentration, drain width and depth is slightly reduced, moderate bed slope is available, silted, bed is in natural condition, max. obstructions and also drain walls are in moderate condition. The drain capacity is adequate for ten year return period.
- •Near Richard's town the existing storm drain is having a smaller catchment area, more time of concentration, sufficient drain width and depth, good bed slope is available, silted, bed is in natural condition, max. obstructions and also drain walls are in good condition. The drain capacity is adequate for twenty year return period.
- •Near Cox town the existing storm drain is having a smaller catchment area, more time of concentration, sufficient drain width and depth, good bed slope is available, silted, bed is in natural condition, max. obstructions and also drain walls are in good condition. The drain capacity is adequate for twenty year return period.
- •Near Jeevanahalli the existing storm drain is having a wider catchment area, more time of concentration, drain width and depth is drastically reduced, moderate bed slope is available, silted, bed is in natural condition, max. obstructions and also drain walls are in moderate condition. The drain capacity is adequate for one year return period.

>Cross Drains:

Existing culverts based on their structural conditions, no. of vents, no. of utilities laid across SWD at the culvert location which in turn causing obstruction for free flow of water were identified during reconnaissance survey and further analysed for their carrying capacity.

Table 4.3 & 4.4 shows the carrying capacity (Q) near the culverts along with all other data required to derive the same. The procedure adopted to workout the required data are furnished below:

- 1.Adequacy check is carried out under clean condition only, since the drains on either side of the culvert are proposed to be free of silt and vegetation to achieve optimum carrying capacity.
- 2.Dimensions shown in the table is the existing dimensions and the vent way considered is actually collected from site, and accordingly vent way has been worked out.
- 3. The bed slope in the direction of flow is assumed as 1 in 500 (0.002), which may produce a reasonable velocity of flow through the vent way to prevent deposition of silt and a scouring action. Bed slope at existing culvert could not be taken due to flow of water.
- 4. Free board is taken as 0.3 m. for one, two & five year storms.
- 5. The percentage area reduction at the vent way of the culvert with reference to the upstream side drain area are worked out for reference and guidance.
- 6.Coefficient of roughness(n) is considered as 0.02.
- 7.Design runoff are worked out based on the runoff calculated for the drain segment both upstream and down stream side (near the culvert locations) for the length of about 100 m.

The remarks column of these tables, indicated the existing culvert which are

inadequate to carry the design runoff and such culverts are found to be very few. These culverts which are considered to be inadequate were jointly site inspected with BMP officials and various possibilities are studied and incorporated to increase the carrying capacity before deciding for remodelling.

The existing culvert in Challaghatta main valley & Ulsoor valley which are considered to be inadequate are listed in Table -4.5

The inspection details of these existing culverts/bridges is enclosed in Volume 2 - Condition Survey.

Based on the assessment, 20 culverts which were in moderate condition and drastically obstructing the flow, has been shortlisted and considered for reconstruction. Out of 20 culverts 3 culverts i.e, near Ulsoor lake, Indiranagar 100 ft. road and Airport Road have been taken up under different projects.

The detailed designs and estimates of these culverts / bridges is enclosed in Volume 3 and relevant drawings in Volume 4. The list of culverts / bridges proposed for reconstruction is as listed below and the same is depicted in Figure 4.1.

	Table	- 4.5 List	of Culverts / Bridges Considered Challaghatta Valley	for Remodeling in
SI. No.	Culvert No.	Chainage (m.)	Location	Remarks
1	CVC -1	377	Miller's Road	Ex. Culvert/Bridge considered for remodelling
2	CVC - 1A	640	Miller Tank Bund Road (near K.B. Asson.)	Ex. Culvert/Bridge considered for remodelling
3	CVC-6A	1823	Old bamboo bazar Road	Ex. Culvert/Bridge considered for remodelling
4	CVC – 6 B	1905	Charminar Masjid Road	Ex. Culvert/Bridge considered for remodelling
5	CVC – 6 C	2020	Jumma Masjid Road	Ex. Culvert/Bridge considered for remodelling
6	CVC - 7	2127	Seppings Road	Ex. Culvert/Bridge considered for remodelling
7	CVC - 11	2600	Kamaraj Road	Ex. Culvert/Bridge considered for remodelling
8	CVC - 12	2838	St. John's Road	Ex. Culvert/Bridge considered for remodelling
9	CVC - 13	3167	Anna Swamy Mudaliar Road	Ex. Culvert/Bridge considered for remodelling
10	CVC - 14	4015	Kensington Road (Opp. Gurudwara)	Ex. Culvert/Bridge considered for remodelling
11	CVC - 22	7572	Indiranagar 100 ft. Road	Note: Considered by BDA under Flyover Project.
12	CVC - 23	7683	Airport Road (Opp. Diamond Dist. Appartment)	Note : Considered by BDA under Flyover project.
13	N - 1	9232	Wind Tunnel Road (Near Texas Instrument	Proposed New Bridge
14	N - 2	9675	Belur Road (Behind Airport)	Proposed New Bridge
Ulsoo	r Valley (C2):		
1	MVC-4	265	1 st Cross, J.C. Nagar, Ramgeetha Block	Ex. Culvert/Bridge considered for remodelling
2	MVC-8	441	1 st Main Road, Krishnamanagar	Ex. Culvert/Bridge considered for remodelling
3	MVC-7	468	2 nd Main Road, Krishnamanagar	Ex. Culvert/Bridge considered for remodelling
4	N – 3 / MVC 18	1462	S.K. Garden Main Road	Proposed New Bridge
5	MVC-19	1862	Pottery Town Main Road	Ex. Culvert/Bridge considered for remodelling
6	MVC-25	2982	Stephen's Cross Road	Ex. Culvert/Bridge considered for remodelling
7	MVC-26	3162	Wheeler's Road (Opp. Community Centre) (Frazer town)	Ex. Culvert/Bridge considered for remodelling
8	MVC-30	4100	Near Lake View Maha Ganapathy Temple	Note: Considered by BMP under Ulsoor Lake Restoration Project.
Richard	's Town Sec	ondary Storn	n Drain (C202):	
1		905	Wheeler's Road (Opp. Gymkhana Ground)	Ex. Culvert/Bridge considered for remodelling

Table 4.3 Check for Existing Culverts with measured Site Slopes for Adequacy (Challaghatta - Primary Culverts)

	1	1			1		1	I	1	-			1	1								r									
SI.No.	Culvert No.	Chainage	Vent	Width of the drain	Depth of the drain	Slope	(Di) (D- 0.1)	A= (B × Di)	.S.D Area (Da)	– A)/Da x 100	P = (B+2Di)	R = A / P	(u)	= (1/n) R ^{2/3} S ^{0.5}	Q = A x V	Q total		Disc	harge (Q	Reqd.)			R	Remark	s			Widt	h Require	ed(B)	
	0			Widt	Dept		U)	4	U.S	(Da	WP) = V	0		1year	2year	5year	10year	20year	1year	2year	5year	10year	20year	1year	2year	5year	10year	20year
		(m)	No.	(B) m	(D) m	(S)	(D- 0.1) m	(m²)	(m²)	%	(m)	(m)		(m/s)	(Cumec)	(Cumec)	(Cumec)	(Cumec)	(Cumec)	(Cumec)	(Cumec)										
1	CVC2	Queens Road @1032	1	3.000	4.000	0.0012	3.900	11.700			10.800	1.083	0.015	2.436	28.501																
			2	3.000	4.000	0.0012	3.900	11.700			10.800	1.083	0.015	2.436	28.501																
				6.000			3.900	23.400	25.500	8.235				2.436		57.002	10.870	15.010	19.220	22.790	28.230	AD	AD	AD	AD	AD					
2	CVC3	Payappa Garden Road @1062	1	4.000	1.700	0.0196	1.600	6.400			7.200	0.889	0.015	8.628	55.222																
		11000 @ 1002	2	3.500	1.750	0.0196	1.650	5.775			6.800	0.849	0.015	8.370	48.337																
				7.500			1.600	12.175	33.670	63.840				8.370		103.560	11.160	15.420	19.740	23.410	28.990	AD	AD	AD	AD	AD					
3	CVC4	Old Cemetry Road @1287	1	2.000	2.420	0.0025	2.320	4.640			6.640	0.699	0.015	2.625	12.180																
		HUAU @1207	2	2.000	2.250	0.0025	2.150	4.300			6.300	0.683	0.015	2.584	11.111																
-			3	2.000	2.940	0.0025	2.840	5.680			7.680	0.740	0.015	2.726	15.484																
				6			2.320	14.620	19.210	23.894				2.600		38.775	12.480	17.240	22.080	26.180	32.420	AD	AD	AD	AD	AD					
5	CVC4A	D' No. 1 Street	1	2.500	1.750	0.0080	1.650	4.125			5.800	0.711	0.015	4.751	19.598																
5	00047	@1431	'																												
			2	2.500	1.750	0.0080	1.650	4.125			5.800	0.711	0.015	4.751	19.598																
		Obiusii Daad		5			1.650	8.250	7.830	-5.364				4.751		39.196	13.360	18.460	23.630	28.020	34.700	AD	AD	AD	AD	AD					
6	CVC5	Shivaji Road @1462	1	5.000	1.525	0.0040	1.425	7.125			7.850	0.908	0.015	3.953	28.162																
				5.000			1.425	7.125	10.530	32.336				3.953		28.162	13.500	18.660	23.890	28.330	35.080	AD	AD	AD	IA	IA				5.03	6.23
7	CVC6	Board Way Road @1737	1	6.000	1.500	0.0030	1.400	8.400			8.800	0.955	0.015	3.540	29.736																
				6.000			1.400	8.400	9.460	11.205				3.540		29.736	15.120	20.890	26.750	31.720	39.270	AD	AD	AD	IA	IA				6.4	7.92
8	CVC6A	Sri Nanjunda Murthy Temple @1789	1	2.200	1.750	0.0034	1.650	3.630			5.500	0.660	0.015	2.947	10.697																
			2	2.200	1.750	0.0034	1.650	3.630			5.500	0.660	0.015	2.947	10.697																
				4.400			1.650	7.260	11.590	37.360				2.947		21.393	15.410	21.300	27.270	32.330	40.040	AD	AD	IA	IA	IA			5.61	6.65	8.23
1		I											I					I									I				

(Clean Condition n = 0.015) (with freeboard 100mm)

STUP Consultants Ltd.

Remodeling of Primary and Secondary Storm Water Drain in Bangalore City

SI.No.	Culvert No.	Chainage	Vent	Width of the drain	Depth of the drain	Slope	(Di) (D- 0.1)	A= (B × Di)	U.S.D Area (Da)	– A)/Da x 100	= (B+2Di)	= A / P	(u)	= (1/n) R ^{2/3} S ^{0.5}	Q = A x V	Q total		Disc	harge (Q	Reqd.)			F	Remark	s			Wid	th Require	ed(B)	
	Cu	0		Width	Depth		(D)	A=	U.S.I	(Da –	WP	ш		V = (1	σ		1year	2year	5year	10year	20year	1year	2year	5year	10year	20year	1year	2year	5year	10year	20year
		(m)	No.	(B) m	(D) m	(S)	(D- 0.1) m	(m²)	(m²)	%	(m)	(m)		(m/s)	(Cumec)	(Cumec)	(Cumec)	(Cumec)	(Cumec)	(Cumec)	(Cumec)										
9	CVC7	Seppings Road @2128	1	2.500	1.500	0.0025	1.400	3.500			5.300	0.660	0.015	2.528	8.847																
			2	2.500	1.500	0.0025	1.400	3.500			5.300	0.660	0.015	2.528	8.847																
			3	2.500	1.500	0.0025	1.400	3.500			5.300	0.660	0.015	2.528	8.847																
				7.500			1.400	10.500	8.930	-17.581				2.528		26.542	15.700	21.700	27.790	32.950	40.800	AD	AD	IA	IA	IA			7.85	9.31	11.53
10	CVC8	Jewellery Street @2190	1	2.500	1.500	0.0030	1.400	3.500			5.300	0.660	0.015	2.769	9.692																
			2	2.700	1.500	0.0030	1.400	3.780			5.500	0.687	0.015	2.844	10.749																
			3	2.700	1.400	0.0030	1.300	3.510			5.300	0.662	0.015	2.774	9.738																
				7.900			1.400	10.790	13.920	22.486				2.769		30.179	17.760	24.540	31.420	37.250	46.130	AD	AD	IA	IA	IA			8.11	9.61	11.9
11	CVC9	Narayana Pillai Street @2242	1	3.500	1.250	0.0104	1.150	4.025			5.800	0.694	0.015	5.329	21.449																
			2	3.500	1.300	0.0104	1.200	4.200			5.900	0.712	0.015	5.420	22.765																
				7.000			1.150	8.225	14.620	43.741				5.350		44.215	18.110	25.030	32.050	38.010	47.050	AD	AD	AD	AD	IA					7.65
12	CVC10	Arm Strong Road @2439	1	3.500	1.500	0.0032	1.400	4.900			6.300	0.778	0.015	3.189	15.628																
		-	2	3.500	1.500	0.0032	1.400	4.900			6.300	0.778	0.015	3.189	15.628																
				7.000			1.400	9.800	17.580	44.255				3.189		31.257	19.770	27.340	35.050	41.620	51.400	AD	AD	IA	IA	IA			7.85	9.32	11.51
13	CVC11A	Goutham Sound Lights @2730	1	2.500	1.500	0.0034	1.400	3.500			5.300	0.660	0.015	2.948	10.318																
			2	2.500	1.500	0.0034	1.400	3.500			5.300	0.660	0.015	2.948	10.318																
			3	2.500	1.500	0.0034	1.400	3.500			5.300	0.660	0.015	2.948	10.318																
				7.500			1.400	10.500	14.010	25.054				2.948		30.953	22.260	30.820	39.550	47.040	57.920	AD	AD	IA	IA	IA			9.58	11.4	14.03
14	CVC12	St. Jhons Road @2837	1	3.000	1.800	0.0022	1.700	5.100			6.400	0.797	0.015	2.688	13.707																
			2	2.500	1.850	0.0022	1.750	4.375			6.000	0.729	0.015	2.533	11.083																
			3	2.000	1.750	0.0022	1.650	3.300			5.300	0.623	0.015	2.280	7.524																
				7.500			1.700	12.775	22.170	42.377				2.533		32.314	23.090	31.970	41.050	48.850	60.090	AD	AD	IA	IA	IA			9.53	11.34	13.95
15	CVC13	Anna Swamy Mudaliar Street @3167	1	1.500	1.680	0.0020	1.580	2.370			4.660	0.509	0.015	1.900	4.502																

Page

Challaghatta Valley

Remodeling of Primary and Secondary Storm Water Drain in Bangalore City

A)/Da x 100 S 0.5 drain drain U.S.D Area (Da) = (B+2Di) Discharge (Q Read.) Culvert No. (Di) (D- 0.1) (B x Di) Remarks Width Required(B) Chainage $\mathsf{R}=\mathsf{A}/\mathsf{P}$ = A x V V = (1/n) R 2/3 Jepth of the Q total SI.No. Nidth of the Slope /ent Ξ A= (ΜÞ ä Da – 20year l Oyear 20year 10year 20year l 0year 2year 5year lyear 2year 5year lyear 2year 5year (D- 0.1) (m) No. (B) m (D) m (S) (m²) (m²) % (m) (m) (m/s) (Cumec) (Cumec) (Cumec) (Cumec) (Cumec) (Cumec) (Cumec) m 2 1.500 1.680 0.0020 1.580 2.370 4.660 0.509 0.015 1.900 4.502 3 1.500 2.030 0.0020 1.930 2.895 5.360 0.540 0.015 1.977 5.724 1.500 2.030 0.0020 1.930 2.895 5.360 0.540 0.015 1.977 5.724 Λ 5 1.500 2.030 0.0020 1.930 2.895 5.360 0.540 0.015 1.977 5.724 7.500 1.750 13.425 30.110 55.413 1.930 26.177 25.780 35.730 45.930 54.710 67.160 AD IA IA IA IA 10.58 13.6 16.2 19.88 CVC14 Old Madras Road 16 2.000 3.500 0.0058 3.400 6.800 8.800 0.773 0.015 4.275 29.073 @4000 2.000 3.500 0.0058 3.400 6.800 8.800 0.773 0.015 4.275 29.073 3 2.000 3.500 0.0058 3.400 6.800 8.800 0.773 0.015 4.275 29.073 2.000 3.500 0.0058 3.400 6.800 8.800 0.773 0.015 4.275 29.073 4 2.000 3.500 6.800 0.773 0.015 4.275 29.073 5 0.0058 3.400 8.800 10.000 3.400 34.000 45.600 25.439 4.275 145.363 56.680 78.810 101.700 121.780 148.040 AD AD AD AD IA 10.19 Yellamma 17 CVC15 Temple Street 3.500 3.000 0.0142 2.900 10.150 9.300 1.091 0.015 8.421 85.475 @4138 2 3.500 3.000 0.0142 2.900 10.150 1.091 0.015 8.421 85.475 9.300 3 3.500 3.000 0.0142 2.900 10.150 9.300 1.091 0.015 8.421 85.475 10.500 2.900 30.450 26.250 -16.000 8.421 256.426 58.480 81.310 104.930 125.640 152.740 AD AD AD AD AD Sathyanarayana 18 CVC16 Temple Road 1 6.000 2.000 0.0032 1.900 11.400 9.800 1.163 0.015 4.171 47.553 @4477 2 6.000 2.000 0.0032 1.900 11.400 9.800 1.163 0.015 4.171 47.553 87.150 112.460 134.660 163.710 AD AD IA IA IA 12.000 22.800 31.640 27.939 4.171 95.105 62.680 14.19 20.66 1.900 16.99 Sada Shiva CVC17 Mudaliyar Road 19 6.000 2.000 0.0020 1.900 11,400 9.800 1.163 0.015 3.298 37.594 @4910 6.000 2.000 0.0020 1.900 11.400 9.800 1.163 0.015 3.298 37.594 12.000 1.900 22.800 29.760 23.387 3.298 75.187 67.010 93.260 120.470 144,440 175.160 AD IA IA IA IA 14.88 19.23 23.05 27.95 Old Madras Road 9.200 1.070 0.015 32.077 20 CVC18 4.000 2.400 0.0025 2.300 8.600 3.487 @5046

Page

SI.No.	Culvert No.	Chainage	Vent	Width of the drain	h of the drain	Slope	(Di) (D- 0.1)	A= (B × Di)	.S.D Area (Da)	- A)/Da x 100	• = (B+2Di)	R = A / P	(u)	1/n) R ^{2/3} S ^{0.5}	(Q total		Disc	harge (Q	Reqd.)			F	lemarks	S			Wid	th Require	ed(B)	
	С	0		Widt	Depth		Q)	A	U.S.	(Da -	WP	-		V = (a		1year	2year	5year	10year	20year	1year	2year	5year	10year	20year	1year	2year	5year	10year	20year
		(m)	No.	(B) m	(D) m	(S)	(D- 0.1) m	(m²)	(m²)	%	(m)	(m)		(m/s)	(Cumec)	(Cumec)	(Cumec)	(Cumec)	(Cumec)	(Cumec)	(Cumec)										
			2	4.000	2.400	0.0025	2.300	9.200			8.600	1.070	0.015	3.487	32.077																
			3	4.000	2.400	0.0025	2.300	9.200			8.600	1.070	0.015	3.487	32.077																
				12.000			2.300	27.600	31.360	11.990				3.487		96.231	68.270	95.030	122.800	147.300	178.490	AD	AD	IA	IA	IA			15.31	18.37	22.26
21	CVC19	Cambridge Road @6092	1	4.000	2.500	0.0008	2.400	9.600			8.800	1.091	0.015	1.998	19.183																
			2	5.200	2.500	0.0008	2.400	12.480			10.000	1.248	0.015	2.186	27.278																
			3	4.500	1.500	0.0008	1.400	6.300			7.300	0.863	0.015	1.709	10.768																
				13.700			2.200	28.380	36.460	22.161				1.998		57.229	99.120	138.150	178.790	214.890	259.430	IA	IA	IA	IA	IA	22.55	31.43	40.67	48.89	59.02
22	CVC21	Domular Bus Stand @7120	1	7.500	2.950	0.0012	2.850	21.375			13.200	1.619	0.015	3.185	68.071																
			2	7.500	2.850	0.0012	2.750	20.625			13.000	1.587	0.015	3.141	64.793																
				15.000			2.800	42.000	41.400	-1.449				3.150		132.864	110.180	153.880	199.670	240.780	288.890	AD	IA	IA	IA	IA		17.45	22.64	27.3	32.75
23	CVC24	Royal Orchid Park Plaza @8060	1	4.000	3.200	0.0015	3.100	12.400			10.200	1.216	0.015	2.941	36.469																
			2	4.000	3.400	0.0015	3.300	13.200			10.600	1.245	0.015	2.989	39.449																
			3	4.000	3.200	0.0015	3.100	12.400			10.200	1.216	0.015	2.941	36.469																
				12.000			3.200	38.000	63.180	39.854				2.950		112.387	124.620	174.070	225.910	272.480	326.790	IA	IA	IA	IA	IA	13.2	18.44	23.93	28.86	34.62

Check for Existing Culverts with measured Site Slopes for Adequacy (Ulsoor - Primary Culverts)

(Clean Condition n = 0.015) (with freeboard 100mm)

			_												· · · · ·																
SI.No.	Culvert No.	Chainage	Vent	Width of the drain	Depth of the drain	Slope	(Di) (D- 0.1)	A= (B × Di)	U.S.D Area (Da)	– A)/Da x 100	WP = (B+2Di)	= A / P	(u)	= (1/n) R ^{2/3} S ^{0.5}	= A x V	Q total		Disc	harge (Q	Reqd.)			F	lemark	s			Widt	h Require		
	Cu	ō		Width	Depth		(Di)	A=	U.S.E	(Da –	WP	с		V = (1	Ø	0	1year	2year	5year	10year	20year	1year	2year	5year	10year	20year	1year	2year	5year	10year	20year
		(m)	No.	(B) m	(D) m	(S)	(D- 0.1) m	(m²)	(m²)	%	(m)	(m)		(m/s)	(Cumec)	(Cumec)	(Cumec)	(Cumec)	(Cumec)	(Cumec)	(Cumec)										
1	MVC3	1 st Cross J.C. Nagar Ramgeetha Block @75	1	1.500	1.200	0.0160	1.100	1.650			3.700	0.446	0.015	4.922	8.122																
			2	1.500	1.200	0.0160	1.100	1.650			3.700	0.446	0.015	4.922	8.122																
				3.000			1.100	3.300	9.340	64.668				1.348		16.243	5.170	7.190	9.280	11.110	13.510	AD	AD	AD	AD	AD					
2	MVC4	1 st Cross J.C. Nagar @ 270	1	4.600	1.200	0.0128	1.100	5.060			6.800	0.744	0.015	6.194	31.339																
				4.600			1.100	5.060	11.080	54.332				6.194		31.339	5.960	8.280	10.680	12.790	15.560	AD	AD	AD	AD	AD					
3	MVC5	2 nd Cross J.C. Nagar @380	1	1.800	1.600	0.0076	1.500	2.700			4.800	0.563	0.015	3.960	10.693																
			2	1.800	1.600	0.0076	1.500	2.700			4.800	0.563	0.015	3.960	10.693																
				3.600			1.500	5.400	11.580	53.368				3.960		21.386	6.510	9.060	11.680	13.990	17.010	AD	AD	AD	AD	AD					
4	MVC6	1 [≋] Main Road Krishnamma Nagar @435	1	1.000	1.600	0.0080	1.500	1.500			4.000	0.375	0.015	3.101	4.651																
			2	1.000	1.600	0.0080	1.500	1.500			4.000	0.375	0.015	3.101	4.651																
				2			1.500	3.000	10.060	70.179				3.101		9.302	6.740	9.370	12.080	14.460	17.600	AD	IA	IA	IA	IA		2.01	2.6	3.11	3.78
5	MVC7	1st Main Road Krishnamma Nagar @460	1	3.000	1.400	0.0072	1.300	3.900			5.600	0.696	0.015	4.445	17.334																
				3.000			1.300	3.900	8.800	55.682				4.445		17.334	6.850	9.520	12.290	14.700	17.890	AD	AD	AD	AD	IA					3.1
6	MVC8	Anjaneyyappa Block @550	1	1.800	1.500	0.0065	1.400	2.520			4.600	0.548	0.015	3.599	9.068																
			2	1.800	1.500	0.0065	1.400	2.520			4.600	0.548	0.015	3.599	9.068																
				3.600			1.400	5.040	7.640	34.031				3.599		18.137	7.300	10.140	13.090	15.660	19.050	AD	AD	AD	AD	IA					3.78
7	MVC9	Mosque Street @660) 1	2.000	1.500	0.0075	1.400	2.800			4.800	0.583	0.015	4.031	11.286																

Remodeling of Primary and Secondary Storm Water Drain in Bangalore City


Challaghatta Valley

			r -	1				1	1	1	1	1	1	1			1	1	1	1							1		1	1	1
			2	2.000	1.500	0.0075	1.400	2.800			4.800	0.583	0.015	4.031	11.286																
				4.000			1.400	5.600	7.300	23.288				4.031		22.572	7.740	10.760	13.890	16.620	20.220	AD	AD	AD	AD	AD					
8	MVC10	Anjaneyyappa Block 3 rd Cross @710	1	3.000	1.500	0.0076	1.400	4.200			5.800	0.724	0.015	4.687	19.684																
			2	3.000	1.500	0.0076	1.400	4.200			5.800	0.724	0.015	4.687	19.684																
				6.000			1.400	8.400	8.980	6.459				4.687		39.368	7.970	11.080	14.290	17.100	20.800	AD	AD	AD	AD	AD					
9	MVC11	Sheshadri Road @810	1	2.300	0.600	0.0048	0.500	1.150			3.300	0.348	0.015	2.287	2.630																
			2	2.300	0.600	0.0048	0.500	1.150			3.300	0.348	0.015	2.287	2.630																
				4.600			0.500	2.300	11.710	80.359				2.287		5.261	8.410	11.700	15.090	18.060	21.970	IA	IA	IA	IA	IA	7.35	10.23	13.19	15.79	19.21
10	MVC12	Chinnappa Garden 14 th Cross @950	1	2.200	0.900	0.0060	0.800	1.760			3.800	0.463	0.015	3.091	5.441																
		-	2	2.200	0.900	0.0060	0.800	1.760			3.800	0.463	0.015	3.091	5.441																
			1	4.400			0.800	3.520	10.030	64.905				3.091		10.881	9.080	12.630	16.290	19.500	23.720	AD	IA	IA	IA	IA		5.11	6.59	7.89	9.59
11	MVC13	Muddamma Garden 1 st Main Road	1	3.700	1.200	0.0056	1.100	4.070			5.900	0.690	0.015	3.895	15.852																
		@1050		3.700			1.100	4.070	6.880	40.843				3.895		15.852	9.530	13.250	17.090	20.460	24.890	AD	AD	IA	IA	IA			3.99	4.78	5.81
																														-	
12	MVC14	Muddamma Garden	4	5.100	1.900	0.0096	1.800	9.180			8.700	1.055	0.015	6.770	62.149																
12	1010014	13th Cross @1110	Ľ		1.500	0.0090			0.050	44.070	8.700	1.055	0.013		02.149		0.750	10.500	17 100		05.170			4.5		AD					
		Muddamma Garden		5.100			1.800	9.180	8.250	-11.273				6.770		62.149	9.750	13.560	17.490	20.940	25.470	AD	AD	AD	AD	AD					
13	MVC15	10th Cross @1175	1	2.200	2.100	0.0056	2.000	4.400			6.200	0.710	0.015	3.969	17.465																
			2	2.200	2.100	0.0056	2.000	4.400			6.200	0.710	0.015	3.969	17.465																
				4.400			2.000	8.800	10.050	12.438				3.969		34.930	10.090	14.020	18.090	21.660	26.350	AD	AD	AD	AD	AD					
14	MVC16	@1260	1	2.000	1.900	0.0056	1.800	3.600			5.600	0.643	0.015	3.716	13.378																
			2	2.000	1.900	0.0056	1.800	3.600			5.600	0.643	0.015	3.716	13.378																
			1	4.000			1.800	7.200	11.230	35.886				3.716		26.755	10.420	14.490	18.690	22.380	27.220	AD	AD	AD	AD	IA					4.07
15	MVC17	S.K. Garden @1350	1	1.800	1.500	0.0056	1.400	2.520			4.600	0.548	0.015	3.340	8.417																
			2	1.800	1.500	0.0056	1.400	2.520			4.600	0.548	0.015	3.340	8.417																
			╞	3.600			1.400	5.040	8.540	40.984				3.340	<u> </u>	16.834	10.870	15.110	19.500	23.340	28.390	AD	AD	IA	IA	IA			4.17	4.99	6.07
			1																												
	I		1	1							1	1	1																		

		nary and Secondary Storm			J																									Challaghatt	
16	MVC18	S.K. Garden @1475	1	1.900	0.900	0.0060	0.800	1.520			3.500	0.434	0.015	2.961	4.501																
			2	1.900	0.900	0.0060	0.800	1.520			3.500	0.434	0.015	2.961	4.501																
				3.800			0.800	3.040	11.160	72.760				2.961		9.003	11.430	15.890	20.500	24.530	29.850	IA	IA	IA	IA	IA	4.82	6.71	8.65	10.35	12.6
17	MVC19	Pottery Town @1850) 1	4.200	1.000	0.0025	0.900	3.780			6.000	0.630	0.015	2.450	9.260																
			2	4.200	1.000	0.0025	0.900	3.780			6.000	0.630	0.015	2.450	9.260																
				8.400			0.900	7.560	10.380	27.168				2.450		18.519	14.220	19.770	25.530	30.580	37.150	AD	IA	IA	IA	IA		8.97	11.58	13.87	16.85
18	MVC20	Bore Bank Road @2075	1	5.500	1.950	0.0142	1.850	10.175			9.200	1.106	0.015	8.496	86.447																
		-	2	5.500	1.950	0.0142	1.850	10.175			9.200	1.106	0.015	8.496	86.447																
				11.000			1.850	20.350	22.240	8.498				8.496		172.895	16.340	22.730	29.360	35.190	42.690	AD	AD	AD	AD	AD					<u> </u>
19	MVC21	@2180	1	1.800	2.100	0.0060	2.000	3.600			5.800	0.621	0.015	3.758	13.527																
			2	1.800	2.100	0.0060	2.000	3.600			5.800	0.621	0.015	3.758	13.527																
			3	1.800	2.100	0.0060	2.000	3.600			5.800	0.621	0.015	3.758	13.527																
			4	1.800	2.100	0.0060	2.000	3.600			5.800	0.621	0.015	3.758	13.527																
			5	1.800	2.100	0.0060	2.000	3.600			5.800	0.621	0.015	3.758	13.527																
				9.000			2.000	18.000	23.570	23.632				3.758		67.635	17.110	23.810	30.750	36.870	44.720	AD	AD	AD	AD	AD					
20	MVC22	More Road @2450	1	2.750	1.300	0.0016	1.200	3.300			5.150	0.641	0.015	1.982	6.541																
			2	2.750	1.300	0.0016	1.200	3.300			5.150	0.641	0.015	1.982	6.541																
				5.500			1.200	6.600	22.780	71.027				1.982		13.081	17.870	24.860	32.090	38.440	46.700	IA	IA	IA	IA	IA	7.51	10.45	13.49	16.16	19.63
21	MVC23	Mosque Road @2675	1	3.000	1.600	0.0036	1.500	4.500			6.000	0.750	0.015	3.302	14.859																
		-	2	3.000	1.600	0.0036	1.500	4.500			6.000	0.750	0.015	3.302	14.859																
				6.000			1.500	9.000	31.720	71.627				3.302		29.717	19.020	26.470	34.180	40.970	49.720	AD	AD	IA	IA	IA			6.9	8.27	10.04
22	MVC24	@2860	1	7.000	3.000	0.0040	2.900	20.300			12.800	1.586	0.015	5.734	116.402													<u> </u>		Í	
			Ľ		5.000	0.00+0					.2.000	1.000	5.010		. 10.402		00.075	07.045	00.445	10.015	50.405		4.5	10						├	
			\vdash	7.000			2.900	20.300	28.960	29.903				5.734		116.402	20.070	27.940	36.110	43.310	52.480	AD	AD	AD	AD	AD					
		Otenhanal, D. J.	\vdash																												<u> </u>
23	MVC25	Stephene's Road @3000	1	2.800	0.800	0.0032	0.700	1.960			4.200	0.467	0.015	2.269	4.447															i -	1

Remodeling of Primary and Secondary Storm Water Drain in Bangalore City

STUP Consultants Ltd.



4.2 STRATEGIC ACTIONS AND RECOMMENDATIONS:

>CHALLAGHATTA MAIN VALLEY:

- •The existing drain opposite to Kodava Samaja near Vasanthanagar needs to be desilted and a steel grating has to be provided.
- •Tertiary drains in Vasanthanagar needs to be desilted and regarded to match the new drain bed level.
- •Few old buildings that exists inside corporation dobhi ghat needs to be dismantled and the existing drain needs to be widened and deepened.
- •The covered reach of drain needs to be opened, desilted and widened adjacent to Millers Arcade, near Millers Road.
- •Existing sewerage system has to be extended to the entire locality and ensured that all house connections are made in Vasanthanagar.
- •Silt barriers needs to be constructed near the open ground like Palace grounds, cantonment railway station adjoining areas, Mount carmel college ground etc.
- •The tertiary drain starting from Cunningham road upto Aiyappa temple needs to be desilted and a steel grating has to be provided at that location. Further, the drain reach which is encroached by commercial establishments i.e., opposite to Jain Nursing College needs to be restored and properly connected to the main drain near Millers Arcade.
- •The existing culvert/bridge constructed across Millers road needs to be reconstructed with a wider span.
- •The covered reach of drain inside Ambedkar bhavan needs to be widened.

- •Debris that has been dumped over the drain i.e., behind Mahaveer jain hospital needs to be removed and existing drain needs to be widened. This reach of drain should be kept open for scheduled maintenance.
- •The existing culvert/bridge constructed across Millers tank bund road needs to be reconstructed with a wider span.
- •Tertiary drains from Cunningham road and adjacent to billiards association needs to be desilted, widened and regarded to match the new drain bed level.
- •The approach bridges that are constructed across storm drain by Karnataka badminton association and Indian council association for social welfare needs to be replaced with single span culverts.
- •Large quantity of sewage that is flowing from the tertiary drain that exists inside police quarters and also corporation colony needs to be prevented.
- •Sewer lines and manholes that are noticed near Shivaji road needs to be relocated and also few disused manholes that exists inside the drain needs to be dismantaled.
- •Sewerage system and solid waste management system in this area needs to be improved.
- •Shops that are constructed over the storm drain near Broadway road needs to be relocated, desilted, widened and deepened.
- •Discharge of liquid wastes that are generated from slaughter house needs to be prevented from entering into the drain and it has to be collected and treated separately.
- •Caution boards and sign boards needs to be displayed to create awareness among people about storm drain and its management.

- •The existing culverts constructed across storm drain at old bamboo bazaar road, Juma Masjid road, Charminar Masjid road and Seppings road needs to be reconstructed.
- •Solid waste management in this region needs to be improved.
- All openings made to the drain wall needs to be closed in this region to avoid back flow of water.
- Construction of public toilet blocks adjacent to storm drain and also discharge of raw sewage from these toilet blocks, needs to be avoided.
- •Existing tertiary drain network in Shivajinagar area needs to be desilted and remodeled to match the new drain bed level. (As per the sketch enclosed for low lying area improvement works).
- •The existing culverts constructed across storm drain at Kamaraj road, St. Johns road and Anna Swamy Mudaliar road needs to be reconstructed and drain reach adjacent to Block Education building needs to be widened to provide access for free flow of water.
- Vegetal growth noticed near St. Johns road and RBANMS college needs to be removed.
- The waste weir and BWSSB manhole constructed across storm drain adjacent to RBANMS college needs to be relocated.
- •The drain reach, adjacent to Ulsoor lake needs to be regarded after lowering the drain bed near Gurudwara.

Kensington Road Proposal:

✓Alternative – 1

•To regrade the drain bed from Shivajinagar and also to prevent stagnatation of water and solid wastes accumulation opposite to Gurudwara it is very much essential to remove the existing school building constructed by Gurudwara association. Further, The existing culverts constructed across storm drain at Kensington road needs to be dismantelled and reconstructed with single span bridge after lowering the rocky outcrop that is encountered near Gurudwara.

\checkmark Alternative – 2

- •To regrade the drain bed from Shivajinagar and also to prevent stagnatation of water and solid wastes accumulation opposite to Gurudwara it is very much essential to altering the alignment of storm drain and constructing RCC box drain for a length of about 120 m. across Kensington road and extend it in Yellamma temple street. Further, connect the box drain to the existing open drain adjacent to slum. But to execute this proposal a small scale industry and BWSSB sewerline needs to be relocated. (As per enclosed Sketch).
- •Liquid waste and solid wastes generated from Munivenkatappa garden slum needs to be prevented from getting discharged into storm drain.
- •Near Guptha layout, solid waste collection system needs to be improved, and caution boards and sign boards needs to be displayed to create awareness among people about storm drain and its management.
- The existing low level bridge constructed adjacent to Cambridge layout bridge needs to be removed and also BWSSB manholes constructed just at the vent portion of this bridge needs to be relocated.
- •The existing drain reach needs to be widened on left hand side upto Airport

road.

- •Liquid waste and solid wastes generated from the slum, situated adjacent to Cambridge layout bridge needs to be prevented from getting discharged into storm drain.
- •The existing RCC hume pipe culvert constructed across storm drain near Domlur 2nd stage needs to be replaced with RCC slab culvert at the later stage of the project.
- •The existing RCC hume pipe culvert constructed across storm drain near Indiranagar 100 ft. road needs to be replaced with RCC slab culvert at the later stage of the project.
- •The existing RCC hume pipe culvert constructed across Airport Road storm drain needs to be replaced with RCC slab culvert at the later stage of the project.
- •The existing 1800 mm dia. BWSSB CI sewerline i.e., noticed behind Diamond district apartments needs to be lowered or relocated or in the drain bed syphon has to be created
- •Existing drain reach adjacent to Karnataka Golf Club needs to be widened and stone revetment has to be provided.
- •Existing drain alignment near Texas instruments needs to be slightly altered to connect the main drain to the existing drain constructed by Airport authorities inside the Airport compound.
- •The drain inside Airport compound after deepening the drain bed (i.e., constructed by Airport authorities), 2 new bridges has to be constructed i.e, one across wind tunnel road and other across Bellur main road. (As per enclosed Sketch)
- •For easy access and maintenance of drain by BMP, the compound wall of Airport needs to be shifted on the other side (left side) of the drain so that the drain inside the airport compound will be outside the Airport compound

and the drain can be maintained for smooth flow of storm water.

- •Behind Airport, new drain has to be constructed upto Bellandur tank and stone revetment has to be provided.
- •Encroachment / Development of land near the tank bed needs to be prevented.
- •Provision for future drain requirement and also for service roads needs to be demarcated.

>CHALLAGHATTA MAIN VALLEY SECONDARY STORM DRAINS:

>Murugeshpalya drain - C101:

- •The existing closed drain reach Anandapuram needs to desilted, widened and replaced with RCC box drain.
- •The open drain reach near Nanjareddy colony needs to desilted, widened and bed improvement to be done upto Airport Road.
- •The drain reach near Airport road culvert and also drain reach adjacent to Airport road needs to be desilted, deepened, widened and replaced with RCC Box drain.
- •The drain reach adjacent to Composite college needs to desilted and manholes needs to be lowered.
- •The box drain construction work which is under progress needs to be expedited.

>Shastrinagar Drain - C102:

•Dense vegetal growth noticed near Indiranagar Bus Depot needs to be removed, minor rehabilitation works to be attended and bed protection to be provided. •The covered drain reach near CMH Road culvert and also drain reach adjacent to Lakshmipura road needs to be desilted, deepened, and minor rehabilitation works needs to be provided.

>I.S.R.O. Complex Drain - C105:

- •Dense vegetal growth that is noticed near I.S.R.O. complex needs to be removed, minor rehabilitation works to be attended and bed protection to be provided.
- •The drain reach near Kodihalli village needs to be desilted, widened, deepened, bed protection, utility shifting and minor rehabilitation works needs to be done.

>ULSOOR VALLEY:

- •Construction of shops over the drain near J.C. Nagar main road needs to be avoided.
- •Dumping of debris inside the storm drain needs to be avoided.
- Sewer pipelines and manholes that are constructed inside the drainage channel near Krishnammanagar needs to be relocated.
- •Loose gravelly sand / silt that existes / filled inside the drainage channel for providing cover for pipelines needs to be removed.
- Manholes that are constructed exactly at the vent location of culverts needs to be relocated near Krishnammanagar.
- •Residential building that is constructed inside the drainage channel near Aiyappa Swamy temple at Krishnammanagar needs to be removed.
- •K.P.T.C.L. transformer that has been installed near Krishnammanagar needs to be relocated and drain has to be widened.

- •Existing stone slab culverts situated near Ramgeetha block and Krishnammanagar needs to be reconstructed.
- •Solidwaste management system near Kempiah block, Krishnammanagar, and Ramgeetha block needs to be improved.
- •Existing tertiary drain network Munireddypalya and Chinnappa garden area needs to be desilted and remodeled to match the new drain bed level. (As per the sketch enclosed for low lying area improvement works).
- •Caution boards and sign boards needs to be displayed to create awareness among people about storm drain and its management.
- •New RCC box drain has to be constructed at 13th Cross Muddamma garden upto S.K. Garden main road and which act as a bypass drain.
- •A new open drain has to be constructed adjacent to defence area at S.K. garden main road.
- •The existing drain adjacent to defence land near S.K garden needs to be widened and also existing A.C sheet residential buildings that are noticed near Pottery town bridge location needs to be relocated..
- •Existing stone slab skew bridge near Pottery town needs to be replaced with RCC slab bridge.
- •Existing sewerage system in S.K.Garden and its adjoining areas has to be extended to the entire locality and also it has to be ensured that all the houses are connected to the system.
- •Silt barriers needs to be constructed near Tannery road and Pottery town main road to prevent entry of silt from adjoining open areas into storm drains.

•Existing silt traps constructed near Mosque road, Asseya road and Sindhi

colony needs to be desilted.

- •Sewerlines and manholes constructed inside drainage channel near More road and Mosque Road needs to be relocated.
- •Existing stone slab bridge near Stephen's Cross Road and Wheelers Road needs to be replaced with RCC slab bridge.
- •The existing bridge near Ganapati temple near Ulsoor lake needs to be remodelled. (Work is taken up under Ulsoor lake development program)
- •Existing drain needs to be widened and debris that are being dumped by defence authorities into storm drain behind corporation ward office (near Lake view Maha Ganapathy temple) needs to be prevented.

>ULSOOR VALLEY SECONDARY STORM DRAINS:

>Ganesh Temple Drain - C201:

 The existing drain reach is in natural condition minor rehabilitation works and bed protection to be done.

>Cox Town Drain - C202:

- ·Large quantity of mud filled inside the drain near Frazer town police station needs to be removed.
- •The existing covered drain reach near Frazer town police station needs to desilted, widened and reconstructed.
- •The existing stone slab culvert near wheelers road needs to be replaced with RCC box culvert.
- •The drain reach near Gymkhana ground needs to be desilted, widened and bed improvements to be done.

•The existing silt trap near Gymkhana ground needs to be desilted.

>Sagayapuram Drain - C203:

•The existing covered drain reach near Tannery road needs to be desilted, widened and bed protection to be done.

>Jeevanahalli Drain - C204:

- •The drain reach near Kandaswamy garden road and BDA qtrs. needs to desilted, deepened, widened and bed protection to be provided.
- •Dense vegetal growth noticed near Railway track needs to be removed and bed protection to be provided.
- •The drain reach inside M.E.G. Centre needs to be desilted, widened and stone revetment walls to be provided on either side and also bed protection to be provided.
- •The drain reach near Ulsoor lake bridge location needs to be desilted, and bed protection to be provided.

4.3 MITIGATIVE MEASURES FOR LOW LYING AREAS:

4.3.1 Vasanthanagar, Miller tank & Shivajinagar (Ward No. 78 & 79):

Mitigative Measures:

- >The existing SWD size inside Dobhi Ghat area has to be increased and also accordingly road side drain bed needs to be regraded immediately.
- •The covered portion of existing SWD (with BS slabs) near Millers road adjacent to Mount Carmal College Play Ground/Millers Arcade on Millers Road needs to be removed and the drain has to be desilted and widened immediately.
- •The existing bridge constructed across Millers road needs to replaced with single span bridge

(Refer Plate No. 1)

- •Steel gratings needs to be provided for the tertiary drain joining this primary drain opposite to Kodava samaja and Aiyappa Swamy temple.
- •The encroached portion of tertiary drain opposite to Millers Arcade needs to be properly aligned and widened.
- •Existing tertiary drains near Cunningham road, Thimmaiah Road, tank bund road, Venkataswamy naidu road, Chandani chowk road, Dharmaraja Koil street, Veera pillai street and Armugum road needs to be desilted, properly networked and widened. And also these existing tertiary drains needs to be maintained in good condition at all times.

(Refer: enclosed sketch)

- The construction debris dumped over the SWD near Ambedkar Bhavan needs to be cleared and SWD has to be widened from Millers Road upto Mahaveer Jain hospital to provide access for free flow of water and further this reach of drain needs to be protected from dumping debris into SWD.
- •The approach bridges constructed across SWD by Karnataka Badminton Association & Indian Council of social welfare needs to be immediately removed to provide access for free flow of water. (Refer Plate No. 2).
- >The concerned authority should extend the existing sewerage system to the entire locality to prevent entry of sewage into existing SWD.
- >Debris and garbage dump noticed inside the existing storm drain (both upstream & down stream) has to be cleared immediately.
- •All the disused manholes noticed near Shivajinagar area inside drainage channel needs to be dismantled immediately to avoid accumulation of silt, garbage etc. and also to provide access for free flow of water. (Refer Plate No. 3).

•The commercial shops constructed over storm water drain near Shivajinagar market has to be removed/relocated and drain has to be widened, deepened and accordingly road side drains needs to be regraded inorder to accommodate for free flow of water.

(Refer Plate No. 4).

- ·Large Nos. of public toilet blocks which have been constructed over SWD needs to be removed / relocated to provide access for free flow of water and also to prevent entry of raw sewage into storm drain. (Refer Plate No. 5).
- •The debris and vegetal growth noticed near Ulsoor lake needs to be cleared to provide access for free flow of water. (Refer Plate No. 6).
- •Large Nos. of garbage heaps noticed at many places inside the storm drain which needs to be cleared immediately to avoid blockage further down stream and also to restrict the quality of storm water from further deterioration.

(Refer Plate No. 7).

- •Retaining walls distracted for desilting needs to be restored immediately to prevent general public from dumping garbage inside the drain. (Refer Plate No. 8).
- >Caution boards/display boards have to be installed to educate and create public awareness regarding storm water and storm drain management.
- >Emergency squads have to be formed to provide necessary assistance to flood affected people during heavy storms.

4.3.2 Murgeshpalya - K.R. Garden Area (Ward No. 73):

Mitigative Measures:

- >Construction activity of RCC Box drain in K.R. Garden area has to be expedited. (Refer: Plate 1).
- >Proposed RCC Box drain needs to be extended upto Challaghatta valley primary storm drain. (Refer: Plate 2).
- >Decision on relocating the existing residential building on 8th Main Road has to be taken immediately to expedited the construction work. (Refer: enclosed sketch).
- >The concerned authority should extend the existing sewerage system to the entire locality to prevent entry of sewage into SWD.
- >Existing tertiary drains at Nanjareddy colony and Cauvery pura and K.R. garden needs to be realigned and their carrying capacity needs to be increased and also these drains needs to be maintained at regular intervals. (Refer: enclosed sketch)
- >Debris and garbage dump noticed inside the drain (both upstream & down stream) has to be cleared immediately before monsoon.
- >Caution boards/display boards has to be installed to educate and create public awareness regarding storm water and storm drain management.
- >Emergency squads have to be formed to provide necessary assistance to flood affected people during heavy storms.

4.3.3 Jogupalya and Someshwarapura (Ward No.):

Mitigative Measures:

- >Existing tertiary drains at Jogupalya and Someshwarapura main road needs to be desilted, realigned and their carrying capacity of these drains has to be increased and apart from all these drains needs to be maintained at regular intervals. (Refer: enclosed sketch)
- •Large quantity of debris and garbage dumps that are noticed needs to be removed at many places inside the existing SWD.
- •Steel gratings needs to be provided at regular intervals and also at all road junctions.
- Street sweeping and solid waste management system needs to be improved in these localities.
- •Emergency squads have to be formed to provide necessary assistance to flood affected people during heavy storms.

Munireddypalya and Chinnappa Garden (Ward No. 4.3.4):

Mitigative Measures:

- >Existing tertiary drains at Pemme gowda road, Church street, Chinnappa garden and Coles road in Frazer town needs to be desilted, realigned and their carrying capacity of these drains has to be increased and apart from all these drains needs to be maintained at regular intervals. (Refer: enclosed sketch)
- •Large quantity of debris and garbage dumps that are noticed needs to be removed at many places inside the existing SWD.

- •Steel gratings needs to be provided at regular intervals and also at all road junctions.
- •Street sweeping and solid waste management system needs to be improved in these localities.
- •Drain improvements works suggested for primary drain at these localities needs to be carried out.
- •Emergency squads have to be formed to provide necessary assistance to flood affected people during heavy storms.

Apart from above referred strategic actions and recommendations, following Best management practices also needs to be followed to achieve the very objectives of storm drains in totality.

4.4 BEST MANAGEMENT PRACTICES:

>Implement pollution prevention methods.

- >Designate and implement minimum best management practices to protect water quality.
- Implement a maintenance schedule for all structural controls designed to reduce pollutant discharges and the storm water conveyance system, to include:

•Inspection & removal of waste between May 1st and Sept. 30th.

•Additional cleaning between October 1st and April 30th.

•Records of cleaning and waste removal quantity.

•Proper waste disposal.

>Measures to eliminate discharges during maintenance & cleaning.

>Limit infiltration from sanitary sewer to storm drains through routine maintenance.

>Implement an Educational Program for all pertinent target audiences.

- >Inspect and clean catch basins and keep appropriate records.
- Remove trash and debris from open channels and properly dispose of these materials to prevent them from being washed into receiving waters.
- Report prohibited non-storm water discharges observed during the course of normal daily activities so they can be investigated, contained and cleaned up or eliminated.
- Review maintenance activities to verify that appropriate storm water maintenance practices are being utilized.
- >Educate employees for pollution prevention techniques.
- Inspect and clean as needed all inlets/catch basins at least once every other year (at least 50% of the entire system inspected and cleaned each year)
- >Inspect and clean as needed all inlets/catch basins in known problem areas at least once a year.
- >Inspect and clean as needed all storm drain lines in known problem areas at least once a year.
- >Inspect and clean as needed sumps and debris racks at pump stations, detention basins, drainage ditches and debris basins throughout the year.
- >Cleaning activities may occur on a year round basis, however, known problem areas shall be targeted prior to the rainy season.
- Inspect and clean as needed all storm drain facilities that have been affected by emergency response activities.
- >Additional cleanings shall be conducted as necessary during the non rainy

(Oct. 1st through April 30th). season

>Slide and Embankment Repair of Channels

To improve the section of the drain and to minimize the flooding problems in low lying areas, various drain improvement methods suggested are :-

1. Increase the carrying capacity of existing tertiary drains.

- 2. Provision of cut off drain (bypass drains) around the low lying area to prevent adjoining area water entering into the low lying area and construction of sump for pumping out water at a location closer to the main drains (downstream end) and also it should be located in such a way that it should be easily accessible by vehicles that are mounted with pump.
- 3. The improvement shall be taken up from the down stream of the valley. If remodeling works are commenced from upstream side, situation at the downstream end may get further aggravated.
- 4.Set-up a vigilance squad to prevent debris dumping, encroachment of drains, local obstruction, such as, pipe crossing, construction inside the drain, any discharges other than storm water.
- 5. Encourage rain water harvesting in institutions, public parks, open grounds, etc.,

	uo	Drain	Reach	Chaina	age (m)	Area A		locity c		Discharg	ges (Q in	m³/sec)		.Drain in m.	Are	ea requir	ed for dra	ain (A in	m²)	Drain m.)		Required	Drain W	/idth (m))		R	Remarks	3	
SI.No.	Description	From	То	From	То	Catchment / (Ha.)	Type	Average Velocity V m/sec	1 year	2year	5year	10year	20year	Existing Av. Depth D	1 year	2year	5year	10year	20year	Existing Av. Width W(1 year	2year	5year	10year	20year	1 year	2year	5year	10year	20year
1	C100	Palace Grounds	Millers Road	0	575	144.6	Pri.	2.61	8.22	11.32	14.43	17.01	21.3	1.5	3.15	4.34	5.53	6.52	8.16	2.5	2.1	2.89	3.69	4.34	5.44	AD	IA	IA	IA	IA
2	C100	Millers Road	Sepping's Road	575	2200	304.17	Pri.	2.89	18.15	25.06	32.04	37.93	47.11	2	6.28	8.67	11.09	13.12	16.3	5	3.14	4.33	5.54	6.56	8.15	AD	AD	IA	IA	IA
3	C100	Sepping's Road	Anna Swamy Mudaliar Road	2200	3175	450.74	Pri.	2.36	26.38	36.53	46.88	55.75	68.65	2.25	11.18	15.48	19.86	23.62	29.09	9.5	4.97	6.88	8.83	10.5	12.93	AD	AD	AD	IA	IA
4	C100	Anna Swamy Mudaliar Road	Kensngton Road	3175	3975	605.66	Pri.	1.81	33.98	47.14	60.65	72.36	88.58	2.68	18.78	26.04	33.51	39.98	48.94	15.5	7.01	9.72	12.5	14.92	18.26	AD	AD	AD	AD	IA
5	C100	Kensngton Road	Sathya Narayana Temple Street	3975	4500	1299.08	Pri.	4.16	38.04	52.83	68.08	81.37	99.25	2.69	9.14	12.7	16.37	19.56	23.86	13	3.4	4.72	6.08	7.27	8.87	AD	AD	AD	AD	AD
6	C100	Sathya Narayana Temple Street	Saraswathpura Road	4500	5500	1522.81	Pri.	3.06	47.38	66.06	85.56	102.93	124.06	2.48	15.48	21.59	27.96	33.64	40.54	15	6.24	8.71	11.27	13.56	16.35	AD	AD	AD	AD	IA
7	C100	Saraswathpura Road	Shammana Gowda Layout 4 th Main Road	5500	5800	1871.98	Pri.	3.26	66.24	92.17	119.05	142.71	173.13	2.1	20.32	28.27	36.52	43.78	53.11	17.5	9.68	13.46	17.39	20.85	25.29	AD	AD	AD	IA	IA
8		Shammana Gowda Layout 4th Main Road	Domlur listage near TERI	5800	7075	2274.67	Pri.	3.04	82.39	115.17	149.61	180.69	216.19	2.19	27.1	37.88	49.21	59.44	71.11	15	12.38	17.3	22.47	27.14	32.47	AD	IA	IA	IA	IA
9	C100	Domlur listage near TERI	Airport Road	7075	7675	2408.57	Pri.	2.66	86.96	121.69	158.31	191.54	228.4	2.48	32.69	45.75	59.51	72.01	85.86	22	13.18	18.45	24	29.04	34.62	AD	AD	IA	IA	IA
10	C100	Airport Road	Royal Orchid Park Hotel	7675	8225	2671.06	Pri.	3.16	101.18	141.52	183.99	222.42	265.64	3.02	32.02	44.78	58.22	70.39	84.06	22	10.6	14.83	19.28	23.31	27.84	AD	AD	AD	IA	IA
11	C100	Royal Orchid Park Hotel	Wind Tunnel Road	8225	9350	3034.15	Pri.	2.63	111.79	156.76	204.45	248.16	294.15	2.2	42.51	59.6	77.74	94.36	111.84	18	19.32	27.09	35.33	42.89	50.84	IA	IA	IA	IA	IA
12	C100	Wind Tunnel Road	Bellur Main Road	9350	10275	3417.28	Pri.	2.77	125.45	176.14	230.11	279.9	330.46	1.83	45.29	63.59	83.07	101.05	119.3	15	24.75	34.75	45.39	55.22	65.19	IA	IA	IA	IA	IA
13	C101	Anandanagar	K.R. Garden	0	1875	217.53	Sec.	2.1	8.39	11.8	15.45	18.83	22.13	1.1	3.99	5.62	7.36	8.97	10.54	2	3.63	5.11	6.69	8.15	9.58	IA	IA	IA	IA	IA
14	C105	Jeevanbhimanagar	Kodihalli	0	2500	262.49	Sec.	2.62	14.22	19.83	25.68	30.88	37.24	1.8	5.43	7.57	9.8	11.79	14.21	3.65	3.02	4.2	5.45	6.55	7.9	AD	IA	IA	IA	IA

Table Showing Adequacy Analysis Results for Challaghatta Valley - Existing Hydraulic Flow Conditions

Table	Showing	Adequacy Analysis	Results for Ulsoor	Valley -	- Existing Hydraulic Flow Conditions
-------	---------	-------------------	---------------------------	----------	--------------------------------------

	uo	Drain R	each	Chaina	age (m)	Area A		ocity V	[Discharg	es (Q in	m³/sec)		.Drain in m.	Area	a require	d for dra	in (A in	1 m²)	Drain (m.)	F	Require	d Drain '	Width (r	n)		R	emark	6	
SI.No.	Description	From	То	From	То	Catchment / (Ha.)	Type	Average Velocity m/sec	1year	2year	5year	10year	20year	Existing Av. Depth D	1year	2year	5year	10year	20year	Existing Av. I Width W(1year	2year	5year	10year	20year	1year	2year	5year	10year	20year
1	C200	J.C.Nagar Main Road	S.K.Garden Main Road	0	1625	239.76	Pri.	3.76	12.47	17.31	22.27	26.57	32.52	2	3.32	4.6	5.92	7.07	8.65	4.8	1.66	2.3	2.96	3.53	4.32	AD	AD	AD	AD	AD
2	C200	S.K.Garden Main Road	Bore Bank Road	1625	2150	336.94	Pri.	3.31	17.63	24.48	31.52	37.64	45.99	2.1	5.33	7.4	9.52	11.37	13.89	7.8	2.54	3.52	4.53	5.41	6.62	AD	AD	AD	AD	AD
3		Bore Bank Road	More Road	2150	2550	353.87	Pri.	3.01	18.81	26.09	33.57	40.04	49.03	2.63	6.25	8.67	11.15	13.3	16.29	10.45	2.38	3.3	4.24	5.06	6.19	AD	AD	AD	AD	AD
4	C200	More Road	Wheeler's Road	2550	3350	468.48	Pri.	3.12	24.94	34.63	44.63	53.33	65.07	2.46	7.99	11.1	17.09	17.09	20.85	10.41	3.25	4.51	6.95	6.95	8.48	AD	AD	AD	AD	AD
5	C200	Wheeler's Road	Ulsoor Tank	3350	4200	500.59	Pri.	3.01	27.1	37.61	48.41	57.78	70.67	2	9	12.49	16.08	19.2	23.48	10.4	4.5	6.25	8.04	9.6	11.74	AD	AD	AD	AD	IA
6	C202	Richards Town	Gymkana Ground	0	1170	32.11	Sec.	3.05	2.17	2.98	3.79	4.45	5.6	1.7	0.71	0.98	1.24	1.46	1.84	5.4	0.42	0.57	0.73	0.86	1.08	AD	AD	AD	AD	AD
7	C203	Sagayapuram	Cleveland Town	0	737	16.93	Sec.	3.14	1.18	1.62	2.05	2.4	3.04	1.6	0.38	0.51	0.65	0.77	0.97	2.42	0.23	0.32	0.41	0.48	0.61	AD	AD	AD	AD	AD
8	C204	Jeevanahalli	Ulsoor Tank	0	2000	192.83	Sec.	2.38	10.93	15.22	19.67	23.59	28.59	1.24	4.59	6.39	8.26	9.91	12.01	4	3.7	5.16	6.66	7.99	9.69	AD	IA	IA	IA	IA

ıt drain	Chai	nage	ant	a.)	d paved	lopen a.)	ousness	nutes	Ë	Velo	rage city in sec.	nin.)	min.)	f min.)	nt "C"	Rainfa	all Inter	nsity "i'	' in mn	n/hour	Qı	uantity (C	ຊ)= 10 C.	iAm3/⊧	sec.	th in m	ain m	Area	a requ	uired fo m2	or Drai	in in	Widt	th requ	uired for	r drain	in m
Description about drain	from	to	Sub Catchment	Total Area (Ha.)	Area of bulitup and paved areas (Ha.)	Area of parks and open space, etc. (Ha.)	Weighted Imperviousnes (%)	Inlet Time in minutes	Slope of terain	For terain	For Drain	Flow in drain (min.)	Flow in Terain (min.)	Total time of concentration (min.)	Runoff Coeffiecent "C'	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	Existing Ave.width in m	Ave. Depth of drain m	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)
C100	0	575	A1(a)	95.38	67.64	27.74	59	12.33	0.01	1.2	2.61	3.67	9.72	25.72	0.448	46.57	64.08	81.63	96.14	120.55	5.53	7.61	9.69	11.41	14.31												
			A1(b)	49.22	31.85	17.37	55.59	12.82	0.01	1.2	2.61	3.67	10.42	26.91	0.437	45.18	62.26	79.44	93.79	117.08	2.7	3.72	4.74	5.6	6.99												
			Total	144.6							2.61										8.22	11.32	14.43	17.01	21.3	2.5	1.5	3.2	4.3	5.5	6.5	8.2	2.1	2.9	3.7 4	4.3	5.4
C100	575	2200	A2 (a)	59.93	59.93	0	75	10	0.02	1.5	2.89	9.37	7.78	27.15	0.524	44.91	61.91	79.03	93.34	116.42	3.91	5.4	6.89	8.14	10.15												
			A2 (b)	99.64	99.64	0	75	10	0.01	1.2	2.89	9.37	13.19	32.57	0.547	39.74	55.10	70.87	84.49	103.55	6.01	8.34	10.72	12.78	15.67												
				159.57																	9.93	13.73	17.61	20.92	25.82												
			Total	304.17							2.89			32.57							18.15	25.06	32.04	37.93	47.11	5	2	6.3	8.7	11.1	13.1	16.3	3.1	4.3	5.5 6	6.6	8.2
C100	2200	3175	A3 (a1)	87.97	87.97	0	75	10	0.01	1.2	2.36	18.36	8.33	36.69	0.561	36.67	51.05	65.98	79.15	95.88	5.03	7	9.05	10.86	13.15												
			A3 (b1)	58.6	56.26	2.34	72.8	10.32	0.01	1.2	2.36	18.36	10.42	39.1	0.560	35.14	49.02	63.52	76.45	92.04	3.2	4.47	5.79	6.97	8.39										$ \rightarrow$	\bot	
				146.57																	8.23	11.47	14.84	17.82	21.54											\perp	
			Total	450.74							2.36			39.1							26.38	36.53	46.88	55.75	68.65	9.5	2.25	11.2	15.5	19.9	23.6	29.1	5.0	6.9	8.8 1	0.5	12.9
																															$\left - \right $					+	
C100	3175	3975	A3 (a2)	95.44	91.26	4.18	72.59	10.35	0.01	1.2	1.81	16.34	13.19	39.89	0.560	34.66	48.40	62.76	75.61	90.86	5.14	7.18	9.31	11.22	13.48						\mid				\rightarrow	\rightarrow	
			A3 (b2)	59.48	24.16	35.32	42.34	14.75	0.01	1.2	1.81	16.34	10.42	41.51	0.441	33.75	47.18	61.28	73.98	88.56	2.46	3.43	4.46	5.38	6.45											+	
				154.92																	7.6	10.62	13.77	16.61	19.93						$\left - \right $					+	
			Total	605.66							1.81			41.51							33.98	47.14	60.65	72.36	88.58	15.5	2.68	18.8	26.0	33.5	40.0	48.9	7.0	9.7	12.5 1	4.9	18.3
C200	0	1625	A1(a)	26.26	15		51.42	13.43	0.01		3.76			31.74	0.44			71.96		105.27		1.81	2.33	2.77	3.41						\mid				\rightarrow	+	\square
			A1(b)	172.64	130.49		61.57	11.95			3.76	7.2		33.05	0.492		54.59			102.58		12.89	16.59	19.79	24.22						\mid				\rightarrow	+	
			A1(c)	40.86	18.81	22.05	45.32	14.32	0.02	1.5	3.76	7.2	12.22	33.74	0.426	38.80	53.87	69.38	82.87	101.21	1.88	2.6	3.35	4.01	4.89						\mid				\rightarrow	+	
			Total	239.76							3.76			33.74							12.47	17.31	22.27	26.57	32.52	4.8	2	1.5	4.6	5.9	7.1	8.6	0.8	2.3	3.0 3	3.5	4.3

Remodeling of Primary and Secondary Storm Water Drain in Bangaore City

Feasibility Report for Challaghatta Valley

ıt drain	Chai	nage	ant	la.)	d paved	l open la.)	ousness	nutes	Ŀ		rage city in sec.	min.)	(min.)	of min.)	nt "C"	Rainfa	all Inter	nsity "i'	' in mn	n/hour	Qı	uantity (C	ຊ)= 10 C.	iAm3∕	sec.	th in m	ain m	Area	a requ	iired fo m2	or Drai	n in	Wid	th requ	Jired fc	or drain	in m
Description about drain	from	to	Sub Catchment	Total Area (Ha.)	Area of bulitup and paved areas (Ha.)	Area of parks and open space, etc. (Ha.)	Weighted Imperviousnes (%)	Inlet Time in minutes	Slope of terain	For terain	For Drain	Flow in drain (min.)	Flow in Terain (min.)	Total time of concentration (min.)	Runoff Coeffiecent "C'	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	Existing Ave.width in m	Ave. Depth of drain m	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)
																																	\square		\square	\square	
C200	1625	2150	A2 (a)	68.53	64.48	4.05	71.75	10.47	0.01	1.2	3.31	10.83	13.61	34.91	0.537	37.92	52.71	67.98	81.34	99.01	3.88	5.39	6.95	8.32	10.13												
			A3 (a)	28.65	12.72	15.93	44.42	14.45	0.01	1.2	3.31	10.83	9.72	35	0.425	37.86	52.62	67.88	81.23	98.86	1.28	1.78	2.3	2.75	3.35								\square		\square	\square	
				97.18																	5.16	7.17	9.25	11.07	13.47								\square		\square	\square	
			Total	336.94							3.31			35							17.63	24.48	31.52	37.64	45.99	7.8	2.1	2.5	7.4	9.5	11.4	13.9	1.2	3.5	4.5	5.4	6.6
C203	0	737	A3 (b)	16.93	16.93	0	75	10	0.01	1.2	3.14	2.12	11.11	23.23	0.503	49.87	68.39	86.75	101.64	128.71	1.18	1.62	2.05	2.4	3.04								$ \rightarrow$		$ \rightarrow $	$ \rightarrow $	
			Total	16.93							3.14										1.18	1.62	2.05	2.4	3.04	2.42	1.6	0.4	0.5	0.7	0.8	1.0	0.2	0.3	0.4	0.5	0.6
C200	2150	2550	Total	353.87							3.01			37.12							18.81	26.09	33.57	40.04	49.03	10.4 5	2.63	6.3	8.7	11.2	13.3	16.3	2.4	3.3	4.2	5.1	6.2
C200	2550	3350	A4 (a)	78.02	76.49	1.53	73.92	10.16	0.01	1.2	3.12	17.9	9.72	37.77	0.557	35.96	50.11	64.84	77.90	94.11	4.34	6.05	7.82	9.4	11.35										\square		
			A5 (a)	36.59	26.25	10.34	59.46	12.26	0.02	1.5	3.12	17.9	10	40.15	0.509	34.51	48.19	62.51	75.34	90.48	1.78	2.49	3.23	3.9	4.68												
				114.61																	6.12	8.54	11.06	13.29	16.03												
			Total	468.48							3.12			40.15							24.94	34.63	44.63	53.33	65.07	10.4 1	2.46	8.0	11.1	14.3	17.1	20.9	3.2	4.5	5.8	6.9	8.5
C202	0	1170	A6 (a)	32.11	32.11	0	75	10	0.01	1.2	3.05	6.39	8.33	24.73	0.508	47.83	65.72	83.58	98.24	123.65	2.17	2.98	3.79	4.45	5.6												
			Total	32.11							3.05										2.17	2.98	3.79	4.45	5.6	5.4	1.7	0.7	1.0	1.2	1.5	1.8	0.4	0.6	0.7	0.9	1.1
C200	3350	4200	Total	500.59							3.01			46.55							27.1	37.61	48.41	57.78	70.67	11	2	9.0	12.5	16.1	19.2	23.5	4.5	6.2	8.0	9.6	11.7
																																			\square		
C204	0	2000	A6 (b)	114.77	110.49	4.28	72.95	10.3	0.01	1.2	2.38	14.01	9.72	34.03	0.542	38.58	53.58	69.03	82.49	100.66	6.66	9.25	11.92	14.24	17.38										\square		
			A7 (a)	78.06	78.06	0	75	10	0.02	1.5	2.38	14.01	16.67	40.67	0.576	34.21	47.80	62.04	74.81	89.73	4.27	5.97	7.75	9.34	11.21												
			Total	192.83							2.38			40.67							10.93	15.22	19.67	23.59	28.59		1.24	4.6	6.4	8.3	9.9	12.0					9.7
																					38.04	52.83	68.08	81.37	99.25	In ti	his cha	linage,	100%	of UI		orm W ake	ater o	verflov	vs from	n the UI	soor
C100	3975	4500	Total	1299.08							4.16			46.55							38.04	52.83	68.08	81.37	99.25	13	2.69	9.1	12.7	16.4	19.6	23.9	3.4	4.7	6.1	7.3	8.9
C100	4500	5500	A4 (a)	105.2	105.2	0	75	10	0.01	1.2	3.06	32.68	16.67	59.35	0.629	26.53	37.53	49.47	60.83	70.35	4.87	6.89	9.09	11.17	12.92												

Remodeling of Primary and Secondary Storm Water Drain in Bangaore City

Feasibility Report for Challaghatta Valley

ıt drain	Chai	nage	ant	la.)	d paved	lopen a.)	ousness	nutes	n	Ave Veloc m/s		min.)	(min.)	ıf min.)	nt "C"	Rainfa	all Inter	nsity "i'	' in mn	n/hour	Qı	antity (C	ຊ)= 10 C.	iAm3/	sec.	th in m	ain m	Area	a requ	iired fo m2	or Drai	n in	Wid	th requ	lired for	drain in m
Description about drain	from	to	Sub Catchment	Total Area (Ha.)	Area of bulitup and paved areas (Ha.)	Area of parks and open space, etc. (Ha.)	Weighted Imperviousnes (%)	Inlet Time in minutes	Slope of terain	For terain	For Drain	Flow in drain (min.)	Flow in Terain (min.)	Total time of concentration (min.)	Runoff Coeffiecent "C'	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	Existing Ave.width in m	Ave. Depth of drain m	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year) (For 20 Year)
			A4 (b1)	118.53	79.65	38.88	56.96	12.62	0.01	1.2	3.06	32.68	20.83	66.14	0.550	24.67	35.02	46.36	57.33	65.60	4.47	6.34	8.4	10.38	11.88											
				223.73																	9.34	13.23	17.48	21.56	24.8											
			Total	1522.81							3.06			66.14							47.38	66.06	85.56	102.93	124.06	15	2.48	15.5	21.6	28.0	33.6	40.5	6.2	8.7	11.3 1	3.6 16.3
C102	0	500	A4 (c)	87.64	44.09	43.55	47.67	13.98	0.01	1.2	2.64	3.16	8.33	25.47	0.399	46.89	64.50	82.12	96.67	121.32	4.55	6.27	7.98	9.39	11.79											
			A4 (d)	158.91	101.54	57.37	55.14	12.89	0.01	1.2	2.64	3.16	13.89	29.93	0.452	42.05	58.16	74.54	88.48	109.32	8.39	11.6	14.87	17.65	21.8											
			Total	246.55							2.64										12.94	17.86	22.84	27.04	33.59	4	2.3	4.9	6.8	8.7	10.2	12.7	2.1	2.9	3.8 4	4.5 5.5
C102	500	1250	A4 (b2)	102.62	102.62	0	75	10	0.01	1.2	2.51	4.98	20.83	35.81	0.558	37.27	51.85	66.95	80.21	97.40	5.93	8.24	10.64	12.75	15.48											
				102.62																	5.93	8.24	10.64	12.75	15.48											
				349.17							2.51										18.87	26.11	33.49	39.79	49.07	5	2	7.5	10.4	13.3	15.9	19.6	3.8	5.2	6.7 7	7.9 9.8
C100	5500	5800	Total	1871.98							3.26			69.29							66.24	92.17	119.05	142.71	173.13	17.5	2.1	20.3	28.3	36.5	43.8	53.1	9.7	13.5	17.4 2	0.8 25.3
C100	5800	7075	A5 (a)	129.91	118.79	11.12	70.29	10.68	0.01	1.2	3.04	35.64	25	71.32	0.610	23.44	33.37	44.32	55.01	62.49	5.16	7.34	9.75	12.1	13.74											
			A5 (b)	272.78	272.78	0	75	10	0.01	1.2	3.04	35.64	27.78	73.41	0.631	22.99	32.76	43.55	54.15	61.34	10.99	15.65	20.82	25.88	29.32										\square	
				402.69																	16.15	22.99	30.56	37.98	43.06											
			Total	2274.67							3.04			73.41							82.39	115.17	149.61	180.69	216.19	15	2.19	27.1	37.9	49.2	59.4	71.1	12.4	17.3	22.5 2	7.1 32.5
																																			\bot	
C100	7075	7675	A6 (a)	133.9	94.76	39.14	58.92	12.34	0.01	1.2	2.66	44.49	21.6	78.42	0.559	21.99	31.40	41.87	52.23	58.78	4.57	6.52	8.7	10.85	12.21										\bot	
				133.9																	4.57	6.52	8.7	10.85	12.21										\bot	
			Total	2408.57							2.66			78.42							86.96	121.69	158.31	191.54	228.4	22	2.48	32.7	45.7	59.5	72.0	85.9	13.2	18.4	24.0 2	9.0 34.6
																													\square			⊢			\bot	\perp
C105	0	2500	A6 (b)	62.7	62.7	0	75	10	0.02	1.5	2.2	5.3	20	35.3	0.558	37.63	52.33	67.52	80.84	98.30	3.66	5.08	6.56	7.85	9.55				\square			⊢			\bot	\perp
			A6 (c)	199.79	180.85	18.94	69.79	10.76	0.01	1.2	2.2	5.3	23.61	39.67	0.547	34.79	48.56	62.97	75.84	91.18	10.57	14.75	19.12	23.03	27.69				\square			⊢			\bot	\perp
				262.49							2.2										14.22	19.83	25.68	30.88	37.24	3.65	1.8	6.5	9.0	11.7	14.0	16.9	3.6	5.0	6.5 7	7.8 9.4

about drain	Chai	inage	ant	(На.)	d paved	l open a.)	ousness	minutes	'n	Velo	rage city in sec.	(min.)	(min.)	of (min.)	nt "C"	Rainfa	all Inter	nsity "i'	' in mn	n/hour	Qı	antity (C	Q)= 10 C.	iAm3∕	sec.	th in m	ain m	Area	a requ	uired fo m2	or Dra	in in	Wid	lth requ	uired fo	or drai	n in m
Description abou	from	to	Sub Catchment	Total Area (H	Area of bulitup and paved areas (Ha.)	Area of parks and space, etc. (Ha	Weighted Imperviousnes (%)	Inlet Time in mi	Slope of terain	For terain	For Drain	Flow in drain (Flow in Terain	Total time c concentration (Runoff Coeffiecent	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	Existing Ave.width	Ave. Depth of drain	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)
C100	7675	8225	Total	2671.06							3.16			83.72							101.18	141.52	183.99	222.42	265.64	22	3.02	32.0	44.8	58.2	70.4	84.1	10.6	14.8	19.3	23.3	27.8
C100	8225	9350	A7 (a)	174.05	56.94	117.11	37.99	15.38	0.01	1.2	2.63	55.61	19.44	90.44	0.469	19.98	28.66	38.44	48.31	53.63	4.53	6.5	8.72	10.96	12.17			is Chaii ainage									
			A7 (b)	189.04	164.28	24.76	67.8	11.05	0.01	1.2	2.63	55.61	27.78	94.43	0.597	19.41	27.88	37.46	47.18	52.15	6.08	8.74	11.74	14.78	16.34		GI	anage	urann	deptil,		ove wi		13 163	is than	i inai c	i tile
				363.09																	10.62	15.24	20.46	25.74	28.51												
			Total	3034.15							2.63			94.43							111.79	156.76	204.45	248.16	294.15	18	2.2	42.5	59.6	77.7	94.4	111.8	19.3	27.1	35.3	42.9	50.8
C101	0	1875	A7 (c)	163.44	74.56	88.88	45.09	14.35	0.01	1.2	2.1	14.88	19.44	48.68	0.48	30.32	42.61	55.71	67.81	79.93	6.54	9.19	12.01	14.62	17.24												
			A8(c1)	54.09	13.78	40.31	34.01	15.96	0.01	1.2	2.1	14.88	25	55.84	0.45	27.64	39.02	51.31	62.89	73.16	1.85	2.61	3.43	4.21	4.9												
			Total	217.53							2.1										8.39	11.8	15.45	18.83	22.13	2	1.1	4.0	5.6	7.4	9.0	10.5	3.6	5.1	6.7	8.2	9.58
C100	9350	10275	A8(a)	165.6	155.55	10.05	71.66	10.49	0.01	1.2	2.77	61.82	27.78	100.09	0.61	18.66	26.86	36.18	45.7	50.24	5.27	7.58	10.21	12.9	14.18												
			Total	3417.28							2.77										125.45	176.14	230.11	279.9	330.46	15	1.83	45.3	63.6	83.1	101.0	119.3	24.7	34.7	45.4	55.2	65.19

	u	Drain	Reach	Chaina	age (m)	rea A		city V		Discha	rges (Q in r	n³/sec)		Drain m.	Ar	ea requir	ed for dra	ain (A in i	m²)	. Drain m.)		Require	ed Drain	Width (m)			R	emarks	3	
SI.No.	Description	From	То	From	То	Catchment Area / (Ha.)	Type	Average Veloo m/sec	1 year	2year	5year	10year	20year	Proposed Av. Depth D in	1year	2year	5year	10year	20year	Proposed Av. Width W(1year	2year	5year	10year	20year	1 year	2year	5year	10year	20year
1	C100	Palace Grounds	Millers Road	0	575	144.6	Pri.	3.96	8.22	11.32	14.43	17.01	21.3	1.5	2.08	2.86	3.65	4.3	5.38	2.5	1.39	1.91	2.43	2.87	3.59	AD	AD	AD	IA	IA
2	C100	Millers Road	Sepping's Road	575	2200	304.17	Pri.	4.17	18.15	25.06	32.04	37.93	47.11	2	4.36	6.02	7.69	9.11	11.31	5	2.18	3.01	3.85	4.55	5.66	AD	AD	AD	AD	IA
3	C100	Sepping's Road	Anna Swamy Mudaliar Road	2200	3175	450.74	Pri.	4.08	26.38	36.53	46.88	55.75	68.65	2.25	6.46	8.94	11.48	13.65	16.81	9.5	2.87	3.97	5.1	6.07	7.47	AD	AD	AD	AD /	AD
4	C100	Anna Swamy Mudaliar Road	Kensngton Road	3175	3975	605.66	Pri.	2.88	33.98	47.14	60.65	72.36	88.58	2.68	11.8	16.36	21.05	25.12	30.75	15.5	4.4	6.11	7.86	9.37	11.47	AD	AD	AD	AD /	AD
5	C100	Kensngton Road	Sathya Narayana Temple Street	3975	4500	1299.08	Pri.	5.40	38.04	52.83	68.08	81.37	99.25	2.69	7.04	9.78	12.61	15.07	18.38	13	2.62	3.64	4.69	5.6	6.83	AD	AD	AD	AD /	AD
6	C100	Sathya Narayana Temple Street	Saraswathpura Road	4500	5500	1522.81	Pri.	4.08	47.38	66.06	85.56	102.93	124.06	2.48	11.62	16.2	20.98	25.24	30.42	15	4.68	6.53	8.46	10.18	12.27	AD	AD	AD	AD /	AD
7	C100	Saraswathpura Road	Shammana Gowda Layout 4 th Main Road	5500	5800	1871.98	Pri.	3.67	66.24	92.17	119.05	142.71	173.13	2.1	18.06	25.12	32.45	38.9	47.19	17.5	8.6	11.96	15.45	18.52	22.47	AD	AD	AD	IA	IA
8	C100	Shammana Gowda Layout 4th Main Road	Domlur listage nea TERI	r 5800	7075	2274.67	Pri.	3.50	82.39	115.17	149.61	180.69	216.19	2.4	23.54	32.9	42.75	51.63	61.77	20	9.81	13.71	17.81	21.51	25.74	AD	AD	AD	IA	IA
9	C100	Domlur listage near TERI	Airport Road	7075	7675	2408.57	Pri.	2.92	86.96	121.69	158.31	191.54	228.4	2.48	29.77	41.66	54.19	65.57	78.19	22	12	16.8	21.85	26.44	31.53	AD	AD	AD	IA	IA
10	C100	Airport Road	Royal Orchid Park Hotel	7675	8225	2671.06	Pri.	3.39	101.18	141.52	183.99	222.42	265.64	3.02	29.85	41.75	54.28	65.62	78.37	22	9.88	13.83	17.97	21.73	25.95	AD	AD	AD	AD	IA
11	C100	Royal Orchid Park Hotel	Wind Tunnel Road	8225	9350	3034.15	Pri.	3.10	111.79	156.76	204.45	248.16	294.15	2.8	36.06	50.57	65.95	80.05	94.89	24	12.88	18.06	23.55	28.59	33.89	AD	AD	AD	IA	IA
12	C100	Wind Tunnel Road	Bellur Main Road	9350	10275	3417.28	Pri.	3.70	125.45	176.14	230.11	279.9	330.46	2.4	33.91	47.61	62.19	75.65	89.31	26	14.13	19.84	25.91	31.52	37.21	AD	AD	AD	IA	IA
13	C101	Anandanagar	K.R. Garden	0	1875	217.53	Sec.	3.80	8.39	11.8	15.45	18.83	22.13	1.4	2.21	3.11	4.07	4.96	5.82	3.5	1.58	2.22	2.9	3.54	4.16	AD	AD	AD	IA	IA
14	C105	Jeevanbhimanagar	Kodihalli	0	2500	262.49	Sec.	3.70	14.22	19.83	25.68	30.88	37.24	1.8	3.84	5.36	6.94	8.35	10.06	4	2.14	2.98	3.86	4.64	5.59	AD	AD	AD	IA	IA

Table Showing Adequacy Analysis Results for Challaghatta Valley - Proposed Hydraulic Flow Conditions

	u	Drain R	each	Chaina	age (m)	Area A		Velocity V 'sec	[Discharg	es (Q in	m³/sec))	.Drain in m.	Are	ea require	ed for dra	in (A in r	n²)	Drain (m.)	I	Require	ed Drain	Width (I	n)		R	emarks	 3	
SI.No.	Description	From	То	From	То	Catchment / (Ha.)	Type	Average Vel m/sec	1 year	2year	5year	10year	20year	Existing Av. Depth D i	1 year	2year	5year	10year	20year	Existing Av. I Width W(1 year	2year	5year	10year	20year	1year	2year	5year	10year	20year
1	C200	J.C.Nagar Main Road	S.K.Garden Main Road	0	1625	239.76	Pri.	5.4	12.47	17.31	22.27	26.57	32.52	2	2.31	3.2	4.12	4.92	6.02	4.8	1.15	1.6	2.06	2.46	3.01	AD	AD	AD	AD	AD
2	C200		Bore Bank Road	1625	2150	336.94	Pri.	4.49	17.63	24.48	31.52	37.64	45.99	2.1	3.92	5.45	7.02	8.38	10.24	7.8	1.87	2.59	3.34	3.99	4.87	AD	AD	AD	AD	AD
3	C200	Bore Bank Road	More Road	2150	2550	353.87	Pri.	4.29	18.81	26.09	33.57	40.04	49.03	2.63	4.38	6.08	7.82	9.32	11.42	10.45	1.67	2.31	2.97	3.54	4.34	AD	AD	AD	AD	AD
4	C200		Wheeler's Road	2550	3350	468.48	Pri.	4.31	24.94	34.63	44.63	53.33	65.07	2.46	5.78	8.03	12.37	12.37	15.09	10.41	2.35	3.27	5.03	5.03	6.14	AD	AD	AD	AD	AD
5	C200	Wheeler's Road	Ulsoor Tank	3350	4200	500.59	Pri.	2.59	27.1	37.61	48.41	57.78	70.67	2	10.45	14.5	18.67	22.29	27.25	10.4	5.23	7.25	9.34	11.14	13.63	AD	AD	AD	IA	IA
6	C202	Richards Town	Gymkana Ground	0	1170	32.11	Sec.	5.4	2.17	2.98	3.79	4.45	5.6	1.7	0.4	0.55	0.7	0.82	1.04	5.4	0.24	0.32	0.41	0.48	0.61	AD	AD	AD	AD	AD
7	C203	Sagayapuram	Cleveland Town	0	737	16.93	Sec.	4.61	1.18	1.62	2.05	2.4	3.04	1.6	0.26	0.35	0.44	0.52	0.66	2.42	0.16	0.22	0.28	0.33	0.41	AD	AD	AD	AD	AD
8	C204	Jeevanahalli	Ulsoor Tank	0	2000	192.83	Sec.	3.5	10.93	15.22	19.67	23.59	28.59	1.6	3.12	4.35	5.62	6.74	8.17	4	1.95	2.72	3.51	4.21	5.1	AD	AD	AD	IA	IA

Table Showing Adequacy Analysis Results for Ulsoor Valley - Proposed Hydraulic Flow Conditions

ıt drain	Chai	nage	ant	la.)	d paved	lopen a.)	nsness	nutes	Ē	Veloc	rage city in sec.	nin.)	min.)	f min.)	nt "C"	Rainfa	all Inte	nsity "i'	' in mn	n/hour	Qu	uantity (C	ຊ)= 10 C.	iAm3/s	sec.	th in m	ain m	Area	requir	ed for	Drain i	in m2	Wid	lth requ	ired for	r drain i	n m
Description about drain	from	to	Sub Catchment	Total Area (Ha.)	Area of bulitup and pavec areas (Ha.)	Area of parks and open space, etc. (Ha.)	Weighted Imperviousness (%)	Inlet Time in minutes	Slope of terain	For terain	For Drain	Flow in drain (min.)	Flow in Terain (min.)	Total time of concentration (min.)	Runoff Coeffiecent "C'	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	Existing Ave.width in m	Ave. Depth of drain m	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)
C100	0	575	A1(a)	95.38	67.64	27.74	59	12.33	0.01	1.2	2.61	3.67	9.72	25.72	0.448	46.57	64.08	81.63	96.14	120.55	5.53	7.61	9.69	11.41	14.31												
			A1(b)	49.22	31.85	17.37	55.59	12.82	0.01	1.2	2.61	3.67	10.42	26.91	0.437	45.18	62.26	79.44	93.79	117.08	2.7	3.72	4.74	5.6	6.99												
			Total	144.6							2.61										8.22	11.32	14.43	17.01	21.3	2.5	1.5	3.2	4.3	5.5	6.5	8.2	2.1	2.9	3.7	4.3	5.4
C100	575	2200	A2 (a)	59.93	59.93	0	75	10	0.02	1.5	2.89	9.37	7.78	27.15	0.524	44.91	61.91	79.03	93.34	116.42	3.91	5.4	6.89	8.14	10.15												
			A2 (b)	99.64	99.64	0	75	10	0.01	1.2	2.89	9.37	13.19	32.57	0.547	39.74	55.10	70.87	84.49	103.55	6.01	8.34	10.72	12.78	15.67												
				159.57																	9.93	13.73	17.61	20.92	25.82												
			Total	304.17							2.89			32.57							18.15	25.06	32.04	37.93	47.11	5	2	6.3	8.7	11.1	13.1	16.3	3.1	4.3	5.5	6.6	8.2
C100	2200	3175	A3 (a1)	87.97	87.97	0	75	10	0.01	1.2	2.36	18.36	8.33	36.69	0.561	36.67	51.05	65.98	79.15	95.88	5.03	7	9.05	10.86	13.15												
			A3 (b1)	58.6	56.26	2.34	72.8	10.32	0.01	1.2	2.36	18.36	10.42	39.1	0.560	35.14	49.02	63.52	76.45	92.04	3.2	4.47	5.79	6.97	8.39												
				146.57																	8.23	11.47	14.84	17.82	21.54												
			Total	450.74							2.36			39.1							26.38	36.53	46.88	55.75	68.65	9.5	2.25	11.2	15.5	19.9	23.6	29.1	5.0	6.9	8.8	10.5	12.9
C100	3175	3975	A3 (a2)	95.44	91.26	4.18	72.59	10.35	0.01	1.2	1.81	16.34	13.19	39.89	0.560	34.66	48.40	62.76	75.61	90.86	5.14	7.18	9.31	11.22	13.48												
			A3 (b2)	59.48	24.16	35.32	42.34	14.75	0.01	1.2	1.81	16.34	10.42	41.51	0.441	33.75	47.18	61.28	73.98	88.56	2.46	3.43	4.46	5.38	6.45												
				154.92																	7.6	10.62	13.77	16.61	19.93												
			Total	605.66							1.81			41.51							33.98	47.14	60.65	72.36	88.58	15.5	2.68	18.8	26.0	33.5	40.0	48.9	7.0	9.7	12.5	14.9	18.3
C200	0	1625	A1(a)	26.26	15	11.26	51.42	13.43	0.01	1.2	3.76	7.2	11.11	31.74	0.44	40.42	56.01	71.96	85.68	105.27	1.31	1.81	2.33	2.77	3.41												
			A1(b)	172.64	130.49	42.15	61.57	11.95	0.01	1.2	3.76	7.2	13.89	33.05	0.492	39.35	54.59	70.25	83.82	102.58	9.29	12.89	16.59	19.79	24.22												
			A1(c)	40.86	18.81	22.05	45.32	14.32	0.02	1.5	3.76	7.2	12.22	33.74	0.426	38.80	53.87	69.38	82.87	101.21	1.88	2.6	3.35	4.01	4.89												
			Total	239.76							3.76			33.74							12.47	17.31	22.27	26.57	32.52	4.8	2	1.5	4.6	5.9	7.1	8.6	0.8	2.3	3.0	3.5	4.3
C200	1625	2150	A2 (a)	68.53	64.48	4.05	71.75	10.47	0.01	1.2	3.31	10.83	13.61	34.91	0.537	37.92	52.71	67.98	81.34	99.01	3.88	5.39	6.95	8.32	10.13												

STUP Consultants Ltd.

Feasibility Report for Challaghatta Valley

ıt drain	Chai	nage	ent	la.)	d paved	lopen a.)	ousness	nutes	Ē	Ave Veloc m/s	rage city in sec.	nin.)	min.)	f min.)	nt "C"	Rainf	all Inte	nsity "i	" in mr	n/hour	Qu	uantity (0	Q)= 10 C	.i A m3/s	sec.	lth in m	ain m	Area	requir	ed for	Drain	in m2	Wic	ith requ	uired for	r drain	in m
Description about drain	from	to	Sub Catchment	Total Area (Ha.)	Area of bulitup and paved areas (Ha.)	Area of parks and open space, etc. (Ha.)	Weighted Imperviousnes: (%)	Inlet Time in minutes	Slope of terain	For terain	For Drain	Flow in drain (min.)	Flow in Terain (min.)	Total time of concentration (min.)	Runoff Coeffiecent	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	Existing Ave.width in m	Ave. Depth of drain m	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)
			A3 (a)	28.65	12.72	15.93	44.42	14.45	0.01	1.2	3.31	10.83	9.72	35	0.425	37.86	52.62	67.88	81.23	98.86	1.28	1.78	2.3	2.75	3.35												
				97.18																	5.16	7.17	9.25	11.07	13.47												
			Total	336.94							3.31			35							17.63	24.48	31.52	37.64	45.99	7.8	2.1	2.5	7.4	9.5	11.4	13.9	1.2	3.5	4.5	5.4	6.6
C203	0	737	A3 (b)	16.93	16.93	0	75	10	0.01	1.2	3.14	2.12	11.11	23.23	0.503	49.87	68.39	86.75	101.64	128.71	1.18	1.62	2.05	2.4	3.04												
			Total	16.93							3.14										1.18	1.62	2.05	2.4	3.04	2.42	1.6	0.4	0.5	0.7	0.8	1.0	0.2	0.3	0.4	0.5	0.6
C200	2150	2550	Total	353.87							3.01			37.12							18.81	26.09	33.57	40.04	49.03	10.4 5	2.63	6.3	8.7	11.2	13.3	16.3	2.4	3.3	4.2	5.1	6.2
C200	2550	3350	A4 (a)	78.02	76.49	1.53	73.92	10.16	0.01	1.2	3.12	17.9	9.72	37.77	0.557	35.96	50.11	64.84	77.90	94.11	4.34	6.05	7.82	9.4	11.35												
			A5 (a)	36.59	26.25	10.34	59.46	12.26	0.02	1.5	3.12	17.9	10	40.15	0.509	34.51	48.19	62.51	75.34	90.48	1.78	2.49	3.23	3.9	4.68												
				114.61																	6.12	8.54	11.06	13.29	16.03												
			Total	468.48							3.12			40.15							24.94	34.63	44.63	53.33	65.07	10.4 1	2.46	8.0	11.1	14.3	17.1	20.9	3.2	4.5	5.8	6.9	8.5
C202	0	1170	A6 (a)	32.11	32.11	0	75	10	0.01	1.2	3.05	6.39	8.33	24.73	0.508	47.83	65.72	83.58	98.24	123.65	2.17	2.98	3.79	4.45	5.6												
			Total	32.11							3.05										2.17	2.98	3.79	4.45	5.6	5.4	1.7	0.7	1.0	1.2	1.5	1.8	0.4	0.6	0.7	0.9	1.1
C200	3350	4200	Total	500.59							3.01			46.55							27.1	37.61	48.41	57.78	70.67	11	2	9.0	12.5	16.1	19.2	23.5	4.5	6.2	8.0	9.6	11.7
C204	0	2000	A6 (b)	114.77	110.49	4.28	72.95	10.3	0.01	1.2	2.38	14.01	9.72	34.03	0.542	38.58	53.58	69.03	82.49	100.66	6.66	9.25	11.92	14.24	17.38												
			A7 (a)	78.06	78.06	0	75	10	0.02	1.5	2.38	14.01	16.67	40.67	0.576	34.21	47.80	62.04	74.81	89.73	4.27	5.97	7.75	9.34	11.21												
			Total	192.83							2.38			40.67							10.93	15.22	19.67	23.59	28.59	4	1.24	4.6	6.4	8.3	9.9	12.0	3.7	5.2	6.7	8.0	9.7
																					38.04	52.83	68.08	81.37	99.25	In	this c	chainag	e, 100%	6 of Uls	soor sto	rm Wate	er overf	lows fro	om the U	JIsoor L	ake
C100	3975	4500	Total	1299.08							4.16			46.55							38.04	52.83	68.08	81.37	99.25	13	2.69	9.1	12.7	16.4	19.6	23.9	3.4	4.7	6.1	7.3	8.9
C100	4500	5500	A4 (a)	105.2	105.2	0	75	10	0.01	1.2	3.06	32.68	16.67	59.35	0.629	26.53	37.53	49.47	60.83	70.35	4.87	6.89	9.09	11.17	12.92												
			A4 (b1)	118.53	79.65	38.88	56.96	12.62	0.01	1.2	3.06	32.68	20.83	66.14	0.550	24.67	35.02	46.36	57.33	65.60	4.47	6.34	8.4	10.38	11.88												
				223.73																	9.34	13.23	17.48	21.56	24.8												
			Total	1522.81							3.06			66.14							47.38	66.06	85.56	102.93	124.06	15	2.48	15.5	21.6	28.0	33.6	40.5	6.2	8.7	11.3	13.6	16.3

STUP Consultants Ltd.

Feasibility Report for Challaghatta Valley

ıt drain	Chai	nage	ant	la.)	d paved	liopen la.)	ousness	nutes	Ē		rage city in sec.	min.)	(min.)	of min.)	nt "C"	Rainfa	all Inte	nsity "i'	" in mr	n/hour	Qı	uantity (0	Q)= 10 C	.iA m3/s	sec.	lth in m	ain m	Area	requir	ed for	Drain i	n m2	Wid	lth requ	iired fo	r drain i	n m
Description about drain	from	to	Sub Catchment	Total Area (Ha.)	Area of bulitup and paved areas (Ha.)	Area of parks and open space, etc. (Ha.)	Weighted Imperviousness (%)	Inlet Time in minutes	Slope of terain	For terain	For Drain	Flow in drain (min.)	Flow in Terain (min.)	Total time of concentration (min.)	Runoff Coeffiecent	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	Existing Ave.width in m	Ave. Depth of drain m	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)
C102	0	500	A4 (c)	87.64	44.09	43.55	47.67	13.98	0.01	1.2	2.64	3.16	8.33	25.47	0.399	46.89	64.50	82.12	96.67	121.32	4.55	6.27	7.98	9.39	11.79												
			A4 (d)	158.91	101.54	57.37	55.14	12.89	0.01	1.2	2.64	3.16	13.89	29.93	0.452	42.05	58.16	74.54	88.48	109.32	8.39	11.6	14.87	17.65	21.8												
			Total	246.55							2.64										12.94	17.86	22.84	27.04	33.59	4	2.3	4.9	6.8	8.7	10.2	12.7	2.1	2.9	3.8	4.5	5.5
C102	500	1250	A4 (b2)	102.62	102.62	0	75	10	0.01	1.2	2.51	4.98	20.83	35.81	0.558	37.27	51.85	66.95	80.21	97.40	5.93	8.24	10.64	12.75	15.48												
				102.62																	5.93	8.24	10.64	12.75	15.48												
				349.17							2.51										18.87	26.11	33.49	39.79	49.07	5	2	7.5	10.4	13.3	15.9	19.6	3.8	5.2	6.7	7.9	9.8
C100	5500	5800	Total	1871.98							3.26			69.29							66.24	92.17	119.05	142.71	173.13	17.5	2.1	20.3	28.3	36.5	43.8	53.1	9.7	13.5	17.4	20.8	25.3
C100	5800	7075	A5 (a)	129.91	118.79	11.12	70.29	10.68	0.01	1.2	3.04	35.64	25	71.32	0.610	23.44	33.37	44.32	55.01	62.49	5.16	7.34	9.75	12.1	13.74												
			A5 (b)	272.78	272.78	0	75	10	0.01	1.2	3.04	35.64	27.78	73.41	0.631	22.99	32.76	43.55	54.15	61.34	10.99	15.65	20.82	25.88	29.32												
				402.69																	16.15	22.99	30.56	37.98	43.06												
			Total	2274.67							3.04			73.41							82.39	115.17	149.61	180.69	216.19	15	2.19	27.1	37.9	49.2	59.4	71.1	12.4	17.3	22.5	27.1	32.5
C100	7075	7675	A6 (a)	133.9	94.76	39.14	58.92	12.34	0.01	1.2	2.66	44.49	21.6	78.42	0.559	21.99	31.40	41.87	52.23	58.78	4.57	6.52	8.7	10.85	12.21												
				133.9																	4.57	6.52	8.7	10.85	12.21												
			Total	2408.57							2.66			78.42							86.96	121.69	158.31	191.54	228.4	22	2.48	32.7	45.7	59.5	72.0	85.9	13.2	18.4	24.0	29.0	34.6
C105	0	2500	A6 (b)	62.7	62.7	0	75	10	0.02	1.5	2.2	5.3	20	35.3	0.558	37.63	52.33	67.52	80.84	98.30	3.66	5.08	6.56	7.85	9.55												
			A6 (c)	199.79	180.85	18.94	69.79	10.76	0.01	1.2	2.2	5.3	23.61	39.67	0.547	34.79	48.56	62.97			10.57	14.75	19.12	23.03	27.69												
			- (-)	262.49							2.2										14.22	19.83	25.68	30.88	37.24	3.65	1.8	6.5	9.0	11.7	14.0	16.9	3.6	5.0	6.5	7.8	9.4
C100	7675	8225	Total	2671.06							3.16			83.72							101.18				265.64		3.02	32.0	44.8	58.2	70.4	84.1	10.6	14.8	19.3	23.3	27.8
																					•																
C100	8225	9350	A7 (a)	174.05	56.94	117.11	37.99	15.38	0.01	1.2	2.63	55.61	19.44	90.44	0.469	19.98	28.66	38.44	48.31	53.63	4.53	6.5	8.72	10.96	12.17												
0100	0220	5550	A7 (a)	189.04	164.28		67.8	11.05	0.01	1.2			27.78		0.409				47.18		6.08	8.74	11.74	14.78	16.34		In thi	s Chain drain de	age, Exerting ag	isting d , Propo	rain de sed wid	oth is m th is le	ore thar ess than	that of	of the al the abo	oove cha	ainage 1.
			A7 (0)	109.04	104.28	24.70	07.0	11.05	0.01	1.2	2.03	10.01	21.18	94.43	0.597	19.41	27.08	37.40	47.18	32.15	0.08	0.74	11.74	14.78	10.34												

ut drain	Chai	nage	ant	(Ha.)	d paved	d open ta.)	ousness	minutes	ain	Ave Veloc m/s	ity in	(min.)	(min.)	of (min.)	ent "C"	Rainfa	all Inter	nsity "i'	' in mn	n/hour	Qı	uantity (C	Q)= 10 C.	iAm3/s	sec.	lth in m	drain m	Area	requir	ed for	Drain i	n m2	Wid	lth requ	ired fo	r drain i	n m
Description abou	from	to	Sub Catchme	Total Area (H	Area of bulitup and areas (Ha.)	Area of parks and space, etc. (Ha	Weighted Impervio (%)	Inlet Time in mi	Slope of tera	For terain	For Drain	Flow in drain (Flow in Terain	Total time c concentration (Runoff Coeffiece	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	Existing Ave.width	Ave. Depth of dr	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)	(For 1 Year)	(For 2 Year)	(For 5 Year)	(For 10 Year)	(For 20 Year)
				363.09																	10.62	15.24	20.46	25.74	28.51												
			Total	3034.15							2.63			94.43							111.79	156.76	204.45	248.16	294.15	18	2.2	42.5	59.6	77.7	94.4	111.8	19.3	27.1	35.3	42.9	50.8
C101	0	1875	A7 (c)	163.44	74.56	88.88	45.09	14.35	0.01	1.2	2.1	14.88	19.44	48.68	0.48	30.32	42.61	55.71	67.81	79.93	6.54	9.19	12.01	14.62	17.24												
			A8(c1)	54.09	13.78	40.31	34.01	15.96	0.01	1.2	2.1	14.88	25	55.84	0.45	27.64	39.02	51.31	62.89	73.16	1.85	2.61	3.43	4.21	4.9												
			Total	217.53							2.1										8.39	11.8	15.45	18.83	22.13	2	1.1	3.99	5.62	7.36	8.97	10.54	3.63	5.11	6.69	8.15	9.58
C100	9350	10275	A8(a)	165.6	155.55	10.05	71.66	10.49	0.01	1.2	2.77	61.82	27.78	100.09	0.61	18.66	26.86	36.18	45.7	50.24	5.27	7.58	10.21	12.9	14.18												
			Total	3417.28							2.77										125.45	176.14	230.11	279.9	330.46	15	1.83	45.29	63.59	83.07	101.05	119.3	24.75	34.75	45.39	55.22	65.19

CHAPTER - 5

ENVIRONMENTAL AND SOCIAL IMPACT

5.1 INTRODUCTION:

This chapter provides a strategic framework to ensure that existing storm drainage system in Bangalore is managed in a reliable, affordable, sustainable and environmentally friendly manner, which is most essential for success of any project. But from the existing management practices followed by the stakeholders and also with the prevailing site conditions, it appears that, along with the resources required to achieve the recommended targets, strategies and actions, they also needs to adopt best storm drain management practices, improvised construction and construction supervision techniques, strengthened organisational setup, major legislative changes, coordination with other stakeholders, public awareness campaigns and their participation to minimise the adverse implications on storm drain functionality and storm drain management practice in the city.

5.2 ENVIRONMENTAL CONDITIONS:

Open parks, major waterways and water bodies that exists in a city like Bangalore can be a significant amenity for flood protection. But in recent times, due to lack of planning and rapid changes in the landuse, these amenities have been largely ignored by various stakeholders, service providers and the public in general. In the recent history, there has been no comprehension of the need to provide for storm water drains to service urban development beyond the sub-divisional level of tertiary drainage. As a consequence, the primary and secondary drainage systems in the core (BMP) area have developed on an adhoc basis and now they have reached a saturation level and not in a position to provide security to the low lying areas during most needed situations. Further, there are evidence that in areas outside the BMP administered region, the development authorities do not enforce and adopt even rudimentary practices for planning, construction and maintenance of primary and secondary drains and also they are lack of resources and technical expertise to adopt best storm drain management practices. Significantly what is seen over a period of time, that many lakes that were existing in BMRDA area have been converted into residential layouts. These lakes otherwise would have acted as flood buffer zone. The tank beds are being the lowest point at the end of valleys, in most of the cases to prevent flooding in such areas,. It requires mechanical means. Therefore public, public representatives and all concerned needs to be educated against encroachment of tank areas. If possible restoration work of tanks need to be taken up on priority, which intern reduce the runoff and flooding problems in some of the adjoining low lying areas.

Challaghatta valley is one such valley which suffers from all the above mentioned reasons. As mentioned earlier in the Chapter 2, storm drains in Challaghatta valley flows through dense residential and commercial areas of the city. Since the drain is flowing through dense residential areas in the initial reaches the natural coarse of the drain is altered at many places due to encroachments and also inappropriate planning by the landuse planners. Further, the carrying capacity is also reduced due to dumping of construction debris, municipal solid wastes and also discharging raw sewage into the drains by the commercial establishments like restaurants, lodges, marriage halls etc. and low income residential houses thereby distracting the visual aesthetic amenity of waterway, causing siltation problems, inconvenience to the surrounding localities and threatening the health aspects of the communities residing in the close proximity of the waterway.

Further, the drainage channel flows through dense commercial areas, wherein large numbers of shops and public toilet blocks have been constructed over the drain and also sewerlines have been laid and manholes protruding well above the bed level are constructed inside the drainage channel. Even though the sewer lines exists, the sewer out lets from the public toilets are not connected to the sewerage system and they are discharging raw sewage directly into storm drains and also due to lack of timely maintenance of chocked sewer pipelines, manholes, under capacity sewer pipelines, and lack of sewer connectivity, raw sewage is also being allowed to enter into storm drain thereby distracting the visual aesthetic amenity of waterway, making place favorable for mosquito breading, causing substantial inconvenience to the surrounding locality resident, pedestrians and vehicular movement and also the slaughter houses located near the drains are also threatening the health aspects of the communities residing in the close proximity of the waterway.

Since the topography of the terrain is sloping towards the drain and also due to improper solid waste collection and conveyance arrangement all the solid waste generated from the commercial establishments and the greasy liquid waste from service stations, find their way into the storm drain, further all the floating materials gets clogged with the utility lines laid across storm drain and culvert locations with inadequate vent sizes at some places obstructing free flow of water and intern causing localized flooding problems and pose substantial damage to both life and property.

Due to lack of sediment erosion control measures and devices, large quantity of silt is being accumulated inside the drain thereby causing siltation, ponding of water and intern making places favorable for mosquito breading.

The more extensive tertiary drains that exists are the key elements of the urban drainage system, but due to deficiencies in designs and maintenance practice, the existing tertiary drains are not serving upto the intended level of service during most needed hour of service.

Further down the stream near the receiving water body, new layouts that are formed are recently developed. But since the land value is very high, widening of drains is restricted and also the existing tertiary drains, due to deficiencies in design and maintenance practices they are not functioning upto the intended level of services during large storms and causing localised flooding problems.

Further, one significant cause of frequent flooding of low-lying areas near the receiving water body is due to large accumulation of sediments and vegetal growth that reduce the capacity of the drains. Insufficient collection of solid wastes and a lack of understanding of the impact of casual litter disposal on drains are significant factors contributing to the high waste volumes found in drains. Similarly, erosion control practices in construction sites, public parklands, private gardens and on the medians and verges of roads are not sufficient to control large silt loads reaching the main drains. These factors, combined with infrequent clearance of drains by responsible authorities, occasionally lead to unsanitary conditions in drains and further aggregate the already aggravated situation.

5.2.1 Relationships between Solid Waste and Drainage

Until recent times, the relationship between solid waste materials and drainage system and its impact on the environmental attributes was not considered to be significant due to various reasons, even though the responsibility for both drainage and solid waste management in the core area lies with BMP and outer periphery areas with CMC/TMC.

As observed during reconnaissance survey, disposal of bio degradable and non degradable material dumps into the drains were of a common practice all along the drain and intern factors that were influenced to affect the functionality of the system were also noted and few factors that were noted are as explained in brief here under,

The disposals of house hold garbage and street sweepings into drains near Shivajinagar and Ulsoor is affecting free flow of water, reducing the aesthetic appearance, reducing the quality of environmental attributes in that region. Apart from affecting the flow, solid wastes have particular impact on the smaller tertiary drains, often obstructing flow completely, and causing short term localized flooding that can be especially dangerous to both pedestrians and vehicular movement. Further to improve the situation in that region improvised method of solid waste collection and conveyance system, community awareness campaigns in that region is most essential.

The disposals of house hold garbage, street sweepings and construction debris into drains at J.C. Nagar near Munireddypalya, Chinnappa garden and Frazer town is affecting free flow of water, reducing the aesthetic appearance, quality of environmental attributes in that region. Apart from affecting the flow, solid wastes have particular impact on the smaller tertiary drains, often obstructing flow completely, and causing short term localized flooding that can be especially dangerous to both pedestrians and vehicular movement. Further to improve the situation in that region community awareness campaigns, improvised method of solid waste collection and conveyance system and prevention of dumping debris in that region is most essential.

5.2.2 Conflicts between Sewers and Drains:

At present there are some trunk sewers laid within drainage channels. Problems that arise from sewers in drainage channels are numerous and include:

- capacity reduction of drains due to manholes;
- restrictions on channel augmentation options;
- ready opportunities to relieve excess sewage into channels;
- need for parallel programming and close coordination, where rehabilitation of either service is proposed;
- difficult access for sewer maintenance;
- lack of access to sewers under lined inverts and cross drainage culverts
- potential damage to or from drain assets; and
- poor construction due to difficult access and flow diversion problems.

Benefits are few and include:

- no need for separate sewer easement; and
- relatively low excavation cost due to shallow depth.

All the above problems mentioned outweigh the benefits accrued in the Challaghatta valley and therefore urgent efforts are required to cleanse the entire system.

5.2.3 Impacts of Poor Storm Water Drainage System:

The importance of adequate storm water and wastewater drainage, in tandem with sufficient water supply, cannot be over emphasised, if full health benefits from provision of services are to be derived. Inadequate drainage causes inconvenience and loss both to life and property varying in nature ranging from:

 Inundation of houses and establishments on the floodplains, caused by large scale "valley" flooding from overflow of primary and secondary drains.

 local area inundation and water stagnation in residential areas, caused by "local" drainage deficiencies and run-off from adjacent local catchments as in Vasanthanagar, Shivajinagar, Jogupalya area, Munireddypalya, Chinnappa Garden and K.R. garden areas etc.

- •Causes extensive damage to infrastructure works and intern reduces the aesthetic appearance of the city and reduces the land value cost adjacent to drains etc.
- •Having high solid waste and sewage concentrations, the flood waters which inundate dwellings and their curtilages create particularly very objectionable conditions in Bangalore.
- •The frequency and duration of flooding is relatively high in some of the locations, occurring usually during the south west monsoon period. Whilst valley flooding occurs several times per year in down stream areas. Under these latter conditions, poor drainage causes water stagnation and creates the surrounding area favorable for mosquitoes breeding and intern leads to unsanitary conditions. Even the water quality in some of the borewells that are dug adjacent to storm drains are polluted.
- •Out of the 360 officially recognized slums in Bangalore, only 30 percent have underground sewerage services. Hence, the major portion of the wastewater generated from such slums will be discharged via the storm water system causing very unhygienic conditions.

5.3 ENVIRONMENTAL MANAGEMENT PLAN:

The proposed activities arising from this chapter are strategic in nature, and as such, the detailed investigations required have not been performed. Consequently the environmental assessment of the proposed activities addresses generic environmental impacts and mitigation measures only.

Recommendations:

- Prepare a comprehensive management plan which is acceptable and affordable by the community.
- >Prepare a risk assessment plan and risk management plan.

Prepare a construction and maintenance schedule to ensure effective functionality of the system.

Implement an effective, improvised solid waste collection and conveyance system.Prepare a strategic plan for development of land in low lying areas.


- Municipal authorities should be more vigilant on the contractors responsible for disposal of solid wastes generated from the market yards, slums and densely populated areas.
- >There should be stringent penalty on commercial establishments, hospitals lying in the catchment area, are disposing off their liquid/solid waste in the valley in an inappropriate manner.
- >There should be a ban on the construction of public toilets on the banks of the waterway.
- Service station / garages should not be allowed to dispose the greasy effluent into the drain.
- There should be a strict vigil on slaughter houses which are discharging the liquid waste directly into drains and they should be instructed to dispose of their waste in a secured manner.
- Horticulture gardens and nurseries situated along the banks of the valleys should be cordoned off from the valley and should dispose the vegetative waste separately outside as a landfill and not to discard in the drain.
- >There should be no UGD inlet into the drain from slums and other residential areas.
- Silt traps and silt barriers must be constructed along the drain at strategic locations to reduce silt load at downstream of the valley.
- >Municipal authorities should encourage public and private sector enterprises for usage of recycled water and adopt rain water harvesting techniques in open lands etc.
- >Create awareness among the public, regarding importance of the system functionality.

Detention ponds for recharging ground water should be constructed along the strategic vantage locations in the valley. Some areas where such ponds could be provided apart from existing parks maintained by BMP are as listed below and the same is depicted in *Figure 5.1.*

Table 5.1 List of Locations For Construction of Detention Ponds

- 1.Bangalore Palace Grounds, near Vasanthanagar.
- 2.Defence land, near Potters town.
- 3. Muslim community burial ground, on Nandi Durga Road.
- 4. Burial ground, near Wahid garden.
- 5. Educational institutions, near Sagayapuram.
- 6.Open space area, near East Railway Station.
- 7.Open space area, near Jeevanahalli.
- 8.M.E.G. Centre, near Ulsoor lake.
- 9.Kalpally cemetry.
- 10.T.B.Sanatorium area, near Indiranagar 1st Stage.
- 11.Open space area, near Jivanbhimanagar (National Assn. for blind, 10th Cross Road).
- 12.H.A.L. Staff College.
- 13.I.S.R.O. Complex near Airport Road.
- 14.I.S.R.O. Complex near Jivanbhimanagar.
- 15.ESI hospital/Dr. Ambedkar college, near Indiranagar.
- 16.Muslim burial ground, near Indiranagar BMTC bus depot.
- 17.Behind F.M. Cariappa defence qtrs., near Command hospital.
- 18.Defence land, near Ulsoor.
- 19.Kendriya Vidhyalaya, near St. Johns Road.
- 20.K.V.S. Stadium, near St. Johns Church Road.
- 21.K.K & G defence land at Cubbon Road.
- 22.Contonment railway property.
- 23.BMRDA & its adjoining park area on Millers Road.
- 24.Mount carmel college grounds on Millers Road.
- 25.Parks near Domlur in Air Port road.

5.4 SOCIAL IMPACTS:



Baseline data together with data on social and environmental impact of flooding has been collected during reconnaissance survey to ascertain the level of service offered by the existing drainage system at various locations in the BMP, BDA and BMA administered areas.

The Baseline survey provided the following statistics on the incidence, nature and possible cause of flooding:

•7% of the household in B.M.P. area, reported that they faced instances of flooding.

- 10% of households of lower socio-economic status reported that they had faced flooding in the past decade-instances of flooding had been more common in the central part of the city.
- •Of the house holds that had experienced flooding, 72% reported such occurrences in the last one year, 15% had experienced flooding in the year 1999, 7% during the period 1995 to 1998, while 2% reported that they had experienced flooding prior to 1995.
- •Of the households that had experienced flooding, a majority said that the effects had lasted for one to three days, while 3 % said they had extended beyond a week.
- •Two thirds of the households ascribed the reasons for flooding to blockages in the sewerage system, 12% to ingress of rain water into the house, while 11% said that it had been caused by a blocked drains or gutter.
- •Lower income households and those living in the slums were more vulnerable to flooding caused by blocked drains; and
- •All households reported damage to assets and loss of workdays on account of such flooding.
- •Few households from the conurbation and green belt areas reported that their houses had been flooded in the recent past, suggesting the high density of houses and lack

of planned development have contributed to the problem of improper drainage in the corporation area.

•Out of 360 officially recognized slum in Bangalore, only 30% have underground sewerage services. Hence, in the majority of slums wastewater must be discharged via. the storm water system, during flooding instances due to water stagnation, it provides a breeding ground for mosquitoes and leads to generally unsanitary conditions and health hazards.

Details on the areas affected, the frequency of flooding, the impacts and the cause of flooding would all be relevant for an effective management of the drainage system, but such records are not kept. But, during reconnaissance survey such information's were collected from public as first hand information and were considered during the evaluation of analysis results to improve the existing situation.

CHAPTER - 6

COST ESTIMATION

6.1 COST ESTIMATE:

Cost estimate has been worked out for rehabilitation of existing culverts/bridges, construction of new drains and bridges, and providing improvement works for increasing the carrying capacity of the system and also providing measures like increasing the capacity of tertiary drains and other allied works to minimizing the flooding problems in low lying areas.

Rehabilitation work includes drain wall reconstruction, cavity filling, providing pointing and where as carrying capacity improvement work includes plastering, desilting, widening, deepening, wall raising and providing bed protection.

For ease of assessment, carrying capacity improvement works and rehabilitation works have been identified and assessed for every kilometer length and accordingly cost estimates and bill of quantities have been prepared which is given in Volume IV of this report. Further for better understanding strip plans have been prepared and enclosed in this chapter.

For assessment of cost, detailed hydraulic design, structural designs, quantity estimation and cost estimation as per current schedule of rates have been carried out

A lumpsum amount provision for construction of detention ponds, utility shifting, traffic diversion and land acquisition are made in the estimate.

Table 6.1 & 6.2 indicates carrying capacity improvement works & rehabilitation works for Primary storm drain in Challaghatta Main Valley.

Table 6.3 & 6.4 indicates carrying capacity improvement works & rehabilitation works for Secondary storm drains in Challaghatta Main Valley.

Table 6.5 & 6.6 indicates carrying capacity improvement works & rehabilitation works for Primary storm drain in Ulsoor Valley.

Table 6.7 & 6.8 indicates carrying capacity improvement works & rehabilitation works for Secondary storm drains in Ulsoor Valley.

Table 6.9 Indicates abstract of cost for remodelling of existing culverts / bridges and also construction of new bridges in Challghatta Valley.

Lump sum amount provision for improving the existing tertiary drains has been made in the estimate and the same is indicated in Table 6.10.

6.2 Work Programme for Challaghatta Valley:

The works proposed in the above referred tables i.e., Table 6.1 to Table 6.10 shall be taken up in two phases,

✓Phase – I works in Challaghatta Main Valley:

The works indicated in Table 6.1 and 6.2 for Challaghatta Valley Primary Storm drain prioritized to be takenup in Phase I includes;

> Challaghatta Valley Primary Storm Drain – C100:

- •The works proposed near Vasanthanagar i.e., from Vasanthanagr upto Millers tank bund road like desilting, widening, tertiary drain improvement, deepening, culvert reconstruction, debris removal, new wall construction, utility shifting, removal of culvert near Karnataka Badminton Association and minor rehabilitation works may be takenup in Phase I.
- •The works proposed near Corporation Colony i.e., from Queens Road upto Old Bamboo Bazar Road like desilting, new wall construction, obstruction removal, utility shifting and minor rehabilitation works may be takenup in Phase I..
- •The works proposed near Shivajinagar i.e., from Old bamboo bazaar Road upto St, Johns Road like removal / relocating the shops and desilting, widening, tertiary drain improvement, deepening, new wall construction, culvert reconstruction, drain widening and new wall construction near Block Education department, utility shifting, relocation of toilet blocks and minor rehabilitation works may be takenup in Phase I.
- •The works proposed near RBANMS College i.e., from Anna Swamy Mudaliar Road upto Kensington road like desilting, widening, removal of obstructions, deepening of

drain near Gurudwara, bridge reconstruction, new wall construction, utility shifting and minor rehabilitation works may be takenup in Phase I.

- •The works proposed near Karnataka Golf Club association i.e., from Royal Orchid Park hotel upto Bellandur tank like desilting, widening, changing the alignment of drain near Wind tunnel road, deepening of drain inside Airport, bridge construction, new drain construction near Belur Road, demarcation of land for drain, service road, utility shifting and minor rehabilitation works may be takenup in Phase I.
- •Desilting, debris removal, obstruction removal, encroachment removal and utility shifting works for the entire length of drain may be taken up in Phase I itself.

And phase II works are as mentioned below.

✓Phase – II works in Challaghatta Main Valley:

The works indicated in Table 6.1 and 6.2 for Challaghatta Valley Primary Storm drain to be takenup in Phase II includes;

> Challaghatta Valley Primary Storm Drain – C100:

- •The works proposed near Karnataka Badminton Association i.e., from Miller tank bund Road upto Queens Road like new wall construction may be takenup in Phase II.
- •The works proposed near Guptha layout i.e., from backside of Gurudwara upto Old Madras Road like deepening, widening, wall reconstruction may be takenup in Phase II.
- •The works proposed near Saraswathipura i.e., from Old Madras Road upto Cambridge layout like deepening, widening, wall reconstruction, removal of encroachments near Cambridge layout bridge may be taken up in Phase II.
- •The works proposed near Cambridge layout i.e., from Cambridge layout bridge location upto Domlur 2nd Stage like desilting, deepening, widening may be takenup in Phase II.

- •The works proposed near Domlur 2nd Stage i.e., from TERI upto Airport Road like deepening, widening, wall reconstruction may be taken up in Phase II.
- •The works proposed near Diamond District Apartments i.e., from Airport Road upto Karnataka Golf Club like deepening, widening, wall reconstruction works may be takenup in Phase II.

✓Phase – I works in Challaghatta Main Valley for Secondary storm drains:

The works indicated in Table 6.3 and 6.4 for Challaghatta Valley Secondary Storm drains prioritized to be takenup in Phase I includes;

>Murugeshpalya drain - C101:

•All the works proposed for this drain near Anandanagar and K.R. Garden needs to be takenup like desilting, widening, deepening, construction of new drains, tertiary drain improvements, utility shifting and minor rehabilitation works deepening of drain inside Airport, utility shifting and minor rehabilitation works may be takenup in Phase I.

>Shastrinagar Drain - C102:

•All the works proposed for this drain near Shastrinagar and Lakshmipura needs to be takenup like desilting, widening, deepening, construction of new drains, tertiary drain improvements, utility shifting and minor rehabilitation works, dense vegetation growth removal near CMH Road, utility shifting and minor rehabilitation works may be takenup in Phase I.

>I.S.R.O. Complex Drain - C105:

•All the works proposed for this drain near Jeevanabhimanagar, Indiranagar and Kodihalli Village needs to be takenup like desilting, widening, deepening, tertiary drain improvements, dense vegetal growth removal near ISRO, utility shifting and minor rehabilitation works may be takenup in Phase I.

>Thippasandra Drain - C106:

•All the works proposed for this drain near Jeevanabhimanagar needs to be takenup like desilting, tertiary drain improvements, utility shifting utility shifting and minor rehabilitation works may be takenup in Phase I.

6.3 Work Programme for Ulsoor Valley:

The works proposed in the Table 6.3 to Table 6.4 shall be taken up in two phases,

✓Phase – I works in Ulsoor Valley:

The works indicated in the above referred tables for Ulsoor Valley Primary Storm drain which are prioritized and to be takenup in Phase I includes;

>Ulsoor Valley Primary Storm Drain – C200:

- •The works proposed near J. C. Nagar i.e., from J. C, Nagar upto S.K. Garden Main Road like desilting, widening, tertiary drain improvement, deepening, culvert reconstruction, debris removal, new wall construction, utility shifting and minor rehabilitation works may be takenup in Phase I.
- •The works proposed near S.K. Garden i.e., from S.K. Garden Main Road upto Bore Bank Road like desilting, widening, tertiary drain improvement, deepening, culvert reconstruction, debris removal, new wall construction, utility shifting and minor rehabilitation works may be takenup in Phase I.
- •The works proposed near Frazer Town i.e., from Stephens Cross Road upto Ulsoor Lake like desilting, widening, tertiary drain improvement, deepening, culvert reconstruction, debris removal, desilting of silt traps, new wall construction, utility shifting and minor rehabilitation works may be takenup in Phase I.
- •Desilting, debris removal, obstruction removal, encroachment removal and utility shifting works for the entire length of drain may be taken up in Phase I itself.
- Phase II works in Ulsoor Valley:
- >Ulsoor Valley Primary Storm Drain C200:

The works indicated in Table 6.3 and 6.4 for Ulsoor Valley Primary Storm drain to be takenup in Phase II includes;

•The works proposed near Frazer Town i.e., from Bore Bank Road upto Stephens Cross Road like widening, tertiary drain improvement, deepening, new wall construction may be takenup in Phase II.

✓Phase – I works in Ulsoor Valley for secondary drains:

The works indicated in Table 6.7 and 6.8 for Ulsoor Valley Secondary Storm drains prioritized to be takenup in Phase I includes;

Ganesh Temple Drain - C201:

•All the works proposed for this drain near Ganapathi temple needs to be taken up like deepening may be taken up in Phase I.

≻Cox Town Drain - C202:

•All the works proposed for this drain near Richards town and Cooke town needs to be taken up like widening, deepening may be taken up in Phase I.

>Sagayapuram Drain - C203:

•All the works proposed for this drain near Tannery Road needs to be takenup like widening, deepening may be takenup in Phase I.

>Jeevanahalli Drain - C204:

- •All the works proposed for this drain near Jeevanahalli and M.E.G. Centre needs to be takenup like widening, deepening works may be takenup in Phase I.
- •Desilting, debris removal, obstruction removal, encroachment removal and utility shifting works for the entire length of drain may be taken up in Phase I itself.

Bed protection works and other allied works may be takenup in Phase II for all primary and secondary storm drains both in Challaghatta main valley and Ulsoor valley.

6.4 Operation and Maintenance Cost:

For maintaining the existing drains in good condition and to have maximum hydraulic carrying capacity, the drainage system has to be maintained in good condition. The general maintenance envisaged are:

- 1.Removal of weeds
- 2.Removal of silt
- 3.Removal of debris and garbage
- 4.Repair the drain wall
- 5.Creating public awareness
- 6.Maintenance of desilting equipments
- 7.Administrative cost of drain monitoring squad.

Table 6.11 Indicates abstract of cost for annual operation and maintenance of the drainage system in Challaghatta Valley.

Abstract of Cost

for Remodeling of Primary and Secondary Storm Water Drains, Culverts/Bridges & its appurtenant works in Challaghatta Valley

SI.No.	Description	Amount
31.110.	Description	(Rs. In Lakhs)
	Cost for Remodeling of Primary & Secondary Storm	
1	Water Drains, Construction of New Drains near low lying	10,046.76
	areas, Formation of Service Roads etc.,	
2	Cost for Remodeling of Bridges / Culverts constructed	
2	across Primary & Secondary Storm Water Drains.	1,333.40
3	Cost for shifting utility lines, footpath improvement works, barricading, traffic diversion, strengthening of diversion routes etc.	569.01
4	Construction of Detention Ponds / Retarding Basins	150.00
5	Construction of Wells with pumping arrangement in low lying areas	200.00
6	Procurement of desilting machine	0.00
7	Miscellaneous and rounding off	0.02
8	Advisory, Project Management & Establishment	10150
0	Charges (1.5 % of Item 1 to 7)	184.50
	rtotal	12,483.69
9	Annual Operation & Maintenance Cost	100.00
	(1.0 % of Item 1 to 7)	123.00

Table 6.11Abstract of Cost for Operation and Maintenance ofPrimary and Secondary Storm Water Drains in Challaghatta Valley

Sl. No.	Description	Amount (Rs. In lakhs)	Remarks
1	Operation & Maintenance		(Cost considered is for per annum).
1.1	Establishment Charges	12.30	
1.2	Purchase & maintenance of equipments.	12.30	
1.3	Construction of new components	36.90	
1.4	Drain Desilting works	24.60	Av. Silt depth of Min. 0.3 to 0.5 m. per year
1.5	Rehabilitation works	30.75	
1.6	Staff training, community awareness etc.	6.15	
	Total	123.00	

	Rom	odelini odelini	of Primer	y Secondary St	orm Water Dran	n Bangaloro City	:-					1					E	estbility Raport – C	hallaghatta Valley - C	<u>haplar - 6</u>
				<u>y Secondery Su</u>			Tabl	e - 6.1 Schedule Fo	r Improving t	the Carrying	Capacity of	Existing Prima	ry Storm Dra	n in Challagh	utta Main Valley (C100)			·		२००२ इ.स. १९२२ इ.स. १९२४
ie S	. 5	Ch at	wge (m.)	Lo	ation		Drain V	Adening Sector		Drain Desili	ing & Deepenin	rm Drain — Ca			ents Works		Bed Protection		The formation	
• •	Ha.	From	To	From	To	Chainage (m.)	(~	Remarks	Chainage (m.)	1		Remarks	Chainage (m.)		Remarks	Chainage (m.)	Sand Sand Sand Sand Sand Sand Sand Sand	Remarks	17 107 107 107 10-	
	1	2	3	4	5 nary Storm Di	- 6 Calin		ß	9	10		11	12	13	14	15	16	17	18	-
				Bangalore	Queens Road	a) 275-357	1	a) Right Side - Corp. Dobh	a) 0 - 275	-	a) Evision	ains to be desitted.	a) 275-357				1	a) Existing drain		
	`	Ó٠	1,000	Palace Ground	Queens Road	a) 213-001		Ghat upto Miller Road			1	ting drain bed to be			a) Left Side	s) 0 - 275		bed relevant		
							· ·		b) 275-357		deepened	by \$00 mm from obl Ghat upto Millens	n,		Corp. Dobhi ghat upto Millers Road	b) 275 - 357		b) After desilting for full length & width		
								From 2.5 m to 4.5 m; ht. 2.0 m				ting drain bed to be			From 1.4 m to 2 m					
						ь) 400 - 625		5) Left Side - Millers Road upto Millers Tenk Bund Road	c) 400 - 625		deepened	by SOO mm from ad upto Millers Tank		-		c) 400 - 625		c) After desitting for		
											Bund Read		Ī					full length & width		
~_								From 3.0 m to 6.0 m; lit. 2.0 m								:				
- FC									d) 275 - 1000	۰.	d) Existing dr.	in to by declited		47 E		d) 650 - 1030	-	d) After desilting for full length & width	-72	
	2	1,000	2,000	Queens Road	Juma Məsjid	e) 1800 - 2000		a) <u>Both pide</u> Old Bamboo Bazar Road upto Juma Masfid Road	a) 1050 - 1475		a) After desit	ng drzin bed is to be	_	-	-	s) 1000 ~ 2000		a) After desliting for		
					Road						- From Ove	y 400 mm ens Road to Stubej:				-,		full Length & vidth		
								From 4.5 m to 7.5 m tt. 2.2 m			Road									•
									b) (<75-200		D) deepened t From Shire	ng drain bod is lo bo y 300 nm aji Rand upto Juma							61 m c	
	\vdash				ASU Road			e) frijet Side – Kennard Road			Marfid Ros	d ng Daala bed is to be		-	· · · · · · · · · · · · · · · · · · ·	·				
•	з	2,000	3,000	Arma Marfd Road	(New Ajanitus Road):	a) 2610 - 2725		down story Kuta East beide Block Edan, Dept, Butting	r} 2000 - 3000		 B) Juma Max 	by 500 mm from & Reat upto ASM	a) 2000 2610 ·		a) Both Side	s) 2000 - 0000	ļ	a) After desilting for full Length		
				-							Road. 🛩				Juma Mazfid Road uplo Kamaraj	1				
					`			Erom 7.0 mitr 1625 m H25m							Road From 1.8 m to 2.4 m	•				:
													b] 2610-2725		b) Left Side					
															Kamarej Road down elong Nala					
															Road From 2.2 m to 2.60 m					
\sim													c) 2725 - 3000		c) Both Side					
						}				<i>—</i> ,					Nala Road upto ASM Road from 2.2 m to 2.6 m	•				
	4	3,000	4,000	ASM Road (near	Kensington Road	3075 - 3150	-	L511. Size								,				
				Afanitia liveatre)	Коно		1	RBANIS College upla ASK			After dosial	ng drains bed to be			a) Len Side			a) After desitting,		
									s) 3000 - 4000		 a) deepened by 	750 mm from ASK endation Road	e) 3500 - 3900			a) 3000-14000) for full length & width	١	
							1	From 8.0 m to 12.0 m; Ht. 2.0 m							Drain wat on Ulsoor lake side needs to be raised from 3.0 m to					
			ł	-	ł					-					3,2 m .					
I			<u>J</u>	 .		J.	ł		<u>!</u>	L		<u> </u>					1	<u>د معمد معمد المعمد المعمد</u>	·	

GTUP Consultants P. Ltd.

298 Pago No.

. ____

STUP Consultants P. Ltd.

Remodelling of Primary Secondary Storm Water Dran n Bangalore City

.

1.1

																1			
~ 		2.5.0.00	-	N ISS STATE		1977 - 1978 - 1978 - 1978 - 1978 - 1978 - 1978 - 1978 - 1978 - 1978 - 1978 - 1978 - 1978 - 1978 - 1978 - 1978 -					xisting Stor	m Drain - Can	rying Capaci	ty Improveme	ents Works				
\cup		Chaina	(m) 9	Sol - Loc	tion a second	inana inana ina Ny INSEE DIA	Drain Wi	dening		Drain Desiltin			and the second second second	Chief and a framework a	Raising - Andreas Sciences		Bed Protection		ting to an to
	SL No.					Chainage (m.)		Remarks	Chainage (m.)		<u>an ing ang ang ang ang ang ang ang ang ang a</u>	Remarks	Chainage (m.)		Remarks	Chainage (m.)		Remarks	
		From	To	From	To			8		10		11	12	13	14	15	16	17	18
ſ	5	2	3	4 Kensington Road	6 Old Madras Road	6 a) 4925 - 5000	7	a) Left Side	a) 4250 - 5000		 a) decpened to a cross, M.V. 	ing Grain bed to be by 200 mm from 12th Garden upto Old	-1 4750 - 4075		a) <u>Both Skie</u> - Drain wall open M.V. Garden needs to be raised from 2.6 m to 3.2 m.	a) 4000 - 5000		a) After destiting, for full length & width	
	-		-					Near Murphy Town Market From 11.0 m to 15.0 ht. 3.2 m			Madras Ro	ac	b) 4925 - 5000		<u>b) Right Side</u> Drain wall near Murphy Town	•			
														-	Market needs to be raised from 2.8 m to 3.2 m				
	6	5,000	ର୍ପ୦୦୦	Old Madras Road	Someshwapura 6th Main Road	a) 5000 - 5050		a) Left Side Behind Sri Ram Ashram, Opp Murphy Town Market, From 11.5 m to 15.0 m ht. 3.2 m	a) 5000 - 6000		deepened (a) Madras	ing drain bed to be y 300 mm from Old Road upto rapura 6th Main		-	-	a) 5000 - 6000		a) After desilling, for full length & width	
Ý						b) 5650 - 6000		<u>b) Left Side</u> Near Lakshminarayanapura From 17 m to 20.0 m hL 3.0 m		×	. •		- -	-	-		-		
	7	6,000	7,030	Someshwarapur am 6th Main Road	Dombur II Stage, Mear TERI	e) 6000 - 6725	 	2) <u>Left Side</u> - Someshwarzpun Sth Main Road upto Domkur lind Stage, from 14.5 m to 24 m te 3.0 m	s) 6150 - 7900	-	e) ocepened Somethwa	ing dala bed lo be by 400 mm from tera illi Mala Road tind Stage.		-	-	a) 6000 - 7000 (a		a) After desilting for full length & widtt	
İ						ы) 6750 - 7050	- 4 <u>5</u> 75	01 Lets Side - Near TERL Domber End Stage From 13.0 m to 24 m ht. 3.0 m					-	-	-		·		
	8	7,000	£000	Domlus lind Stage, Noar TERI	Diarovoort District Apartments	s) 7000 - 7 550		a) Left Side - Domiur lind Stage upto Indiranagar 100 FL Road, from 14 m to 26 m ML 3.0 m	u) 7000 - 6000		docpened s) Doctiur (in	ing, drain bed to be by 450 mm from Strge, near TERI Siamond District	a) 7000 - 7500		a) Right Side	a) 7000 - 6000		a) After destiting for full length & width	
															Drain wall from Domiur lind Stage to Indiranagar 100 Ft. Road – From 2.8 m to 3.0 m				
						ь) 7625 - 770 0		b) Left Side - Between Indra- nagar 100 FL Road upto Alroot Road From; 20 m to 26 m M. 3.0	ł				b) 7509 - 8000		a) <u>Rictif Sido</u> - Drain walt from Indiranagar 100 Ft Road to Diarnond District				
										-				ļ	Apartments From 2.8 m to 3.0 m		15-	After desitting drain	<u></u>
	s	6,000	9,000	Diamond District Apartments	K.G.A. Gold Club (near Texas insta.)	a) 8075 - 8600		a) <u>Poith Side</u> - Opp. Royal Orchid Park Hotel	8000 - 9000		deepened	ing diain bed to be by \$00 mm from ist. Apartments upto f Club	h			a) 6000 - 10%0		bed to be provided for full length & width	
		•		· · · ·		b) 8600 - 9000		From 16 m to 28 m width and 2.6 m ht. Stone rivefment and also with 0.5 m h2, Parapet wal to be constructed b) <u>Richt Sidg</u> - After Roya Orchand Park Hote and Inside KGA. From 17 m to 28 m width and 2.6 m h4. Stone rivefment and											
			~					also with 0.5 m hi, Parapet wal to be constructed,			ļ			_			3		

Page No299

• • • •

Remodelling of Primary Secondary Storm Weter Dren n Bangelore City

5

C.

•

	101/10	• <u>• • • • • • • •</u>	1 f fill korf													·			
						and a star same is a straight	والمحاصفة والمستحد والمحاصر				xisting St	orm Drain - Car	ying Capacit	y Improveme	nts Works	and and a second second			
	ŀ	A12-5-5								Drain Desiltin	t & Deepenin			Drain Wall	Raising		Bed Protection		
O	S.	Chaina	ige (m.)	Loca			Drain W	dening			an the second second	_			Remarks	Chainage (m.)	(·	Remarks	1 .
. 1	Ha.	<u> </u>			To	Chainage (m.)		Remarks	Chainage (m.)	. 1.40 ⁽¹⁾		Remarks	Chainage (m.)	V 1= 1914		15	16	17	18
· ·		From	To	From	10					10		11	12	13	14			After desitting bed	
		-2	3	4	6	6	7	a) Both Side								9000 - 1000		protection to be provided for full	
		9,000		K.G.A. Golf Club (near Texas	Challaghatta Main Road (behind Airport)	9000 - 10000						-						length and width	
				insts.)	(Damo reipers		:: - £	K.G.A. Golf Club (near Texas Insts.) upto Chatlaghatta Main Road, New drain has to be constructed for 30 m wide and 2.8 m ht. Providing stone fivetment along with parapet wat	-	-	-		-	-					Sec.
								to be constructed for a ht. of 0.5 m a) Both Side						-		10000 - 11000		After desilting bed protection to be provided for full	
	11	10,000	12,000	Challaghata Main Road (behind Alrport)	Location near Beliandur tank	10000 - 12000		Challaghalta Main Road uplo	•	-								length and width	
				*				Bellandur tank. Kacha drain has											
								and 2.5 m depth from G.L. Also stone rivetment to be provider for a ht. of 2.5 m	4							Ē			
U.								Land demarcation to be made or either side for formation of Service Road. Provision to	AG					1		Ē			
								providing good store @ every5 m istematives to be made in in	đ								5.4		
			1	:				cetinuiz.		-									
			1					1	1		1			l					
	1		¥ 19				l	<u> </u>	<u> </u>										
		<u>.</u>					-				L			1	· · · · · · · · · · · · · · · · · · ·				

.

STUP Consultants P. Ltd.

•

Feesibility Report - Challeghette Valley - Chapter-6

Page No300

Remodeling of Primery Secondary Storm Water Drain in Bangalore City

િઝ

• · · •

Rer	nodelling of	Primery Se	condary Slorn V	Vator Drain in Bai	ngalora City					•	· ·			
·		<u> </u>				Table - 6.2	Schedule For Providing Reha	bilatation to th			imary Storm Drain in Challaghatta		(C100)	
~ S		ge (m.)	Sugar San San Alian Loce	tion		Diala	all Reconstruction		Sec. 17.	\sim H	g Storm Drain Rehabilitation Wo Nall Restoration	rks	Utility Shirting &	Other Obstruct
N:		То	From	То	Chainage (m.)		Remarks	Chainage (m.)			Remarks	Chainage (m.)		
	From	3	4	5	6	7	8	9	10		11	12	13	<u></u>
c	00 Chal	laghatta		y Storm Drain	a) 900 - 925	-	a) Left Side	в) 275-357			a) Left Side	1) 0 - 500		1) a) _{Nā}
	0	1,000	Bangalore Palace Ground	Queen's Road	8) 300-323		4 m length, 2 m ht. wall to be reconstructed.	1 1			After desitting pointing to be provided to , a ht. of 1 m from drain bed	2} 500 - 1000		4 ros. o 2) a) above dr 825 - 850
								b) 400 - 625			 b) <u>Right side</u> After desitting pointing to be provided to a height of 1 m from drain bed. 			2 no. of b) m HL exis
								c) 625 - 100			 <u>Both side</u> After desitting pointing to be provided to a height of 1 m from drain bed. 			

. .

•

\mathbb{C}									a) 1000 - 1800	 	After desitting pointing to be provided to a height of 1 m from drain bed. a) <u>Both Sides</u>	1) 1000 - 1500	a) 5 nos. of 12 r
	2	1,000	2,000	Queens Road	Juma Masjid • Road		-		a) 1000 - 1800	-	After desitting pointing to be provided for full height from the drain bed.		b) 7 nos. of teley @ rebout 1.2 c) 3 nos. of 7.5 d) 3 nos. of 250 pipuline exist 17 nos. of m m L from dra
							-			~		e) 1500 - 2000	a) 1 ne. of 40 n Ch. 1750 m 5 ncs. of 40 © Ch. 1750 m 6 ncs. of 1.2 c) 0.6 m from 0 1550 - 1800
	3	2,000	3,009	Juma Masjid Road	Mudaliar Road	 a) 2125-2150 b) 2450 - 2475 c) 2725 - 2750 d) 2825 - 2850 e) 2850 - 2925 f) 2975 - 3000 		 a) <u>Right Side</u> m length, 2.4 m ht wall to be reconstructed b) <u>Right Side</u> th length, 2.4 m ht wall to be reconstructed <u>Left Side</u> m length, 2.6 m ht wall to be reconstructed d) <u>Right Side</u> m length; 2.6 m ht wall to be reconstructed. Right Side m length; 2.6 m ht wall to be reconstructed. To m length; 1.0 m ht parapet wall be reconstructed. Left Side m length, 2.6 m ht wall to be reconstructed. 	b) 2610 - 2725 c) 2725 - 3000		 a) <u>Both sides</u> After desilting pointing to be provided to a ht. of 1.0 m from drain bed. b) <u>Left Sido</u> After desilting pointing to be provided to a ht. of 1.0 m from drain bed. c) <u>Both Sides</u> After desilting pointing to be provided to a ht. of 1.0 m from drain bed. 	o	 a) 4 nos. of 15 between Ct b) 2 nvs. of 50 between Ct c) 6 nos. of 2. from drain d) 15 nos. of 1 Ht from dra a) 2 nos. of 1 pipetine b) 1 no. of 40 c) 8 nos. of 2 ht from dra d) 8 nos. of 40 d) 8 nos. of 1 ht from dra

÷

tion Removals	1.1.2 - 12 1.7.4
Remarks	9 <u>-</u>
	15 .
14	
of telephone cable @ 1 m ht. Irain bed level exists between Ch. 50 1.2 m dia. manhole between 0.1 cists between Ch. 825 - 925 m	
of 12 mm dia. encasement pipe	
of telephone cables of 6 mm dia. ut 1.2 m hL sbove drain bed leve	1.
of 7.5 mm dia, Cable lines	
of 250 mm dia, water supply (w/s e exists between 1100 - 1500	;)
: of manhole of 1.2 m dia. & 0.6 om drain bed exists.	
of 40 mm dia cable line exists @ 50 m of 40 mm dia. W/s pipeline exist	s
. 1700 m	
of 1.2 m dia M.H. & 8.5 m ht. & from drain wall exists between - 1800	
_	
i, of 15 mm of a. cable lines exists een Ch. 2425 - 2450 5. of 50 mm of a. cable lines exists een Ch. 2525 - 2550 5. of 2.0 m of a., manholos 0.5 m drain bed. os. of 1.2 m of a. manholes & 0.2 om drain bed. os. of 110 mm of a. water suj	ht.
ine , of 40mm cia. cable line. s, of 2.0m cia manholes & 0.70 om drain bed exists. s, of 1.2m cia. Manholes & 0.50 rom drain bed.	ļ
	<u>, 10</u>

11 (2) (1)

-5

Pago No301

		- <u>6</u> - 9 - 1	0.5 ** .	
· · · · · ·	المسادقة مراد	•••••		
<u>Remodelling of</u>	Primary Sec	201061	ry Storm Water Drain in Bangalore City	
•	• • •		•	

														-		
Q	SL.	Sector States	age (m.)		ation						14 F. 15 . 14	ing Storm Drain - Rehabilitation W	21-1-10 P			
		From	То	From	To	Chainage (m.)	(F Taba	All Reconstruction	Chainage (m.	Ţ.	Dráh	Wall Restoration	Chainage (m.)	Uuliny shirting s	Other	Obstr
	1	2	3	4	5	6	7	8	9		10	11	12	13		
•••	-4	3,000	4,000	ASM Road (near Ajantha Theatre)	Kensington Road	a) 3225 - 3250		 a) <u>Left Side</u> 20 m length, 3.4 m ht wall to be reconstructed 	a) 3000 - 4000			 Both Side After desilting pointing to be provided to a ht, of 1.5 m ht, from drain bed. 	1) 3000 - 3500		1) 8)	6 nos. línes e
		-				b) 3250 - 3500	- j. an	b) <u>Left Side</u> 50 m length, 3.4 m ht. Wal to be reconstructed.					2) 3500 - 4000	:	ь)	1 no. (
	5	4,000	5,000	Kensington Road	Old Madras Road	a) 4175-4200		a) <u>Right</u> <u>Side</u> 10 m lenth, 3.2 m ht drain wall to be reconstructed.	2) 4000 - 5000			a) <u>Both Side</u> After desiting pointing to be provided to	1) 4000 - 4500		1. 8)	5 ncs. @ ch.
$\widehat{}$						b) 4400 - 4425		<u>Right Side</u> - 10 m length, 3.2 m ht. b) wall to be reconstructed. Drain wali to be reconstructed.	ь) 4500 - 5000			a ht, f 0.5 m ht, from drain bed.			b)	
Ŭ.,															d} :	exists 2 nos, sbove
													b) 4500 - 5000			ht abo
	6	5,600	6,0 03	Old Madras Road	Someshwarapu ra 6th Main Road	-	-		a) 5000 - 6000			a) <u>Both Sides</u> After desiting pointing to be provided to	1) 5000 - 5500		1.a) : (b) :	@ Ch.
							-					a hL of 0.5 m from drain bed.	2) 5500 - 6000		2.a) 1 (b) 5	m 1 nc. c exises
	7	6,600	7,000	Someshwarapu ra Main Road	Domiur End Stage, near TERI	-	-		n) 6000 - 7000			b} Both Sides	1) 6000 - 6500		6	mm di 6175 r
\sim								-				After desiting pointing to be provided to a ht of 1 no. from drain bed.			ĩ	dia, 2 nos. o betvici
	 			Derek lind	Diamond		-	<u>Right Side</u> - 5 m length, 3.0 m ht.				<u>Both side</u> - After desiling pointing to be	2) 6500 - 7000			exis!s Ni
	8	7,000	8,000	Domk:) IInd Slage near TERI		a) 7400 - 7475		wall to be reconstructed.	a) 7000 - 6000			 a) provided to a ht_ of 1.0 m from drain bed. 	в) 7000 - 7500			2 ncs.
						b) 7500 - 8000		<u>Right Side</u> - 50 m length, 3.0 m ht. wall to be reconstructed.			er.		b) 7500 - 8000		() () () () () () () () () () () () () (@ Ch. 10 no near C 1 no. 0 drain t m 1 no. pipelin 0.3 m
	9	8,000	9,000	Diamond District Apartmonts	K.G.A. Golf Club (near Texas Instruments)	-	-	-	a) 6600 - 9000		-	Left Side - After desilting and drain widening, pointing to be provided to a ht of 1.5 m from drain bed.	aj 0000 - 0000			

Feasibility Rep	oort – Challaghatta Valley	/- Chapler- 6
be truction Removals	To the Unit For	
Remarks	1	
14	15	
nos. of 180 mm dia. Telephone cable nes exists		
no. of 750 mm dia, w/s pipeline exists.	<i></i> •	
ncs. of 110 mm dia. w/s pipeline exists) ch. 4100 m		
ncs, of cable lines		
nos. of 110 mm dia. w/s pipe line ists @ Ch.4450 - 4475 m nos. of 1.6 m dea. Manhole & 1.2 m ht		
nove drain bed. nos. of 1.2 m dia. Manholes & 1.0 m	العندية. العندي	
. zbove drain bed. ncs. of 110 mm dia w/s pipeline exists Ch. 5100 m		
nos. of cable Fries exists @ Ch. 5350		
nc. of 2.0 m dea. Manhole of 1.0 m ht	-	•
iss @ Ch.5775 m ncs. of 1.2 m dia. Manhole of 1.0 m hL isis b/w ch. 5725 -5900 m.		
nos, of 150 mm dia & 4 nos. of 110 m dia, Sewer ⊑ne oxists @ ch. 6150 - /75 m		
nes, of 120 mm dia, 1 no. of 200 mm a, 2 nos. of 75 mm dia. w/s line and 5 s. of 110 mm dia. Cable lines exists tween Ch. 6400 - 6500 m		
nos. of 2,0 m dia & 1,2 m ht. Manhole ists @ Ch. 6125 m 1		
		3
ncs, of w/s lines of 300 mm dia. Exists Ch, 7915 m		
) nos of PVC service pipeline exists er Ch. 7975 m no. of 2 m dia manhole, 1 m ht. From		
aln bed exists between Ch. 7775-7600		
no, of 1800 mm dia. C.I. Sower peline exists near Ch. 7925 m @ ht. Of 3 m above drain bad.	The second	
ncs, of w/s line of 150 mm dia,		

Page No302

1

.

•

5

.

Remodelling of Primary Secondery Storm Weter Drain in Bengelore City

٠

1

STUP Consultants P. Ltd.

									an although that shat a c						
3	જ્ઞ	122	ge (m.)									ing Storm Drain - Rehabilitation W			
~	No.						Oraln W	all Reconstruction			Drain	Wall Restoration		Utility shifting &	Other Obstruction
		From	το	From	То	Chainage (m.)		Remarks	Chainage (m.)	· · ·	- :: 	Remarks	Chalnage (m.)	(. **	-
					5	6	7	8	9		10	11	12	13	
	1	2	3	_							*				b) 5 ncs. of 1 near Ch. 8
							-	•		~	<u>;</u> *		b) 8500 - 9000		
	10	9,000	10,000	K.G.A. Golf Club near Texas Insts.	Challaghatta Main Road (behind Airport)	-	-	<u>-</u>	-		-		a) 9000 - 9500		a) 3 nos. of y día.
							-				-			¢.	b) 3 nos.of 1
	11	10,000	12,000	Challaghatta Main Road (behind Airport)	Location near Bellandur Tank	-	-	-	-			-		-	
							-				-	р.			
5	י י			· · · · · · · · · · · · · · · · · · ·	<u> </u>		-							i ant	
	L														

A CONTRACTOR OF	CONTINUE AND AND ADD DEPENDENCES
State of the second state of the	
the first start was a set of the	
and the second se	
ction Removals	
CHOIL VEILUARD COMPANY COMPANY	
	•
Remarks	
NCHIMANS .	
	15
14	1.2
of 110 mm dia. Cable lines exists	
n. 8200 m.	
. 0200 11.	
- ·	
f. I. f	
of w/s line of 110, 150 & 180 mm	
of 110 mm dia, Cable lines exists	
	•
	· . ·
	· · ·
i	
9	
	1
	· · (

Page No. 303

t

Remodelling of Primery Secondary starm water drain hi Bangalore City

	[1			a hali taketa	And the second second second	St Market Contractor	1	able - 6.3 Schedule	e For Improvi	ng the Carry	ing Capacity	of Existing Se	condary Stor	m Drains in	Challaghatta Main Valley	,			
Ì			nice (m.		cation			人和存在方法的主要的主要	5 St. 6 1.55		Existing S	torm Drain-20	Carrying Cap	acity Improv	ements Works		11 1	L. C.	100 CONTRACTOR
	SL Na						Orain V	Widening		Drair	Contraction in the family		1 1.5 million 2 for a constant of a	CALLED METLES STATISTICS		1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997	and the second		
		From	То	From	To	Chainage (m.	•	Remarks		1	1		1		ali Raising		Bed Prote	ction	
	1	•	3	4	- 6	6		Remarks 8	Chainage (m.)			Remarks	Chainage (m.)	A	Remarks	Chainage (m.)	1	Remarks	242 ···
		_			ondary Storm	Drain: Murug			1 8	10		11	12	13	14	15	16	17	18
						1			1	1	a) After des	tting existing oper				<u> </u> .			
	1	0	1,000	Sudhamanaga	ar K.R. Garden	250 - 500		Right Side	a) 500 - 630		I urain nee	to be deepened from near Papalat	-1		Drain wall on Heritage Centr Side near Papaiah Layout need to be raised from 1.2 m to 2.0 m	s a) 0 - 250		a) After desilting drain bed lining to be provided for full length & width.	
								Layout. Existing covere drain (1.2 x 1.0 m) needs t be replaced with RCC Bo drain of size (3 m x 2m)	9									Existing width : 3 m	
						500-630		<u>Right Side</u>	b) 700-950		by 500 r	ing existing open is to be deepened nm From Airport Sriram Nagar.	1					 b) After desilting drain bed lining to be provided for full length & width 	
								Near Papaiah Layout Existing open drain to be widened From 1.5 m to 3 m ht. 2 m,								-		(Existing width : 3 m)	
_						660 - 700		Left Side Adjacent to Airport Road B.S.											
							· _	Slab covered Existing drain (1.2 x 1.0 m) needs to be replaced with RCC Bax drain of size (3 m x 2 m)											
	2 1	200,	1,875	K.R. Garden	Airport	1000 - 1875		Note:- Construction of RCC Bax dezin of size (3 x 2 m) under progress.		-		-	-	-	-	-	-	-	-
ŀ				•				l						4.4.					
ŀ	-2017	-Chain	ighatta V		y Storm Drain; \$	Shashingar De	205											<u>}</u>	
	1	C	1,000	Sweepers Colony near Indiranagar BMTC Depot	Shastrinagar near CMH Road	0-603	-	Note:- Drain Reach is under Defence Controlled Area	-	-		-	-			a) 600 - 1000	.	a) After desitting chain bed lining to be provided for full length & width	· .
		<u> </u>									e) Existing	corract durin e opored (B						(Existing width ≖ 4 m)	
)	2 1	830	1,600	Shastrinagar near CMH Road	Chollaghatta Valley Primary Storm drain	-	-	-	¤) 1000 - 1600		reguler in desilled and 500 mm fro Main I	orval) furthor doepanod by Lekshmi-pura load upto Valloy Primary	-	-	-	b) 1000 - 1600		b) After desilting drain bed lining to be provided for full length and width	
									·			┼╌╌╾╼┼							
												<mark>╎╶┄┈╼╶┛</mark>						(Existing width = 4 m)	
c	105 - 1	Chaila	ghutta Va	ner Secondary	Storm Drain; 15	SRO Complex D	rains		l										
	5	o	1,000	Joevanbhima Nagar	Kodīhalli Main Rosd	-	-		400 - 1000		ba daapana	g drain bed to d by 500 mm bhime Negar	-	-	-	400 - 1000	، د ژ.	After desilting drain bed Uning to be provided for full length & width	
:	2 1,0	200	2,000	Kodihalli Maln Road	Indiranagar		-	-	1000 - 2000	<u>ا</u> نہ	After desiltin be despend near Kodihall	g drain bad to by 300 mm Villago.	•	•	•	1000 - 2000		(Existing width - 4 m) After desitting drain bed taking to be provided for full length & width	·
	2,0	xxx :	3,000	Indiranegar	Airport Road	-	-	-			· · .		-	-	-	2000 - 3000	· · ·	(existing width - 4 m) After desitting drain bod lining to be provided for full longth and width	
	_ <u></u>																	(Existing width : 6 m)	
								•-	1	2.5 F								, (mart o ny	
A) (2)	1.5i			Martin States and States			<u></u>			l_									2 T

Table - 6.3 Schedule For Improving the Carrying Capacity of Existing Secondary

STUP Consultants P. Ltd.

ر_) ا

ЪĨ

Page No.304

Remodeling of Primery Secondary storm water drain in Bangalore City

~~~ (

 $\overline{\mathbb{O}}$ 

γ. .





| s    | Chain     | (m.)       | مان <u>المراجع</u>                       | ation                        |                   |             |                                                                                                         |                |            | ting Storm Drain – Rehabilitation W                                                            | 計測化学研究の言          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                      |
|------|-----------|------------|------------------------------------------|------------------------------|-------------------|-------------|---------------------------------------------------------------------------------------------------------|----------------|------------|------------------------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|
| Na.  |           |            |                                          | <i>1990 - 20</i> 1<br>I      |                   | Drain W     | all Reconstruction                                                                                      |                |            | Wall Restoration                                                                               | STATES STATES     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | L'Other Ob           |
| Ì    | From      | To         | From                                     | То                           | Chainage<br>(m.)  |             | Remarks                                                                                                 | Chainage (m.)  | · ···· · · | Remarks .                                                                                      | Chainage (m_)     | States and |                      |
| 1    | 2         | 3          | 4                                        | 6                            | 6                 | 7           | 8                                                                                                       | 9              | 10         | 11                                                                                             | 12                | 13                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | <u> </u>             |
| C101 | I — Chall | laghatta   | Valley Second                            | lary Storm Dra               | in: Murogeshpa    | alya drains |                                                                                                         | · · ·          |            | · · · · · · · · · · · · · · · · · · ·                                                          |                   | ······································                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                      |
| 1    | 0         | 1,000      | Anandnagar                               | K.R. Garden                  | 700-950           |             | Right Side                                                                                              |                |            |                                                                                                | 1a) 0-500         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 1 I<br>ht            |
|      |           |            |                                          |                              |                   |             | Drain wall to be reconstructed for a<br>length of 250 m & 2 m ht, from Airport<br>Road upto Sriramnagar |                |            |                                                                                                | 2 a) 500 - 1000   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 21                   |
| {    |           |            |                                          | •                            |                   |             |                                                                                                         |                |            |                                                                                                |                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | ( ь)                 |
| ĺ    |           |            |                                          |                              |                   |             |                                                                                                         |                |            |                                                                                                |                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | c)<br>hi             |
|      |           |            |                                          |                              |                   |             |                                                                                                         |                |            | · ·                                                                                            |                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | <u></u>              |
| 2    | 1,000     | 1,875      | K.R. Garden                              | Airport                      | 1000 - 1875       |             | Note: Construction of RCC Box drain<br>of size (3 x 2 m) under progress.                                | -              |            | •                                                                                              | 1) a)1000 - 1875  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 1)<br>Pių<br>ex      |
|      |           |            |                                          | ļ                            | l                 |             |                                                                                                         | l              |            |                                                                                                |                   | <u>├</u>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                      |
| 407  |           | nhatta Val |                                          |                              | ນສາວັດຂຽວ: Drains |             | ·                                                                                                       | L              |            |                                                                                                | ſ                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | <del> </del>         |
|      |           |            | Sweepers                                 |                              | - 7               |             |                                                                                                         |                |            |                                                                                                |                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                      |
| 1    | o         | 000,1      | Colony near<br>Indiranagar<br>BMTC Depol | Shantinagar<br>near CMH Road | -                 | -           |                                                                                                         | a) 600 - 1000  |            | a) <u>Both side</u>                                                                            | 1) a) 0 - 500     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 1)                   |
|      |           |            |                                          |                              |                   |             |                                                                                                         |                |            | a) After desiting, pointing to be provided<br>for 1 m ht. From chain bed level.                | 2) 500 - 1000     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 2) a) 21             |
|      |           |            |                                          |                              |                   |             |                                                                                                         |                |            |                                                                                                |                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | b) 41                |
|      |           |            |                                          | Ciastaghetta                 |                   |             |                                                                                                         |                |            |                                                                                                |                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                      |
| 2    | 1.000     | 1,600      | Shardinəçər<br>nez: CMit Road            | Vallar Drimany               | 1350 - 1375       | 1           | <u>Left Side</u>                                                                                        | z) 1000 - 1600 |            | a) <u>Both side</u>                                                                            | a) 1000 - 1600    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                      |
|      |           |            |                                          | SIGHTER                      |                   |             | 10 ක length, 2 m ht. හෝ be<br>reconstructed.                                                            |                |            | After desitting and deepening, pointing to<br>be provided for 1 m ht. from chain bed<br>fevel. |                   | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | -                    |
|      |           |            |                                          |                              |                   |             |                                                                                                         |                |            | · · · ·                                                                                        |                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                      |
| :105 | Challa    | ahatta Val | ley Secondary                            | Storm Drzin: ISi             | RO Complex Drzł   | ع           |                                                                                                         |                |            |                                                                                                |                   | ·····                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | - <u></u>            |
| 1    | 0         | 1,000      | Jeevanbhima<br>Nagar                     | Kodihalli Main<br>Road       | -                 | -           | •                                                                                                       | a) 400 - 1000  |            | a) <u>Both side</u>                                                                            | 1) a) 0 - 500     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 1) a) 7 (<br>ex      |
|      |           |            | t to get                                 |                              |                   |             |                                                                                                         |                |            | After desilting, pointing to be provided for<br>a ht, of 1 m from the drain bed.               |                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | b) 91                |
|      |           |            |                                          |                              |                   |             | 3                                                                                                       |                |            | }                                                                                              | 2) 500 - 1000     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | <sup>2) a)</sup> 2 a |
|      |           |            |                                          |                              |                   |             |                                                                                                         |                |            |                                                                                                |                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | b) 1 (               |
|      |           |            |                                          |                              |                   |             |                                                                                                         |                |            |                                                                                                | l<br>             | <u> </u>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | dr                   |
| 2    | 1,000     | 2,000      | Kodihalli Main<br>Rood                   | indiranogar                  | 1200 - 1225       |             | Right Side                                                                                              | a) 1000 - 2000 |            | a) <u>Both sides</u>                                                                           | 1) a) 1000 - 1500 | ••                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | '" Pi                |
|      |           |            |                                          |                              |                   |             | 10 m length 2 m ht, wall to be<br>reconstructed,                                                        |                |            | After desitting pointing to be provided for<br>a fit, of 1 m from the drain bed.               |                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | <sup>b)</sup> 6      |
|      |           |            |                                          |                              |                   |             |                                                                                                         |                |            |                                                                                                |                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | c) 4                 |
|      | -         |            |                                          |                              |                   |             |                                                                                                         |                |            |                                                                                                | 2) 1500 - 2000    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 2)                   |
| 3    | 2,000     | 3,000      | Indiranagar                              | Airport Road                 |                   |             | -                                                                                                       | e) 2000 - 3000 |            | a) Both sides                                                                                  | 1) 2000 - 2500    | <u> </u>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 1                    |
|      |           | -,         |                                          |                              |                   |             |                                                                                                         |                |            | After desitting pointing to be provided for                                                    |                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 1                    |
|      |           |            |                                          |                              |                   |             |                                                                                                         |                |            | a ht, of 1 m from the drain bod.                                                               | 2) 2500 - 3000    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 2)a)1                |
|      |           |            |                                          | ۱ <u></u>                    |                   | ·           |                                                                                                         | Iį             |            | l                                                                                              | l                 | <b> </b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                      |

STUP Consultanta P. Lid.

|                                                       | CHARLEN STATES                           |
|-------------------------------------------------------|------------------------------------------|
|                                                       | and the second second second             |
|                                                       | and the free management and easy for the |
| tion Removals of the second                           |                                          |
|                                                       | Len                                      |
| Remarks                                               | 12- bet hannt.                           |
| 14                                                    | 16                                       |
|                                                       |                                          |
|                                                       | ·                                        |
| 10. of 1.2 m dia. manhole & 1.2 m<br>drain bed exists |                                          |
|                                                       |                                          |
| o. of 110 mm dia, w/s pipeline                        |                                          |
|                                                       |                                          |
| . of 100 mm dia, cable line exists.                   |                                          |
|                                                       |                                          |
| is. of 1.2 m dea manhole & 1.2 m                      |                                          |
| between Ch.700 to 950 m.                              | - <u>-</u> _                             |
|                                                       | ۳.                                       |
| no. of 450 mm dia & C.I. Sewer                        | ······                                   |
| e @ ht. of 0.4 m from drain bed                       |                                          |
| Ch. 1460 m (Adjacent to Airport                       |                                          |
| ind)                                                  |                                          |
|                                                       | Ĩ                                        |
|                                                       |                                          |
| · · · · · · · · ·                                     |                                          |
|                                                       |                                          |
|                                                       |                                          |
| -                                                     | -                                        |
|                                                       |                                          |
|                                                       |                                          |
| ( 160 mm dia, w/s pipeline exists.                    |                                          |
|                                                       |                                          |
| l cable line exists                                   |                                          |
|                                                       |                                          |
|                                                       |                                          |
|                                                       |                                          |
|                                                       | 1.                                       |
|                                                       | à .                                      |
|                                                       |                                          |
|                                                       |                                          |
|                                                       |                                          |
|                                                       |                                          |
|                                                       |                                          |
| · · · · · · · · · · · · · · · · · · ·                 | · · · · · · · · · · · · · · · · · · ·    |
|                                                       |                                          |
|                                                       |                                          |
| f 110 mm dia PVC w/s pipeline                         |                                          |
|                                                       |                                          |
| f 50 mm da, cable line exists.                        | ·                                        |
| outlets are closed,                                   |                                          |
|                                                       |                                          |
| 1.2 m dia, M.H. et 2 m hL from<br>d exists,           |                                          |
| 50 to 300 mm dia GI & PVC w/s                         | · · · · · · · · · · · ·                  |
| extenses                                              |                                          |
|                                                       |                                          |
| f 150 mm dia cable line exists.                       |                                          |
| f Sewer outlets are noticed.                          |                                          |
|                                                       |                                          |
|                                                       | · .                                      |
|                                                       |                                          |
|                                                       |                                          |
|                                                       | 1                                        |
|                                                       |                                          |
| 300 mm dia. C.I. Sewer pipe line                      |                                          |
| ht, of 0.5 m from drain bod.                          |                                          |
|                                                       | 1                                        |

, Page No. 305

e Leere,

< 0

### Table - 6.5 Schedule For Improving the Carrying Capacity of Existing Primary Storm Drain in Ulsoor Valley (C 200)

| 51.<br>No.<br>F<br>C200 - | From<br>2          | То<br>3               | From<br>4<br>ey Primary S                         | Cation<br>To<br>6                                | Chainage (m.)         | Drain W     | Adening                                                                                                       |                |                   |                                                                                            | n Drain – C                                                    | Carrying Cap   | acity Improv | vements Works                                                                                              | S. States      |                   |                                                                                                                 |                                  |
|---------------------------|--------------------|-----------------------|---------------------------------------------------|--------------------------------------------------|-----------------------|-------------|---------------------------------------------------------------------------------------------------------------|----------------|-------------------|--------------------------------------------------------------------------------------------|----------------------------------------------------------------|----------------|--------------|------------------------------------------------------------------------------------------------------------|----------------|-------------------|-----------------------------------------------------------------------------------------------------------------|----------------------------------|
| 51.<br>No.<br>F<br>C200 - | From<br>2<br>1 Ufs | To<br>3<br>soor Valle | From<br>4                                         | To                                               |                       | Drain W     | <i>lidening</i>                                                                                               |                |                   |                                                                                            |                                                                |                |              |                                                                                                            |                |                   | the second se | <b>24-27-26-26-26-26-2</b> 2-26- |
| 1<br>C200 -               | 2<br>Ufs           | soor Valk             | 4                                                 |                                                  | Chainage (m.)         |             | 1                                                                                                             |                |                   | ling & Deepening                                                                           |                                                                |                | Drain V      | Vall Raising                                                                                               |                | Bed Prote         | ction                                                                                                           | • • • • • • • • • • • • • • • •  |
| C200 -                    | Ufs                | soor Valk             |                                                   | 6                                                | 1                     |             | Remarks                                                                                                       | Chainage (m.)  | ي.<br>و. ما يار ا | Re                                                                                         | marks                                                          | Chainage (m.)  |              | Remarks                                                                                                    | Chainage (m.)  | 1                 | Remarks                                                                                                         |                                  |
|                           |                    | 1                     | ey Primary S                                      | · · · · · · · · · · · · · · · · · · ·            | 6                     | 7           | 8                                                                                                             | 9              | 10                |                                                                                            | 11                                                             | 12             | 13           | 14                                                                                                         | 16             | 16                | 17                                                                                                              | - 18                             |
| Ŧ                         | 0                  | 1,000                 | 1                                                 | 1                                                | 1                     | <del></del> |                                                                                                               |                |                   |                                                                                            |                                                                |                |              |                                                                                                            |                | <u> </u>          |                                                                                                                 |                                  |
|                           |                    | }                     | J.C. Nagar<br>Main Road                           | Ramakka<br>Block Main<br>Road                    | a) 270 - 320          |             | Right Side                                                                                                    | a) 0 - 250     |                   | a)<br>Existing drain                                                                       |                                                                | -              | -            | -                                                                                                          | a) 75 - 1000   |                   | After desilting drain bed<br>to be provided for full<br>length and width.                                       |                                  |
|                           |                    |                       |                                                   |                                                  |                       |             | Near J.C. Naga<br>Ramageetha Block, 1st<br>Cross, from 4.5 m to 6.0 m,<br>2m ht. wall to be<br>reconstructed. | ť              |                   | 1st Cross,                                                                                 | drain bed to be<br>500 mm from<br>Rama-geetha<br>Ramakka Block |                |              |                                                                                                            |                |                   |                                                                                                                 |                                  |
|                           |                    | ,                     |                                                   |                                                  | b) 445 - 465          | -           | Right Side<br>Near Krishnammanagar 1st<br>Main Road from 4 m to 6.5 m<br>2 m ht. wall to be<br>reconstructed. |                |                   |                                                                                            |                                                                |                | -            |                                                                                                            |                | -                 |                                                                                                                 |                                  |
| 2 1.                      | 1,000              | 2,000                 | Ramakka<br>Block Main<br>Road                     | S.K. Garden<br>Main Road<br>near Pottery<br>Town | a) 1050 - 1200        |             | a) New RCC Box drain of<br>size 4 m width, 2 m ht, for a<br>length of about 150 m needs<br>to be constructed. | a) 1000 - 2000 |                   | After desilting<br>deepened by<br>Ramakka Blo<br>Garden Main R                             | 500 mm from<br>st. uxto SK                                     | a) 1500 - 1825 |              | Left Side                                                                                                  | a) 1000 - 2000 |                   | After desitting drain bed<br>to be provided for full<br>length & width                                          |                                  |
|                           |                    |                       |                                                   |                                                  | ь) 1200 - 1500        |             | oj now uper, prain or size p<br>m wide, 2.4 m ht, for a length<br>of about 300 m needs to be<br>remainment    | i i            | -                 |                                                                                            |                                                                | b) 1875 - 1975 |              | Near S.K.Garden Main Road<br>(Adjacent to Defence Land) from<br>2.0m to 2.4m<br>b) Right Side              |                |                   |                                                                                                                 |                                  |
|                           |                    |                       | -                                                 |                                                  | c) 1520-1525          | ł           | Right Side<br>Up mean S.A. Galvert mante<br>Road (Adjacent to Defence<br>Lend) from 5m to 9m ht.              |                |                   |                                                                                            |                                                                | c) 1975 - 2000 |              | Near Pottery Town bridge<br>location from 2 m to 2.4 m<br>c) <u>Both side</u><br>Corp. Kalyana Mantap near |                |                   |                                                                                                                 |                                  |
|                           |                    |                       |                                                   |                                                  | d) 1875 - 1975        | ~ ÷         | Left Silde<br>Near Potery Town bridge<br>location from 8 m to 10 m ht.<br>2.4 m                               |                |                   |                                                                                            |                                                                |                |              | Pottery Town from 2m to 2.4m                                                                               |                |                   |                                                                                                                 |                                  |
| 3 24                      | 2003               | 3,600                 | S.X. Garden<br>Lizin Road<br>near Pottery<br>Town | Stephen's<br>Cross Road                          | <b>8) 2075 - 2175</b> |             | Near Bore Bank Road (near                                                                                     | a) 2000 - 2200 |                   | <ul> <li>a) Existing drain to</li> <li>After desilting d</li> <li>deepened by 3</li> </ul> | rain Led to be                                                 | -              | -            | -                                                                                                          | a) 2000 - 3000 |                   | After desilting drain bed<br>to be provided for full<br>length and width.                                       |                                  |
|                           |                    |                       |                                                   |                                                  |                       |             | Railway Bridge) from 8 m to<br>11 m ht. 2.4 m                                                                 |                |                   | b) Bore Bank<br>Railway Bridge)<br>Road                                                    | Road (near                                                     |                |              |                                                                                                            |                |                   |                                                                                                                 |                                  |
|                           |                    | [                     |                                                   |                                                  | 3                     |             |                                                                                                               | c) 2700 - 3000 | 3£.1              | <ul> <li>c) Existing drain to</li> </ul>                                                   | be desitted.                                                   |                | -            |                                                                                                            | ،<br>ا         | н <del>т</del> ., |                                                                                                                 |                                  |
| 4 3,0                     | .000               | 4,100                 | Stephen's<br>Cross Road                           | Ulsoor Lake                                      | a) 4050 - 4100        |             |                                                                                                               | a) 3000 - 4100 |                   | After desilting, deepened by 300                                                           | nain bed to be<br>Cmm                                          | -              | -            | -                                                                                                          | n) 3000 - 4100 |                   | After desilting drain bed<br>to be provided for full<br>length & width.                                         | '                                |
|                           |                    |                       |                                                   |                                                  |                       |             | 4th Cross, Sindhi Colony to<br>be Lako View Maha<br>Ganapathy lemplo from 11 m<br>to 14 m ht. 2.6 m           |                |                   |                                                                                            | •                                                              |                |              |                                                                                                            |                |                   |                                                                                                                 |                                  |
|                           |                    |                       |                                                   |                                                  |                       | · =         |                                                                                                               |                |                   |                                                                                            |                                                                |                |              |                                                                                                            |                |                   |                                                                                                                 |                                  |

. ..

STUP Consultants P. Ltd.

کل ت .

Page No.306

Remodeling of Primery Secondery Storm Water Drains in Bengelore City

Table - 6.6 Schedule For Providing Rehabilatation to the Existing Primary Storm Drain in Ulsoor Valley (C 200) 0 Existing Storm Drain -- Rehabilitation Works SL. Location Chainage (m. No Drdn Wall Restoration Drain Wall Reconstruction and the states of the Chainage Chainage Ta Remarks To From Remarks From - (1 Chainage (m.) (m.) 6 5 7 B 9 1 2 3 4 11 10 12 13 C200 - Ulsoor Valley Primary Storm Drain .C. Nagar Main Ramakka Block a) 125 - 150 1) a) 0 - 500 Right Side 2) 80 - 1000 1 1,000 0 Both Side -Main Road Road 10 m length, 2.6 m ht walls to be After desitting pointing to be provided for 8) reconstructed. a ht. of above 1 m from the draina bed. Both side b) 175-200 15 m length, 2.6 m ht. walls to be reconstructed. c) 375 - 400 Left Side 2) b) 500-1000 21 25 m length, 2.6 m hL wall to be reconstructed. S.K. Garden Ramakka Block After checking, pointing to be provided 0 Main Road near a) 1350 - 1475 a) 1000 - 2000 2 1,000 2,000 a) Left Side 8) a) 1000 - 1500 Main Road a for a ht. of about 1 m from the drain bed. Pottery Town 25 m length, 2.6 m ht. wall to be reconstructed. b) 1350 - 1475 b) Right Side 10 m length, 2.6 m ht. wall to be reconstructed. b) 1500 - 2000 121 ..... ь S.K. Gerden Stephen's 3 2,009 3,000 Main Road near a) 2225-2250 Right Side a) 2000 - 3000 a) 2000 - 2500 Both Side 1) a Cross Road Pottery Town 6.0 m length, 2.6 m ht. was its be a) After desitting, pointing to be provided for e ht. of about 1 m from drain bed. reconstructed. b) 2325-2500 Right Side ь١ 10.0 m length 2.6 m ht was to be C) reconstructed. c] 2925-3000 Left Side X, 15 m length 2.6 m ht wall to be reconstructed, ь) 2500 - 3000 2) ь١

STUP Consultants P. LLL

· :.

| 532      |                                                                                                                                                                                                                                                                   |                   |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|
| ţjej     | Costruction Removals                                                                                                                                                                                                                                              |                   |
| •        | Remarks                                                                                                                                                                                                                                                           |                   |
| _        | 14                                                                                                                                                                                                                                                                | 15                |
|          |                                                                                                                                                                                                                                                                   |                   |
| ) a)     | 1 no. 110 mm dia. w/s pipe line exists                                                                                                                                                                                                                            |                   |
| b)       | 12 nos. of 110 mm dia. Sewer outlets                                                                                                                                                                                                                              |                   |
| c)<br>a) | 27 nos. of 1.2 m dia. manhole & 0.5 m<br>ht. From drain bed exists.<br>Na                                                                                                                                                                                         |                   |
| <br>9)   | 11 nos. of 300 mm dia stoneware pipes<br>exists between Ch. 1000 - 1500                                                                                                                                                                                           |                   |
| 8)<br>1  | 22 nos. of 110 mm dia. PVC pipe sewer<br>outlets are noticed.<br>5 nos. of 1.2 m dia manhole & 0.75 m<br>13 from drain bed exists.<br>15 nos. of 110 mm dia PVC sewer<br>cutlets are noticed.<br>5 nos. of 1.2 m dia, manhole 0.5 m ht.<br>from drain bed exists. |                   |
| a)       | 2 ncs. of 750 mm dia. GI w/s pipelines.                                                                                                                                                                                                                           |                   |
| 1        | ઇ nos. of 110 mm dia PVC w/s pipeline<br>exists.                                                                                                                                                                                                                  |                   |
| )        | S nos, of PVC Sewer outlets are noticed.                                                                                                                                                                                                                          |                   |
| }        | 10 nos. of 1.2 m dia. Manhole 0.5 m ht.<br>from drain bed (left side) exists.<br>7 nos. of 1.2 m dia, Manhaole 0.8 m ht.<br>from drain bed (Right Side) exists.                                                                                                   | · · · <del></del> |
| a)       | t nos, of 110 mm dia w/s pipeline                                                                                                                                                                                                                                 |                   |
| }        | 33 nos. of 1.2 m dia. mathole, U.7 m ht<br>From drain bed exists between Ch.2550<br>2000                                                                                                                                                                          | ,                 |
|          |                                                                                                                                                                                                                                                                   |                   |

Page NS07

Remodelling of Primary Secondary Storm Water Drains in Bangalore City

| Ó | SL<br>No. | Chahu | <b>(a.</b> ) |                                        | ation   |                                                                                                                                                            | Draln M | All Reconstruction                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                | 1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1- | ing Storm Drain - Rehabilitation Wo                                                                 |                |    |                                                                                                                                                                                                                                                           |    |
|---|-----------|-------|--------------|----------------------------------------|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|----------------------------------------|-----------------------------------------------------------------------------------------------------|----------------|----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|
| • |           | From  | To           | From                                   | το<br>5 | Chalnage<br>(m.)                                                                                                                                           |         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Chainage (m.)  | F 5.                                   |                                                                                                     | Chainage (m.)  | 1  | 8 Other Obstruction Removals                                                                                                                                                                                                                              |    |
|   |           | 2     | 3            | 4<br>Stephon's                         |         | 6                                                                                                                                                          | 7       | 6                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 9              | 10 #                                   | 11                                                                                                  | 12             | 13 | 14                                                                                                                                                                                                                                                        | 15 |
| Ô | 4         | 3,000 | 4,100        | Stephen's<br>Cross Road                |         | <ul> <li>a) 3500 - 3525</li> <li>b) 3800 - 3825</li> <li>c) 3075 - 3125</li> <li>d) 3300 - 3425</li> <li>e) 3600 - 3525</li> <li>f) 3975 - 4033</li> </ul> |         | <ul> <li>a) Left Side <ol> <li>m length, 2.4 m ht wall to be reconstructed.</li> <li>Right Side <ol> <li>m length, 2.4 m ht wall to be reconstructed.</li> </ol> </li> <li>c) Right Side <ol> <li>m length, 2.4 m ht wall to be reconstructed.</li> </ol> </li> <li>d) Right Side <ol> <li>m length, 2.4 m ht. wall to be reconstructed.</li> </ol> </li> <li>d) Right Side <ol> <li>m length, 2.4 m ht. wall to be reconstructed.</li> </ol> </li> <li>e) Right Side <ol> <li>m length, 2.4 m ht. wall to be reconstructed.</li> </ol> </li> <li>f) m length, 2.4 m ht. wall to be reconstructed.</li> <li>f) m length, 2.4 m ht wall to be reconstructed.</li> <li>f) m length, 2.4 m ht wall to be reconstructed.</li> </ol> </li> </ul> | a) 5000 - 4100 |                                        | Both Side<br>After desilting, pointing to be provided for<br>a ht. of about 1 m from the drain bed. | 1) 3000 - 3500 |    | 1) a) 2 nos. of telephone line exists         b) \$ nos. of 1.2 m dia Manhole at 0.8 m ht from drain bed.         c) a) 2 nos. of 110 mm dia. cable line exists         @ Ch. 3525 m         b) 1 no. of 250 mm dia. w/s pipline exists         @ Ch.3850 |    |
| ļ |           |       |              | · · · ·                                |         |                                                                                                                                                            |         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                |                                        |                                                                                                     |                |    |                                                                                                                                                                                                                                                           |    |
| L |           |       |              | ······································ |         |                                                                                                                                                            |         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                | 1                                      |                                                                                                     |                | ·  | -                                                                                                                                                                                                                                                         | ÷  |

- Ê

8TUP Consultants P. Ltd.

4.0274 (A.M. 1911年)

•

 $\mathcal{A}$ 

. Page No.308

Remodelling of Primary Secondary Storm Water Drains in Bangalore City

STUP Consulants P. L.L.





Table - 6.7 Schedule For Improving the Carrying Canadian and the Secondary Stern During the

| $\sim$ | <u> </u>    | 1           |           |                               |                                                |                |                                                                                            | Table - 6.7 Sch                                                                                                                                                                                                                  | edule For Ir | nproving the | Carrying Ca                       | Pacity of Evictin                                                                  | ng Secondar    | Storm Drai            | ns in Ulsoor Valley   |                          |                     |
|--------|-------------|-------------|-----------|-------------------------------|------------------------------------------------|----------------|--------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------|--------------|-----------------------------------|------------------------------------------------------------------------------------|----------------|-----------------------|-----------------------|--------------------------|---------------------|
| 3      |             |             | inage (or |                               | ocation                                        |                |                                                                                            |                                                                                                                                                                                                                                  |              |              | Existing                          | Storm Dela                                                                         | Carrying Can   | acity Improv          | /ements:Works         | Signal State State State |                     |
|        | Ho<br>Ho    | ي فارز ا    |           |                               | ocauon 2.                                      |                | Drain W                                                                                    | Adening                                                                                                                                                                                                                          |              | Drain Desi   | iting & Deepeni                   |                                                                                    |                | 1-12 - How man states |                       |                          | <u>2235</u><br>2251 |
|        | .           | From        | ι Το      | From                          | To                                             | Chainage (m.)  | 1                                                                                          | Remarks                                                                                                                                                                                                                          | Chainage (n  | 1            | <u>arwaiteataaaaa</u>             | THE OWNER AND A DESCRIPTION                                                        |                |                       | all Raising           |                          |                     |
|        | 1           | 2           | 3         | 4                             | 5                                              | 6              | 7                                                                                          | 8                                                                                                                                                                                                                                | 9            | 10           |                                   | Remarks                                                                            | Chainage (m.)  | <u> </u>              | Remarks               | Chainage (m.)            |                     |
|        | 2           | 01-00       | soor Val  | icy Seconda                   | ry Storm Drain                                 | n: Ganesh Ten  | npie Drains                                                                                |                                                                                                                                                                                                                                  |              |              | · ·                               |                                                                                    | 12             | 13                    | 14                    | 16                       | 1                   |
|        | 1           | O           | 250       | Ganesh<br>Temp <del>l</del> e | MEG Centre                                     | -              | -                                                                                          |                                                                                                                                                                                                                                  | e) 0 - 250   |              | a) After de<br>deepend<br>Ganesh  | silting, drain bed to b<br>d by 300 mm nea<br>Temple                               | e<br>r -       | -                     | -                     | a) 0 - 250               |                     |
|        |             |             |           |                               |                                                |                |                                                                                            |                                                                                                                                                                                                                                  | ····         |              | 1                                 |                                                                                    | <u> </u>       | <u>-</u>              |                       |                          |                     |
|        | C20         | )2 Uli<br>1 | 600r V원(  | ey Secondar                   | y Storm Drain                                  | : Cox Town D   | rain<br>                                                                                   |                                                                                                                                                                                                                                  |              |              |                                   |                                                                                    |                |                       |                       |                          | 1                   |
|        | 1           | ο           | 1,170     | Richard Town                  | Gymkhana<br>Ground near<br>Assayce Road        | a) 400 - 600   |                                                                                            | a) <u>Both Side</u><br>Existing covered reach of                                                                                                                                                                                 | a) 250 - 600 |              | a) deepene<br>KPTCL               | itting, drain bed to be<br>d by 500 mm from<br>Office upto Frazer<br>free Station. | a) 1000 - 1075 |                       | a) <u>Left Side</u>   | a) 400 - 1170            |                     |
| 3      |             |             |           |                               |                                                |                |                                                                                            | drain Opp. Corp. Health<br>Centre upto Frazer Town<br>Police Station needs to be<br>widened.<br>From 2.5 m to 5.5 m ht. 1.8<br>m                                                                                                 |              | -            |                                   |                                                                                    |                |                       | Near Gymkhana Grounds |                          |                     |
|        |             |             |           |                               |                                                | a) 1000 - 1075 |                                                                                            | b) <u>Right Side</u><br>Near Gymkhana Play-ground                                                                                                                                                                                |              |              | -                                 |                                                                                    |                |                       | From 1.6 m to 2.0 m   |                          |                     |
|        |             |             |           |                               |                                                |                |                                                                                            | from 5.5 m to 7.5 m ht, 2.0 m                                                                                                                                                                                                    |              |              |                                   |                                                                                    |                |                       |                       |                          |                     |
|        |             |             |           |                               | · · · · · · · · · · · · · · · · · · ·          |                |                                                                                            | <u> </u>                                                                                                                                                                                                                         |              |              |                                   |                                                                                    |                |                       |                       |                          | · .                 |
|        | C203        | Uls         | oor Valle | y Secondary                   | Storm Drain:                                   | Sagayapuram    | Drein                                                                                      |                                                                                                                                                                                                                                  |              |              | L                                 |                                                                                    |                |                       |                       |                          |                     |
|        | 1           | 0           | 750       | Sagayapuram                   | Cleaveland<br>Town                             | a) 450-750     |                                                                                            | a) <u>Left Side</u>                                                                                                                                                                                                              | a} 300-750   |              | a) After desit<br>deepened        | ng, drain bed to be<br>by 500 mm,                                                  | -              |                       | -                     | a) 300 - 450             |                     |
|        |             |             |           |                               |                                                |                | 1                                                                                          | Existing covered reach co<br>drain, Opp. KU/FC Market<br>uplo Railway Bidge location<br>need to be widened                                                                                                                       |              |              | From K.<br>Radway Br<br>Bore Bank | M. Rosd upto<br>Edge location near<br>Road                                         |                |                       |                       |                          |                     |
|        |             |             |           |                               |                                                |                | 1                                                                                          | From 1.5 m to 4.0 m ft. 2.0                                                                                                                                                                                                      |              |              |                                   |                                                                                    |                |                       |                       |                          |                     |
|        |             |             |           |                               |                                                |                |                                                                                            |                                                                                                                                                                                                                                  |              |              |                                   | <u>1</u>                                                                           |                | -                     |                       |                          |                     |
|        | <u>C204</u> |             | or Veiler |                               |                                                | Jeevanabally [ |                                                                                            |                                                                                                                                                                                                                                  |              |              | <u>.</u>                          |                                                                                    |                |                       |                       |                          |                     |
| 2      | 1           | O           | 1,000     | near                          | Inside MEG<br>Centre towards<br>Railway Bridge | ø) 100 - 350   | ļ                                                                                          | a) <u>Both Side</u>                                                                                                                                                                                                              |              |              |                                   |                                                                                    |                |                       |                       |                          |                     |
|        | -           |             |           |                               |                                                | 5) 350 - 500   | C<br>E<br>c<br>c<br>v<br>v<br>fr<br>a<br>a<br>c                                            | Kandaswamy Garden 2nd<br>Cross upto BDA Qrts. Road.<br>Existing drain is in natural<br>condition and it has to be<br>ridened on left hand side<br>from 1 m to 2.5 m ht. 1.8 m<br>nd new wall to be<br>constructed on both side.  | a) 0 - 1000  |              | , deepened b                      | ng drain bed to be<br>γ 5γ0 π.n. From<br>υρίο MEG Centre                           | 1              | -                     | -                     | a) 0 - 1000              |                     |
|        |             |             |           |                               |                                                |                | 8<br>R<br>Is<br>Iu<br>Iu<br>Iu<br>Iu<br>Iu<br>Iu<br>Iu<br>Iu<br>Iu<br>Iu<br>Iu<br>Iu<br>Iu | DA Quartens Road upto<br>laiway track. Existing drain<br>in natural condition and it<br>as to be wider-ed on left<br>and side from 2.0 m to 4.5<br>i and ht. 1.8 m and further<br>ow wall has to be<br>constructed on both side. |              |              |                                   |                                                                                    |                |                       |                       |                          |                     |
|        | 1.5         |             |           |                               |                                                |                |                                                                                            |                                                                                                                                                                                                                                  |              |              |                                   |                                                                                    |                |                       |                       |                          |                     |

نوب بېزې د پر درون کالانو -

الموجوع بالمحرك المجروب مردي والمراكب مع ومراكب المراجع والمستمع المحرك فالمحمد للما

#### Feesibility Report - Chelleghette Vellay

|                            | ÷.               |                                                                                                                |             |
|----------------------------|------------------|----------------------------------------------------------------------------------------------------------------|-------------|
| Construction of the second | сy.              | representation and a constant                                                                                  |             |
| Bed Prote                  | ct               | kon Statistica (                                                                                               |             |
| ••••••••                   | _                | Remarks                                                                                                        | · · · · · · |
| 16                         |                  | 17                                                                                                             | 18          |
|                            |                  |                                                                                                                |             |
| _                          |                  | <ul> <li>a) After desilting drait</li> <li>bed to be provided for full</li> <li>length &amp; width.</li> </ul> |             |
|                            |                  | (Existing width: 4 m)                                                                                          |             |
|                            | -                |                                                                                                                |             |
|                            |                  | <b></b> .                                                                                                      |             |
|                            |                  |                                                                                                                |             |
|                            |                  | a) After desilting drain<br>bed to be provided for ful<br>length and width<br>lectisting width: 5 - 6 m)       |             |
|                            |                  |                                                                                                                |             |
| · ·                        | 1                |                                                                                                                |             |
|                            | <b>-</b>         |                                                                                                                |             |
|                            |                  |                                                                                                                | 1           |
|                            | b<br>k           | ) After desilting drain<br>ed to be provided for full<br>ngth & width<br>bosting width : 4,0 m)                |             |
|                            |                  |                                                                                                                |             |
|                            |                  |                                                                                                                |             |
|                            | a)<br>pro<br>fut | After desitting bed<br>xection be provided for<br>I length & width.                                            |             |
|                            |                  |                                                                                                                |             |

### Remodelling of Primery Secondary Slorm Water Desins in Bengaloce City

-

| $\widehat{C}$ | SL<br>₩0. | いたの   | cage (m.) | i e i e i Loc                                    | nion        |                 |          | 1ening                                                                                                                                                                                                                                  |               |       | Existing Storm Drain – C                                                                           | arrying Capa  | Drain Wali | ments Works |                | - Bed Protec | Bon - Cast                                                                       |         |
|---------------|-----------|-------|-----------|--------------------------------------------------|-------------|-----------------|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|-------|----------------------------------------------------------------------------------------------------|---------------|------------|-------------|----------------|--------------|----------------------------------------------------------------------------------|---------|
| -             |           | From  | •- то     | From                                             | To          | Chainage (m.)   | <b>C</b> | Remarks                                                                                                                                                                                                                                 | Chainage (m.) | · · · | Remarks                                                                                            | Chainage (m.) | ·          | Remarks     | Chainage (m.)  |              | Remarks                                                                          | • • • • |
|               |           | 2     | 3         | - 4                                              | 6           | 6               | 7        | 8                                                                                                                                                                                                                                       | 9             | 10    | 11                                                                                                 | 12            | 13         | 14          | 16             | 16           | 17                                                                               | 18      |
|               |           |       |           |                                                  |             | , c) 600 - 1000 | 1        | c) <u>Both Side</u><br>Existing drain is in natural<br>condition J.e. Inside MEG<br>Centre and it has to be<br>widened on Right hand side<br>from 3 m to 6 m. Further, dry<br>stone revetment has to be<br>provided for a ht. of 2.0 m. |               | -     |                                                                                                    |               | -          | ·           |                |              |                                                                                  |         |
| $\mathcal{C}$ | 2         | 1,000 | 2,000     | Inside MEG<br>Centre<br>(towards Riy,<br>Bridge) | Uisoor Lake | a) 1000 - 2000  |          | a) <u>Both Side</u><br>Inside MEG Centre existing<br>drain is in natural condition<br>and it has to be widened from<br>3.5 m to 8.0 m. Further, dry<br>stone, revelment has to be<br>provided for a ht. of 2.0 m.                       |               |       | After desitting drain bed to bo<br>a) deepened by 300 mm inside<br>MEG Centre<br>Inside MEG Centre | -             | -          | -           | a) 1000 - 2000 |              | a) After desiting bed<br>protection to be provided<br>for full length and width. | -       |

.

4

STUP Consulants P. Ltd.

ان از این از این از می والد و میکند. از می والد از می والد از می والد و این از میکند و ا از میکند و این از می ٠.

(

 $\langle \hat{\ }$ 

#### Feasibility Report - Challaghatta Valley

.

:

| Rem  | odelling | of Prime | ny Second | ary Storm Walar | <u>Drains in Bangak</u>                  | Ior <del>a</del> City |           |                                                                               |                  |                       |                                                                                                                                                                      |                | ·.              | . <u>Fonsibilit</u>                                                                               | y Report - Challanhatta |
|------|----------|----------|-----------|-----------------|------------------------------------------|-----------------------|-----------|-------------------------------------------------------------------------------|------------------|-----------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|-----------------|---------------------------------------------------------------------------------------------------|-------------------------|
| O    | [        |          |           |                 |                                          |                       | Table -   | 6.8 Schedule For Providing R                                                  | ehabilatation to |                       | g Secondary Storm Drains in Ulsoo                                                                                                                                    |                | 0)              |                                                                                                   | •                       |
| <br> | sı       | Chaina   | Qe (m.)   | Loca            | tion                                     |                       |           |                                                                               |                  |                       | ng Storm Drain – Rehabilitation Wo                                                                                                                                   | rks            |                 |                                                                                                   |                         |
|      | No.      |          |           |                 |                                          | 法运行的条件                | Drain Wal | Il Reconstruction                                                             |                  | <u>al a secondada</u> | Wall Restoration                                                                                                                                                     | 199255555555   | innth Sulting a | Outer Obstraction Reinovals 20 - Steven Steven                                                    |                         |
|      |          | From     | То        | From            | το                                       | Chainago<br>(m.)      |           | Remarks                                                                       | Chainage (m.)    |                       | <u> </u>                                                                                                                                                             | Chainage (m.)  |                 | Remarks                                                                                           | <br>15                  |
|      |          | 2        | 3         | 4               | 5                                        | 6                     | 7         | 8                                                                             | 9                | 10                    | 11                                                                                                                                                                   | 12             | 13              | 14                                                                                                |                         |
|      | C201     | Ulso     | or Valley | Secondary St    | orm Drain: Ga                            | anesh Temple d        | rains     |                                                                               | r                |                       |                                                                                                                                                                      | ·····          | <u> </u>        | 1                                                                                                 |                         |
|      | 1        | 0        | 250       | Ganesh Temple   | MEG Centre                               | -                     | -         | -                                                                             | a) 0 - 250       |                       | <ul> <li><u>Both Sides</u></li> <li>After desilting, pointing to be provided to<br/>the existing stone revetment wall for a ht<br/>of 1 m from drain bed.</li> </ul> |                | · -             | -                                                                                                 | 4 7                     |
|      |          |          | or Valley | Secondary St    | torm Drain: Co                           | ox Town Drain         |           |                                                                               |                  |                       |                                                                                                                                                                      |                |                 |                                                                                                   |                         |
|      | 1        | 00       |           | Richard Town    | Gymkhhana<br>Ground near<br>Assayee Road | -                     | -         |                                                                               | a) 0 - 400       |                       | a) <u>Both side</u>                                                                                                                                                  |                |                 | :                                                                                                 |                         |
| 0    |          |          | ł         |                 |                                          |                       |           |                                                                               | b) 600 - 1000    |                       | After desilting, pointing to be provided for<br>1 m ht. from drain bed.<br>b) <u>Both side</u>                                                                       | 1) a) 0 - 500  |                 | 1) 6) 4 nos. of 100 mm dia Cable lines.<br>b) 2 nos. of 160 mm dia. w/s pipeline<br>exists.       |                         |
|      |          |          |           |                 |                                          |                       |           | ·                                                                             |                  |                       | After desiting, pointing to be provided for<br>1 m ht. from drain bed.                                                                                               |                |                 | c) 10 nos. of Sewer outlets<br>12 nos. of 1.2 m dia. Manhole at 0.8 m<br>d) lit. from drain walk. |                         |
|      |          |          |           |                 |                                          | -                     |           |                                                                               | c) 1000 - 1075   |                       | <ul> <li>c) <u>Left side</u></li> <li>After desiting, pointing to be provided for<br/>a ht. of 1 no. from drain bed.</li> </ul>                                      | 2) a) 500-1170 | -               | 2) Nii                                                                                            |                         |
|      |          |          |           |                 |                                          |                       |           |                                                                               | d) 1075 - 1170   |                       | <ul> <li><u>Both Sides</u></li> <li>After desitting, pointing to be provided for<br/>a ht. of 1 no. from drain bed.</li> </ul>                                       |                |                 |                                                                                                   |                         |
|      |          |          | ļ         |                 | [                                        | <u>}</u>              |           |                                                                               | J                | ±                     |                                                                                                                                                                      |                |                 |                                                                                                   |                         |
|      | czo      | 3-U/so   | xor Valle | Secondary Si    | torm Draia: S                            | lagayapura Drai       | n.        |                                                                               |                  |                       |                                                                                                                                                                      |                |                 |                                                                                                   |                         |
|      | 1        | D        | 750       | Sagayapuram     | Cleave Land<br>Towns                     |                       |           | <u>Both Sides</u><br>60 m length 1.6 m ht. drain wall to be<br>reconstructed. | e) 0 - 75        |                       | <ul> <li>B) <u>Right Side</u></li> <li>After desiting, pointing to be provided for<br/>a ht of 1 m from the drain bed.</li> </ul>                                    | 1) 0 - 725     |                 | 1) a) 1 no. of 60 mm dia w/s pipeline at a ht.<br>of 1 m from drain bed.                          |                         |
| ():  |          |          |           |                 |                                          |                       |           |                                                                               | ь) 300 – 450     |                       | <ul> <li>b) <u>Both Side</u><br/>After desilting, pointing to be provided for<br/>a ht of 1 m from the drain bed.</li> </ul>                                         |                |                 |                                                                                                   |                         |
|      |          |          |           |                 |                                          | b) 75-100             | -         | Right Side<br>25 m length 1,6 m ht. drain wall to be<br>reconstructed.        | c) 450 - 750     |                       | <ul> <li><u>Right Side</u></li> <li>After desilting pointing to be provided for<br/>a ht_ of 1 m from drain bed.</li> </ul>                                          |                |                 |                                                                                                   | 1                       |
|      |          | l        | <u> </u>  |                 | l                                        | l                     | · ·       |                                                                               | ·                | <u> </u>              |                                                                                                                                                                      |                |                 |                                                                                                   | :                       |

STUP Consultants P. Ltd.

•

C

## Remodelling of Prinary Secondary Storm Water Drains in Bangalore City

 $\widehat{C}$ 

(

1

R

| ոսլ      | Chako  | ge (m.)   | - toc                                             |                |                  | Drain W | all Reconstruction |               |    |    | ng Storm Drain – Rehabilitation Wo<br>Mail Restoration                                   | orks                            | Utility Shirting 6 | Cother Of                                            |
|----------|--------|-----------|---------------------------------------------------|----------------|------------------|---------|--------------------|---------------|----|----|------------------------------------------------------------------------------------------|---------------------------------|--------------------|------------------------------------------------------|
|          | From   | To        | From                                              | το             | Chainage<br>(m.) |         | Remarks            | Chainage (m.) | ١, | •  | Remarks                                                                                  | Chainage (m.)                   |                    |                                                      |
| ┥        | 2.     | 3         | 4                                                 | 5              | 6                | 7       | 6                  | 9             |    | 10 | 11                                                                                       | 12                              | 13                 |                                                      |
| <br>C204 | 1 Ulso | or Valley | Secondary St                                      | torm Drain: Je | evanahalli Drai  | in      |                    | <b></b> ,     |    |    |                                                                                          | <u>,</u>                        |                    | <del></del>                                          |
| 1        | 0      |           | ITC Colony nea:<br>Jeevanahati                    | inside MEG     | -                | -       | -                  | a) 500 - 600  |    |    | Both Side<br>After desilting pointing to be provided for<br>a ht, of 1 m from drain bed. | 1) a) 0 - 500<br>2) a) 500-1000 |                    | 1)a) 1 (<br>ab<br>2)a) 1 (<br>b) 1 (<br>of<br>c) 1 ( |
| 2        | 1,000  | 2,000     | Inside MEG<br>Centre (towards<br>Rail-way Bridge) | Ulsoor Lake    | -                | -       | -                  | -             |    | -  | _                                                                                        | -                               |                    |                                                      |
|          |        | <u> </u>  | <u> </u>                                          | L              | l                |         |                    | •             |    |    |                                                                                          |                                 |                    | _[                                                   |

.

•

.

1

•

. Anno 1997

3

| bstruction Removals                                                                                               |                                       |
|-------------------------------------------------------------------------------------------------------------------|---------------------------------------|
| Remarks                                                                                                           |                                       |
| 14                                                                                                                | 15                                    |
|                                                                                                                   |                                       |
| no. of 1.2 m dia Manhole at 0.6 m ht.<br>bove drain bed exists.                                                   |                                       |
| no, of 50 mm dia cable line exists.<br>no, of 110 mm dia, w/s pipeline at a ht.<br>f 0.8 m from drain bed exists. |                                       |
| no, of 1.2 m dia. manhole exists                                                                                  |                                       |
| -                                                                                                                 | -                                     |
|                                                                                                                   | . N                                   |
|                                                                                                                   | · · · · · · · · · · · · · · · · · · · |

Page No312

#### CHAPTER – 7

#### **TECHNO – ECONOMIC ANALYSIS**

#### 7.1 INTRODUCTION:

CHALLAGHATTA valley is located east of Bangalore, where natural lakes and trees abound. The valley is spread in around 60 sq. km out of a total area of 225 sq. km for the Bangalore city. The total population of Bangalore city as per 2001 census is 4.5 million (the municipal limits are divided into 100 wards) and around 0.6 million people live in the 15 wards of CHALLAGHATTA valley area. There are 49,451 residential and 9107 non-residential properties in the area. CHALLAGHATTA Valley project is part of the overall modernization program of BMP for all four major valleys in the city (other three valleys being Hebbal, Vrishabavathi and Koramangala).

The Valley projects when implemented would not generate additional revenue for the principal implementing agency viz. BMP. Thus, it is a social infrastructure project attempting to restore the eco-system and relieve the citizens and residents of hardships that they are currently exposed by way of polluted drains, flooding and potential danger of public health hazards. These characteristics of the project lend itself for grants, aid and soft loans. Not withstanding the above social aspects, BMP would provide appropriate support to the project by means of initial seed amount and through budget provision to support the operation and maintenance of the SWD's once constructed.

#### 7.2 OUT COME OF THE VALLEY PROJECTS:

Sustainable ecosystem for lakes, river beds and other water bodies around river valleys; prevention and management of floods in low-lying areas and livable environ for citizens and residents.

#### 7.3 STAKE HOLDERS OF THE PROJECT:

The project is designed to address the varying requirements of the stakeholders. They are:

| INTERNAL                                             | EXTERNAL                                                                      |
|------------------------------------------------------|-------------------------------------------------------------------------------|
| Bangalore Mahanagara Palike (BMP)                    | Citizens (residents of the area)                                              |
| Bangalore Water, Sewage and Sanitation Board (BWSSB) | Industries and other occupants of the area                                    |
| Lake Development Authority (LDA)                     | NGOs                                                                          |
| City Municipal Corporations<br>(CMC/TMC)             | Funding Agencies                                                              |
| Bangalore Development Authority (BDA)                | Government of Karnataka (GOK)                                                 |
| Karnataka State Pollution Control<br>Board (KSPCB)   | Karnataka Urban Infrastructure<br>Development Finance Corporation<br>(KUIDFC) |
| Elected representatives                              | Government of India (GOI)                                                     |

#### 7.4 STAKEHOLDER REQUIREMENTS, OUTPUTS AND BENEFITS:

| Residents:                  | No flooding                                                            |
|-----------------------------|------------------------------------------------------------------------|
|                             | Odour less and free flow of drain                                      |
|                             | Green environment                                                      |
|                             | Separation of sewage and storm water                                   |
|                             | Excellent Bellandur lake and tanks                                     |
|                             | Financially not inconvenienced                                         |
|                             | Selected owners of land will benefit from and value appreciation       |
| Lake Development Authority: | Water entering the lakes is as per the acceptable technical standards; |
|                             | Visually fresh water fish should thrive in the lakes                   |
|                             | Possibility for increased tourism                                      |

| Bangalore Mahanagara Palike: | One major issue resolved in line with 'citizen first' approach                                                                                                                               |
|------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                              | Good branding possibility<br>Success can be replicated in other valley<br>projects                                                                                                           |
|                              | Publish a comprehensive book                                                                                                                                                                 |
|                              | Success will enhance and ensure better flow of funds for future projects                                                                                                                     |
| BWSSB                        | One major issue resolved, rehabilitation of<br>existing sewerage system to collect, treat<br>and dispose the treated sewage there by<br>abating the raw sewage flow into drains and<br>lakes |
|                              | Diversion of sewage lines from the storm<br>water drain network enabling proper care<br>and maintenance of the sewerage system                                                               |
| GOK                          | Rediscover Bangalore as city of gardens, lakes etc.                                                                                                                                          |
| GOI                          | A template for urban development; model to empower local governments                                                                                                                         |
| Funding Agency               | Better chance of realizing ROI; fulfilling the<br>purpose to assist developing countries in<br>their efforts to develop economic and social<br>infrastructure and stabilize their economies  |

#### 7.5 **PROJECT OBJECTIVES**:

- To rectify current localized flooding problems in the critical low lying areas identified in the study.
- To cope with additional areas being included into the BMP administered area in terms of expansion of the storm water drain network.
- To prevent polluted water getting into lakes and river beds
- Encourage rain water harvesting in institutions, public parks, open grounds, etc
- To improve and extend the security of services in vulnerable areas of the current BMP administered area.

- To improve and protect the quality of environmental attributes including aesthetic appearance of city's environs.
- To minimize cost implication on operation and maintenance of the system.
- To educate the residents and citizens to be aware of the effect of dumping solid waste and other wastes into the drains (which are open by design)
- To educate and enforce measures to prevent industries and commercial establishments from discharging toxic and wastewater into drains, lakes and river beds
- To design, develop and implement information architecture to capture and incorporate vector and raster data to be used by multiple agencies on a shared basis. Information architecture is designed to support sustainability.

#### 7.6 VARIABLES AND MEASUREMENTS:

It would be essential to translate the requirements in to variables that could be subject to measurement in order to monitor the performance. The table below depicts the variables and measurements and the scale as applicable for measurement.

| VARIABLE                                                                           | MEASURE                                                                                                                                                                        | METRICS      |
|------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------|
| Capacity of the local body of the Government (BMP)                                 | Capacity to carry out environment<br>management plan; ability to<br>enforce relevant rules or<br>regulations                                                                   | Scale 1 to 5 |
| Flexibility to accept change in<br>terms of new approaches to<br>environment plans | Willingness of employees<br>and authorities of BMP and other<br>internal stakeholders to accept<br>professional and outcome based<br>approaches to maintenance of<br>ecosystem | Scale 1 to 5 |
| Commitment to the implementation of the project                                    | Demonstration by<br>allocating required resources and<br>competencies on a timely basis;<br>enacting office orders and other<br>instruments to facilitate<br>implementation    | Definitive   |
| Effort to build awareness                                                          | Including a component for<br>education and awareness in the<br>project cost and engaging the<br>citizens at various levels of project<br>formulation and implementation        | Definitive   |
| Plan quality                                                                       | Clarity of scope of work<br>and definitiveness                                                                                                                                 | Scale 1 to 5 |
| Risk of flooding                                                                   | Property loss, public health hazard, damages to structures                                                                                                                     | Scale 1 to 3 |

| Regulatory policies              | Permitted land uses,<br>density controls over land use,<br>transfer of development rights,<br>cluster development provisions,<br>set back requirements, site review<br>requirements, spatial study or<br>impact assessment requirements,<br>building standards for flood prone<br>area developments, financing for<br>mitigation | Combinatio<br>n |
|----------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|
| Awareness                        | Educational awareness,<br>voluntary real estate disclosure,<br>flood warning systems, posting of<br>signs to indicate flood prone areas                                                                                                                                                                                          | Definitive      |
| Emergency planning<br>provisions | Evacuation provisions,<br>sheltering provisions, emergency<br>plan provision                                                                                                                                                                                                                                                     | Scale 1 to 3    |
| Change interventions             | Willingness to train and<br>orient personnel to achieve<br>common and shared objectives of<br>the local body                                                                                                                                                                                                                     | Scale 1 to 5    |

The parameters and indicators identified above have been studied in detail while preparing the detailed project report for the valley as well to develop the risk management plan. The primary risk identified for the implementation of the storm water drain project relates to coordination among various stakeholders in terms of timely execution of individual projects and schemes in order that the overall environmental condition of the valleys is restored.

#### 7.7 ABSTRACT OF COST:

For Remodeling of Primary and Secondary Storm Water Drains, Culverts/Bridges & its appurtenant works in Challaghatta Valley;

| SI. No. | Description                                                                                                                                            | Amount<br>(Rs. In Crores) |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------|
| 1       | Cost for Remodeling of Primary & Secondary Storm Water<br>Drains, Construction of New Drains near low lying areas,<br>Formation of Service Roads etc., |                           |
| 2       | Cost for Remodeling of Bridges / Culverts constructed across<br>Primary & Secondary Storm Water Drains.                                                | 13.33                     |
| 3       | Cost for shifting utility lines, footpath improvement works, barricading, traffic diversion, strengthening of diversion routes etc.                    |                           |
| 4       | Construction of Detention Ponds / Retarding Basins                                                                                                     | 1.50                      |
| 5       | Construction of Wells with pumping arrangement in low lying areas                                                                                      | 2.00                      |
| 6       | Procurement of desilting machine                                                                                                                       | 0.00                      |
| 7       | Miscellaneous and rounding off                                                                                                                         | 0.02                      |
| 8       | Advisory, Project Management & Establishment Charges (1.5 % of Item 1 to 7)                                                                            | 1.85                      |
|         | TOTAL                                                                                                                                                  | 124.84                    |
| 9       | Annual Operation & Maintenance Cost<br>(1.0 % of Item 1 to 7)                                                                                          | 1.23                      |

For the purpose of seeking external funding only the core capital expenditure of Rs.124.84 crores is considered whereas the amount required for operation and maintenance would be funded by Bangalore Mahanagara Palike out of its budget allocations (internal resources).

The direct beneficiaries of the clean environment that would ensue upon implementation of the project are the residents spread over 15 wards in the city. The demographic details of them are provided herewith:

| Description           | Ward | Ward Names               | Denulation | Pro         | perties         |
|-----------------------|------|--------------------------|------------|-------------|-----------------|
| Description           | No   | ward names               | Population | Residential | Non-Residential |
|                       | 72   | Domlur                   | 44,339     | 4436        | 274             |
| Challaghatta          | 73   | H.A.L. Airport           | 41,465     | 6807        | 748             |
| Main Valley<br>(C100) | 74   | Jeevanbhimanagara        | 39,670     | 4755        | 635             |
|                       | 75   | Jogpalya                 | 35,984     | 4139        | 184             |
|                       | 78   | Vasanthanagara           | 36,928     | 3707        | 1665            |
|                       | 79   | Shivajinagara            | 34,941     | 2977        | 3543            |
|                       | 80   | Bharathinagara           | 35,569     | 2352        | 404             |
|                       | 81   | Ulsoor                   | 39,715     | 2954        | 1017            |
|                       | 82   | Hoyasalanagara           | 33,283     | 2543        | 227             |
|                       | 83   | Sri. C.V.<br>Ramannagara | 49,487     | 1890        | 31              |
|                       | 85   | Sarvagnanagara           | 34,984     | 2420        | 153             |
|                       | 86   | Maruthisevanagara        | 39,620     | 4241        | 51              |
| Ulsoor Valley         | 90   | Sagayapura               | 43,399     | 1281        | 96              |
| (C200)                | 91   | Pulikeshinagara          | 42,010     | 5136        | 280             |
|                       | 92   | Jayamahal                | 39,726     | 4249        | 73              |
|                       | Тс   | otal                     | 5,91,120   | 49,451      | 9,107           |

### 7.8 WARD AND DEMOGRAPHICS OF CHALLAGHATTA VALLEY:

#### CHAPTER – 8

#### SUSTAINABILITY EVALUATION

#### 8.1 LEGAL ASSESSMENT:

#### 8.1.1 LAND ACQUISITION:

The optimal engineering solution emerging in the techno economic study would require removal of structures and houses that have sprung up along the sides of the storm water drain. There are instances where structures have been built on the side walls of the drain itself impairing scope for widening of the drains. The width of the storm water drains right through the city is greatly reduced by encroachments thus reducing the carrying capacity of the drains. There are instances of dwellings built right on top of the drains in certain areas (Yeshwantpur – beginning of Hebbal Valley drain).

Considering the prolonged process that would be necessary to enforce vacation of properties built around the storm water drain network the solution proposed avoids land acquisition on a large scale for the initiative. Where it is absolutely necessary land acquisition is envisaged considering the rehabilitation programme for people who would get displaced on account of the project implementation. The land acquisition is proposed through a process of conferring development rights (Transfer of Development Rights) by which the owner of the land who has surrendered the part of the land towards infrastructure projects would be allowed to carry out construction based on enhanced floor space index (FSI) conferred by the TDRs.

#### 8.1.2 ENFORCEMENT MEASURES:

To deal with indiscriminate dumping of solid waste in to the storm water drains, apart from education and awareness programme, enforcement measures that act as deterrent are also required to be imposed. Based on experience in dealing with such situations it is recommended that the civic authority is empowered to deal firmly with violators of law in respect of dumping of solid waste that include construction debris, dead animals and hazardous waste material. To sustain the initiative enforcement measures are proposed against unauthorized constructions and to deal with encroachments. Further, there are many instances of evidence that in areas outside the BMP administered region, the development authorities do not enforce and adopt even rudimentary practices for planning, construction and maintenance of primary and secondary drains and also they lack resources and technical expertise to adopt best storm drain management practices. In the new areas strict enforcement of law and procedures would discourage the citizens and commercial establishments from treating storm water drains as mere sewage drains.

#### 8.2 ESTABLISHMENT OF INSTITUTIONAL FRAME WORK:

There are multiple agencies of the Government that are directly involved and accountable to ensure that the storm water drains in Bangalore carry only storm water and nothing else (0% impurity whether liquid waste or solid waste). The agencies are Bangalore Mahanagara Palike (BMP) who is directly responsible as the implementing agency as well as the entity vested with the construction and maintenance of the drains in the city. The other agency is Bangalore Water Supply and Sanitation Board (BWSSB) whose function is to ensure that sewage is collected and conveyed to the sewage network and that it does not mix with the storm water. The current situation, however reveals that the storm water drains in Bangalore carry much of sewage as these are either directly disposed in to the drains or they overflow from the manholes and pipes located inside the storm water drains. The third agency having a stake in the upkeep of the storm water drains is the Lake Development Authority (LDA) whose mandate is to keep the lakes on the down streams to be pollution free.

The fourth agency involved in the issue is Bangalore Development Authority (BDA) who allots and plans residential and commercial sites in and around Bangalore. When sites are allotted without considering the existence of water and sanitation networks, citizens have little choice in the disposal of waste and most often they find their way in to the storm water drains.

| Institution | Primary Role                                                                             | Impact on SWDs                                                                                                                                                                                                                 | Area of<br>cooperation                                                                                                       | Severity<br>of non-<br>cooperati<br>on/<br>inaction |
|-------------|------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------|
| BMP         | Planning,<br>Development,<br>Financing,<br>Construction,<br>operation and<br>maintenance | Carrying capacity,<br>flooding, pollution of<br>the environment                                                                                                                                                                | Timely execution of<br>projects<br>Educating the<br>citizens on proper<br>solid waste disposal                               | Medium to<br>High                                   |
| BWSSB       | Collection,<br>Conveyance and<br>disposal of<br>sewerage                                 | Mixing of sewage<br>with storm water<br>polluting the drains,<br>clogging, spreading<br>odour and finally<br>polluting the lakes<br>and water bodies                                                                           | Integrated planning<br>and removal of<br>sewage network<br>components form<br>the storm water<br>drains                      | High                                                |
| BDA         | Land Use<br>Planning and<br>allotment of sites                                           | Residents forced to<br>discharge sewage<br>in to SWDs where<br>sewage networks<br>have not been<br>planned but<br>construction permits<br>given                                                                                | Coordination with<br>BMP/BWSSB to<br>create the<br>infrastructure in a<br>coordinated manner<br>while allotting sites        | Medium                                              |
| LDA         | Upkeep of lakes<br>and water bodies                                                      | Closing of entry<br>points in to lakes<br>due to polluted<br>water entering the<br>lakes thus making<br>the environment<br>around the lake<br>unhygienic (lake<br>itself may be pure of<br>sewage and other<br>contaminations) | Participate in<br>planning and<br>development of<br>schemes to treat<br>the unclean water<br>before entry in to<br>the lakes | Medium                                              |

To realize the outcome of 100% pure flow of storm water in the drains all the above agencies need to participate and implement plans in an integrated and coordinated manner. The Government of Karnataka represented by the Urban Development Department has constituted an inter-institutional committee with members drawn from the following to give shape to the proposal for coordination and effective management of the storm water drain initiatives:

- Commissioner, BMP Chairman of the Committee
- Secretary, Urban Development, GOK
- Chairman, BWSSB
- Chairman, BDA
- Chairman, LDA

Another critical institutional aspect for the storm water drain projects is the need to establish a dedicated project management cell within BMP to undertake such a massive and citizen sensitive project.

#### 8.3 RATIONALE FOR A PROJECT MANAGEMENT UNIT:

There is a need for an organization which could handle joint projects among stakeholders cutting across various government entities. Such an organization should address the needs of the city – Greater Bangalore – a Techno polis, fast emerging as an intelligent city. The informal arrangement that was started a few years back in the form of BATF (Bangalore Agenda Task Force) needs to be formalized now by establishing a new organization that would focus on delivering citizen services by concentrating on urban infrastructure planning and execution. A strategic plan for the city development in terms of urban infrastructure shall be developed by the proposed organization along with a clear road map with milestones to translate the strategy to actions.

To execute a project with multiplicity of stakeholders profound project management skills and inter-disciplinary approaches are essential. In order to effectively implement, monitor and control the schemes envisaged under the storm water drain initiative it is strongly recommended that a Project Management Unit (PMU) as an exclusive entity responsible for storm water projects be established. Funding agencies stipulate evidence of professional management skills and best practices for sanction and disbursal of funds for such of these schemes. BMP readily accepted the recommendation and it has been suggested that PMU be established as part of BMP functioning independently to carry out the storm water drain projects in accordance with JNNURM guidelines and reforms agenda agreed among the stakeholders.

It has been observed in many infrastructure project implementation schemes that cost and time overruns could have been avoided if a separate dedicated unit or cell were vested with the authority and powers to deal with the project implementation cycle. There has been a significant improvement in performance of dedicated units wherein policy, implementation and regulation are clearly isolated and delineated. It is proposed that PMU functions as an execution agency of policies framed by BMP / Government and thus focusing on deliverables in terms of performance. Weak institutional mechanism coupled with lack of application of contracting skills affect the implementation of large infrastructure schemes. Channeling right competencies required for handling such schemes is vital but found to be non-existent under bundled institutional setups created around budgetary focus for expenditure monitoring. Performance measurement in terms of timely completion and construction as per requirements and specifications, are few aspects that are not given due importance under current functioning of these institutions.

Projects executed as part of many government schemes are susceptible to delays on account of slow decision making process and sometimes by the application of bureaucratic procedures. Focused attention and clearly defined roles among implementation agencies are seldom noticed in routine schemes funded either through budgetary allocations or through external funding mechanisms. Systems of the government remain inflexible and unable to cope up and address the needs of the funding agencies and contractors to deal effectively with emerging situations, uncertainties and risks.

While establishing the PMU, its governance structure, its inter-play with various internal and external stakeholders and its role, responsibility, powers, authority and liabilities need to be defined. More importantly the framework should highlight on the organization structure, the profile and attributes of the Chief Executive Officer and outsourcing mechanisms to pool resources. The recommendation would lay the basis for the establishment and operation of the PMU as well as its future role in respect of similar large urban infrastructure projects in Bangalore city.

The likelihood of achieving the project outcomes as per the specifications and within the timeframe planned would be greatly enhanced if the PMU is mandated to design, develop, implement and oversee the operation and maintenance phases. Performance orientation and achievement of measurable goals would be the hallmark of PMU and the knowledge gained should also be gradually transferred to its contractors, outsource partners and stakeholders.

PMU should be designed and structured in such a way that it is independent and allowed to function as an autonomous unit and be part of BMP. Performance measures of PMU shall be agreed between the designated state government agency and PMU and also in consultation with major stakeholders like BMP, BWSSB, LDA, BDA, CMCs etc. PMU should be evaluated based on its efficiency and effectiveness parameters and evolve initiatives and projects that are economically viable and politically sustainable. PMU could have its resources picked up from among various constituents of the government apart from external professional pool. An organization structure that would primarily meet with the engineering and enforcement aspects of the project is developed and presented here. The administrative functions like land acquisition and arrangement of finance are to be dealt with by the inter-institutional committee recommended as part of the reforms agenda.

Organization structure of the Project Management Unit (PMU) for implementing the remodeling of storm water drain network in Bangalore City.

#### 8.4 EDUCATION AND AWARENESS PROGRAMME:

Awareness program as a tool is designed to address issues and propagate messages relevant to segmented consumers in respect of maintaining the environment to defined standards. The messages would include the types of technology, sources (availability), behavior pattern, ways to prevent dumping of waste, significance of clean environment with respect to health and safety and impact (social & economic) of not adhering to recommended rules and procedures.

Communication in the form of scientific intervention is critical to educate the economically weaker sections of the society, policy makers from health department, local bodies in charge of maintaining the environment around the storm water drains, lakes and other water bodies. They need to be aware of the systems governing safe environment, clean air and lakes with fresh water allowing fish to thrive. Unclean environment and the resultant odour and mosquito infestation affect their livelihood and also their health. The awareness in respect of impact of letting out wastewater without treatment on the environment and personal health are equally important. The communication program aims to create awareness on the ill-effects of having unclean storm water drain and water bodies and living in the midst of polluted environment caused by letting out un-treated wastewater and solid waste in to the open. It has been established through studies that more than 60% of the diseases caused are water borne and by effectively controlling sections of the society to seek and resort to safe disposal of both solid and liquid waste substantial savings would be made in the outlays currently made by the health department to address the public-health concerns. Orientation of the society through communication is an effective tool to achieve the desired results concerning behavior of citizens. They would emulate what is told if they are convinced of the impact in their lives. Practical demonstrations with test reports and certificates from authorized agencies entwined with communications program for spreading the message would achieve the desired result. Messages propagated in the local lingua and through personalities accepted by the community would have a significant impact in terms of acceptability and remembrance.

#### 8.5 **OBJECTIVES OF THE INTERVENTION:**

The segmented target groups for this program are primarily economically weaker sections of the society, policy makers from health sector, local bodies in charge of wastewater and solid waste disposal, commercial establishments in the Hebbal Valley apart from potential polluting industrial units. For them the objectives are to:

- Introduce awareness on disposal pattern of waste and environmental factors associated with water and wastewater; especially focusing on organic matter in the form of bacteria, viruses and the like.
- Develop and administer awareness programs and education material in simple forms for school children.
- For the local bodies' material containing information on availability of cost effective technologies, transportation, quality control, costs, impact on environment would be developed and disseminated.
- Structure media programs along with direct campaigns to instill the awareness program.
- Sustain the message and effective follow up with repeated contacts and innovative schemes.
- Craft slide presentations, printable handouts, posters, and short movies for effective communication. The material prepared and administered would be in local language and simple to understand.

#### 8.6 TARGET GROUP(S) WITH LOCATION SPECIFIC INFORMATION:

Bangalore City consists of 100 wards and the total population in the four valleys is around 4,500,000. The target group for the communications program will comprise segmented sections of weaker sections, schools (primary, middle and higher), and policy makers from health sector and local bodies in charge of storm ware drains, sanitation and lake maintenance. These would be chosen from the wards of the valleys. The target audience would be graded into government and the private sector comprising the policy makers, influencers, decision makers and implementing authorities. Citizens would be targeted through a network of non-government organizations (NGOs) who have established direct contact at various levels of communities.

#### 8.7 DURATION OF THE INTERVENTION:

It is estimated that the intervention would be completed within a period of 36 months from commencement. There would be an intensive planning and requirement analysis process in the initial three months period formulating plans for implementing the awareness and communications program. Review and monitoring activities would form part of the intervention schedule to make an effective impact of the awareness program. The intervention would be administered both during the construction (remodeling of the drains) and the operation phase.

#### 8.8 JUSTIFICATION FOR UNDERTAKING THE PROPOSED INTERVENTION:

A large engineering project with an outlay over Rs 7000 million without an education and awareness component is not likely to produce sustainable results. One of the key assumptions of the storm ware project is that raw sewage will not enter the drains once remodeling is complete. This assumption can not be satisfied through and engineering intervention alone. People have to be educated and made aware of the importance of sustaining the eco-system in order to protect the environment. If practices that are currently in vogue continues after the remodeling the purpose of the project initiative would have been completely missed. In order to realize the core objectives the proposed intervention is viewed as absolutely necessary. A program of Rs 30 million administered over a period of 36 months is likely to protect the investments made to the tune of Rs 7000 million. Enforcement alone is not likely to result in achieving the desired results. By directly engaging the segmented citizens the likelihood of protecting the investment and the maintenance of the eco-system of Hebbal Valley would be greatly enhanced.

#### 8.9 APPROACH & METHODOLOGY:

Basic research in terms of segmentation of communities in terms of language, income level, literacy and vocation would be conducted in the first three months to gather data which will enable development of suitable programs for spreading the awareness. It is proposed to conduct an analysis and requirement planning to identify the areas where communication channels for the segmented target groups should be established and improved. The identification process would also focus on designing the content of the communication and awareness program suited to the target groups identified in terms of simplicity, vernacular and easy to comprehend and relate to real life situations. In case of school children curriculum on environmental health dealing with aspects of safe disposal of waste and keeping the environment clean and health aspects would be designed and promoted to authorities in the educational sector. Similarly, biological effects of living in unclean and polluted environ and methods to prevent unsafe methods of disposal of waste would be packaged in program for the health sector department. Impact of use of safe environment around the storm water drains on the spending by the health department would be clearly captured and popularized. Pilot schemes with focus target groups would be developed and administered. Lessons from the pilot schemes would be analyzed and evaluated for use in subsequent interventions in other community development programs as part of the education and awareness intervention.

### 8.10 DESCRIPTION OF THE TARGET AREA, TARGET GROUP (S) ALONG WITH THEIR CURRENT SOCIOECONOMIC STATUS:

The target area comprises four valleys (Challaghatta, Hebbal, Koramangala & Vrishabavathi) spread over 100 municipal corporation wards. The socioeconomic conditions of people living in the target area and in the target groups are quite mixed but predominantly economically weaker sections. For the target groups and in fact for all consumers, health costs arising out of water borne diseases are proving to be a great burden and continuously rising. Problems of flooding in the low lying areas due to clogging of drains with silt and waste have been witnessed in the past. Residents, commercial establishments and industries today are unaware of the ill-effects of throwing waste and discharging sewage in to storm water drains.

#### 8.11 RELEVANCE OF THE INTERVENTION TO THE WORK ALREADY GOING ON:

A number of NGOs today interact with communities in regard to various socioeconomic issues affecting the lives of the society. The proposed program would be designed in such a way to take advantage of the existing communication channels and also the network of NGOs to effectively promote the campaign. The emphasis would be to prevention of dumping of solid waste in to the storm water drains. The current programme would be suitably intermixed with ongoing communication programmes that are underway so that the citizens do not feel another massive programme thrust on them.

### 8.12 UTILISATION OF THE EXPECTED OUTCOME FROM THE INTERVENTION AND ITS BENEFICIARIES:

The outcomes expected from this intervention are two fold: firstly, it is to ensure acceptance of the program by the community in terms of change in practices for disposal of waste; effectives to be measured in terms of creating and sustaining a clean and green environment around the storm ware drains in the Hebbal Valley. Opportunities for employment creation within the local community for operation and maintenance of facilities would also be explored and established.

#### 8.13 RISK ASSESSMENT:

Internal risks come mainly from three sources: the project, the organizations involved, and the relationships among partners. Most projects suffer at least temporarily, from a deficient project structure: many are launched even though objectives are not clear, a business case had not been completed, and milestones were only vaguely defined, if defined at all. On the organizational side, lack of project control mechanisms is the factor that most impede many projects. Finally, risks associated with the relationships among partners has been the major source of concern present in all projects, lack of definition of role and responsibility as the most important problem for project implementation.

The risks associated with the storm water drain projects fall in to three categories:

- Multiple stakeholder coordination risk during execution of work
- Project risk
- Acquisition of land and removal of encroachments while widening the drains

Continuing discharge of sewerage in to the drains – BWSSB is expected to draw up plans for connecting the households that now discharge the sewerage direct to the drains. Coordination and integration of BWSSB's plans with that of BMP alone will ensure the drains carrying the storm water of acceptable quality

Indiscriminate dumping of solid waste and debris in to the drains is another aspect exposed to risk. BMP has earmarked areas in each of the wards in the city where construction debris could be dumped. The exercise has begun and once implemented would greatly reduce the amount of debris being dumped in to the storm water drains. This combined with proper education and awareness programmes would help prevention of debris getting in to the drains.

| Risk                     | Stakeholders                            | Severity of<br>risk | Solution                                                                                                                                                           |  |  |
|--------------------------|-----------------------------------------|---------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|
| Acquisition of land      | BMP, Government<br>of Karnataka         | Medium              | A combination of<br>enforcement and<br>rehabilitation measures is<br>required to notify the<br>affected people and provide<br>alternate arrangements for<br>living |  |  |
| Removal of encroachments | BMP, BDA,<br>Government of<br>Karnataka | Medium              | Legislation followed by<br>proper enforcement;<br>affected people to be<br>considered for housing<br>under basic services to<br>urban poor plan                    |  |  |

#### 8.14 RISK MANAGEMENT:

Internal risks associated with storm water drain projects in the four valleys of Bangalore city with suggested measures to address the risks.

| Risks associated with the project itself | <i>Characteristics of clients/users of the service:</i> resistance to change, lack of involvement, inadequate education level, difficulties in communicating, unrealistic expectations. (to overcome BMP is seeking citizen participation through ward committees and other for a)   |  |  |  |  |  |
|------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|--|--|
|                                          | <b>Scope of the project:</b> universality or specificity of the service, number of partners involved, number of clients, size of budget. (contract documentation being revamped to define the role and responsibility very clearly)                                                  |  |  |  |  |  |
|                                          | <i>Complexity of the project:</i> especially organizational and technological complexity. (consultant would evaluate various assumptions made in the design and detailed engineering)                                                                                                |  |  |  |  |  |
|                                          | <b>Definition and structure of the project</b> : unclear objectives, ill-defined specifications and functional requirements, changes in the scope or the reach of the project, difficulties in integrating data or processes. (flexibility to accommodate changes from contractors)  |  |  |  |  |  |
| Organizational risks                     | <i>Lack of resources:</i> uncertainty of funding, inadequate resources, lack of expertise in complex resource management.                                                                                                                                                            |  |  |  |  |  |
|                                          | <b>Project team competencies:</b> lack of experience, expertise, stability, and communication skills. (it is proposed to establish a PMU with requisite skills and experience)                                                                                                       |  |  |  |  |  |
|                                          | <b>Management strategy</b> : inadequate or inappropriate organizational support and control, absence of a champion, lack of leadership, unavailability of tested management tools and processes. (inter-institutional committee proposed to deal with policy level decisions)        |  |  |  |  |  |
|                                          | <b>Technological know-how:</b> absence of an adequate technological infrastructure and of in-house technological competencies. (Competencies being upgraded).                                                                                                                        |  |  |  |  |  |
| Relationship risks                       | <i>Form of collaboration:</i> inadequate or inappropriate type of agreement, misunderstandings regarding the content of the agreement; inappropriate selection of partners. (all contractual frameworks to define the role, responsibility and liability of various parties clearly) |  |  |  |  |  |
|                                          | <b>Collaborative process:</b> problems occurring with coordination, communications, inertia, dependency, mistrust, lack of consensus or involvement. (change management proposed)                                                                                                    |  |  |  |  |  |

#### **CHAPTER 9**

#### FINANCIAL AND OPERATING PLAN

The storm water drain valley projects when implemented would not generate additional revenue for the principal implementing agency viz. BMP. Thus, it is a social infrastructure project attempting to restore the eco-system and relieve the citizens and residents of hardships that they are currently exposed by way of polluted drains, flooding and potential danger of public health hazards. These characteristics of the project lend itself for grants, aid and soft loans. Not withstanding the above social aspects, BMP would provide appropriate support to the project by means of initial seed amount and through budget provision to support the operation and maintenance of the SWDs once constructed.

However, BMP is examining the possibility of levying a one time collection charges from property owners in the city towards partial recovery of capital cost that is estimated for the remodeling of the storm water drains. It is under consideration to recover at the maximum 40% of the capital cost through such cess. The recovery would be made over a period of five years from the property owners. This scheme is subject to willingness and affordability criteria of the residents and the approval of the BMP council and the State Government.

The revenue accrual on account of the proposed cess is summarized below – a total collection of Rs 302.50 Crores from the years 2007-08 till 2011-12.

| Storm Water Drain | 45.00 | 55.00 | 65.00 | 67.50 | 70.00 |
|-------------------|-------|-------|-------|-------|-------|
| Cess              |       |       |       |       |       |

#### – Project Repor

### **Estimated Capital Costs**

#### **Cost in Rs Crores**

| Name of                      | Capital<br>Cost as<br>per<br>DPR | Years   |         |         |         |         |         |  |
|------------------------------|----------------------------------|---------|---------|---------|---------|---------|---------|--|
| Component                    |                                  | 2006-07 | 2007-08 | 2008-09 | 2009-10 | 2010-11 | 2011-12 |  |
| Storm Water<br>Drain Network |                                  |         |         |         |         |         |         |  |
| Challaghatta<br>Valley       | 124.83                           | 49.93   | 49.93   | 24.97   | -       | -       | -       |  |
| Hebbal Valley                | 190.13                           | 76.05   | 76.05   | 38.03   | -       | -       | -       |  |
| Koramangala<br>Valley        | 118.43                           | 47.37   | 47.37   | 23.69   | -       | -       | -       |  |
| Vrishabhavathi<br>valley     | 245.54                           | 98.22   | 98.22   | 49.11   | -       | -       | -       |  |
| Sub-total for four valleys   | 678.93                           | 271.57  | 271.57  | 135.79  | 0.00    | 0.00    | 0.00    |  |

## Funding pattern for Storm Water Drain Valley Projects (Rs Crores)

| Funding Pattern | Total  | 2006-07 | 2007-08 | 2008-09 |  |
|-----------------|--------|---------|---------|---------|--|
| GOI Grant 35%   | 237.63 | 95.05   | 95.05   | 47.53   |  |
| GOK Grant 15 %  | 101.84 | 40.74   | 40.74   | 20.37   |  |
| BMP financing   | 339.47 | 135.79  | 135.79  | 67.89   |  |
| Total           | 678.93 | 271.57  | 271.57  | 135.79  |  |

The funding pattern is based on the JNNURM guidelines.

The fund flow statement for BMP for the next 10 years has been developed taking into consideration the financing of major infrastructure projects under JNNURM stream and non-JNNURM stream. These projections are under review by SBI Caps who are carrying out a due diligence exercise as well as the evaluation of viability for seeking external funding (viability gap after grant funding). The viability gap is proposed to be funded by direct loans as well as tax free municipal bonds that is under active consideration of both the State and the Central governments.

The basic assumptions in the financial projections are:

The property tax collection would move from Rs 320 crores in the year 2006-07 to Rs 750 Crores in the year 2015-16; this is being achieved with reforms in the property tax collection mechanism aided by GIS system for all the 100 municipal wards of BMP. The collection efficiency is estimated to go up to 85% by the year 2015-16 (the efficiency currently is 60%).

The revenue accretion from the State Government is estimated to move up from Rs 121 Crores in the year 2006-07 to Rs 302 Crores in the year 2015-16. This is based on the devolution criteria and guidelines provided by the Urban Development Department of the Government of Karnataka

Levy of storm water drain cess as a one time fee to be collected from all property owners – 10% cess on property tax paid – this would result in revenue accretion of Rs 302.50 crores over a period of 5 years

The total capital expenditure programme envisaged by BMP under JNNURM is approximately Rs 8000 crores including the basic services to urban poor component. Out of this BMP needs to mobilize Rs 4000 crores. It is assumed that BMP would arrange for term loans to the extent of Rs 1000 crores and the balance Rs 3000 crores would be obtained through issuing a series of tax free municipal bonds

Government of Karnataka would provide guarantees for the issue of municipal bonds to the extent of viability gap identified by the financial advisor

The cost of the municipal bonds is taken as 7% per annum and the bonds would be redeemed after 7 years period

The interest rate for future loans is assumed as 7.5 % per annum

The projections show a deficit in the terminal years when the bonds get redeemed; BMP proposes to identify additional sources of revenue from the year 2008-09 to improve its financial position in order to fund capital expenditure as well as honour financial commitments

The projections based on the assumptions are as follows:

Remodeling of Primary & Secondary Strom Water Drains in Bangalore City - Project Repor

# Projected Funds Flow Statement for BMP

# (Rs. In Crores)

| REVENUE                 | 2005-06 | 2006-07 | 2007-08 | 2008-09 | 2009-10 | 2010-11 | 2011-12 | 2012-13 | 2013-14 | 2014-15 | 2015-16 |
|-------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| REVENUE RECEIPTS        |         |         |         |         |         |         |         |         |         |         |         |
| Tax Revenues            |         |         |         |         |         |         |         |         |         |         |         |
| Property Tax            | 320.00  | 400.00  | 450.00  | 550.00  | 650.00  | 675.00  | 700.00  | 725.00  | 750.00  | 750.00  | 750.00  |
| Advertisement Taxes     | 15.47   | 16.86   | 18.55   | 20.40   | 22.44   | 24.68   | 27.15   | 29.87   | 32.86   | 36.14   | 39.75   |
| Surcharge on Stamp Duty | 15.00   | 20.00   | 22.00   | 24.20   | 26.62   | 29.28   | 32.21   | 35.43   | 38.97   | 42.87   | 47.16   |
|                         | 350.47  | 436.86  | 490.55  | 594.60  | 699.06  | 728.97  | 759.36  | 790.30  | 821.83  | 829.01  | 836.91  |

| Non Tax Revenues           |        |        | _      |        | _      | _      |        |        | _      |        |        |
|----------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Grants                     |        |        |        |        |        |        |        |        |        |        |        |
| SFC Grants                 | 110.00 | 131.00 | 149.00 | 182.00 | 219.00 | 231.00 | 240.00 | 257.00 | 257.00 | 257.00 | 257.00 |
| Other Grants:              | 11.00  |        |        |        |        |        |        |        |        |        |        |
| Grants towards electricity |        | 25.00  | 25.00  | 25.00  | 25.00  | 25.00  | 25.00  | 25.00  | 25.00  | 25.00  | 25.00  |
| Incentivisation            |        | 10.00  | 10.00  | 10.00  | 10.00  | 10.00  | 10.00  | 10.00  | 10.00  | 10.00  | 10.00  |
| Twelfth Finance Commission |        | 10.00  | 10.00  | 10.00  | 10.00  | 10.00  | 10.00  | 10.00  | 10.00  | 10.00  | 10.00  |
|                            | 121.00 | 176.00 | 194.00 | 227.00 | 264.00 | 276.00 | 285.00 | 302.00 | 302.00 | 302.00 | 302.00 |

| Service Charges                     |       |       |       |        |        |        |        |        |        |        |        |
|-------------------------------------|-------|-------|-------|--------|--------|--------|--------|--------|--------|--------|--------|
| Infrastructure Cess / User charges  | 20.00 | -     | 20.00 | 20.00  | 20.00  | 20.00  | 20.00  | 20.00  | 20.00  | 20.00  | 20.00  |
| SWM Cess                            | 30.00 | 30.00 | 30.00 | 30.00  | 30.00  | 30.00  | 30.00  | 36.00  | 36.00  | 36.00  | 36.00  |
| Service chgs on Tax exempt<br>Props | 15.00 | 25.00 | 25.00 | 25.00  | 25.00  | 25.00  | 25.00  | 25.00  | 25.00  | 25.00  | 25.00  |
|                                     | 65.00 | 55.00 | 75.00 | 75.00  | 75.00  | 75.00  | 75.00  | 81.00  | 81.00  | 81.00  | 81.00  |
|                                     |       |       |       |        |        |        |        |        |        |        |        |
| Fees & Fines                        |       |       |       |        |        |        |        |        |        |        |        |
| Building License Fees               | 5.25  | 11.60 | 11.60 | 11.60  | 11.60  | 11.60  | 11.60  | 12.76  | 12.76  | 12.76  | 12.76  |
| Compounding Fees                    | 4.50  | 10.00 | 11.00 | 12.10  | 13.31  | 14.64  | 16.11  | 17.72  | 19.49  | 21.44  | 23.58  |
| Development Charges                 | 3.00  | 8.86  | 9.75  | 10.72  | 11.79  | 12.97  | 14.27  | 15.70  | 17.27  | 18.99  | 20.89  |
| Ground Rent                         | 3.06  | 8.24  | 9.06  | 9.97   | 10.97  | 12.06  | 13.27  | 14.60  | 16.06  | 17.66  | 19.43  |
| Road Cutting Charges                | 6.02  | 0.45  | 0.50  | 0.54   | 0.60   | 0.66   | 0.72   | 0.80   | 0.88   | 0.96   | 1.06   |
| Khata Transfer & Extract fees       | 8.94  | 11.35 | 12.49 | 13.73  | 15.11  | 16.62  | 18.28  | 20.11  | 22.12  | 24.33  | 26.76  |
| Hotel / Power License Fees          | 3.50  | 5.00  | 5.50  | 6.05   | 6.66   | 7.32   | 8.05   | 8.86   | 9.74   | 10.72  | 11.79  |
| Fee for Quality Control             | -     | 5.00  | 5.50  | 6.05   | 6.66   | 7.32   | 8.05   | 8.86   | 9.74   | 10.72  | 11.79  |
| Others                              | 44.94 | 24.86 | 27.35 | 30.08  | 33.09  | 36.40  | 40.04  | 44.04  | 48.45  | 53.29  | 58.62  |
|                                     | 79.21 | 85.36 | 92.74 | 100.85 | 109.77 | 119.59 | 130.39 | 143.43 | 156.50 | 170.87 | 186.68 |

| Receipts from Corporation Prop | erties |        |        |         |         |              |         |              |              |              |              |
|--------------------------------|--------|--------|--------|---------|---------|--------------|---------|--------------|--------------|--------------|--------------|
| Rent from Shops /Leased        | 9.31   | 23.50  | 23.50  | 23.50   | 23.50   | 23.50        | 23.50   | 25.85        | 25.85        | 25.85        | 25.85        |
| Others                         | 1.08   | 0.81   | 0.85   | 0.89    | 0.94    | 0.98         | 1.03    | 1.09         | 1.14         | 1.20         | 1.26         |
|                                | 10.39  | 24.31  | 24.35  | 24.39   | 24.44   | 24.48        | 24.53   | 26.94        | 26.99        | 27.05        | 27.11        |
|                                | •      |        |        |         |         |              |         |              |              |              |              |
| Total Revenue Receipts         | 626.07 | 777.53 | 876.63 | 1,021.8 | 1,172.2 | 1,224.0<br>4 | 1,274.2 | 1,343.6<br>7 | 1,388.3<br>2 | 1,409.9<br>3 | 1,433.7<br>0 |

| REVENUE                                                      | 2005-06 | 2006-07 | 2007-08 | 2008-09 | 2009-10 | 2010-11 | 2011-12 | 2012-13 | 2013-14 | 2014-15 | 2015-16 |
|--------------------------------------------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| Capital Grants                                               |         |         |         |         |         |         |         |         |         |         |         |
| MOU Grants                                                   | 81.90   | -       | -       | -       | -       | -       | -       | -       | -       | -       | -       |
| JNNURM Funds                                                 | -       | 434.04  | 902.54  | 929.64  | 666.75  | 603.75  | 457.75  |         | -       | -       | -       |
|                                                              | 81.90   | 434.04  | 902.54  | 929.64  | 666.75  | 603.75  | 457.75  | -       | -       | -       | -       |
|                                                              |         |         |         |         |         |         |         |         |         |         |         |
| Long Term Loans                                              |         |         |         |         |         |         |         |         |         |         |         |
| Loans from Financial Institutions for JNNURM matching grants | -       | 108.06  | 224.70  | 231.45  | 166.00  | 150.31  | 113.96  | -       | -       | -       | -       |
| Bonds for JNNURM matching grants                             |         | 325.98  | 677.84  | 698.20  | 500.75  | 453.44  | 343.79  | -       | -       | -       | -       |
| Loans from Financial Institutions others                     | 545.53  | 396.60  | -       | -       | -       | -       | -       | -       | -       | -       | -       |
|                                                              | 545.53  | 830.64  | 902.54  | 929.65  | 666.75  | 603.75  | 457.75  | -       | -       | -       | -       |
| Others                                                       |         |         |         |         |         |         |         |         |         |         |         |
| Improvement Charges                                          | 30.00   | 30.00   | 30.00   | 30.00   | 30.00   | 30.00   | 36.00   | 36.00   | 36.00   | 36.00   | 36.00   |
| Bldg Deviation Regularisation                                | 100.00  | 10.00   | 100.00  | 10.00   | 10.00   | 10.00   | 10.00   | 10.00   | 10.00   | 10.00   | 10.00   |
| Sale of Properties                                           | 16.25   | 21.50   | 21.50   | 21.50   | 21.50   | 21.50   | 21.50   | 21.50   | 21.50   | 21.50   | 21.50   |
|                                                              | 146.25  | 61.50   | 151.50  | 61.50   | 61.50   | 61.50   | 67.50   | 67.50   | 67.50   | 67.50   | 67.50   |

|--|

## **Other Receipts**

| Cesses collected on Property Tax   | 108.80       | 136.00       | 153.00       | 187.00       | 221.00       | 229.50       | 238.00       | 246.50       | 255.00       | 255.00       | 255.00       |
|------------------------------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|
| Storm Water Drain Cess             |              |              | 45.00        | 55.00        | 65.00        | 67.50        | 70.00        |              |              |              |              |
| Deposits, Statutory Deductions etc | 52.45        | 62.14        | 143.48       | 143.48       | 143.48       | 143.48       | 143.48       | 20.00        | 20.00        | 20.00        | 20.00        |
|                                    |              |              |              |              |              |              |              |              |              |              |              |
|                                    | 161.25       | 198.14       | 341.48       | 385.48       | 429.48       | 440.48       | 451.48       | 266.50       | 275.00       | 275.00       | 275.00       |
| TOTAL RECEIPTS                     | 1,561.0<br>0 | 2,301.8<br>5 | 3,174.6<br>8 | 3,328.1<br>1 | 2,996.7<br>5 | 2,933.5<br>2 | 2,708.7<br>6 | 1,677.6<br>7 | 1,730.8<br>2 | 1,752.4<br>3 | 1,776.2<br>0 |

| EXPENDITURE                 | 2005-06 | 2006-07 | 2007-08 | 2008-09 | 2009-10 | 2010-11 | 2011-12 | 2012-13 | 2013-14 | 2014-15 | 2015-16 |
|-----------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| Administrative Expenses     |         |         |         |         |         |         |         |         |         |         |         |
| Salaries                    |         |         |         |         |         |         |         |         |         |         |         |
| Pay of Officers             | 6.26    | 5.81    | 6.39    | 7.03    | 7.73    | 8.51    | 9.36    | 10.29   | 11.32   | 12.45   | 13.70   |
| Pay of Establishment        | 62.37   | 72.74   | 80.01   | 88.02   | 96.82   | 106.50  | 117.15  | 128.86  | 141.75  | 155.92  | 171.52  |
| Allowances                  | 63.00   | 64.18   | 70.60   | 77.66   | 85.42   | 93.97   | 103.36  | 113.70  | 125.07  | 137.58  | 151.33  |
| Pension / Gratuity          | 30.50   | 34.50   | 37.95   | 41.75   | 45.92   | 50.51   | 55.56   | 61.12   | 67.23   | 73.95   | 81.35   |
|                             | 162.13  | 177.23  | 194.95  | 214.45  | 235.89  | 259.48  | 285.43  | 313.97  | 345.37  | 379.91  | 417.90  |
|                             |         |         |         |         |         |         |         |         |         |         |         |
| Advertisement & Publicity   | 2.12    | 2.33    | 2.80    | 3.36    | 4.03    | 4.83    | 5.80    | 6.96    | 8.35    | 3.08    | 3.69    |
| Printing & Stationery       | 3.25    | 1.58    | 1.74    | 1.91    | 2.10    | 2.31    | 2.54    | 2.80    | 3.08    | 3.39    | 3.73    |
| Telephone Charges           | 0.84    | 1.19    | 1.25    | 1.31    | 1.38    | 1.45    | 1.52    | 1.59    | 1.67    | 1.76    | 1.85    |
| Electricity Charges         | 30.54   | 25.60   | 26.88   | 28.22   | 29.64   | 31.12   | 32.67   | 34.31   | 36.02   | 37.82   | 39.71   |
| Water Charges               | 4.30    | 2.20    | 2.31    | 2.43    | 2.55    | 2.67    | 2.81    | 2.95    | 3.10    | 3.25    | 3.41    |
| Council related Expenditure | 3.90    | 5.49    | 5.76    | 6.05    | 6.36    | 6.67    | 7.01    | 7.36    | 7.72    | 8.11    | 8.52    |
| Office Infrastructure       | 3.98    | 4.61    | 4.84    | 5.08    | 5.34    | 5.60    | 5.88    | 6.18    | 6.49    | 6.81    | 7.15    |
| Vehicles - M & R Cost       | 10.03   | 10.25   | 10.76   | 11.30   | 11.87   | 12.46   | 13.08   | 13.74   | 14.42   | 15.14   | 15.90   |
| Other Expenses              | 93.63   | 65.66   | 68.95   | 72.40   | 76.02   | 79.82   | 83.81   | 88.00   | 92.40   | 97.02   | 101.87  |

|                                        |        |        |        |        |        |        |        |        |        |        | ,      |
|----------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
|                                        | 152.59 | 118.91 | 125.29 | 132.06 | 139.26 | 146.93 | 155.12 | 163.87 | 173.25 | 176.38 | 185.83 |
|                                        |        |        |        |        |        |        |        |        |        |        |        |
| Welfare Activities                     |        | -      |        |        | -      |        | -      |        |        | -      |        |
| 18% Allocation                         | 14.53  | 27.76  | 27.76  | 27.76  | 27.76  | 27.76  | 27.76  | 27.76  | 27.76  | 27.76  | 27.76  |
| Backward Classes & Minority<br>Welfare | 2.58   | 11.35  | 11.35  | 11.35  | 11.35  | 11.35  | 11.35  | 11.35  | 11.35  | 11.35  | 11.35  |
| Women Welfare                          | 6.48   | 4.99   | 4.99   | 4.99   | 4.99   | 4.99   | 4.99   | 4.99   | 4.99   | 4.99   | 4.99   |
| General                                | 0.70   | 0.80   | 0.80   | 0.80   | 0.80   | 0.80   | 0.80   | 0.80   | 0.80   | 0.80   | 0.80   |
|                                        | 24.29  | 44.90  | 44.90  | 44.90  | 44.90  | 44.90  | 44.90  | 44.90  | 44.90  | 44.90  | 44.90  |
| Educational Promotion Activities       | 5      |        |        |        |        |        |        |        |        |        |        |
| 18% allocation                         | 2.02   | 0.20   | 0.20   | 0.20   | 0.20   | 0.20   | 0.20   | 0.20   | 0.20   | 0.20   | 0.20   |
| General                                | 3.47   | 7.20   | 7.78   | 7.78   | 7.78   | 7.78   | 7.78   | 7.78   | 7.78   | 7.78   | 7.78   |
| Sports Activities                      | 1.55   | 1.07   | 1.52   | 1.52   | 1.52   | 1.52   | 1.52   | 1.52   | 1.52   | 1.52   | 1.52   |
|                                        | 7.04   | 8.47   | 9.50   | 9.50   | 9.50   | 9.50   | 9.50   | 9.50   | 9.50   | 9.50   | 9.50   |
|                                        |        |        |        |        |        |        |        | -      | -      |        |        |

| Health & Sanitation      | -       | •       |         |         |         |         |         |         |         | •       |         |
|--------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| Cleaning of Garbage      | 40.00   | 50.00   | 52.50   | 55.13   | 57.88   | 60.78   | 63.81   | 67.00   | 70.36   | 73.87   | 77.57   |
| Decentralised Composting | 0.10    | 0.10    | 0.11    | 0.11    | 0.12    | 0.12    | 0.13    | 0.13    | 0.14    | 0.15    | 0.16    |
| Street Dog Management    | 0.85    | 1.50    | 1.58    | 1.65    | 1.74    | 1.82    | 1.91    | 2.01    | 2.11    | 2.22    | 2.33    |
| Tipping Fees             | 2.50    | 2.00    | 2.10    | 2.21    | 2.32    | 2.43    | 2.55    | 2.68    | 2.81    | 2.95    | 3.10    |
| Others                   | 3.95    | 15.61   | 16.39   | 17.21   | 18.07   | 18.97   | 19.92   | 20.92   | 21.96   | 23.06   | 24.22   |
|                          | 47.40   | 69.21   | 72.67   | 76.30   | 80.12   | 84.13   | 88.33   | 92.75   | 97.39   | 102.25  | 107.37  |
| EXPENDITURE              | 2005-06 | 2006-07 | 2007-08 | 2008-09 | 2009-10 | 2010-11 | 2011-12 | 2012-13 | 2013-14 | 2014-15 | 2015-16 |

## **Financial Expenses**

| Total Revenue Expenditure   | 469.96 | 560.33 | 657.99 | 809.42 | 935.23 | 1,043.9<br>1 | 1,138.6<br>2 | 1,210.2<br>7 | 1,234.5<br>5 | 1,195.8<br>1 | 1,139.5<br>0 |
|-----------------------------|--------|--------|--------|--------|--------|--------------|--------------|--------------|--------------|--------------|--------------|
|                             | ·<br>  |        |        |        |        |              |              |              |              |              |              |
|                             | 76.51  | 141.61 | 210.68 | 332.20 | 425.55 | 498.97       | 555.34       | 585.28       | 564.14       | 482.87       | 374.00       |
| Interest on Municipal Bonds | -      | 21.00  | 63.00  | 112.00 | 147.00 | 178.50       | 199.50       | 199.50       | 199.50       | 178.50       | 136.50       |
| Interest on Loans           | 76.51  | 120.61 | 147.68 | 220.20 | 278.55 | 320.47       | 355.84       | 385.78       | 364.64       | 304.37       | 237.50       |

#### CAPITAL EXPENDITURE

| Public Works                      |        |        |        |        |        |        |       |       |       |       |       |
|-----------------------------------|--------|--------|--------|--------|--------|--------|-------|-------|-------|-------|-------|
| Solid Waste Management            | 7.90   | 6.60   | 6.93   | 7.28   | 7.64   | 8.02   | 8.42  | 8.84  | 9.29  | 9.75  | 10.24 |
| Engineering - Zonal               | 462.44 | 383.19 | 25.00  | 26.25  | 27.56  | 28.94  | 30.39 | 31.91 | 33.50 | 35.18 | 36.94 |
| Multi Purpose Engg Divisions      | 33.77  | 29.55  | 20.00  | 10.00  | 10.00  | 10.00  | 10.00 | 10.00 | 10.00 | 10.00 | 10.00 |
| Projects                          | 138.27 |        |        |        |        |        |       |       |       |       |       |
| Infrastructure                    | 134.37 |        |        |        |        |        |       |       |       |       |       |
| Comprehensive Development<br>Plan | 43.60  |        |        |        |        |        |       |       |       |       |       |
| Storm Water Drain Network         |        |        |        |        |        |        |       |       |       |       |       |
| Challaghatta Valley               |        | 49.93  | 49.93  | 24.97  | -      | -      | -     | -     | -     | -     | -     |
| Hebbal Valley                     |        | 76.05  | 76.05  | 38.03  | -      | -      | -     | -     | -     | -     | -     |
| Koramangala Valley                |        | 47.37  | 47.37  | 23.69  | -      | -      | -     | -     | -     | -     | -     |
| Vrishabhavathi valley             |        | 98.22  | 98.22  | 49.11  | -      | -      | -     | -     | -     | -     | -     |
| Sub-total for four valleys        |        | 271.57 | 271.57 | 135.79 | -      | -      | -     | -     | -     | -     | -     |
| Extension work into CMC areas     |        | 86.00  | 106.00 | 106.00 | 106.00 | 106.00 | -     | -     | -     | -     | -     |

| Environment Management                   |               |        |        |        |        |        |   |   |   |   |
|------------------------------------------|---------------|--------|--------|--------|--------|--------|---|---|---|---|
| Tanks                                    | 15.00         | 17.00  | 17.00  | 17.00  | 17.00  | 17.00  | - | - | - | - |
| Parks                                    | 15.00         | 8.00   | 8.00   | 7.00   | 6.00   | 6.00   | - | - | - | - |
| Incinerator, Crematorium and Abattoirs   | 9.00          | 16.00  | 16.00  | 17.00  | 17.00  | 16.00  | - | - | - | - |
| Tree Plantation and Nurseries            | 1.50          | 1.50   | 1.50   | 1.50   | 1.50   | 1.50   | - | - | - | - |
| Urban Renewal                            | Urban Renewal |        |        |        |        |        |   |   |   |   |
| Decongestion                             |               | 30.00  | 30.00  | 30.00  | 30.00  | 30.00  | - | - | - | - |
| Development of CBD                       |               | 20.00  | 20.00  | 20.00  | 20.00  | 20.00  | - | - | - | - |
|                                          |               |        |        |        |        |        |   |   |   |   |
| Road Network                             |               |        |        |        |        |        |   |   |   |   |
| Arterial and Sub arterial roads          | 125.00        | 150.00 | 400.00 | 325.00 | 250.00 | 250.00 | - | - | - | - |
| * Includes IT/BT, Flood<br>damaged roads |               |        |        |        |        |        |   |   |   |   |
| Grade Separators                         | 120.00        | 200.00 | 150.00 | 150.00 | 200.00 | 80.00  | - | - | - | - |
| Pedestrian subways                       | 5.00          | 15.00  | 15.00  | 15.00  | 15.00  | 10.00  | - | - | - | - |
| Foot Over Bridges                        | -             | 5.00   | 5.00   | 5.00   | 5.00   | 5.00   | - | - | - | - |
| Foot Path improvements                   | -             | 20.00  | 20.00  | 20.00  | 20.00  | 20.00  | - | - | - | - |
| Internal Core Ring Road                  |               | 200.00 | 200.00 |        | -      | -      | - | - | - | - |

|        | 120.00                                                         |                                                                                                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                           | I                                              | 1                                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
|--------|----------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------|------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|        | 120.00                                                         | 180.00                                                                                                                                                                                                                                                           | 180.00                                                                                                                                                                                                                                                                                                                                    | 110.00                                         | 110.00                                         | 100.00                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|        |                                                                |                                                                                                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                           |                                                |                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
|        | -                                                              | 175.00                                                                                                                                                                                                                                                           | 70.00                                                                                                                                                                                                                                                                                                                                     | -                                              | -                                              | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|        | -                                                              | 40.00                                                                                                                                                                                                                                                            | 35.00                                                                                                                                                                                                                                                                                                                                     | 60.00                                          | 60.00                                          | 60.00                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| -      | 100.00                                                         | 350.00                                                                                                                                                                                                                                                           | 450.00                                                                                                                                                                                                                                                                                                                                    | 450.00                                         | 350.00                                         | 300.00                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| 14.91  | 43.85                                                          |                                                                                                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                           |                                                |                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| 23.72  | 34.40                                                          | 42.40                                                                                                                                                                                                                                                            | 42.40                                                                                                                                                                                                                                                                                                                                     | 42.40                                          | 42.40                                          | 42.40                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 42.40                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 42.40                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 42.40                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 42.40                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| 56.84  | 28.72                                                          | 30.16                                                                                                                                                                                                                                                            | 31.66                                                                                                                                                                                                                                                                                                                                     | 33.25                                          | 34.91                                          | 36.65                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 38.49                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 40.41                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 42.43                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 44.55                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| 915.82 | 1,665.9<br>6                                                   | 2,201.1<br>3                                                                                                                                                                                                                                                     | 2,112.6<br>6                                                                                                                                                                                                                                                                                                                              | 1,454.3<br>5                                   | 1,331.7<br>7                                   | 1,043.3<br>7                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 131.64                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 135.60                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 139.76                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 144.13                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| es     |                                                                |                                                                                                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                           |                                                |                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| 70.18  | 112.46                                                         | 160.59                                                                                                                                                                                                                                                           | 216.36                                                                                                                                                                                                                                                                                                                                    | 257.10                                         | 280.35                                         | 289.54                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 207.18                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 146.27                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 108.88                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 78.63                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| -      | -                                                              | -                                                                                                                                                                                                                                                                | -                                                                                                                                                                                                                                                                                                                                         | -                                              | -                                              | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 300.00                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 600.00                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 700.00                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| 70.18  | 112.46                                                         | 160.59                                                                                                                                                                                                                                                           | 216.36                                                                                                                                                                                                                                                                                                                                    | 257.10                                         | 280.35                                         | 289.54                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 207.18                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 446.27                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 708.88                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 778.63                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|        |                                                                |                                                                                                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                           |                                                |                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| 986.00 | 1,778.4<br>2                                                   | 2,361.7<br>2                                                                                                                                                                                                                                                     | 2,329.0<br>3                                                                                                                                                                                                                                                                                                                              | 1,711.4<br>5                                   | 1,612.1<br>2                                   | 1,332.9<br>1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 338.82                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 581.88                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 848.64                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 922.76                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|        |                                                                |                                                                                                                                                                                                                                                                  | 1                                                                                                                                                                                                                                                                                                                                         | 1                                              | 1                                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
|        | 14.91<br>23.72<br>56.84<br>915.82<br>es<br>70.18<br>-<br>70.18 | -       100.00         14.91       43.85         23.72       34.40         56.84       28.72         915.82       1,665.9         6       6         70.18       112.46         -       -         70.18       112.46         -       -         70.18       112.46 | 40.00          100.00       350.00         14.91       43.85          23.72       34.40       42.40         56.84       28.72       30.16         915.82       1,665.9       2,201.1         6       3          70.18       112.46       160.59              70.18       112.46       160.59              70.18       112.46       160.59 | Image: Mark Mark Mark Mark Mark Mark Mark Mark | Image: Mark Mark Mark Mark Mark Mark Mark Mark | Image: series         Image: s | Image: Marking | Image: set of the set | Image: set of the set | Image: state in the s |

| Other Payments                                  |              |              |              |              |              |              |              |              |              |              |              |
|-------------------------------------------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|
| Repayment of Cesses - Current                   | 27.84        | 36.00        | 114.75       | 140.25       | 165.75       | 172.13       | 178.50       | 184.88       | 191.25       | 191.25       | 191.25       |
| Repayment of Cesses - Arrears                   | -            | 32.73        | -            | -            | -            | -            | -            | -            | -            | -            | -            |
| Repayment of Statutory<br>Deductions / Deposits | 41.52        | 45.48        | 43.04        | 43.04        | 100.43       | 100.43       | 100.43       | 14.00        | 14.00        | 14.00        | 14.00        |
|                                                 | 69.36        | 114.21       | 157.79       | 183.29       | 266.18       | 272.56       | 278.93       | 198.88       | 205.25       | 205.25       | 205.25       |
|                                                 |              |              | 1            |              | 1            |              |              | 1            |              | 1            |              |
| TOTAL PAYMENTS                                  | 1,525.3<br>2 | 2,452.9<br>7 | 3,177.5<br>1 | 3,321.7<br>4 | 2,912.8<br>6 | 2,928.5<br>9 | 2,750.4<br>6 | 1,747.9<br>7 | 2,021.6<br>7 | 2,249.6<br>9 | 2,267.5<br>1 |
|                                                 |              |              |              |              |              |              |              |              |              |              |              |
| Net Surplus / Deficit                           | 35.68        | (151.12)     | (2.82)       | 6.38         | 83.89        | 4.93         | (41.70)      | (70.30)      | (290.85)     | (497.26)     | (491.31)     |

## CHAPTER - 10

#### IMPLEMENTATION PLAN

#### 10.1 INTRODUCTION:

This chapter provides a strategic framework to ensure that the Remodeling of storm water drain project proposed for Bangalore city is managed in a reliable, affordable, sustainable and environmentally friendly manner, and which is most essential for success of any project.

But from the existing management practices followed by the stakeholders and also with the prevailing site conditions, it appears that, along with the resources required to achieve the recommended targets, strategies and actions, they also needs to adopt best storm drain management practices, improvised construction and construction supervision techniques, strengthened organizational setup, major legislative changes, coordination with other stakeholders, public awareness campaigns including their participation to minimize the adverse implications on storm drain functionality and storm drain management practice in the city.

In order to achieve the overall objectives of the project, it is very much essential to have a proper implementation programme that could ensure better control over the project cost and resources mobilized etc. BMP also proposes to have a separate project implementation unit within BMP (other than members from stake holders dept.), headed by a senior officer from the Engineering wing, Revenue wing, consortia of Technical consultants, Financial advisors, Project management consultants, co ordination committee members (other stake holders dept. members), PRO's & NGO's.

## 10.2 STAGES OF THE PROJECT:

The proposed project is take up in two stages and it is proposed that Stage – I activities will be carried out by external Technical Consultants and Stage – II activities shall be monitored by the design consultants and the same will be over seen by BMP.

#### Stage – I PREPARATION OF DETAILED PROJECT REPORT:

- **Phase 1:** Technical, Economical and Environmental Feasibility Study of the Project of Remodeling of the Storm Water Drain System.
- Phase 2: Detailed engineering design, preparation of tender documents, cost estimates for the remodeling work, Preparation of Bid document and assist BMP to entrust the work to experienced, competent and successful agency.

A brief scope of assignment to be rendered by the Technical Consultants is given below:

- Detailed topographical and geo-technical survey
- Assessment of quantity of runoff
- Adequacy analysis of existing drains
- Hydraulic and structural designs and drawings
- Cost estimation and Bill of Quantities
- Technical specifications.
- Bid Documents
- Slicing and Packaging (Phasing for Implementation)
- Assistance in Inviting and evaluating Bids
- Project management and Quality assurance

The outline methodology Phase – I & Phase- II works & activity bar chart for Stage – I works is enclosed in this chapter as Fig. 10.1, Fig. 10.2 & Fig. 10.3.

#### Stage – II PROJECT IMPLEMENTATION:

The works envisaged in the project are grouped into 16 packages and each package costing around Rs. 20 Crores.

The details of the works identified are narrated in detail in the previous chapters and the summary of the same is indicated packages are as mentioned in the Table 10.1. and the same is depicted in Figure no. 10.4.

|                                       | Drain Ler                            | igth, (Km.) | Total No. of                                      |                                  |  |  |  |  |  |  |
|---------------------------------------|--------------------------------------|-------------|---------------------------------------------------|----------------------------------|--|--|--|--|--|--|
| Name of the Valley                    | Name of the Valley<br>Primary Second |             | Culverts/Bridges<br>Considered for<br>Remodelling | Tender Package No.               |  |  |  |  |  |  |
| Koramangala Valley                    |                                      |             |                                                   |                                  |  |  |  |  |  |  |
| Koramangala Main<br>Valley            | 12.000                               | 17.710      | 12                                                | K1VD – I, K1VD- II &<br>K1VD- IV |  |  |  |  |  |  |
| Tavarekere Valley                     | 7.650                                | 18.825      | 9                                                 | K2VD - III                       |  |  |  |  |  |  |
| Challaghatta Valley                   |                                      |             |                                                   |                                  |  |  |  |  |  |  |
| Challaghatta Main<br>Valley           | 12.000                               | 13.400      | 14                                                | C1VD - II & C1VD- III            |  |  |  |  |  |  |
| Ulsoor Valley                         | 4.150                                | 4.170       | 9                                                 | C2VD - I                         |  |  |  |  |  |  |
| Hebbal Valley                         |                                      |             |                                                   |                                  |  |  |  |  |  |  |
| Hebbal Main Valley                    | 4.425                                | 4.800       | 5                                                 | H1VD- I                          |  |  |  |  |  |  |
| Hebbal Main Valley - I                | 9.000                                | 10.695      | 6                                                 | H2VD- II                         |  |  |  |  |  |  |
| Hebbal Minor Valley - I               | 7.375                                | 9.330       | 16                                                | H3VD- III                        |  |  |  |  |  |  |
| Hebbal Minor Valley - II              | 5.000                                | 0.950       | 1                                                 | H4VD- IV                         |  |  |  |  |  |  |
| Vrishabhavathi Valley                 |                                      |             |                                                   |                                  |  |  |  |  |  |  |
| Vrishabhavathi Main<br>Valley         | 14.000                               | 30.945      | 18                                                | V1VD - I & V1VD- II              |  |  |  |  |  |  |
| Kethmaranahalli &<br>Arkavathi Valley | 13.300                               | 14.675      | 15                                                | V2VD - III & V2VD- IV            |  |  |  |  |  |  |
| Kathriguppe Valley                    | 4.850                                | 11.400      | 6                                                 | V3VD- V                          |  |  |  |  |  |  |

Detailed Project Report




Figure 10.4 Packages Details

The site activities envisaged in all the 16 packages are classified into five categories viz'

#### Rehabilitation works to existing system:

- I. Reconstruction of collapsed wall
- II. Restoration of broken wall
- III. Cavity filling, restoration of eroded stones, providing pointing to the existing drain walls etc.

#### Carrying capacity improvement works:

- I. Widening of Drains
- II. Desilting and drain deepening
- III. Drain bed protection

# Remodeling of existing inadequate vent way/Structurally unstable - bridges/culverts.

#### Removal of obstacles – pipe lines, manholes, cables etc.

#### Training & Community awareness campaigns.

The works proposed for remodeling of storm drains shall be taken up in a phased manner simultaneously in all the packages. Since, some of the critical issues like coordination from other agencies in several instances, community participation, acquisition of land from government & public, shifting of major utilities, traffic diversion at several places etc., are envisaged in all the packages.

After having several discussion with senior officials of BMP and other stake holders and beneficiaries of the project. Work programme with a broader contest has been formulated keeping in view the availability of the resources, minimum distraction to the adjoining properties, to cause less inconvenience to the public, considering the environmental aspects etc., also for smooth and successful implementation of the project, which is as narrated below,

# Brief Work Programme for Remodeling of Storm Water Drains in Bangalore City:

- All the works considered under remodeling project shall start simultaneously from down stream end of respective packages.
- Vegetation growth noticed inside the drain at various locations shall be removed in all the packages.
- Shifting of service lines which are noticed all along the entire length of the drain at various locations, shall be taken up simultaneously in coordination with various agencies in all the packages.
- Stoppage of sewage and other undesirable liquid wastes entry into storm drains which are noticed over the entire length shall be taken up simultaneously in all the packages.
- Desilting of drains, removal of debris/solid wastes etc., which are noticed over the entire length of storm drain, shall be taken up simultaneously in all the packages.
- Widening of storm drains at the critical reaches, which are identified at various locations under the project, shall be taken up simultaneously in all the packages.
- Culvert/bridges considered for remodeling under the project, at various locations shall be taken up simultaneously in all the packages.
- Construction of new drains considered for minimizing the flooding problems in low lying areas which are spread over at various locations shall be taken up simultaneously in all the packages.
- Reaches of existing drain walls proposed for reconstruction/restoration under the project at various locations in the entire length of drain, shall be taken up simultaneously in all the packages.
- Providing rehabilitation works to existing drain walls and other structures considered under the project at various locations, shall be taken up simultaneously in all the packages.
- Construction of new drain wall / stone revetment in the reaches identified at various locations under the project shall be taken up simultaneously in all the packages.
- Providing pointing and skin reinforcement to the entire length of existing SSM storm drain walls shall be taken up simultaneously in all the packages.

- Construction of water recharging structures and development of land along side of the drain shall be taken up simultaneously in all the packages.
- Providing bed protection to the entire length of storm drains shall be taken up simultaneously in all the packages.
- Restoration of roads, cross drains and other infrastructure facilities, after completion of the works at various locations, shall be taken up simultaneously in all the packages.
- Providing improvements works at along side of the storm drains, shall be taken up simultaneously in all the packages.
- Periodic maintenance of storm drainage system shall be taken up for the entire length of the drains in all the packages.

#### **10.3 IMPLEMENTATION PROGRAMME:**

It is estimated that the work envisaged under remodeling of storm water drain project would involve period of 24 months from bidding with first six months dedicated to tender process and award of contract, which will be done as per KTTP act and 18 months for the execution of civil works.

It is proposed that BMP, the nodal agency will set up a separate implementation unit whose responsibilities would include ensuring the deployment of adequate staff, usage of quality materials, construction practices of acceptable standards and quality of works carried out, monitoring and reporting the project progress to the project monitoring agencies.

Tender specifications and construction practices are reflected in the bid document issued by BMP for its works related to construction of system components. The contractor would also adhere to the environmental regulations in practices and keep the citizens informed of the scheduled of the project underway in a periodic manner.

Detailed item wise implementation schedule for the execution of the project is enclosed in this report.